Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #42 - Non-Dairy Operation Less Than 300 AU with Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a small non-dairy Animal Feeding Operation (AFO) of less than 300 animal units (AU)--primarily swine, poultry, and beef AFOs. The producer may export (material transferred to another owner with written documentation of the transfer) modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan must include all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of a small sized non-dairy AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS with the CNMP Case File data that describes management and conservation practice solutions to all identified resource concerns on the small-sized non-dairy AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to reduce soil erosion on land application areas to sustainable levels; land apply waste material nutrients in a manner than meets NRCS 590 Nutrient Management standard technical criteria. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Practices selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with the practice standards. Accurate recordkeeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $8,351.86

Scenario Cost/Unit: $8,351.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	55	$5,055.05
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	43	$3,296.81

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #43 - Dairy Operation Less Than 300 AU with Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) and CNMP Case File will be developed to address resource concerns on a small Dairy Animal Feeding Operation (AFO) of less than 300 animal units (AU). The producer may export (material transferred to another owner with written documentation of the transfer) modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan must include all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of a small sized dairy AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS the CNMP with Case File data that describes management and conservation practice solutions to all identified resource concerns on the small-sized dairy AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to reduce soil erosion on land application areas to sustainable levels; land apply waste material nutrients in a manner than meets NRCS 590 Nutrient Management standard technical criteria. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Practices selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with the practice standards. Accurate recordkeeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $10,420.07

Scenario Cost/Unit: $10,420.07

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	75	$6,893.25
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	46	$3,526.82

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #44 - Non-Dairy Operation Greater Than or Equal to 300 AU and Less Than 700 AU with Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a medium non-dairy Animal Feeding Operation (AFO) of greater than or equal to 300 and less than 700 animal units (AU).--primarily swine, poultry, and beef AFOs. The producer may export (material transferred to another owner with written documentation of the transfer) modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan must include all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of a medium sized non-dairy AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS with the CNMP Case File data that describes management and conservation practice solutions to all identified resource concerns on the non-dairy AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to reduce soil erosion on land application areas to sustainable levels; land apply waste material nutrients in a manner than meets NRCS 590 Nutrient Management standard technical criteria. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Practices selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with the practice standards. Accurate recordkeeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $10,757.70

Scenario Cost/Unit: $10,757.70

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	72	$6,617.52
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	54	$4,140.18

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #45 - Dairy Operation Greater Than or Equal to 300 AU and Less Than 700 AU with Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a medium Dairy Animal Feeding Operation (AFO) of greater than or equal to 300 and less than 700 animal units (AU). The producer may export (material transferred to another owner with written documentation of the transfer) modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan must include all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of a medium sized Dairy AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS the CNMP with Case File data that describes management and conservation practice solutions to all identified resource concerns on the dairy AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to reduce soil erosion on land application areas to sustainable levels; land apply waste material nutrients in a manner than meets NRCS 590 Nutrient Management standard technical criteria. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Practices selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with the practice standards. Accurate recordkeeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $11,906.81

Scenario Cost/Unit: $11,906.81

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	82	$7,536.62
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	57	$4,370.19

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #46 - Non-Dairy Operation Greater Than or Equal to 700 AU with Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a large non-dairy Animal Feeding Operation ((AFO) of greater than or equal to 700 animal units (AU)--primarily swine, poultry, and beef AFOs. The producer may export (material transferred to another owner with written documentation of the transfer) modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan must include all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of a large sized non-dairy AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS with the CNMP Case File data that describes management and conservation practice solutions to all identified resource concerns on the non-dairy AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to reduce soil erosion on land application areas to sustainable levels; land apply waste material nutrients in a manner than meets NRCS 590 Nutrient Management standard technical criteria. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Practices selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with the practice standards. Accurate recordkeeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $12,994.96

Scenario Cost/Unit: $12,994.96

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	88	$8,088.08
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	64	$4,906.88

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #47 - Dairy Operation Greater Than or Equal to 700 AU with Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a large Dairy Animal Feeding Operation (AFO) of greater than or equal to 700 animal units (AU). The producer may export (material transferred to another owner with written documentation of the transfer) modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan must include all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of a large sized Dairy AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS the CNMP with Case File data that describes management and conservation practice solutions to all identified resource concerns on the dairy AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to reduce soil erosion on land application areas to sustainable levels; land apply waste material nutrients in a manner than meets NRCS 590 Nutrient Management standard technical criteria. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Practices selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with the practice standards. Accurate recordkeeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $13,240.21

Scenario Cost/Unit: $13,240.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	89	$8,179.99
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	66	$5,060.22

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #48 - Livestock Operation Less Than 300 AU without Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a small Animal Feeding Operation (AFO) of less than 300 animal units (AU). The producer exports (material transferred to another owner with written documentation of the transfer) nearly all of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas owned or controlled by the AFO owner/operator. In this scenario, the primary focus will be addressing resource concerns present on the production area, including manure/wastewater handling and storage, and documentation of manure generation by the AFO, and its export. Production area components of the plan must include animal confinement facilities, feeding and lounging areas, animal mortality facilities, and manure containment and storage facilities. Planned practices on the production area must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner’s/operator's production objectives.

Before Situation:

The owner/operator of a small AFO has not received a written comprehensive nutrient management plan (CNMP) that addresses all resource concerns present on the facility production areas and any applicable land application areas. Partial implementation of CNMP- related practices for the AFO has potentially occurred. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Resource concerns on the AFO production area remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, erosion and runoff issues from feeding and lounging areas, and recordkeeping documentation of manure generation and exports. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for inspection and monitoring of the existing CNMP-related practices, manure imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive conservation plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS a the CNMP Case File that describes management and conservation practice solutions to all identified resource concerns on the small sized AFO production area and any applicable land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories/evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; minimize erosion and runoff from feeding and lounging areas, keep accurate AFO animal inventory information, and document AFO manure generation and exports. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Decisions selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with those in the conservation practice. Accurate recordkeeping documents for operation and maintenance of existing and new CNMP-related practices, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist..

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $7,522.79

Scenario Cost/Unit: $7,522.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	66	$6,066.06
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	19	$1,456.73

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #49 - Livestock Operation Greater Than 300 AU without Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a medium-large Animal Feeding Operation (AFO) of greater than or equal to 300 animal units (AU). The producer exports (material transferred to another owner with written documentation of the transfer) nearly all of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas owned or controlled by the AFO owner/operator. In this scenario, the primary focus will be addressing resource concerns present on the production area, including manure/wastewater handling and storage, and documentation of manure generation by the AFO, and its export. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Planned practices on the production area must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner's/operator's production objectives.

Before Situation:

The owner/operator of a medium-large sized AFO has not received a written comprehensive nutrient management plan (CNMP) that addresses all resource concerns present on the facility production areas and any applicable land application areas. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Resource concerns on the AFO production area remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, erosion and runoff issues from feeding and lounging areas, and recordkeeping documentation of manure generation and exports. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for inspection and monitoring of the existing CNMP-related practices, manure imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive conservation plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS a the CNMP Case File that describes management and conservation practice solutions to all identified resource concerns on the small sized AFO production area and any applicable land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories/evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; minimize erosion and runoff from feeding and lounging areas, keep accurate AFO animal inventory information, and document AFO manure generation and exports. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Decisions selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with those in the conservation practice. Accurate recordkeeping documents for operation and maintenance of existing and new CNMP-related practices, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $9,345.75

Scenario Cost/Unit: $9,345.75

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	85	$7,812.35
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	20	$1,533.40

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #135 - CNMP Less Than or Equal to 300 AU with Land Application (Minimal Engineer Assistance)

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a small non-dairy Animal Feeding Operation (AFO) of less than 300 animal units (AU)--primarily swine, poultry, and beef AFOs. This scenario is for sites or states where the services of a professional engineer are minimal. The producer may export modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan includes all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas result in meeting NRCS planning criteria for water quality, soil erosion, and air quality concerns. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of an AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. Partial implementation of conservation practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts issues may remain on the AFO, and recordkeeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS with the CNMP Case File data that describes management and conservation practice systems to address all identified resource concerns on the AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to address soil erosion, water quality, and air quality within the NRCS planning criteria. Accurate record keeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP.

Feature Measure: Each

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $4,844.10

Scenario Cost/Unit: $4,844.10

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	50	$3,925.00
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	10	$919.10

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #136 - CNMP Less Than or Equal to 300 AU without Land Application (Minimal Engineer Assistance)

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on the Animal Feeding Operation (AFO) of less than 300 or equal animal units (AU). This scenario is for sites or states where the services of a professional engineer are minimal. The producer exports nearly all of the manure or organic products from the farm. The CNMP is a conservation plan that addresses soil erosion, water quality, and air quality resource concerns on the AFO production area and land application areas owned or controlled by the AFO owner/operator. In this scenario, the primary focus will be addressing soil erosion, water quality, and air quality resource concerns present on the production area, including manure/wastewater handling and storage, and documentation of manure generation by the AFO, and its export. Production area components of the plan must include animal confinement facilities, feeding and lounging areas, animal mortality facilities, and manure containment and storage facilities. Planned practices on the production area must result in meeting NRCS planning criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner€™s/operator's production objectives.

Before Situation:

The owner/operator of the AFO has not received a written comprehensive nutrient management plan (CNMP) that addresses all resource concerns present on the facility production areas and any applicable land application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Resource concerns on the AFO production area remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, erosion and runoff issues from feeding and lounging areas, and record keeping documentation of manure generation and exports. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and record keeping methods for inspection and monitoring of the existing CNMP-related practices, manure imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive conservation plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS a the CNMP Case File that describes management and conservation practice practices to address all identified soil erosion, water quality, and air quality resource concerns on the AFO production area and any applicable land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories/evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria. Conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; minimize erosion and runoff from feeding and lounging areas, keep accurate AFO animal inventory information, and document AFO manure generation and exports. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Decisions selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with those in the conservation practice. Accurate record keeping documents for operation and maintenance of existing and new CNMP-related practices, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP.

Feature Measure: Each

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $2,835.85

Scenario Cost/Unit: $2,835.85

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	10	$919.10
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	25	$1,916.75

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #137 - CNMP Greater Than 300 AU with Land Application (Minimal Engineer Assistance)

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on an Animal Feeding Operation (AFO) of greater than or equal to 300 animal units (AU). This scenario is for sites or states where the services of a professional engineer are minimal. The producer may export modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most manure nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan must include all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas must result in meeting NRCS planning criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of an AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and record keeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS with the CNMP Case File data that describes management and conservation practices to address all identified soil erosion, water quality, and air quality resource concerns on the AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to reduce soil erosion on land application areas to sustainable levels; land apply waste material nutrients in a manner than meets NRCS 590 Nutrient Management standard technical criteria. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts. Practices selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with the practice standards. Accurate record keeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP.

Feature Measure: Each

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $6,362.20

Scenario Cost/Unit: $6,362.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	15	$1,378.65
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	65	$4,983.55

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #138 - CNMP Greater Than 300 AU without Land Application (Minimal Engineer Assistance)

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on an Animal Feeding Operation (AFO) of greater than 300 animal units (AU). This scenario is for sites or states where the services of a professional engineer are minimal. The producer exports nearly all of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The CNMP is a conservation plan that addresses the soil erosion, water quality, and air quality resource concerns on the AFO production area and land application areas owned or controlled by the AFO owner/operator. In this scenario, the primary focus will be addressing resource concerns present on the production area, including manure/wastewater handling and storage, and documentation of manure generation by the AFO, and its export. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Planned practices on the production area must result in meeting NRCS planning criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owners/operator's production objectives.

Before Situation:

The owner/operator of an AFO has not received a written comprehensive nutrient management plan (CNMP) that addresses the soil erosion, water quality, and air quality resource concerns present on the facility production areas and any applicable land application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Resource concerns on the AFO production area remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, soil erosion, water quality, and air quality concerns from feeding and lounging areas, and record keeping documentation of manure generation and exports. Negative air quality impacts issues may remain on the AFO, and record keeping methods for inspection and monitoring of the existing CNMP-related practices, manure imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered to the AFO owner/operator, a comprehensive conservation plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS a the CNMP Case File that describes management and conservation practice solutions to all identified resource concerns on the small sized AFO production area and any applicable land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems are inventoried/evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria. Conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; minimize soil erosion, water quality, and air quality concerns from feeding and lounging areas, keep accurate AFO animal inventory information, and document AFO manure generation and exports. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts. Decisions selected in the Record of Decisions will provide estimated quantities for conservation practices to be installed in units of measure that align with those in the conservation practice. Accurate record keeping documents for operation and maintenance of existing and new CNMP-related practices, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP.

Feature Measure: Each

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,219.20

Scenario Cost/Unit: $3,219.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	10	$919.10
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	30	$2,300.10

Practice: 104 - Nutrient Management Plan - Written

Scenario #44 - Nutrient Management CAP Less Than or Equal to 100 Acres (Not part of a CNMP)

Scenario Description:

Various on-farm land uses where natural or artificial amendments are applied. Natural Resource Concern: Water Quality, Soil Erosion, Water Quantity, and other associated resource concerns.

Before Situation:

Agricultural producer has no plan or minimal knowledge for application and management of nutrients. The producer currently manages nutrient application based upon personal knowledge, or other local criteria. Producer is interested in management of nutrients to maximize yields, profits margin, reduce costs, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Nutrient Management" conservation activity plan consistent with the criteria in CAP 104 and 590 Nutrient Management. The CAP criteria requires the plan to meet quality criteria for the primary Water Quality resource concern and other applicable resource concerns and provides for opportunities to manage nutrients for plant production and address offsite movement of nutrients. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 104 plan as cited in the NRCS Field Office Technical Guide and CPS 590 Nutrient Management.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $2,355.00

Scenario Cost/Unit: $2,355.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	30	$2,355.00

Practice: 104 - Nutrient Management Plan - Written

Scenario #45 - Nutrient Management CAP 104- 101-300 Acres (Not part of a CNMP)

Scenario Description:

Various on-farm land uses where organic or inorganic amendments are applied. Natural Resource Concern: Water Quality, Soil Erosion, Water Quantity, and other associated resource concerns.

Before Situation:

Agricultural producer has no plan or minimal knowledge for applicant and management of land applied nutrients. The producer currently manages nutrient application based upon label instructions, personal knowledge, or other local criteria. Producer is interested in management of nutrients to maximize yields, profits margin, reduce costs, nutrient use efficiency and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Nutrient Management" conservation activity plan. The CAP criteria requires the plan to meet Nutrient Management criteria for the primary Water Quality resource concern and other applicable resource concerns and provides for opportunities to manage nutrients for plant production and address offsite movement of nutrients. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic criteria for the 104 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,140.00

Scenario Cost/Unit: $3,140.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	40	$3,140.00

Practice: 104 - Nutrient Management Plan - Written

Scenario #46 - Nutrient Management CAP 104 Greater Than 300 Acres (Not part of a CNMP)

Scenario Description:

Various on-farm land uses where organic or inorganic amendments are applied. Natural Resource Concern: Water Quality, Soil Erosion, Water Quantity, and other associated resource concerns.

Before Situation:

Agricultural producer has no plan or minimal knowledge for applicant and management of land applied nutrients. The producer currently manages nutrient application based upon label instructions, personal knowledge, or other local criteria. Producer is interested in management of nutrients to maximize yields, profits margin, reduce costs, nutrient use efficiency, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Nutrient Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for the primary Water Quality resource concern and other applicable resource concerns and provides for opportunities to manage nutrients for plant production and address offsite movement of nutrients. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic criteria for the 104 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,925.00

Scenario Cost/Unit: $3,925.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	50	$3,925.00

Practice: 104 - Nutrient Management Plan - Written

Scenario #47 - Nutrient Management CAP 104 Less Than or Equal to 100 Acres (Element of a CNMP)

Scenario Description:

Various on-farm land uses where natural or artificial nutrient amendments are applied. Natural Resource Concern: Water Quality, Soil Erosion, Water Quantity, and other associated resource concerns.

Before Situation:

Agricultural producer has no plan or minimal knowledge for applicant and management of nutrient applied to the land. The producer currently manages nutrient application based upon label instructions, personal knowledge, or other local criteria. Producer is interested in management of nutrients to maximize yields, profits margin, reduce costs, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Nutrient Management" conservation activity plan. The CAP criteria requires the plan to meet nutrient criteria for the primary Water Quality resource concern in 590 and other applicable resource concerns and provides for opportunities to manage nutrients for plant production and address offsite movement of nutrients. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic criteria for the 104 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,925.00

Scenario Cost/Unit: $3,925.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	50	$3,925.00

Practice: 104 - Nutrient Management Plan - Written

Scenario #48 - Nutrient Management CAP 104 - 101-300 Acres (Element of a CNMP)

Scenario Description:

Various on-farm land uses where organic or inorganic amendments are applied. Natural Resource Concern: Water Quality, Soil Erosion, Water Quantity, and other associated resource concerns.

Before Situation:

Agricultural producer has no plan or minimal knowledge for applicant and management of applied nutrients to the land. The producer currently manages nutrient application based upon label instructions, personal knowledge, or other local criteria. Producer is interested in management of nutrients to maximize yields, profits margin, reduce costs, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Nutrient Management" conservation activity plan. The CAP criteria requires the plan to meet 590 criteria for the primary Water Quality resource concern and other applicable resource concerns and provides for opportunities to manage nutrients for plant production and address offsite movement of nutrients. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 104 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $5,495.00

Scenario Cost/Unit: $5,495.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	70	$5,495.00

Practice: 104 - Nutrient Management Plan - Written

Scenario #49 - Nutrient Management CAP 104 Greater Than 300 Acres (Element of a CNMP)

Scenario Description:

Various on-farm land uses where organic or inorganic amendments are applied. Natural Resource Concern: Water Quality, Soil Erosion, Water Quantity, and other associated resource concerns.

Before Situation:

Agricultural producer has no plan or minimal knowledge for applicant and management of nutrient s applied to the land. The producer currently manages nutrient application based upon label instructions, personal knowledge, or other local criteria. Producer is interested in management of nutrients to maximize yields, profits margin, reduce costs, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Nutrient Management" conservation activity plan. The CAP criteria requires the plan to meet 590 criteria for the primary Water Quality resource concern and other applicable resource concerns and provides for opportunities to manage nutrients for plant production and address offsite movement of nutrients. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic criteria for the 104 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $6,672.50

Scenario Cost/Unit: $6,672.50

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	85	$6,672.50

Practice: 106 - Forest Management Plan - Written

Scenario #50 - FMP Less Than or Equal to 20 acres

Scenario Description:

Non Industrial Private Forest Land typically unmanaged or limited management activities. Typical site is approximately 1 to 20 acres in size and consists of existing uneven-aged mixed species stands of harvestable trees. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition; on Forest Land.

Before Situation:

The producer currently manages forested lands without an existing forest management plan, or with an outdated plan. Resource concern(s) exist which are not addressed by a management plan. A Forest Management Plan or Conservation Activity Plan, as defined by EQIP regulation is needed to allow the producer to apply for financial assistance through EQIP or other programs to help implement needed conservation practices. Associated Practices: 472, 666, 654, 655,384, 394, 383, 379, 338, 391, 791, 490, 612, 660, 311, 380.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Forest Management Plan" Conservation Activity Plan (CAP). The CAP criteria requires the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Forest Management CAP is not considered a Forest Harvest Plan, but should complement the needs for harvest if desired by the land user. Additional CAP plan criteria is detailed in the Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $1,413.79

Scenario Cost/Unit: $1,413.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	19	$1,413.79

Practice: 106 - Forest Management Plan - Written

Scenario #51 - FMP 21 to 100 acres

Scenario Description:

Non Industrial Private Forest Land typically unmanaged or limited management activities. Typical site is approximately 21 to 100 acres in size and consists of existing uneven-aged mixed species stands of harvestable trees. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition; on Forest Land.

Before Situation:

The producer currently manages forested lands without an existing forest management plan, or with an outdated plan. Resource concern(s) exist which are not addressed by a management plan. A Forest Management Plan or Conservation Activity Plan, as defined by EQIP regulation is needed to allow the producer to apply for financial assistance through EQIP or other programs to help implement needed conservation practices. Associated Practices: 472, 666, 654, 655,384, 394, 383, 379, 338, 391, 791, 490, 612, 660, 311, 380.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Forest Management Plan" Conservation Activity Plan (CAP). The CAP criteria requires the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Forest Management CAP is not considered a Forest Harvest Plan, but should complement the needs for harvest if desired by the land user. Additional CAP plan criteria is detailed in the Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $1,785.84

Scenario Cost/Unit: $1,785.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	24	$1,785.84

Practice: 106 - Forest Management Plan - Written

Scenario #52 - FMP 101 to 250 acres

Scenario Description:

Non Industrial Private Forest Land typically unmanaged or limited management activities. Typical site is approximately 101 to 250 acres in size and consists of existing uneven-aged mixed species stands of harvestable trees. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition; on Forest Land.

Before Situation:

The producer currently manages forested lands without an existing forest management plan, or with an outdated plan. Resource concern(s) exist which are not addressed by a management plan. A Forest Management Plan or Conservation Activity Plan, as defined by EQIP regulation is needed to allow the producer to apply for financial assistance through EQIP or other programs to help implement needed conservation practices. Associated Practices: 472, 666, 654, 655,384, 394, 383, 379, 338, 391, 791, 490, 612, 660, 311, 380.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Forest Management Plan" Conservation Activity Plan (CAP). The CAP criteria requires the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Forest Management CAP is not considered a Forest Harvest Plan, but should complement the needs for harvest if desired by the land user. Additional CAP plan criteria is detailed in the Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,199.63

Scenario Cost/Unit: $3,199.63

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	43	$3,199.63

Practice: 106 - Forest Management Plan - Written

Scenario #53 - FMP Greater Than 1000 acres

Scenario Description:

Non Industrial Private Forest Land typically unmanaged or limited management activities. Typical site is approximately 1001 acres or greater in size and consists of existing uneven-aged mixed species stands of harvestable trees. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition; on Forest Land.

Before Situation:

The producer currently manages forested lands without an existing forest management plan, or with an outdated plan. Resource concern(s) exist which are not addressed by a management plan. A Forest Management Plan or Conservation Activity Plan, as defined by EQIP regulation is needed to allow the producer to apply for financial assistance through EQIP or other programs to help implement needed conservation practices. Associated Practices: 472, 666, 654, 655,384, 394, 383, 379, 338, 391, 791, 490, 612, 660, 311, 380.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Forest Management Plan" Conservation Activity Plan (CAP). The CAP criteria requires the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Forest Management CAP is not considered a Forest Harvest Plan, but should complement the needs for harvest if desired by the land user. Additional CAP plan criteria is detailed in the Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $6,696.90

Scenario Cost/Unit: $6,696.90

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	90	$6,696.90

Practice: 106 - Forest Management Plan - Written

Scenario #54 - FMP 251 to 500 acres

Scenario Description:

Non Industrial Private Forest Land typically unmanaged or limited management activities. Typical site is approximately 251 to 500 acres in size and consists of existing uneven-aged mixed species stands of harvestable trees. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition; on Forest Land.

Before Situation:

The producer currently manages forested lands without an existing forest management plan, or with an outdated plan. Resource concern(s) exist which are not addressed by a management plan. A Forest Management Plan or Conservation Activity Plan, as defined by EQIP regulation is needed to allow the producer to apply for financial assistance through EQIP or other programs to help implement needed conservation practices. Associated Practices: 472, 666, 654, 655,384, 394, 383, 379, 338, 391, 791, 490, 612, 660, 311, 380.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Forest Management Plan" Conservation Activity Plan (CAP). The CAP criteria requires the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Forest Management CAP is not considered a Forest Harvest Plan, but should complement the needs for harvest if desired by the land user. Additional CAP plan criteria is detailed in the Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $4,613.42

Scenario Cost/Unit: $4,613.42

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	62	$4,613.42

Practice: 106 - Forest Management Plan - Written

Scenario #55 - FMP 501 to 1000 acres

Scenario Description:

Non Industrial Private Forest Land typically unmanaged or limited management activities. Typical site is approximately 501 to 1000 acres in size and consists of existing uneven-aged mixed species stands of harvestable trees. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition; on Forest Land.

Before Situation:

The producer currently manages forested lands without an existing forest management plan, or with an outdated plan. Resource concern(s) exist which are not addressed by a management plan. A Forest Management Plan or Conservation Activity Plan, as defined by EQIP regulation is needed to allow the producer to apply for financial assistance through EQIP or other programs to help implement needed conservation practices. Associated Practices: 472, 666, 654, 655,384, 394, 383, 379, 338, 391, 791, 490, 612, 660, 311, 380.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Forest Management Plan" Conservation Activity Plan (CAP). The CAP criteria requires the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Forest Management CAP is not considered a Forest Harvest Plan, but should complement the needs for harvest if desired by the land user. Additional CAP plan criteria is detailed in the Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $5,357.52

Scenario Cost/Unit: $5,357.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	72	$5,357.52

Practice: 108 - Feed Management Plan - Written

Scenario #46 - Feed Management Plan

Scenario Description:

The owner/operator of an Animal Feeding Operation (AFO) has not received a written Feed Management Plan (FeedMP) that addresses all resource concerns present on the facility. Various levels of management and conservation implementation has occurred in the operation. Little documentation of the methods of feed management used and practices installed exists, and the producer is not likely to developed a complete forage inventory or nutrient analysis. The producer may or may not have a conservation plan or a nutrient management plan. Nutrient management related resource concerns on the operation remain to be addressed through the development of a complete FeedMP including management and conservation practices for proper quantity and quality of available nutrients, feedstuffs, and/or additives fed to livestock or poultry that may be present on the operation. Present operation and feed methodology poses risk of feeding excessive amounts of nutrients in animal manure which result in negative impacts to water quality and odor resource concerns. Negative water and air quality impacts as well as farmstead safety and security issues may remain on the AFO, and inadequate recordkeeping nutrient, inspection and monitoring of the existing operation may need further improvement.

Before Situation:

Producer has no plan or limited knowledge of management of feed, nutrients, feedstuffs, or nutritional additives provided to domestic livestock and poultry. The producer currently manages feed without a plan which would address livestock production limitations and water and air quality resource concern impacts. Producer currently lacks plan to provide proper balance of forage, grains or other feeds and supplements to assure domestic animal nutritional needs are met without negatively impacting water and air quality. Producer is interested in management of feed for domestic animals to maximize profit margin, reduce costs, improve or address livestock production opportunities, and for other environmental benefits. Producer is willing to collaborate with a certified Technical Service Provider (TSP) to develop a plan, and to collect/coordinate data and records to determine current nutritional needs. Associated Practice(s): 590-Nutrient Management

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the “Feed Management” (FM) conservation activity plan (CAP). The CAP criteria requires the plan to meet quality criteria for applicable natural resource concerns and provides for opportunities to identify and implement conservation practices related to management of feed, forages, or delivery of supplements to maximize efficient feeding operations and livestock growth. The CAP plan may serve as the basis for implementation of the primary conservation practice 592-Feed Management. If applicable, the FM CAP may also be developed to complement Comprehensive Nutrient Management Plans (CNMP) or to help meet requirements of NRCS practice standard 590 - Nutrient Management. As addressed in the CAP planning criteria, the plan may include recommendations for addressing associated natural resource concerns with other conservation practices. The FM CAP meets the basic quality criteria for the 108 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $1,840.08

Scenario Cost/Unit: $1,840.08

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	24	$1,840.08

Practice: 110 - Grazing Management Plan - Written

Scenario #1 - Grazing Management Plan Less Than or Equal to 100 acres

Scenario Description:

Small agricultural operation with less than 100 acres grazed land. Natural Resource Concern: Soil erosion, water quality, fish and wildlife, plant condition, and all other appropriate resource concerns.

Before Situation:

Producer has no plan or limited knowledge of management of livestock or other animals on grazed land resources. The producer currently manages animals without plan to address identified natural resource concerns. Producer is interested in management of animals to maximize profit margin, reduce costs, improve or address wildlife opportunities, and for other environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: In addition to the essential practices listed previously, addition practices to consider include: Channel Bank Vegetation, Prescribed Burning, Critical Area Planting, Pond, Windbreak/Shelterbelt Establishment, Silvopasture Establishment, Riparian Herbaceous Cover, Stream Habitat Improvement and Management, Pipeline, Heavy Use Area Protection, Spring Development, and Animal Trails and Walkways.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Grazing Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to implement essential conservation practices: Brush Management, Fencing, Firebreak, Forage Harvest Management, Grazing Land Mechanical Treatment, Herbaceous Weed Control, Nutrient Management, Forage and Biomass Planting, Prescribed Grazing, Range Planting, Access Control, and Watering Facilities. As addressed in the CAP criteria, the plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 110 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $2,308.20

Scenario Cost/Unit: $2,308.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, range conservation	1299	Conservation Activity Plan labor to study, plan the use and management of rangelands to maximize their use in a sustainable manner. Range managers may inventory soils, plants, and animals; develop resource management plans; identify monitoring methods and collect data using those methods to determine if resource management objectives are being met or if adjustments to management activities are needed. For example, they may help ranchers attain optimum livestock production by determining the number and kind of animals to graze, the grazing system to use, and the best season for grazing. Cost associated with this component includes overhead and benefits (market price).	Hour	$76.94	30	$2,308.20

Practice: 110 - Grazing Management Plan - Written

Scenario #2 - Grazing Management Plan 101 to 500 acres

Scenario Description:

Small agricultural operation with 101 to 500 acres grazed land. Natural Resource Concern: Soil erosion, water quality, fish and wildlife, plant condition, and all other appropriate resource concerns.

Before Situation:

Producer has no plan or limited knowledge of management of livestock or other animals on grazed land resources. The producer currently manages animals without plan to address identified natural resource concerns. Producer is interested in management of animals to maximize profit margin, reduce costs, improve or address wildlife opportunities, and for other environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: In addition to the essential practices listed previously, addition practices to consider include: Channel Bank Vegetation, Prescribed Burning, Critical Area Planting, Pond, Windbreak/Shelterbelt Establishment, Silvopasture Establishment, Riparian Herbaceous Cover, Stream Habitat Improvement and Management, Pipeline, Heavy Use Area Protection, Spring Development, and Animal Trails and Walkways.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Grazing Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to implement essential conservation practices: Brush Management, Fencing, Firebreak, Forage Harvest Management, Grazing Land Mechanical Treatment, Herbaceous Weed Control, Nutrient Management, Forage and Biomass Planting, Prescribed Grazing, Range Planting, Access Control, and Watering Facilities. As addressed in the CAP criteria, the plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 110 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,077.60

Scenario Cost/Unit: $3,077.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, range conservation	1299	Conservation Activity Plan labor to study, plan the use and management of rangelands to maximize their use in a sustainable manner. Range managers may inventory soils, plants, and animals; develop resource management plans; identify monitoring methods and collect data using those methods to determine if resource management objectives are being met or if adjustments to management activities are needed. For example, they may help ranchers attain optimum livestock production by determining the number and kind of animals to graze, the grazing system to use, and the best season for grazing. Cost associated with this component includes overhead and benefits (market price).	Hour	$76.94	40	$3,077.60

Practice: 110 - Grazing Management Plan - Written

Scenario #3 - Grazing Management Plan 1501 to 5000 acres

Scenario Description:

Small agricultural operation with 1501 to 5000 acres grazed land. Natural Resource Concern: Soil erosion, water quality, fish and wildlife, plant condition, and all other appropriate resource concerns.

Before Situation:

Producer has no plan or limited knowledge of management of livestock or other animals on grazed land resources. The producer currently manages animals without plan to address identified natural resource concerns. Producer is interested in management of animals to maximize profit margin, reduce costs, improve or address wildlife opportunities, and for other environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: In addition to the essential practices listed previously, addition practices to consider include: Channel Bank Vegetation, Prescribed Burning, Critical Area Planting, Pond, Windbreak/Shelterbelt Establishment, Silvopasture Establishment, Riparian Herbaceous Cover, Stream Habitat Improvement and Management, Pipeline, Heavy Use Area Protection, Spring Development, and Animal Trails and Walkways.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Grazing Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to implement essential conservation practices: Brush Management, Fencing, Firebreak, Forage Harvest Management, Grazing Land Mechanical Treatment, Herbaceous Weed Control, Nutrient Management, Forage and Biomass Planting, Prescribed Grazing, Range Planting, Access Control, and Watering Facilities. As addressed in the CAP criteria, the plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 110 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $4,616.40

Scenario Cost/Unit: $4,616.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, range conservation	1299	Conservation Activity Plan labor to study, plan the use and management of rangelands to maximize their use in a sustainable manner. Range managers may inventory soils, plants, and animals; develop resource management plans; identify monitoring methods and collect data using those methods to determine if resource management objectives are being met or if adjustments to management activities are needed. For example, they may help ranchers attain optimum livestock production by determining the number and kind of animals to graze, the grazing system to use, and the best season for grazing. Cost associated with this component includes overhead and benefits (market price).	Hour	$76.94	60	$4,616.40

Practice: 110 - Grazing Management Plan - Written

Scenario #5 - Grazing Management Plan Greater Than 5000 acres

Scenario Description:

Small agricultural operation with more than 5000 acres grazed land. Natural Resource Concern: Soil erosion, water quality, fish and wildlife, plant condition, and all other appropriate resource concerns.

Before Situation:

Producer has no plan or limited knowledge of management of livestock or other animals on grazed land resources. The producer currently manages animals without plan to address identified natural resource concerns. Producer is interested in management of animals to maximize profit margin, reduce costs, improve or address wildlife opportunities, and for other environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: In addition to the essential practices listed previously, addition practices to consider include: Channel Bank Vegetation, Prescribed Burning, Critical Area Planting, Pond, Windbreak/Shelterbelt Establishment, Silvopasture Establishment, Riparian Herbaceous Cover, Stream Habitat Improvement and Management, Pipeline, Heavy Use Area Protection, Spring Development, and Animal Trails and Walkways.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Grazing Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to implement essential conservation practices: Brush Management, Fencing, Firebreak, Forage Harvest Management, Grazing Land Mechanical Treatment, Herbaceous Weed Control, Nutrient Management, Forage and Biomass Planting, Prescribed Grazing, Range Planting, Access Control, and Watering Facilities. As addressed in the CAP criteria, the plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 110 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $5,385.80

Scenario Cost/Unit: $5,385.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, range conservation	1299	Conservation Activity Plan labor to study, plan the use and management of rangelands to maximize their use in a sustainable manner. Range managers may inventory soils, plants, and animals; develop resource management plans; identify monitoring methods and collect data using those methods to determine if resource management objectives are being met or if adjustments to management activities are needed. For example, they may help ranchers attain optimum livestock production by determining the number and kind of animals to graze, the grazing system to use, and the best season for grazing. Cost associated with this component includes overhead and benefits (market price).	Hour	$76.94	70	$5,385.80

Practice: 110 - Grazing Management Plan - Written

Scenario #66 - Grazing Management Plan 501 to 1500 acres

Scenario Description:

Small agricultural operation with 501 to 1500 acres grazed land. Natural Resource Concern: Soil erosion, water quality, fish and wildlife, plant condition, and all other appropriate resource concerns.

Before Situation:

Producer has no plan or limited knowledge of management of livestock or other animals on grazed land resources. The producer currently manages animals without plan to address identified natural resource concerns. Producer is interested in management of animals to maximize profit margin, reduce costs, improve or address wildlife opportunities, and for other environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: In addition to the essential practices listed previously, addition practices to consider include: Channel Bank Vegetation, Prescribed Burning, Critical Area Planting, Pond, Windbreak/Shelterbelt Establishment, Silvopasture Establishment, Riparian Herbaceous Cover, Stream Habitat Improvement and Management, Pipeline, Heavy Use Area Protection, Spring Development, and Animal Trails and Walkways.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Grazing Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to implement essential conservation practices: Brush Management, Fencing, Firebreak, Forage Harvest Management, Grazing Land Mechanical Treatment, Herbaceous Weed Control, Nutrient Management, Forage and Biomass Planting, Prescribed Grazing, Range Planting, Access Control, and Watering Facilities. As addressed in the CAP criteria, the plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 110 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number of plans

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,847.00

Scenario Cost/Unit: $3,847.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, range conservation	1299	Conservation Activity Plan labor to study, plan the use and management of rangelands to maximize their use in a sustainable manner. Range managers may inventory soils, plants, and animals; develop resource management plans; identify monitoring methods and collect data using those methods to determine if resource management objectives are being met or if adjustments to management activities are needed. For example, they may help ranchers attain optimum livestock production by determining the number and kind of animals to graze, the grazing system to use, and the best season for grazing. Cost associated with this component includes overhead and benefits (market price).	Hour	$76.94	50	$3,847.00

Practice: 112 - Prescribed Burning Plan - Written

Scenario #8 - Prescribed Burning Plan Less Than or Equal to 20 Acres

Scenario Description:

Non Industrial Private Forest Land, Pasture or Range Land typically less than or equal to 20 acres in size and is dominated by fire tolerant species that are competing with undesirable vegetation and accumulating fuel load. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition.

Before Situation:

Producer has no existing plan or an obsolete plan that is insufficient for current stand condition. Due to the size, landscape position, low to moderate fuel loads and presence of both natural firebreaks (i.e. – streams, lakes, etc.) and man-made firebreaks (i.e. – roads, farm paths, agricultural fields, etc.), few newly constructed firebreaks are needed to implement the prescribed burn. A Prescribed Burning Plan or Conservation Activity Plan is needed to enable the producer to apply for financial assistance through EQIP or other financial assistance programs in order to implement needed conservation practices. Associated Practices: 394, 383, 384, 528, 314, 315, 550, 644, 645, 659, 342, 647, 460, 643, 666, 595

After Situation:

After EQIP contract approval, participant has obtained services from a certified Technical Service Provider (TSP) for development of the “Prescribed Burning Plan” Conservation Activity Plan (CAP). The CAP criteria require the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Prescribed Burning Plan CAP is not considered a Forest Management Plan, a Reforestation Plan, a Forest Harvest Plan, or a Prescribed Grazing Plan, but should complement the needs of those plans if they exist and if desired by the decision maker. The CAP plan will fully describe all aspects of the prescribed burn including, but not limited to objectives of the burn (i.e. - site preparation, wildlife habitat, etc.), site conditions (i.e. - fuel load, fuel type, etc.), implementation strategies (i.e. - method of ignition, number of persons required, equipment needs, etc.), tolerable weather parameters (i.e. - wind direction, relative humidity, mixing height, etc.) and identification of Smoke Sensitive Areas. Additional CAP plan criteria are detailed in the Field Office Technical Guide and potentially state developed technical criteria.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $372.05

Scenario Cost/Unit: $372.05

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	5	$372.05

Practice: 112 - Prescribed Burning Plan - Written

Scenario #22 - Prescribed Burning Plan 21-100 Acres

Scenario Description:

Non Industrial Private Forest Land, Pasture or Range Land typically 21 to 100 acres in size and is dominated by fire tolerant species that are competing with undesirable vegetation and accumulating fuel load. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition.

Before Situation:

Producer has no existing plan or an obsolete plan that is insufficient for current stand condition. Due to the size, landscape position, low to moderate fuel loads and presence of both natural firebreaks (i.e. – streams, lakes, etc.) and man-made firebreaks (i.e. – roads, farm paths, agricultural fields, etc.), few newly constructed firebreaks are needed to implement the prescribed burn. A Prescribed Burning Plan or Conservation Activity Plan is needed to enable the producer to apply for financial assistance through EQIP or other financial assistance programs in order to implement needed conservation practices. Associated Practices: 394, 383, 384, 528, 314, 315, 550, 644, 645, 659, 342, 647, 460, 643, 666, 595

After Situation:

After EQIP contract approval, participant has obtained services from a certified Technical Service Provider (TSP) for development of the “Prescribed Burning Plan” Conservation Activity Plan (CAP). The CAP criteria require the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Prescribed Burning Plan CAP is not considered a Forest Management Plan, a Reforestation Plan, a Forest Harvest Plan, or a Prescribed Grazing Plan, but should complement the needs of those plans if they exist and if desired by the decision maker. The CAP plan will fully describe all aspects of the prescribed burn including, but not limited to objectives of the burn (i.e. - site preparation, wildlife habitat, etc.), site conditions (i.e. - fuel load, fuel type, etc.), implementation strategies (i.e. - method of ignition, number of persons required, equipment needs, etc.), tolerable weather parameters (i.e. - wind direction, relative humidity, mixing height, etc.) and identification of Smoke Sensitive Areas. Additional CAP plan criteria are detailed in the Field Office Technical Guide and potentially state developed technical criteria.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $595.28

Scenario Cost/Unit: $595.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	8	$595.28

Practice: 112 - Prescribed Burning Plan - Written

Scenario #23 - Prescribed Burning Plan 101-250 Acres

Scenario Description:

Non Industrial Private Forest Land, Pasture or Range Land typically 101 to 250 acres in size and is dominated by fire tolerant species that are competing with undesirable vegetation and accumulating fuel load. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition.

Before Situation:

Producer has no existing plan or an obsolete plan that is insufficient for current stand condition. Due to the size, landscape position, low to moderate fuel loads and presence of both natural firebreaks (i.e. – streams, lakes, etc.) and man-made firebreaks (i.e. – roads, farm paths, agricultural fields, etc.), few newly constructed firebreaks are needed to implement the prescribed burn. A Prescribed Burning Plan or Conservation Activity Plan is needed to enable the producer to apply for financial assistance through EQIP or other financial assistance programs in order to implement needed conservation practices. Associated Practices: 394, 383, 384, 528, 314, 315, 550, 644, 645, 659, 342, 647, 460, 643, 666, 595

After Situation:

After EQIP contract approval, participant has obtained services from a certified Technical Service Provider (TSP) for development of the “Prescribed Burning Plan” Conservation Activity Plan (CAP). The CAP criteria require the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Prescribed Burning Plan CAP is not considered a Forest Management Plan, a Reforestation Plan, a Forest Harvest Plan, or a Prescribed Grazing Plan, but should complement the needs of those plans if they exist and if desired by the decision maker. The CAP plan will fully describe all aspects of the prescribed burn including, but not limited to objectives of the burn (i.e. - site preparation, wildlife habitat, etc.), site conditions (i.e. - fuel load, fuel type, etc.), implementation strategies (i.e. - method of ignition, number of persons required, equipment needs, etc.), tolerable weather parameters (i.e. - wind direction, relative humidity, mixing height, etc.) and identification of Smoke Sensitive Areas. Additional CAP plan criteria are detailed in the Field Office Technical Guide and potentially state developed technical criteria.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $892.92

Scenario Cost/Unit: $892.92

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	12	$892.92

Practice: 112 - Prescribed Burning Plan - Written

Scenario #24 - Prescribed Burning Plan 251-500 Acres

Scenario Description:

Non Industrial Private Forest Land, Pasture or Range Land typically 251 to 500 acres in size and is dominated by fire tolerant species that are competing with undesirable vegetation and accumulating fuel load. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition.

Before Situation:

Producer has no existing plan or an obsolete plan that is insufficient for current stand condition. Due to the size, landscape position, low to moderate fuel loads and presence of both natural firebreaks (i.e. – streams, lakes, etc.) and man-made firebreaks (i.e. – roads, farm paths, agricultural fields, etc.), few newly constructed firebreaks are needed to implement the prescribed burn. A Prescribed Burning Plan or Conservation Activity Plan is needed to enable the producer to apply for financial assistance through EQIP or other financial assistance programs in order to implement needed conservation practices. Associated Practices: 394, 383, 384, 528, 314, 315, 550, 644, 645, 659, 342, 647, 460, 643, 666, 595

After Situation:

After EQIP contract approval, participant has obtained services from a certified Technical Service Provider (TSP) for development of the “Prescribed Burning Plan” Conservation Activity Plan (CAP). The CAP criteria require the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Prescribed Burning Plan CAP is not considered a Forest Management Plan, a Reforestation Plan, a Forest Harvest Plan, or a Prescribed Grazing Plan, but should complement the needs of those plans if they exist and if desired by the decision maker. The CAP plan will fully describe all aspects of the prescribed burn including, but not limited to objectives of the burn (i.e. - site preparation, wildlife habitat, etc.), site conditions (i.e. - fuel load, fuel type, etc.), implementation strategies (i.e. - method of ignition, number of persons required, equipment needs, etc.), tolerable weather parameters (i.e. - wind direction, relative humidity, mixing height, etc.) and identification of Smoke Sensitive Areas. Additional CAP plan criteria are detailed in the Field Office Technical Guide and potentially state developed technical criteria.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $1,190.56

Scenario Cost/Unit: $1,190.56

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	16	$1,190.56

Practice: 112 - Prescribed Burning Plan - Written

Scenario #25 - Prescribed Burning Plan 501-1000 Acres

Scenario Description:

Non Industrial Private Forest Land, Pasture or Range Land typically 501 to 1000 acres in size and is dominated by fire tolerant species that are competing with undesirable vegetation and accumulating fuel load. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition.

Before Situation:

Producer has no existing plan or an obsolete plan that is insufficient for current stand condition. Due to the size, landscape position, low to moderate fuel loads and presence of both natural firebreaks (i.e. – streams, lakes, etc.) and man-made firebreaks (i.e. – roads, farm paths, agricultural fields, etc.), few newly constructed firebreaks are needed to implement the prescribed burn. A Prescribed Burning Plan or Conservation Activity Plan is needed to enable the producer to apply for financial assistance through EQIP or other financial assistance programs in order to implement needed conservation practices. Associated Practices: 394, 383, 384, 528, 314, 315, 550, 644, 645, 659, 342, 647, 460, 643, 666, 595

After Situation:

After EQIP contract approval, participant has obtained services from a certified Technical Service Provider (TSP) for development of the “Prescribed Burning Plan” Conservation Activity Plan (CAP). The CAP criteria require the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Prescribed Burning Plan CAP is not considered a Forest Management Plan, a Reforestation Plan, a Forest Harvest Plan, or a Prescribed Grazing Plan, but should complement the needs of those plans if they exist and if desired by the decision maker. The CAP plan will fully describe all aspects of the prescribed burn including, but not limited to objectives of the burn (i.e. - site preparation, wildlife habitat, etc.), site conditions (i.e. - fuel load, fuel type, etc.), implementation strategies (i.e. - method of ignition, number of persons required, equipment needs, etc.), tolerable weather parameters (i.e. - wind direction, relative humidity, mixing height, etc.) and identification of Smoke Sensitive Areas. Additional CAP plan criteria are detailed in the Field Office Technical Guide and potentially state developed technical criteria.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $1,488.20

Scenario Cost/Unit: $1,488.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	20	$1,488.20

Practice: 112 - Prescribed Burning Plan - Written

Scenario #26 - Prescribed Burning Plan Greater Than 1000 Acres

Scenario Description:

Non Industrial Private Forest Land, Pasture or Range Land typically greater than 1000 acres in size and is dominated by fire tolerant species that are competing with undesirable vegetation and accumulating fuel load. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition.

Before Situation:

Producer has no existing plan or an obsolete plan that is insufficient for current stand condition. Due to the size, landscape position, low to moderate fuel loads and presence of both natural firebreaks (i.e. – streams, lakes, etc.) and man-made firebreaks (i.e. – roads, farm paths, agricultural fields, etc.), few newly constructed firebreaks are needed to implement the prescribed burn. A Prescribed Burning Plan or Conservation Activity Plan is needed to enable the producer to apply for financial assistance through EQIP or other financial assistance programs in order to implement needed conservation practices. Associated Practices: 394, 383, 384, 528, 314, 315, 550, 644, 645, 659, 342, 647, 460, 643, 666, 595

After Situation:

After EQIP contract approval, participant has obtained services from a certified Technical Service Provider (TSP) for development of the “Prescribed Burning Plan” Conservation Activity Plan (CAP). The CAP criteria require the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Prescribed Burning Plan CAP is not considered a Forest Management Plan, a Reforestation Plan, a Forest Harvest Plan, or a Prescribed Grazing Plan, but should complement the needs of those plans if they exist and if desired by the decision maker. The CAP plan will fully describe all aspects of the prescribed burn including, but not limited to objectives of the burn (i.e. - site preparation, wildlife habitat, etc.), site conditions (i.e. - fuel load, fuel type, etc.), implementation strategies (i.e. - method of ignition, number of persons required, equipment needs, etc.), tolerable weather parameters (i.e. - wind direction, relative humidity, mixing height, etc.) and identification of Smoke Sensitive Areas. Additional CAP plan criteria are detailed in the Field Office Technical Guide and potentially state developed technical criteria.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $1,785.84

Scenario Cost/Unit: $1,785.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	24	$1,785.84

Practice: 114 - Integrated Pest Management Plan - Written

Scenario #17 - IPM Management CAP Small-Specialty Less Than 50 Acres

Scenario Description:

Various on-farm land uses where pests are managed on smaller operations, including organic and specialty crop operations where more complicated pest management evaluations and solutions may be necessary. Current pest control activities cause environmental concerns with water quality and/or erosion. Natural Resource Concern: Water quality and all other appropriate resource concerns.

Before Situation:

Agricultural currently producer has no plan or limited knowledge of development or management of agricultural pests. The producer currently manages pests based upon pesticide label instructions, personal knowledge, or other local criteria. Producer is interested in management of pests and reduce the environmental impacts for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Integrated Pest Management, Crop Rotation, Cover Crop, Field Boarder, Filter Strip, Stripcropping, and Residue and Tillage management practices, or other application conservation practices cited tin the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Integrated Pest Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to utilize the following strategies: Prevention, Avoidance, Monitoring, and Suppression, which will be implemented through use of "Integrated Pest Management and may use one or more conservation practices and/or risk reduction strategies. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 114 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $1,962.50

Scenario Cost/Unit: $1,962.50

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	25	$1,962.50

Practice: 114 - Integrated Pest Management Plan - Written

Scenario #18 - IPM Management CAP Medium 51 - 250 Acres

Scenario Description:

Various on-farm land uses where pests are managed on a moderately-sized farm where IPM is to be applied. Current pest control activities cause environmental concerns with water quality and/or erosion. Natural Resource Concern: Water quality and all other appropriate resource concerns.

Before Situation:

Agricultural currently producer has no plan or limited knowledge of development or management of agricultural pests. The producer currently manages pests based upon pesticide label instructions, personal knowledge, or other local criteria. Producer is interested in management of pests and reduce the environmental impacts for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Integrated Pest Management, Crop Rotation, Cover Crop, Field Boarder, Filter Strip, Stripcropping, and Residue and Tillage management practices, or other application conservation practices cited tin the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Integrated Pest Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to utilize the following strategies: Prevention, Avoidance, Monitoring, and Suppression, which will be implemented through use of "Integrated Pest Management and may use one or more conservation practices and/or risk reduction strategies. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 114 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $2,512.00

Scenario Cost/Unit: $2,512.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	32	$2,512.00

Practice: 114 - Integrated Pest Management Plan - Written

Scenario #19 - IPM Management CAP Large - Greater Than 250 Acres

Scenario Description:

Various on-farm land uses where pests are managed on a larger farm where IPM strategies are to be applied. Current pest control activities cause environmental concerns with water quality and/or erosion. Natural Resource Concern: Water quality and all other appropriate resource concerns.

Before Situation:

Agricultural currently producer has no plan or limited knowledge of development or management of agricultural pests. The producer currently manages pests based upon pesticide label instructions, personal knowledge, or other local criteria. Producer is interested in management of pests and reduce the environmental impacts for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Integrated Pest Management, Crop Rotation, Cover Crop, Field Boarder, Filter Strip, Stripcropping, and Residue and Tillage management practices, or other application conservation practices cited tin the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Integrated Pest Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to utilize the following strategies: Prevention, Avoidance, Monitoring, and Suppression, which will be implemented through use of "Integrated Pest Management and may use one or more conservation practices and/or risk reduction strategies. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 114 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,925.00

Scenario Cost/Unit: $3,925.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	50	$3,925.00

Practice: 118 - Irrigation Water Management Plan - Written

Scenario #7 - Irrigation Water Management Conservation Activity Plan CAP

Scenario Description:

Agricultural operations supported with existing irrigation systems. Natural Resource Concern: Water quantity and all other appropriate resource concerns.

Before Situation:

Currently producer has no plan or limited knowledge for management of water application to meet crop needs and address identified resource concerns. The producer currently manages water application based upon personal knowledge, or other local criteria. Producer is interested in management of irrigation water to maximize yields, profit margin, reduce costs, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Irrigation Water Management (449); Irrigation System (442); Irrigation System, Surface & Subsurface (443); Irrigation Pipeline (430); Irrigation Ditch Lining (428); Irrigation Field Ditch (388); Irrigation Canal or Lateral (320); Structure for Water Control (587); Irrigation Reservoir (436); Irrigation System, Tailwater Recovery (447); Pumping Plant (533); Irrigation Land Leveling (464); Anionic Polyacrylamide (PM) Application (450); Salinity and Sodic Soil Management (590); Nutrient Management (590); Waste Utilization (633); or other applicable conservation practices in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Irrigation Water Management" conservation activity plan to control the volume, frequency, and rate of water for efficient irrigation and to address other resource concerns. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 118 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,216.85

Scenario Cost/Unit: $3,216.85

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	35	$3,216.85

Practice: 118 - Irrigation Water Management Plan - Written

Scenario #17 - Irrigation Water Management CAP with pump test

Scenario Description:

Agricultural operations supported with existing irrigation systems. Natural Resource Concern: Water quantity and all other appropriate resource concerns.

Before Situation:

Currently producer has no plan or limited knowledge for management of water application to meet crop needs and address identified resource concerns. The producer currently manages water application based upon personal knowledge, or other local criteria. The pump for the irrigation system is of unknown performance. Producer is interested in management of irrigation water to maximize yields, profit margin, reduce costs, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Irrigation Water Management (449); Irrigation System (442); Irrigation System, Surface & Subsurface (443); Irrigation Pipeline (430); Irrigation Ditch Lining (428); Irrigation Field Ditch (388); Irrigation Canal or Lateral (320); Structure for Water Control (587); Irrigation Reservoir (436); Irrigation System, Tailwater Recovery (447); Pumping Plant (533); Irrigation Land Leveling (464); Anionic Polyacrylamide (PM) Application (450); Salinity and Sodic Soil Management (590); Nutrient Management (590); Waste Utilization (633); or other applicable conservation practices in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Irrigation Water Management" conservation activity plan to control the volume, frequency, and rate of water for efficient irrigation and to address other resource concerns. Because a pump test was performed, a new pump that operates more efficiently and matches the irrigation system has been analyzed and could possibly be installed such that less water and energy are consumed. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 118 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Acre

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $5,055.05

Scenario Cost/Unit: $5,055.05

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	55	$5,055.05

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #77 - AgEMP Small, One Enterprise

Scenario Description:

Typical operation has either < 300 Acres < 300 AU Up to 2 irrigation pumps <20,000 sq ft of heater greenhouse, or A maple syrup enterprise One enterprise as defined in the ASABE S612 Standard on-farm energy audit standard. A small operation is as described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource: Energy Conservation

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer currently manages a small operation as described above. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $2,106.39

Scenario Cost/Unit: $2,106.39

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	9	$827.19
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$41.34	17	$702.78
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	$28.28	1.5	$42.42
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	$44.50	12	$534.00

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #78 - AgEMP Medium, One Enterprise

Scenario Description:

Typical operation has either 301 to 2500 Ac 301 to 1000 AU 3 to 6 Irrigation Pumps, or 20,001 to 40,000 sq ft heated greenhouse One enterprise as defined in the ASABE S612 Standard on-farm energy audit standard. A medium operation as described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource: Energy Conservation

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer currently manages a medium small operation with enterprise described above. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $2,615.60

Scenario Cost/Unit: $2,615.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	12	$1,102.92
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$41.34	18	$744.12
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	$28.28	2	$56.56
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	$44.50	16	$712.00

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #79 - AgEMP Large, One Enterprise

Scenario Description:

Typical operation has either > 2,500 Ac > 1000 AU More than 7 irrigation pumps or > 40,001 sq ft of heater greenhouse One enterprise as defined in the ASABE S612 Standard on-farm energy audit standard in combination with a large operation with one enterprise, one of which is described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource: Energy Conservation.

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer currently manages a large operation with enterprise described above. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,444.79

Scenario Cost/Unit: $3,444.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	19	$1,746.29
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$41.34	20	$826.80
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	$28.28	2.5	$70.70
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	$44.50	18	$801.00

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #80 - AgEMP Small, Two Enterprise

Scenario Description:

Typical operation has either <300 Ac <300 AU Up to 2 irrigation pumps, or <20,000 sq ft heated greenhouse Two enterprises as defined in the ASABE S612 Standard on-farm energy audit standard. A small operation as described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource: Energy Conservation

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any type small sized operation with two enterprises will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,251.99

Scenario Cost/Unit: $3,251.99

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	15	$1,378.65
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$41.34	21	$868.14
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	$28.28	2.5	$70.70
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	$44.50	21	$934.50

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #81 - AgEMP Medium Two Enterprises

Scenario Description:

Typical operation has either 301 to 2500 Ac 301 to 1000 AU 3 to 6 Irrigation Pumps, or 20,001 to 40,000 sq ft heated greenhouse Two enterprises as defined in the ASABE S612 Standard on-farm energy audit standard in combination with a medium operation, one of which is described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource: Energy Conservation

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any operation with two enterprises will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $4,397.59

Scenario Cost/Unit: $4,397.59

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	21	$1,930.11
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$41.34	25	$1,033.50
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	$28.28	3.5	$98.98
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	$44.50	30	$1,335.00

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #82 - AgEMP Large, Two Enterprises

Scenario Description:

Typical operation has either > 2,500 Ac > 1000 AU More than 7 irrigation pumps or > 40,001 sq ft of heater greenhouse Two enterprises as defined in the ASABE S612 Standard on-farm energy audit standard in combination with a large operation, one of which is described above . Multiple irrigation systems or a mixture of irrigation types may be counted as one of extra enterprises. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource: Energy Conservation

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any operation with two enterprises (complex or multiple irrigation systems can count as one of the extra enterprises) will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. An EMP is developed to assist an owner/operator in meeting all applicable local, tribal, State, and Federal water quality goals or regulations. Associated Practices: 449 Irrigation Water Management, 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $6,002.74

Scenario Cost/Unit: $6,002.74

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	32	$2,941.12
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$41.34	29	$1,198.86
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	$28.28	4.5	$127.26
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	$44.50	39	$1,735.50

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #83 - AgEMP Small, Three Enterprise

Scenario Description:

Typical operation has either < 300 Acres < 300 AU Up to 2 irrigation pumps <20,000 sq ft of heater greenhouse, or Three enterprises as defined in the ASABE S612 Standard on-farm energy audit standard in combination with a small operation, one of which is described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource Concern: Energy

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any type of operation with three enterprises will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 122 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,761.20

Scenario Cost/Unit: $3,761.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	18	$1,654.38
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$41.34	22	$909.48
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	$28.28	3	$84.84
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	$44.50	25	$1,112.50

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #84 - AgEMP Medium, Three Enterprise

Scenario Description:

Typical operation has either 301 to 2500 Ac 301 to 1000 AU 3 to 6 Irrigation Pumps, or 20,001 to 40,000 sq ft heated greenhouse Three enterprises as defined in the ASABE S612 Standard on-farm energy audit standard in combination with a medium operation, one of which is described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource Concern: Energy Conservation.

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any type of operation with three enterprises will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $4,906.80

Scenario Cost/Unit: $4,906.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	24	$2,205.84
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$41.34	26	$1,074.84
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	$28.28	4	$113.12
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	$44.50	34	$1,513.00

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #85 - AgEMP Large, Three Enterprise

Scenario Description:

Typical operation has either > 2,500 Ac > 1000 AU More than 7 irrigation pumps or > 40,001 sq ft of heater greenhouse Three enterprise as defined in the ASABE S612 Standard on-farm energy audit standard in combination with a large operation, one of which is described above. Multiple irrigation systems or a mixture of irrigation types may be counted as one of extra enterprises. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource Concern: Energy Conservation.

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any type operation with three enterprises (complex or multiple irrigation systems can count as one of the extra enterprises) will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 449 Irrigation Water Management, 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $6,603.86

Scenario Cost/Unit: $6,603.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	36	$3,308.76
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$41.34	30	$1,240.20
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	$28.28	5	$141.40
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	$44.50	43	$1,913.50

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #86 - AgEMP Small, Four Enterprises

Scenario Description:

Typical operation has either < 300 Acres < 300 AU Up to 2 irrigation pumps, or <20,000 sq ft of heater greenhouse Four enterprises as defined in the ASABE S612 Standard on-farm energy audit standard in combination with an small operation, one of which is described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource Concern: Energy Conservation.

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any operation with four enterprises will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $4,590.39

Scenario Cost/Unit: $4,590.39

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	25	$2,297.75
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$41.34	24	$992.16
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	$28.28	3.5	$98.98
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	$44.50	27	$1,201.50

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #87 - AgEMP 128 Medium, Four Enterprise

Scenario Description:

Typical operation has either 301 to 2500 Ac 301 to 1000 AU 3 to 6 Irrigation Pumps, or 20,001 to 40,000 sq ft heated greenhouse Four enterprise as defined in the ASABE S612 Standard on-farm energy audit standard in combination with an medium operation, one of which is described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource Concern: Energy Conservation.

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any type of operation with four or more enterprises will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 122 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $5,735.99

Scenario Cost/Unit: $5,735.99

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	31	$2,849.21
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$41.34	28	$1,157.52
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	$28.28	4.5	$127.26
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	$44.50	36	$1,602.00

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #88 - AgEMP 128 Large, Four Enterprise

Scenario Description:

Typical operation has either > 2,500 Ac > 1000 AU More than 7 irrigation pumps or > 40,001 sq ft of heater greenhouse Four enterprises as defined in the ASABE S612 Standard on-farm energy audit standard in combination with an large livestock operation, one of which is described above. . Multiple irrigation systems or a mixture of irrigation types may be counted as one of extra enterprises. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource Concern: Energy Conservation.

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any type of livestock operation with two non-livestock enterprises (complex or multiple irrigation systems can count as one of the extra enterprises) will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 449 Irrigation Water Management, 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $7,524.96

Scenario Cost/Unit: $7,524.96

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	44	$4,044.04
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$41.34	32	$1,322.88
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	$28.28	5.5	$155.54
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	$44.50	45	$2,002.50

Practice: 130 - Drainage Water Management Plan - Written

Scenario #11 - DWMP - Tile Map Available

Scenario Description:

A Drainage Water Management Plan (DWMP) will be developed on a relatively flat crop field with a patterned drainage system, where a map of the tile system is available. The DWMP will document soil, topographic, and drainage system maps of the site, and identify the number and location of water control structures that are needed to implement drainage water management according to Field Office Technical Guide standards. The DWMP will also provide guidelines for management of the water control structures to achieve desired resource outcomes.

Before Situation:

Producer has no plan for or knowledge of managing drainage water. The producer does not manage the field for the purpose of controlling water retention during the crop season and therefore crop yields are reduced. Existing ditches and/or tile drains on the cropland field currently conduct flow off field to waterways resulting in potential water quality resource concerns related to excessive nitrogen.

After Situation:

A certified Technical Service Provider (TSP) develops the "Drainage Water Management" conservation activity plan (CAP). The DWMP documents soil, topographic, and drainage system maps of the site, and identifies the number and location of water control structures that are needed to implement drainage water management according to Field Office Technical Guide standards. The DWMP also provides guidelines for management of the water control structures to achieve desired resource outcomes. The plan is ready for implementation with structural measures and management once the structures are installed. No actual benefits to resource concerns are achieved until the practices in the DWMP are implemented.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $2,732.47

Scenario Cost/Unit: $2,732.47

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, small surveying crew	1296	Conservation Activity Plan labor to perform surveying and mapping duties, usually under the direction of an engineer, surveyor, cartographer, or photogrammetrist to obtain data used for construction, mapmaking, boundary location, mining, or other purposes. May calculate mapmaking information and create maps from source data, such as surveying notes, aerial photography, satellite data, or other maps to show topographical features, political boundaries, and other features. Cost associated with this component includes two man field crew, equipment, vehicle, overhead, and miscellaneous supplies.	Hour	$108.19	8	$865.52
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	13	$996.71
Cap Labor, Survey and Mapping Technician	1591	Conservation Activity Plan labor to perform surveying and mapping duties, usually under the direction of an engineer, surveyor, cartographer, or photogrammetrist to obtain data used for construction, mapmaking, boundary location, mining, or other purposes. May calculate mapmaking information and create maps from source data, such as surveying notes, aerial photography, satellite data, or other maps to show topographical features, political boundaries, and other features. May verify accuracy and completeness of maps.	Hour	$54.39	16	$870.24

Practice: 130 - Drainage Water Management Plan - Written

Scenario #12 - DWMP - No Tile Map Available

Scenario Description:

A Drainage Water Management Plan (DWMP) will be developed on a relatively flat crop field with a patterned drainage system, where no map of the tile system is available. The DWMP will document soil, topographic, and drainage system maps of the site, and identify the number and location of water control structures that are needed to implement drainage water management according to Field Office Technical Guide standards. The DWMP will also provide guidelines for management of the water control structures to achieve desired resource outcomes.

Before Situation:

Producer has no plan for or knowledge of managing drainage water. The producer does not manage the field for the purpose of controlling water retention during the crop season and therefore crop yields are reduced. Existing ditches and/or tile drains on the cropland field currently conduct flow off field to waterways resulting in potential water quality resource concerns related to excessive nitrogen.

After Situation:

A certified Technical Service Provider (TSP) develops the "Drainage Water Management" conservation activity plan (CAP). The DWMP documents soil, topographic, and drainage system maps of the site, and identifies the number and location of water control structures that are needed to implement drainage water management according to Field Office Technical Guide standards. The DWMP also provides guidelines for management of the water control structures to achieve desired resource outcomes. The plan is ready for implementation with structural measures and management once the structures are installed. No actual benefits to resource concerns are achieved until the practices in the DWMP are implemented.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,259.83

Scenario Cost/Unit: $3,259.83

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, small surveying crew	1296	Conservation Activity Plan labor to perform surveying and mapping duties, usually under the direction of an engineer, surveyor, cartographer, or photogrammetrist to obtain data used for construction, mapmaking, boundary location, mining, or other purposes. May calculate mapmaking information and create maps from source data, such as surveying notes, aerial photography, satellite data, or other maps to show topographical features, political boundaries, and other features. Cost associated with this component includes two man field crew, equipment, vehicle, overhead, and miscellaneous supplies.	Hour	$108.19	8	$865.52
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	13	$996.71
Cap Labor, Survey and Mapping Technician	1591	Conservation Activity Plan labor to perform surveying and mapping duties, usually under the direction of an engineer, surveyor, cartographer, or photogrammetrist to obtain data used for construction, mapmaking, boundary location, mining, or other purposes. May calculate mapmaking information and create maps from source data, such as surveying notes, aerial photography, satellite data, or other maps to show topographical features, political boundaries, and other features. May verify accuracy and completeness of maps.	Hour	$54.39	16	$870.24
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	16	$527.36

Practice: 138 - Conservation Plan Supporting Organic Transition - Written

Scenario #12 - Conservation Plan Supporting Organic Transition CAP Crops and Livestock

Scenario Description:

Agricultural operation where producer will transition from conventional to organic to meet USDA National Organic Program (NOP) requirements. Natural Resource Concern: Soil Erosion, Water Quality, Plant Condition, and other identified natural resource concerns.

Before Situation:

Agricultural operation currently managed using traditional and conventional methods for farming and/or ranching mixed operation of crops and livestock. The producer currently manages operation based upon personal knowledge, or other local criteria. Producer is interested in transitioning part or all of the management unit to meet national USDA requirements for certified operation. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Refer to the NRCS Plan Criteria for conservation practices associated with operations transitioning to organic certification and typically needed to address identified natural resource concerns.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP to develop the "Conservation Plan Supporting Organic Transition" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to implement a system of conservation practices which assist the producer to transition from conventional farming or ranching to an organic production system with crops and livestock. The CAP plan will include conservation practices which address related resource concerns. CAP meets the basic quality criteria for the 138 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $5,750.25

Scenario Cost/Unit: $5,750.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	75	$5,750.25

Practice: 138 - Conservation Plan Supporting Organic Transition - Written

Scenario #13 - Conservation Plan Supporting Organic Transition CAP Crops or Livestock

Scenario Description:

Agricultural operation where producer will transition from conventional to organic to meet USDA National Organic Program (NOP) requirements. Natural Resource Concern: Soil Erosion, Water Quality, Plant Condition, and other identified natural resource concerns.

Before Situation:

Agricultural operation currently managed using traditional and conventional methods for farming with only crops. The producer currently manages operation based upon personal knowledge, or other local criteria. Producer is interested in transitioning part or all of the management unit to meet national USDA requirements for certified operation. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Refer to the NRCS Plan Criteria for conservation practices associated with operations transitioning to organic certification and typically needed to address identified natural resource concerns.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP to develop the "Conservation Plan Supporting Organic Transition" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to implement a system of conservation practices which assist the producer to transition from conventional farming or ranching to an organic production system with crops only. The CAP plan will include conservation practices which address related resource concerns. CAP meets the basic quality criteria for the 138 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $4,906.88

Scenario Cost/Unit: $4,906.88

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to producers to make decisions on the treatment of their soil, water, air, plant, animal, and energy resources. May instruct farmers, agricultural production managers, or ranchers in best ways to use crop rotation, contour plowing, or terracing to conserve soil and water; in the number and kind of livestock and forage plants best suited to particular ranges; and in range and farm improvements, such as fencing and reservoirs for stock watering.	Hour	$76.67	64	$4,906.88

Practice: 142 - Fish and Wildlife Habitat Plan - Written

Scenario #7 - Fish and Wildlife Habitat Management CAP

Scenario Description:

Various on-farm land uses. Natural Resource Concern: Fish and Wildlife, and other applicable resource concerns on an agricultural operation.

Before Situation:

Agricultural currently producer has no plan or knowledge of development or management of fish and/or wildlife habitat. The producer does not currently manage or enhance habitat to promote opportunities for fish and/or habitat. Within existing land uses, producer is interested in management of land or for establishment of new habitat for benefit of appropriate fish or wildlife species. Associated Practices: Applicable conservation practices cited in the CAP criteria and NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Fish and Wildlife Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for the primary fish/wildlife habitat resource concern and other applicable resource concerns and provides for opportunities to improve, restore, or enhance habitat that supports native and/or managed species. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 142 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,338.16

Scenario Cost/Unit: $3,338.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, biologist	1298	Conservation Activity Plan labor to study the origins, behavior, diseases, genetics, and life processes of animals and wildlife. May specialize in wildlife research and management. May collect and analyze biological data to determine the environmental effects of present and potential use of land and water habitats. Cost associated with this component includes overhead and benefits (market price).	Hour	$79.48	42	$3,338.16

Practice: 142 - Fish and Wildlife Habitat Plan - Written

Scenario #20 - Fish & Wildlife Habitat Management CAP (2 Land Uses)

Scenario Description:

Various on-farm land uses. Natural Resource Concern: Fish and Wildlife, and other applicable resource concerns on an agricultural operation. CAP addresses fish and wildlife habitat management relative to two land uses on the agricultural operation of which each land use is at least 20 acres in size.

Before Situation:

Agricultural currently producer has no plan or knowledge of development or management of fish and/or wildlife habitat. The producer does not currently manage or enhance habitat to promote opportunities for fish and/or habitat. Within existing land uses, producer is interested in management of land or for establishment of new habitat for benefit of appropriate fish or wildlife species. Associated Practices: Applicable conservation practices cited in the CAP criteria and NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Fish and Wildlife Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for the primary fish/wildlife habitat resource concern and other applicable resource concerns and provides for opportunities to improve, restore, or enhance habitat that supports native and/or managed species. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 142 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,497.12

Scenario Cost/Unit: $3,497.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, biologist	1298	Conservation Activity Plan labor to study the origins, behavior, diseases, genetics, and life processes of animals and wildlife. May specialize in wildlife research and management. May collect and analyze biological data to determine the environmental effects of present and potential use of land and water habitats. Cost associated with this component includes overhead and benefits (market price).	Hour	$79.48	44	$3,497.12

Practice: 142 - Fish and Wildlife Habitat Plan - Written

Scenario #36 - Fish & Wildlife Habitat Management CAP (Three Land Uses)

Scenario Description:

Various on-farm land uses. Natural Resource Concern: Fish and Wildlife, and other applicable resource concerns on an agricultural operation. CAP addresses fish and wildlife habitat management relative to two or more land uses on the agricultural operation of which at least three of the land uses are at least 20 acres in size

Before Situation:

Agricultural currently producer has no plan or knowledge of development or management of fish and/or wildlife habitat. The producer does not currently manage or enhance habitat to promote opportunities for fish and/or habitat. Within existing land uses, producer is interested in management of land or for establishment of new habitat for benefit of appropriate fish or wildlife species. Associated Practices: Applicable conservation practices cited in the CAP criteria and NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Fish and Wildlife Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for the primary fish/wildlife habitat resource concern and other applicable resource concerns and provides for opportunities to improve, restore, or enhance habitat that supports native and/or managed species. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 142 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $4,132.96

Scenario Cost/Unit: $4,132.96

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, biologist	1298	Conservation Activity Plan labor to study the origins, behavior, diseases, genetics, and life processes of animals and wildlife. May specialize in wildlife research and management. May collect and analyze biological data to determine the environmental effects of present and potential use of land and water habitats. Cost associated with this component includes overhead and benefits (market price).	Hour	$79.48	52	$4,132.96

Practice: 142 - Fish and Wildlife Habitat Plan - Written

Scenario #52 - Fish & Wildlife Habitat Management CAP (1 Land Use)

Scenario Description:

Various on-farm land uses. Natural Resource Concern: Fish and Wildlife, and other applicable resource concerns on an agricultural operation. CAP addresses fish and wildlife habitat management relative to only one land use on the agricultural operation.

Before Situation:

Agricultural currently producer has no plan or knowledge of development or management of fish and/or wildlife habitat. The producer does not currently manage or enhance habitat to promote opportunities for fish and/or habitat. Within existing land uses, producer is interested in management of land or for establishment of new habitat for benefit of appropriate fish or wildlife species. Associated Practices: Applicable conservation practices cited in the CAP criteria and NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Fish and Wildlife Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for the primary fish/wildlife habitat resource concern and other applicable resource concerns and provides for opportunities to improve, restore, or enhance habitat that supports native and/or managed species. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 142 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $2,861.28

Scenario Cost/Unit: $2,861.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, biologist	1298	Conservation Activity Plan labor to study the origins, behavior, diseases, genetics, and life processes of animals and wildlife. May specialize in wildlife research and management. May collect and analyze biological data to determine the environmental effects of present and potential use of land and water habitats. Cost associated with this component includes overhead and benefits (market price).	Hour	$79.48	36	$2,861.28

Practice: 146 - Pollinator Habitat Plan - Written

Scenario #12 - Pollinator Habitat Enhancement Plan CAP

Scenario Description:

Various on-farm land uses. Natural Resource Concern: Fish and Wildlife, Plant Condition, Soil Erosion, Water Quality on an agricultural operation.

Before Situation:

Agricultural producer currently has no plan or knowledge of development or management of pollinator habitat. The producer does not currently manage or enhance habitat to promote opportunities for pollinator habitat. Within existing land uses, producer may be interested in management of land or for establishment of new habitat for benefit of appropriate pollinator species. Associated Practices: 311, 322, 327, 328, 656, 332, 340, 342, 647, 386, 393, 412, 422, 603, 379, 512, 595, 338, 528, 550, 329, 643, 391, 390, 381, 395, 580, 585, 612, 645, 601, 659, 657, 644, 380, 650.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Pollinator Habitat Enhancement" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to improve, restore, or enhance flower-rich habitat that supports native and/or managed pollinator species. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 146 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,338.16

Scenario Cost/Unit: $3,338.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, biologist	1298	Conservation Activity Plan labor to study the origins, behavior, diseases, genetics, and life processes of animals and wildlife. May specialize in wildlife research and management. May collect and analyze biological data to determine the environmental effects of present and potential use of land and water habitats. Cost associated with this component includes overhead and benefits (market price).	Hour	$79.48	42	$3,338.16

Practice: 146 - Pollinator Habitat Plan - Written

Scenario #13 - Pollinator Habitat Enhancement Plan CAP - No Local TSP

Scenario Description:

Various on-farm land uses, No qualified TSP within 300 miles. Natural Resource Concern: Fish and Wildlife, Plant Condition, Soil Erosion, Water Quality on an agricultural operation.

Before Situation:

Agricultural producer currently has no plan or knowledge of development or management of pollinator habitat. The producer does not currently manage or enhance habitat to promote opportunities for pollinator habitat. Within existing land uses, producer may be interested in management of land or for establishment of new habitat for benefit of appropriate pollinator species. Associated Practices: 311, 322, 327, 328, 656, 332, 340, 342, 647, 386, 393, 412, 422, 603, 379, 512, 595, 338, 528, 550, 329, 643, 391, 390, 381, 395, 580, 585, 612, 645, 601, 659, 657, 644, 380, 650.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Pollinator Habitat Enhancement" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to improve, restore, or enhance flower-rich habitat that supports native and/or managed pollinator species. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 146 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $4,848.28

Scenario Cost/Unit: $4,848.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, biologist	1298	Conservation Activity Plan labor to study the origins, behavior, diseases, genetics, and life processes of animals and wildlife. May specialize in wildlife research and management. May collect and analyze biological data to determine the environmental effects of present and potential use of land and water habitats. Cost associated with this component includes overhead and benefits (market price).	Hour	$79.48	61	$4,848.28

Practice: 154 - IPM Herbicide Resistance Weed Conservation Plan - Written

Scenario #14 - IPM Herbicide Resistance Weed Management CAP Small-Specialty Less Than or Equal to 50 Acres

Scenario Description:

On-farm cropland where weeds are resistant to herbicides, including organic and specialty crop operations. Natural Resource Concerns: Water quality, soil erosion, soil condition, and plant condition are the appropriate resource concerns.

Before Situation:

Agricultural producer currently has no plan or limited knowledge for management of cropland weeds or for adaptive techniques to address herbicide resistant weeds. The producer currently manages cropland weeds based upon herbicide label instructions, personal knowledge, or other local criteria, and has not implemented strategies to diversity crop rotations and rotate herbicide modes of action for purpose of managing resistant weed spread and protecting soil quality and plant condition. Producer is interested in management of weeds to maximize yields, profit margin, reduce costs, address challenges in herbicide resistant weeds, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Integrated Pest Management, Crop Rotation, Cover Crop, Field Boarder, Filter Strip, Stripcropping, and Residue and Tillage management practices, or other application conservation practices cited tin the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Herbicide Resistance Weed" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to utilize the following strategies: Prevention, Avoidance, Monitoring, and Suppression, which will be implemented through use of Integrated Pest Management and may use one or more of the following conservation practices: Crop Rotation, Cover Crop, and Residue Management. Recommendations on crop system diversification and integration of herbicide mode of action rotation effective for weed control on recommended crop rotation are integral to the CAP. CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 154 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $2,355.00

Scenario Cost/Unit: $2,355.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	30	$2,355.00

Practice: 154 - IPM Herbicide Resistance Weed Conservation Plan - Written

Scenario #15 - IPM Herbicide Resistance Weed Management CAP Medium 51 - 250 Acres

Scenario Description:

On-farm cropland where weeds are resistant to herbicides, including organic and specialty crop operations. Natural Resource Concerns: Water quality, soil erosion, soil condition, and plant condition are the appropriate resource concerns.

Before Situation:

Agricultural producer currently has no plan or limited knowledge for management of cropland weeds or for adaptive techniques to address herbicide resistant weeds. The producer currently manages cropland weeds based upon herbicide label instructions, personal knowledge, or other local criteria, and has not implemented strategies to diversity crop rotations and rotate herbicide modes of action for purpose of managing resistant weed spread and protecting soil quality and plant condition. Producer is interested in management of weeds to maximize yields, profit margin, reduce costs, address challenges in herbicide resistant weeds, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Integrated Pest Management, Crop Rotation, Cover Crop, Field Boarder, Filter Strip, Stripcropping, and Residue and Tillage management practices, or other application conservation practices cited tin the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Herbicide Resistance Weed" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to utilize the following strategies: Prevention, Avoidance, Monitoring, and Suppression, which will be implemented through use of Integrated Pest Management and may use one or more of the following conservation practices: Crop Rotation, Cover Crop, and Residue Management. Recommendations on crop system diversification and integration of herbicide mode of action rotation effective for weed control on recommended crop rotation are integral to the CAP. CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 154 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $3,061.50

Scenario Cost/Unit: $3,061.50

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	39	$3,061.50

Practice: 154 - IPM Herbicide Resistance Weed Conservation Plan - Written

Scenario #16 - IPM Herbicide Resistance Weed Management CAP Large - Greater Than 250 Acres

Scenario Description:

On-farm cropland where weeds are resistant to herbicides, including organic and specialty crop operations. Natural Resource Concerns: Water quality, soil erosion, soil condition, and plant condition are the appropriate resource concerns.

Before Situation:

Agricultural producer currently has no plan or limited knowledge for management of cropland weeds or for adaptive techniques to address herbicide resistant weeds. The producer currently manages cropland weeds based upon herbicide label instructions, personal knowledge, or other local criteria, and has not implemented strategies to diversity crop rotations and rotate herbicide modes of action for purpose of managing resistant weed spread and protecting soil quality and plant condition. Producer is interested in management of weeds to maximize yields, profit margin, reduce costs, address challenges in herbicide resistant weeds, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Integrated Pest Management, Crop Rotation, Cover Crop, Field Boarder, Filter Strip, Stripcropping, and Residue and Tillage management practices, or other application conservation practices cited tin the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Herbicide Resistance Weed" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to utilize the following strategies: Prevention, Avoidance, Monitoring, and Suppression, which will be implemented through use of Integrated Pest Management and may use one or more of the following conservation practices: Crop Rotation, Cover Crop, and Residue Management. Recommendations on crop system diversification and integration of herbicide mode of action rotation effective for weed control on recommended crop rotation are integral to the CAP. CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 154 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: $4,710.00

Scenario Cost/Unit: $4,710.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	60	$4,710.00

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #33 - Data Collect Surface Last Year with two treatment sites

Scenario Description:

This practice scenario provides for the use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and two treatment sites with an average of 20 samples per year per station. The scenario requires the collection and analysis of edge-of-field water quality data along with a comprehensive report to statistically prove relationship between select conservation practices and water quality. The data will be transferred through semi-annual submittal and annual report and a comprehensive report of practice effectiveness. This scenario will be used in the last year of monitoring. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and two treatment sites. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201 to provide a comprehensive report of statistical testing of data collected during to complete monitoring period.

Feature Measure: Measuring site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $26,989.08

Scenario Cost/Unit: $26,989.08

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	150	$11,775.00
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	156	$5,141.76
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	$27.52	6	$165.12
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	30	$825.60

Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	30	$825.60

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #34 - Data Collect Surface Year 1-QAPP

Scenario Description:

This practice scenario provides for the design and use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and one treatment site with an average of 20 samples per year per station. The scenario requires the creation of a survey to site a monitoring station, preparation of monitoring plan and a quality assurance project plan to detail how data will be collected, handled and analyzed, provides for the data collection, analysis, semiannual report, and annual report. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP need to be prepared prior to installation under Edge-of-Field Water Quality Monitoring - System Installation (202). THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will not have a plan or quality assurance project plan prepared for installing equipment nor collecting data for sediment and nutrients leaving the edge of field.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual report, and annual report for one control and one treatment site. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP have been prepared prior to installation under Edge-of-Field Water Quality Monitoring - System Installation (202). The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring Sites

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $22,418.92

Scenario Cost/Unit: $22,418.92

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	100	$7,850.00
CAP Labor, small surveying crew	1296	Conservation Activity Plan labor to perform surveying and mapping duties, usually under the direction of an engineer, surveyor, cartographer, or photogrammetrist to obtain data used for construction, mapmaking, boundary location, mining, or other purposes. May calculate mapmaking information and create maps from source data, such as surveying notes, aerial photography, satellite data, or other maps to show topographical features, political boundaries, and other features. Cost associated with this component includes two man field crew, equipment, vehicle, overhead, and miscellaneous supplies.	Hour	$108.19	16	$1,731.04
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	20	$1,838.20
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	130	$4,284.80
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	$27.52	4	$110.08
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80

Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	20	$550.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	20	$550.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #35 - Data Collect Surface Year 1 - NO QAPP

Scenario Description:

This practice scenario provides for the use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and one treatment site. The scenario requires the collection and analysis of edge-of-field water quality data with an average sample collection of 20 per year for surface systems. The data will be transferred through semi-annual submittal and annual report which include some preliminary annual analysis. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP will be not prepared as this is for an existing monitoring system that has been accepted as meeting both Activity 201 and 202. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and one treatment site. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP have been prepared as part of an existing monitoring system installation where the QAPP and monitoring plan meets Activity 201 requirements and no major changes are needed to meet Activity 202 requirements. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring Site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $15,709.68

Scenario Cost/Unit: $15,709.68

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	60	$4,710.00
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	130	$4,284.80
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	$27.52	4	$110.08
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	20	$550.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	20	$550.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80

Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #36 - Data Collect Surface Year 2+

Scenario Description:

This practice scenario provides for the use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and one treatment site. The scenario requires the collection and analysis of edge-of-field water quality data with an average sample collection of 20 per year for surface systems. The data will be transferred through semi-annual submittal and annual report which include some preliminary annual analysis. This scenario will normally be used in year 2 to next to the last year of monitoring. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and one treatment site. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring Site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $15,709.68

Scenario Cost/Unit: $15,709.68

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	60	$4,710.00
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	130	$4,284.80
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	$27.52	4	$110.08
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	20	$550.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	20	$550.40

Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #37 - Data Collect Surface Last Year

Scenario Description:

This practice scenario provides for the use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and one treatment site with an average of 20 samples per year per station. The scenario requires the collection and analysis of edge-of-field water quality data along with a comprehensive report to statistically prove relationship between select conservation practices and water quality. The data will be transferred through semi-annual submittal and annual report and a comprehensive report of practice effectiveness. This scenario will be used in the last year of monitoring. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and one treatment site. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201 to provide a comprehensive report of statistical testing of data collected to complete monitoring period.

Feature Measure: Measuring Site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $18,849.68

Scenario Cost/Unit: $18,849.68

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	100	$7,850.00
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	130	$4,284.80
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	$27.52	4	$110.08
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	20	$550.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	20	$550.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80

Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	40	$1,100.80

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #42 - Data Collect Surface Year 1-QAPP with two treatment Sites

Scenario Description:

This practice scenario provides for the design and use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and two treatment sites with an average of 20 samples per year per station. The scenario requires the creation of a survey to site a monitoring station, preparation of monitoring plan and a quality assurance project plan to detail how data will be collected, handled and analyzed, provides for the data collection, analysis, semiannual report, and annual report. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP need to be prepared prior to installation under Edge-of-Field Water Quality Monitoring - System Installation (202). THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will not have a plan or quality assurance project plan prepared for installing equipment nor collecting data for sediment and nutrients leaving the edge of field.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual report, and annual report for one control and one treatment site. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP have been prepared prior to installation under Edge-of-Field Water Quality Monitoring - System Installation (202). The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring Sites

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $30,772.94

Scenario Cost/Unit: $30,772.94

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	130	$10,205.00
CAP Labor, small surveying crew	1296	Conservation Activity Plan labor to perform surveying and mapping duties, usually under the direction of an engineer, surveyor, cartographer, or photogrammetrist to obtain data used for construction, mapmaking, boundary location, mining, or other purposes. May calculate mapmaking information and create maps from source data, such as surveying notes, aerial photography, satellite data, or other maps to show topographical features, political boundaries, and other features. Cost associated with this component includes two man field crew, equipment, vehicle, overhead, and miscellaneous supplies.	Hour	$108.19	24	$2,596.56
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural products. Cost associated with this component includes overhead and benefits (market price).	Hour	$91.91	30	$2,757.30
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	156	$5,141.76
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	$27.52	6	$165.12
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20

Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	30	$825.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	30	$825.60

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #43 - Data Collect Surface Year 1 less QAPP (pre-install information) with two treatment sites

Scenario Description:

This practice scenario provides for the use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and two treatment sites. The scenario requires the collection and analysis of edge-of-field water quality data with an average sample collection of 20 per year for each surface system. The data will be transferred through semi-annual submittal and annual report, which include some preliminary annual analysis. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP will not be prepared as this is for an existing monitoring system be accepted as meeting both Activity 201 and 202. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and two treatment sites. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP have been prepared as part of an existing monitoring system installation where the QAPP and monitoring plan meets Activity 201 requirements and no major changes are needed to meet Activity 202 requirements. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $22,279.08

Scenario Cost/Unit: $22,279.08

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	90	$7,065.00
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	156	$5,141.76
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	$27.52	6	$165.12
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	30	$825.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	30	$825.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20

Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #44 - Data Collect Surface Year 2+ with two treatment sites

Scenario Description:

This practice scenario provides for the use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and two treatment sites. The scenario requires the collection and analysis of edge-of-field water quality data with an average sample collection of 20 per year for each surface system. The data will be transferred through semi-annual submittal and annual report, which include some preliminary annual analysis. This scenario will normally be used in year 2 to next to the last year of monitoring. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and two treatment sites. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $22,279.08

Scenario Cost/Unit: $22,279.08

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	90	$7,065.00
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	156	$5,141.76
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	$27.52	6	$165.12
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	30	$825.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	30	$825.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20

Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #45 - Data Collect Surface Last Year with two treatment sites

Scenario Description:

This practice scenario provides for the use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and two treatment sites with an average of 20 samples per year per station. The scenario requires the collection and analysis of edge-of-field water quality data along with a comprehensive report to statistically prove relationship between select conservation practices and water quality. The data will be transferred through semi-annual submittal and annual report and a comprehensive report of practice effectiveness. This scenario will be used in the last year of monitoring. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and two treatment sites. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201 to provide a comprehensive report of statistical testing of data collected during to complete monitoring period.

Feature Measure: Measuring site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $26,989.08

Scenario Cost/Unit: $26,989.08

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	150	$11,775.00
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	156	$5,141.76
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	$27.52	6	$165.12
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	30	$825.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	30	$825.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20

Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration – Preferred, or Total Suspended Solids. Includes materials only.	Each	$27.52	60	$1,651.20

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #24 - System Installation-Surface

Scenario Description:

This edge-of-field water quality monitoring system is applicable to a single control or treatment site that has a field defined with surface runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The component monitoring equipment are associated with a typical system for southern latitudes where winter time heating is not required for sampling. It will allow for installation of automated sampling data collection system with protective housing to reduce potential for vandalism, battery backup for operation during periods when electricity is down or solar panels are not creating an electrical current, and a berm or other directional flow structure to guide the runoff to a sampling flume.

Before Situation:

The agricultural operation prior to installing the monitoring equipment is guessing about the effects of the conservation system with regards to meeting practice intent of avoid, controlling, or trapping sediment and nutrients.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $19,624.10

Scenario Cost/Unit: $19,624.10

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	5	$392.50
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	60	$1,977.60
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will include all materials (electrical, controllers, service drops and etc). This cost will include material, labor and equipment.	Each	$472.52	1	$472.52
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all materials (electrical, controllers, and service drop, etc). This cost will include material, labor and equipment.	Kilowatt	$8,474.04	0.12	$1,016.88
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance irrigation water management and for Activity 202 water quality monitoring .	Each	$1,088.24	1	$1,088.24
Automated sampler with bottles and tubing	2606	Equipment used to collect the water samples on a flow weighted interval of 1.27 mm of runoff (volumetric depth) during a storm event.	Each	$2,413.21	1	$2,413.21
Connectors, cables, platform materials	2607	Miscellaneous (connectors, cables, berm, platform materials); Includes materials only.	Each	$2,201.83	1	$2,201.83
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitering	Each	$3,067.71	1	$3,067.71
Equipment shelter	2609	Building designed to house and reduce the risk of equipment damage from weather, animals, and vandalism.	Each	$774.22	1	$774.22

Pre-calibrated flow control structure-surface	2610	Pre-calibrated flow control structure-surface. Used for A202 water quality monitering	Each	$3,619.46	1	$3,619.46
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	$2,599.93	1	$2,599.93

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #25 - System Installation-Surface Cold Climate

Scenario Description:

This edge-of-field water quality monitoring system is applicable to a single control or treatment site that has a field defined with surface runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The component monitoring equipment are associated with a typical system for northern latitudes where winter time heating is required for sampling. It will allow for installation of automated sampling data collection system with protective housing to reduce potential for vandalism, battery backup for operation during periods when electricity is down or solar panels are not creating an electrical current, a calf hut or other structure with heat is required over the flume to allow sampling under northern latitude winter conditions, and a berm or other directional flow structure to guide the runoff to a sampling flume.

Before Situation:

The agricultural operation prior to installing the monitoring equipment is guessing about the effects of the conservation system with regards to meeting practice intent of avoid, controlling, or trapping sediment and nutrients. Nothing is known about the volume or mass of sediment and nutrients leaving the edge of field through the tile or other subsurface drainage system.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $21,050.55

Scenario Cost/Unit: $21,050.55

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	5	$392.50
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	60	$1,977.60
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will include all materials (electrical, controllers, service drops and etc). This cost will include material, labor and equipment.	Each	$472.52	1	$472.52
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all materials (electrical, controllers, and service drop, etc). This cost will include material, labor and equipment.	Kilowatt	$8,474.04	0.12	$1,016.88
Heater, high efficiency	1165	Natural gas, propane, or fuel oil unit heater or boiler and venting materials. Based on input kBTU/hour. Includes materials and shipping only.	1,000 BTU/Hour	$12.45	1	$12.45
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance irrigation water management and for Activity 202 water quality monitoring .	Each	$1,088.24	1	$1,088.24
Automated sampler with bottles and tubing	2606	Equipment used to collect the water samples on a flow weighted interval of 1.27 mm of runoff (volumetric depth) during a storm event.	Each	$2,413.21	1	$2,413.21
Connectors, cables, platform materials	2607	Miscellaneous (connectors, cables, berm, platform materials); Includes materials only.	Each	$2,201.83	1	$2,201.83

Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitering	Each	$3,067.71	1	$3,067.71
Equipment shelter	2609	Building designed to house and reduce the risk of equipment damage from weather, animals, and vandalism.	Each	$774.22	1	$774.22
Pre-calibrated flow control structure-surface	2610	Pre-calibrated flow control structure-surface. Used for A202 water quality monitering	Each	$3,619.46	1	$3,619.46
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	$2,599.93	1	$2,599.93
Equipment Shed	2617	Equipment Shed (10' x 10') made of steel applied over the sampling flume to allow collection of water samples during the winter in colder climates.	Each	$1,414.00	1	$1,414.00

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #28 - System Installation-Above And Below

Scenario Description:

This edge-of-field water quality monitoring system is applicable where a conservation practice has a pre- and post treatment area in the same field drainage with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The component monitoring equipment are associated with a typical system for southern latitudes where winter time heating is not required for sampling. It will allow for installation of automated sampling data collection system with protective housing to reduce potential for vandalism, battery backup for operation during periods when electricity is down or solar panels are not creating an electrical current, and a berm or other directional flow structure to guide the runoff to a sampling flume. The actual installation will different on the subsurface flow by allowing a smaller precalibrated flume with the addition of a velocity sensor meter as in the tile alternative.

Before Situation:

The agricultural operation prior to installing the monitoring equipment is guessing about the effects of the conservation system with regards to meeting practice intent of avoid, controlling, or trapping sediment and nutrients.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $29,577.20

Scenario Cost/Unit: $29,577.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	6	$471.00
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	60	$1,977.60
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will include all materials (electrical, controllers, service drops and etc). This cost will include material, labor and equipment.	Each	$472.52	1	$472.52
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all materials (electrical, controllers, and service drop, etc). This cost will include material, labor and equipment.	Kilowatt	$8,474.04	0.12	$1,016.88
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance irrigation water management and for Activity 202 water quality monitoring .	Each	$1,088.24	1	$1,088.24
Automated sampler with bottles and tubing	2606	Equipment used to collect the water samples on a flow weighted interval of 1.27 mm of runoff (volumetric depth) during a storm event.	Each	$2,413.21	2	$4,826.42
Connectors, cables, platform materials	2607	Miscellaneous (connectors, cables, berm, platform materials); Includes materials only.	Each	$2,201.83	1	$2,201.83
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitering	Each	$3,067.71	2	$6,135.42

Equipment shelter	2609	Building designed to house and reduce the risk of equipment damage from weather, animals, and vandalism.	Each	$774.22	2	$1,548.44
Pre-calibrated flow control structure-surface	2610	Pre-calibrated flow control structure-surface. Used for A202 water quality monitering	Each	$3,619.46	2	$7,238.92
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	$2,599.93	1	$2,599.93

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #29 - System Installation-Above And Below cold climate

Scenario Description:

This edge-of-field water quality monitoring system is applicable where a conservation practice has a pre- and post treatment area in the same field drainage with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The component monitoring equipment are associated with a typical system for northern latitudes where winter time heating is required for sampling. It will allow for installation of automated sampling data collection system with protective housing to reduce potential for vandalism, battery backup for operation during periods when electricity is down or solar panels are not creating an electrical current, a calf hut or other structure with heat is required over the flume to allow sampling under northern latitude winter conditions, and a berm or other directional flow structure to guide the runoff to a sampling flume. The actual installation will different on the subsurface flow by allowing a smaller pre-calibrated flume with the addition of a velocity sensor meter as in the tile alternative.

Before Situation:

The agricultural operation prior to installing the monitoring equipment is guessing about the effects of the conservation system with regards to meeting practice intent of avoid, controlling, or trapping sediment and nutrients. Nothing is known about the volume or mass of sediment and nutrients leaving the edge of field through the tile or other subsurface drainage system.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $35,030.03

Scenario Cost/Unit: $35,030.03

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	6	$471.00
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	60	$1,977.60
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will include all materials (electrical, controllers, service drops and etc). This cost will include material, labor and equipment.	Each	$472.52	1	$472.52
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all materials (electrical, controllers, and service drop, etc). This cost will include material, labor and equipment.	Kilowatt	$8,474.04	0.12	$1,016.88
Heater, high efficiency	1165	Natural gas, propane, or fuel oil unit heater or boiler and venting materials. Based on input kBTU/hour. Includes materials and shipping only.	1,000 BTU/Hour	$12.45	2	$24.90
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance irrigation water management and for Activity 202 water quality monitoring .	Each	$1,088.24	1	$1,088.24
Automated sampler with bottles and tubing	2606	Equipment used to collect the water samples on a flow weighted interval of 1.27 mm of runoff (volumetric depth) during a storm event.	Each	$2,413.21	2	$4,826.42

Connectors, cables, platform materials	2607	Miscellaneous (connectors, cables, berm, platform materials); Includes materials only.	Each	$2,201.83	1	$2,201.83
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitering	Each	$3,067.71	2	$6,135.42
Equipment shelter	2609	Building designed to house and reduce the risk of equipment damage from weather, animals, and vandalism.	Each	$774.22	2	$1,548.44
Pre-calibrated flow control structure-surface	2610	Pre-calibrated flow control structure-surface. Used for A202 water quality monitering	Each	$3,619.46	2	$7,238.92
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	$2,599.93	2	$5,199.86
Equipment Shed	2617	Equipment Shed (10' x 10') made of steel applied over the sampling flume to allow collection of water samples during the winter in colder climates.	Each	$1,414.00	2	$2,828.00

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #30 - System Installation-Retrofit 1

Scenario Description:

This edge-of-field water quality monitoring system is to retrofit an existing system that is being used in associated with the 799 interim practice or comparable system. The retrofit is applicable to a single control or treatment site that has a field defined with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The data represents the installation of an automated and manual backup rain gauge and back-up/solar power supply be added to existing system. It is actually to represent a cost for any system updates that has component costs of $2,400 or less as per the component costs in various scenarios.

Before Situation:

The agricultural operation prior to retrofit has an edge-of-field data collection system but it does not meet the present standards for accuracy or reliability as detailed in either or both of Activity 201 and Activity 202.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $3,497.50

Scenario Cost/Unit: $3,497.50

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	5	$392.50
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	16	$527.36
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will include all materials (electrical, controllers, service drops and etc). This cost will include material, labor and equipment.	Each	$472.52	1	$472.52
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all materials (electrical, controllers, and service drop, etc). This cost will include material, labor and equipment.	Kilowatt	$8,474.04	0.12	$1,016.88
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance irrigation water management and for Activity 202 water quality monitoring .	Each	$1,088.24	1	$1,088.24

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #31 - System Installation-Retrofit 2

Scenario Description:

This edge-of-field water quality monitoring system is to retrofit an existing system that is being used in associated with the 799 interim practice or comparable system. The retrofit is applicable to a single control or treatment site that has a field defined with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The data represents the installation of an automated and manual backup rain gauge, back-up/solar power supply, communications device, and depth (stage) sensor to be added to existing system. It is actually to represent a cost for any system updates that has component costs greater than $2,400 but less than or equal to $7,300 as per the component costs in various scenarios.

Before Situation:

The agricultural operation prior to retrofit has an edge-of-field data collection system but it does not meet the present standards for accuracy or reliability as detailed in either or both of Activity 201 and Activity 202.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $9,296.98

Scenario Cost/Unit: $9,296.98

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	5	$392.50
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	20	$659.20
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will include all materials (electrical, controllers, service drops and etc). This cost will include material, labor and equipment.	Each	$472.52	1	$472.52
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all materials (electrical, controllers, and service drop, etc). This cost will include material, labor and equipment.	Kilowatt	$8,474.04	0.12	$1,016.88
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance irrigation water management and for Activity 202 water quality monitoring .	Each	$1,088.24	1	$1,088.24
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitering	Each	$3,067.71	1	$3,067.71
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	$2,599.93	1	$2,599.93

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #32 - System Installation-Retrofit 3

Scenario Description:

This edge-of-field water quality monitoring system is to retrofit an existing system that is being used in associated with the 799 interim practice or comparable system. The retrofit is applicable to a single control or treatment site that has a field defined with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The data represents the installation of an automated and manual backup rain gauge, back-up/solar power supply, communications device, pre-calibrated flow control structure, and depth (stage) sensor to be added to existing system. It is actually to represent a cost for any system updates that has component costs greater than $7,300 but less than or equal to $10,500 as per the component costs in various scenarios. Anything above $10,500 will evaluated as a full system replacement as per scenarios for surface or tile (subsurface) drainage.

Before Situation:

The agricultural operation prior to retrofit has an edge-of-field data collection system but it does not meet the present standards for accuracy or reliability as detailed in either or both of Activity 201 and Activity 202.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $13,311.96

Scenario Cost/Unit: $13,311.96

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	5	$392.50
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	32	$1,054.72
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will include all materials (electrical, controllers, service drops and etc). This cost will include material, labor and equipment.	Each	$472.52	1	$472.52
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all materials (electrical, controllers, and service drop, etc). This cost will include material, labor and equipment.	Kilowatt	$8,474.04	0.12	$1,016.88
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance irrigation water management and for Activity 202 water quality monitoring .	Each	$1,088.24	1	$1,088.24
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitering	Each	$3,067.71	1	$3,067.71
Pre-calibrated flow control structure-surface	2610	Pre-calibrated flow control structure-surface. Used for A202 water quality monitering	Each	$3,619.46	1	$3,619.46
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	$2,599.93	1	$2,599.93

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #33 - System Installation-Retrofit Above and Below 1

Scenario Description:

This edge-of-field water quality monitoring system is to retrofit an existing above and below monitoring designed system that is being used in associated with the 799 interim practice or comparable system. The retrofit is applicable to an above and below system that has a field defined with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The data represents the installation of an automated and manual backup rain gauge and two back-up/solar power supply be added to existing paired system. It is actually to represent a cost for any system updates that has component costs of $3,300 or less as per the component costs in various scenarios.

Before Situation:

The agricultural operation prior to retrofit has an edge-of-field data collection system but it does not meet the present standards for accuracy or reliability as detailed in either or both of Activity 201 and Activity 202.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $5,041.75

Scenario Cost/Unit: $5,041.75

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	5	$392.50
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	32	$1,054.72
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will include all materials (electrical, controllers, service drops and etc). This cost will include material, labor and equipment.	Each	$472.52	1	$472.52
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all materials (electrical, controllers, and service drop, etc). This cost will include material, labor and equipment.	Kilowatt	$8,474.04	0.24	$2,033.77
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance irrigation water management and for Activity 202 water quality monitoring .	Each	$1,088.24	1	$1,088.24

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #34 - System Installation-Retrofit Above 2

Scenario Description:

This edge-of-field water quality monitoring system is to retrofit an existing above and below monitoring designed system that is being used in associated with the 799 interim practice or comparable system. The retrofit is applicable to an above and below system that has a field defined with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The data represents the installation of an automated and manual backup rain gauge, two back-up/solar power supplies, two communications devices, and two depth (stage) sensors to be added to existing paired system. It is actually to represent a cost for any system updates that has component costs greater than $3,300 but less than or equal to $13,200 as per the component costs in various scenarios.

Before Situation:

The agricultural operation prior to retrofit has an edge-of-field data collection system but it does not meet the present standards for accuracy or reliability as detailed in either or both of Activity 201 and Activity 202.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $16,455.53

Scenario Cost/Unit: $16,455.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	6	$471.00
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	32	$1,054.72
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will include all materials (electrical, controllers, service drops and etc). This cost will include material, labor and equipment.	Each	$472.52	1	$472.52
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all materials (electrical, controllers, and service drop, etc). This cost will include material, labor and equipment.	Kilowatt	$8,474.04	0.24	$2,033.77
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance irrigation water management and for Activity 202 water quality monitoring .	Each	$1,088.24	1	$1,088.24
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitering	Each	$3,067.71	2	$6,135.42
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	$2,599.93	2	$5,199.86

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #35 - System Installation-Retrofit Above 3

Scenario Description:

This edge-of-field water quality monitoring system is to retrofit an existing above and below monitoring designed system that is being used in associated with the 799 interim practice or comparable system. The retrofit is applicable to an above and below system that has a field defined with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The data represents the installation of an automated and manual backup rain gauge, two back-up/solar power supplies, two communications devices, two pre-calibrated flumes, and two depth (stage) sensors to be added to existing paired system. It is actually to represent a cost for any system updates that has component costs greater than $13,500 but less than or equal to $20,500 as per the component costs in various scenarios. Anything above a $20,500 will evaluated as a full system replacement as per scenarios for surface or tile (subsurface) drainage.

Before Situation:

The agricultural operation prior to retrofit has an edge-of-field data collection system but it does not meet the present standards for accuracy or reliability as detailed in either or both of Activity 201 and Activity 202.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $23,958.13

Scenario Cost/Unit: $23,958.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physical, biological, and mineralogical composition of soils as they relate to plant or crop growth. May classify and map soils and investigate effects of alternative practices on soil and crop productivity. May provide on-site consulting services to help growers troubleshoot nutrient and pest problems, establish appropriate agronomic sampling programs and implement management recommendations in a cost-effective and environmentally sound manner.	Hour	$78.50	6	$471.00
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$32.96	40	$1,318.40
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will include all materials (electrical, controllers, service drops and etc). This cost will include material, labor and equipment.	Each	$472.52	1	$472.52
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all materials (electrical, controllers, and service drop, etc). This cost will include material, labor and equipment.	Kilowatt	$8,474.04	0.24	$2,033.77
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance irrigation water management and for Activity 202 water quality monitoring .	Each	$1,088.24	1	$1,088.24
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitering	Each	$3,067.71	2	$6,135.42
Pre-calibrated flow control structure-surface	2610	Pre-calibrated flow control structure-surface. Used for A202 water quality monitering	Each	$3,619.46	2	$7,238.92
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	$2,599.93	2	$5,199.86

Practice: 297 - Feral Swine Management Conservation Activity - Interim

Scenario #3 - Assessment

Scenario Description:

200 acre tract (all land uses) on which feral swine have negatively impacted water quality (and associated aquatic organisms), soil health and vegetative conditions onsite. Wildlife habitat has been diminished due to feral swine out-competing native species for the same resources (hard and soft mast, tubers, invertebrates), as well as negatively affecting plant regeneration and production. Some species of native wildlife onsite are at risk from predation by feral swine as well as from diseases carried and transmitted either directly or indirectly by feral swine. This scenario should be selected in Year 1 only. The "Evaluation" Scenario should be selected for all subsequent years for which evaluation is necessary.

Before Situation:

Agricultural producer currently has no plan or knowledge of how resource concerns are caused or exacerbated by the presence of feral swine. Within existing land uses, the producer is interested in management of land to reduce impacts caused by feral swine and improve condition of natural resources.

After Situation:

As a result of feral swine surveillance (coupled with resource and inventory of baseline conditions), the nature and extent of natural resource concerns caused or exacerbated by the presence of feral swine are understood through resource assessments sufficient to inform development of a plan of action to meet quality criteria for all identified resource concerns. (Note: All management activities directly involving feral swine, such as trapping, euthanasia and disposal of carcasses will be the responsibility of the landowner, APHIS, or other partners. NRCS will have no role in these activities.)

Feature Measure: Management Site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $912.06

Scenario Cost/Unit: $912.06

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	18	$492.84
Materials						
Camera, Monitoring, Stationary	2638	Motion activated, 8 megapixel, weather proof, stationary camera with infrared capability for night operation. Trigger speed of 1 second or less with SD card storage up to 32 GB (not included in the price). Includes materials and shipping only.	Each	$139.74	3	$419.22

Practice: 297 - Feral Swine Management Conservation Activity - Interim

Scenario #5 - Evaluation

Scenario Description:

200 acre tract (all land uses) on which feral swine have negatively impacted water quality (and associated aquatic organisms), soil health and vegetative conditions onsite. Wildlife habitat has been diminished due to feral swine out-competing native species for the same resources (hard and soft mast, tubers, invertebrates), as well as negatively affecting plant regeneration and production. Some species of native wildlife onsite are at risk from predation by feral swine as well as from diseases carried and transmitted either directly or indirectly by feral swine.

Before Situation:

Agricultural producer is currently or soon will be implementing feral swine component of a conservation plan but the effectiveness of those activities in improving resource conditions is unknown.

After Situation:

Sufficient data and information have been collected to evaluate resource condition relative to baseline conditions and the effectiveness of the feral swine management actions. Necessary adaptive management actions are identified and implemented. (Note: All management activities directly involving feral swine, such as trapping, euthanasia and disposal of carcasses will be the responsibility of the landowner, APHIS, or other partners. NRCS will have no role in these activities.)

Feature Measure: Management Site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $1,095.20

Scenario Cost/Unit: $1,095.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	40	$1,095.20

Practice: 309 - Agrichemical Handling Facility

Scenario #5 - Agrichemical Handling Pad for mixing and loading

Scenario Description:

This practice scenario is an agrichemical handling facility for mixing and loading operations. This practice addresses water quality degradation and due to mis-handling, and mixing of agrichemicals where nutrients and/or chemicals are running off into surface waters or leaching into ground water. Associated practices: Heavy Use Area Protection (561), Diversion (362), Access Road (560), Pipeline (516), Pumping Plant for Water Control (533), Nutrient Management (590), Pest Management (595)

Before Situation:

Agrichemicals are improperly stored on the ground or next to a well. Operator mixes the agrichemicals and fills the sprayer tank next to a hydrant. Spills or overflows of agrichemicals contaminate the soil, runoff to surface waters and leaching to ground water.

After Situation:

This scenario is an agrichemical handling facility pad for mixing and loading operations. The average size of the agrichemical handling pad for mixing and loading is 16' x 40' with an application equipment length of 36 ft. The handling pad for mixing and loading operations is sized to contain the length of the agrichemical spray tank and its volume. Install a curbed reinforced concrete handling pad for mixing and loading. The concrete is sealed and sloped to a collection sump, containment of the pad is surrounded by sloped and ramped reinforced concrete. This practice will contain agrichemicals and prevent contamination of surface and ground water resources.

Feature Measure: Total Containment Area

Scenario Unit:: Square Foot

Scenario Typical Size: 640.0

Scenario Total Cost: $4,696.56

Scenario Cost/Unit: $7.34

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	12	$2,821.08
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$66.84	4	$267.36
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	4	$76.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	4	$102.72
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	$30.09	10	$300.90
Painting, concrete surface, impermeable	1497	Painting of concrete surfaces with an impermeable coating. Includes materials and application.	Square Foot	$0.98	640	$627.20
Pump, Sump, less than 1/4 HP	2582	Utility pump, corrosion-resistant, compact and portable, self-priming at 8 ft or more, 300 GPH at 10', electric, manually operated. Includes materials and shipping (pump and motor).	Each	$173.78	1	$173.78
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 313 - Waste Storage Facility

Scenario #9 - Dry stack, earthen floor, wood or concrete wall

Scenario Description:

This scenario consists of a dry stack facility with compacted earthen floor with wooden walls, posts and a concrete curb. This scenario is intended for dryer material such as poultry litter. The purpose of this practice is to properly store manure and other agricultural by-products until they can be hauled away from the site for proper disposal or utilization on land at agronomical rates. This scenario is applicable when geological, soil, and climate conditions are appropriate for earth floors and are allowed by state and local regulations. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water. Potential Associated practices: 342-Critical Area Planting, 362-Diversion, 561-Heavy Use Area Protection, 367-Roofs and Covers, 558-Roof Runoff Structure, 317-Composting Facility, 633-Waste Recycling, 634-Waste Transfer, 635-Vegetated Treatment Area

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and groundwater, in addition to the use of excessive amounts of fertilizers.

After Situation:

Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. The typical is 4,000 SqFt (40' x 100'). The earthen floor will be prepared by stripping the top 1' of soil and roller compacting it back into floor. Walls are 5' pressure treated wood (2" x 8" boards), 6" x 6" x 8' posts set 4' c-c with 6" concrete curbing. Walls allow for greater storage volume. (Wood walls are 4.5' with 0.5' high concrete curbing.) Walls are along three sides of the facility (both short dimensions and one long dimension). Site preparation includes excavation and compaction of top 1' of material, setting posts, and installing curbing and wooden walls.

Feature Measure: Square Foot Floor Area

Scenario Unit:: Square Foot

Scenario Typical Size: 4,000.0

Scenario Total Cost: $9,712.62

Scenario Cost/Unit: $2.43

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formless, non reinforced	36	Non reinforced concrete cast-in-placed without forms by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$115.86	5.5	$637.23
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$365.63	2	$731.26
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	148	$580.16
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$45.08	12	$540.96
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	$7.39	12	$88.68
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	$3.79	148	$560.92
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	90	$1,710.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	12	$260.52
Materials						
Dimension Lumber, Treated	1044	Treated dimension lumber with nominal thickness equal or less than 2". Includes lumber and fasteners	Board Foot	$0.93	1620	$1,506.60
Lumber, planks, posts and timbers, treated	1609	Treated dimension lumber with nominal thickness greater than 2". Includes lumber and fasteners. Does not include labor.	Board Foot	$1.54	1104	$1,700.16
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 314 - Brush Management

Scenario #1 - Mechanical

Scenario Description:

Removal of small woody vegetation. The practice entails the removal of brush by the use of mechanical cutter, chopper or other light equipment in order to reduce fuel loading and improve ecological site condition. Brush density has exceeded desired levels based on ecological site potential. It has been determined that the brush is a infestation. Typical unit is 40 acres.

Before Situation:

Area consist of excessive stands of shrub species degrading health and vigor of native herbaceous species promoting noxious and invasive species and degrading wildlife habitat.

After Situation:

Woody species are removed to achieve the desirable plant community based on species composition, structure, density, and canopy cover or height. Ecological site condition is progressing in an upward trend, hydrology and plant health and vigor is returning to near normal levels, and improved wildlife habitat.

Feature Measure: Acres treated

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $1,688.76

Scenario Cost/Unit: $42.22

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	$86.58	12	$1,038.96
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	12	$260.52
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24

Practice: 314 - Brush Management

Scenario #2 - Chemical, Spot

Scenario Description:

This Practice is for the implementation of brush management on range, pasture or native pasture using spot or Individual Plant Treatment (IPT). The typical method of control is application of herbicides (basal or foliar location) on selected individual plants.

Before Situation:

Brush species exceed desired levels resulting in degraded plant condition, loss of forage production, or degraded wildlife habitat. Densities of brush exceed levels indicated in the ecological site descriptions.

After Situation:

Brush has been treated to a level which results in improved plant condition, forage production, or wildlife habitat. The typical method of control is application of herbicides (basal or foliar location) on selected individual plants.

Feature Measure: Acres treated

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $2,382.86

Scenario Cost/Unit: $59.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	4	$262.36
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	4	$114.32
Materials						
Herbicide, Triclopyor	338	Refer to WIN-PST for product names and active ingredients. Materials and shipping	Acre	$44.20	40	$1,768.00
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	40	$52.40
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	2	$141.74

Practice: 314 - Brush Management

Scenario #5 - Chemical, Ground Applied, Heavy

Scenario Description:

Apply brush management on 40 acres of pasture thru the use of broadcast application of material using high cost chemical(s) to reduce or remove undesirable deciduous species (brush) in uplands and other areas not in or directly adjacent to streams, ponds, or wetlands. Heavy competition is defined as woody brush stocking more than 300 stems per acre or height greater than 48 inches.

Before Situation:

Plant, animal, or wildlife resource concerns associated with uplands and other areas not in or adjacent to stream, ponds, or wetland on pasture which are adversely affected by brush.

After Situation:

A 40 acre unit of pasture where reduction or removal of undesirable deciduous species have been accomplished by broadcast or spot treatment chemical application to address plant, animal, and wildlife resource concerns.

Feature Measure: Acres planned

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $2,491.09

Scenario Cost/Unit: $62.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	40	$248.00
Materials						
Herbicide, 2,4-D	330	Broadleaf herbicide labeled for cropland and pasture. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$9.42	40	$376.80
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	40	$1,513.20
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	40	$52.40
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 315 - Herbaceous Weed Treatment

Scenario #3 - Chemical, Ground Light

Scenario Description:

Land unit on which weed control would be beneficial in order to set back the plant community succession, improve the ecological condition, and improve forage conditions for domestic livestock or wildlife. The practice entails the eradication of (herbaceous weeds) vegetation by use of weed treatment using ground equipment to apply low cost chemicals, in order to eliminate noxious weeds, promote forage productivity, and improve ecological condition.

Before Situation:

Area consist of excessive stands of herbaceous weeds degrading health and vigor of native herbaceous species promoting noxious and invasive species and degrading wildlife habitat.

After Situation:

Herbaceous weeds are removed to achieve the desirable plant community based on species composition, structure, density, and canopy cover or height. Ecological site condition is progressing in an upward trend, hydrology and plant health and vigor is returning to near normal levels, and improved wildlife habitat.

Feature Measure: Acres treated

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: $555.26

Scenario Cost/Unit: $27.76

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	20	$124.00
Materials						
Herbicide, 2,4-D	330	Broadleaf herbicide labeled for cropland and pasture. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$9.42	20	$188.40
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	20	$26.20
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: 315 - Herbaceous Weed Treatment

Scenario #5 - Chemical, Ground Heavy

Scenario Description:

Land unit on which weed control would be beneficial in order to set back the plant community succession, improve the ecological condition, and improve forage conditions for domestic livestock or wildlife. The practice entails the eradication of (herbaceous weeds) vegetation by use of weed treatment using ground equipment to apply high cost chemicals, in order to eliminate noxious weeds, promote forage productivity, and improve ecological condition.

Before Situation:

Area consist of excessive stands of herbaceous weeds degrading health and vigor of native herbaceous species promoting noxious and invasive species and degrading wildlife habitat.

After Situation:

Herbaceous weeds are removed to achieve the desirable plant community based on species composition, structure, density, and canopy cover or height. Ecological site condition is progressing in an upward trend, hydrology and plant health and vigor is returning to near normal levels, and improved wildlife habitat.

Feature Measure: Acres treated

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: $1,123.46

Scenario Cost/Unit: $56.17

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	20	$124.00
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	20	$756.60
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	20	$26.20
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: 315 - Herbaceous Weed Treatment

Scenario #32 - Chemical, Ground Kudzu

Scenario Description:

Land unit on which kudzu control would be beneficial in order to restore the natural plant community succession, improve the ecological condition, and improve forage conditions for domestic livestock or wildlife or forestry. The practice entails the eradication of invasive kudzu by use of weed treatment using ground equipment to apply chemicals, in order to eliminate noxious weeds, promote forage productivity, and improve ecological condition. Due to 3 dimensional growth aspects of kudzu, requires additional application effort. Typical size is 20 acres. Chemical treatment must be performed for a minimum of 3 years.

Before Situation:

Area consist of excessive stands of kudzu degrading health and vigor of native herbaceous species promoting noxious and invasive species and degrading wildlife habitat. Grazing land, pastureland, forestland degradation, loss of beneficial wildlife habitat.

After Situation:

Kudzu is eradicated/controlled to achieve the desirable plant community based on species composition, structure, density, and canopy cover or height. Ecological site condition is progressing in an upward trend, hydrology and plant health and vigor is returning to near normal levels, and improved wildlife habitat.

Feature Measure: Acres treated

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: $3,088.68

Scenario Cost/Unit: $154.43

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	6	$132.12
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	20	$1,311.80
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	6	$171.48
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	20	$756.60
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	20	$26.20
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	4	$690.48

Practice: 316 - Animal Mortality Facility

Scenario #1 - Incineration less than 350 pound per day Chamber

Scenario Description:

This scenario consists of installing a manufactured Type IV incinerator designed to handle 350 lbs of average daily mortality for the species and size of the operation. System shall use high temperature (>1,300 degrees F) incineration with a secondary combustion or afterburner chamber prior to flue discharge. After determining average daily mortality in lbs, select smallest incinerator that meets capacity. Payment made per unit of actual chamber size obtained from manufacturers' product literature. This option is not typically least-cost. In most states a roofed static compost pile with concrete floor and bins would be considered least cost. Therefore consider reducing payment rate as per State Conservationist discretion. The purpose of the practice is to address resource concerns related to water quality degradation due to excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Air quality impacts due to odors will also be addressed, however, in non-attainment areas, certain states may require a higher level of processing such as gasification or other approved methods. Potential Associated Practices: Heavy Use Area Protection (561), Fence (382), Critical Area Planting (342), Access Road (560), Waste Storage Facility (313), Nutrient Management (590), Roofs and Covers (367), Critical Area Planting (342).

Before Situation:

Animal mortality is done in a manner that results in non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Improper operation results in odors and spread of pathogens from incomplete composting, incineration, or interaction with predators. No plan was formulated for both normal and catastrophic mortality events.

After Situation:

Animal mortality is being done in a manner that prevents non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Proper operation results in little to no odors, complete incineration, and protection from predators to minimize pathogen survival or spreading. An overall plan covers normal and catastrophic mortality events. Selected method for carcass treatment and disposal meet or are permitted by federal, state, and local laws, rules, regulation. Incinerator installed to handle 350 lbs per day average mortality for a small poultry operation. Included is a concrete slab to set the incinerator on. Ash materials to be stored in suitable containers until land disposal as per the nutrient management plan or landfilled.

Feature Measure: Mortality in pounds per day

Scenario Unit:: Pound

Scenario Typical Size: 350.0

Scenario Total Cost: $12,362.93

Scenario Cost/Unit: $35.32

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	4	$940.36
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	8	$16.56
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	1	$114.96
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	1	$19.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	1	$21.71
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	$30.50	4	$122.00
Fuel Tank, Anchored	1033	Fuel tank for operating incinerators and/or gasifiers. Materials only.	Gallon	$3.63	285	$1,034.55
Incinerator, 200 lbs/day	1624	Poultry and livestock incinerator with an approximate chamber capacity of 200 pounds per day. Includes equipment and after burner only.	Each	$9,837.14	1	$9,837.14
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 316 - Animal Mortality Facility

Scenario #2 - Incineration 350 to 850 pound per day chamber

Scenario Description:

This scenario consists of installing a manufactured Type IV incinerator designed to handle 350 to 850 lbs of average daily mortality for the species and size of the operation. Typically very large poultry or medium sized swine operations (700 lbs used) . System shall use high temperature (>1,300 degrees F) incineration with a secondary combustion or afterburner chamber prior to flue discharge. After determining average daily mortality in lbs, select smallest incinerator that meets capacity. Payment made per unit of actual chamber size obtained from manufacturers' product literature. This option is not typically least-cost. In most states a roofed static pile with concrete floor and bins would be considered least cost. Therefore consider reducing payment rate as per State Conservationist discretion. The purpose of the practice is to address resource concerns related to water quality degradation due to excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Air quality impacts due to odors are reduced, however, in non-attainment areas, certain states may require a higher level of processing such as gasification or other approved methods. Potential Associated Practices: Heavy Use Area Protection (561), Fence (382), Critical Area Planting (342), Access Road (560), Waste Storage Facility (313), Nutrient Management (590), Roofs and Covers (367), Critical Area Planting (342).

Before Situation:

Animal mortality is done in a manner that results in non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Improper operation results in odors and spread of pathogens from incomplete composting, incineration, or interaction with predators. No plan was formulated for both normal and catastrophic mortality events.

After Situation:

Animal mortality is being done in a manner that prevents non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Proper operation results in little to no odors, complete incineration, and protection from predators to minimize pathogen survival or spreading. In non-attainment areas, certain states may require a higher level of processing such as gasification or different methods. An overall plan covers normal and catastrophic mortality events. Selected method for carcass treatment and disposal meet or are permitted by federal, state, and local laws, rules, regulation. Incinerator installed to handle 700 lbs per day average mortality for a medium poultry or swine operation. Included is a concrete slab to set the incinerator on. Ash materials to be stored in suitable containers until land disposal as per the nutrient management plan or landfilled.

Feature Measure: Mortality in pounds per day

Scenario Unit:: Pound

Scenario Typical Size: 850.0

Scenario Total Cost: $14,187.78

Scenario Cost/Unit: $16.69

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	4	$940.36
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	8	$16.56
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	1	$114.96
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	1	$19.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	1	$21.71
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	$30.50	4	$122.00
Fuel Tank, Anchored	1033	Fuel tank for operating incinerators and/or gasifiers. Materials only.	Gallon	$3.63	285	$1,034.55
Incinerator, 400 lbs/day	1625	Poultry and livestock incinerator with an approximate chamber capacity of 400 pounds per day. Includes equipment and after burner only.	Each	$11,661.99	1	$11,661.99
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 316 - Animal Mortality Facility

Scenario #4 - Invessel Rotary Drum 250 lbs per day to 400 lbs per day

Scenario Description:

This scenario consists of installing a horizontal rotary drum to compost smaller poultry and swine facility mortality. It can handle between 250 and 400 lbs per day of mortality plus equal or higher volumes of carbon material (i.e. wood chips). A secondary composting storage area is required to finish materials. Payment quantity based on interior volume of rotary composter in cubic feet of smallest drum that can process daily mortality as per manufacturers' recommendations. The purpose of the practice is to address resource concerns related to water quality degradation due to excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Air quality impacts due to odors will also be addressed. Rotary Drums should be considered when the producer has very limited space for his/her animal mortality facility. If space is not the limiting factor, than scenarios 9 or 11 should be used. Potential Associated Practices: Roofs and Covers (367), Waste Storage Facility (313), Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Structure for Water Control (587), Diversion (362), Subsurface Drain (606), and Underground Outlet (620).

Before Situation:

Animal mortality is done in a manner that results in non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Improper operation results in odors and spread of pathogens from incomplete composting, incineration, or interaction with predators. No plan was formulated for both normal and catastrophic mortality events.

After Situation:

Proper operation results in little to no odors, complete composting, and protection from predators to minimize pathogen survival or spreading. An overall plan covers normal and catastrophic mortality events. Installed a 5' diameter by 22' long rotary drum on two concrete pads that can process 250 lbs of mortality per day. Drum rotation moves and mixes mortality and wood chips. Site preparation includes topsoil removal, gravel pad, and concrete pads and slab at two locations plus small floor and walls to complete composting. Input material reduced by 40-60 percent and put into 4' high, three sided, 20'x 20' concrete bin with 10'x20 concrete pad for secondary composting. Area can be protected by adding Roofs and Covers (367) standard.

Feature Measure: Pounds of animal mortality per day

Scenario Unit:: Pound

Scenario Typical Size: 250.0

Scenario Total Cost: $41,284.66

Scenario Cost/Unit: $165.14

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formless, non reinforced	36	Non reinforced concrete cast-in-placed without forms by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$115.86	4	$463.44
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	4	$940.36
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$365.63	6	$2,193.78
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	4	$8.28
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	$30.50	8	$244.00
Composter, drum, 12 CY	1627	12 CY drum composter unit. Total capacity range is 10-19 CY. Includes equipment, operation controls, and shipping. Labor not included.	Each	$37,293.06	1	$37,293.06
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	2	$141.74

Practice: 316 - Animal Mortality Facility

Scenario #9 - Static pile Wood Bins

Scenario Description:

This scenario consists of installing a group of small bins along one side and a long narrow bin on the backside of a concrete pad to compost poultry or small swine mortality in static pile(s) that have sufficient bulking material to allow natural aeration. Piles are turned to go through a second heat cycle prior to final land application. The roofed portion of the facility is addressed with Roofs and Covers (367). Size of facility based on daily mortality and sizing procedures accepted in particular state. Organic sites will require more frequent replacement of lumber. Potential Associated Practices: Roofs and Covers (367), Heavy Use Area Protection (561), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Structure for Water Control (587), Roof Runoff Structure (558), Diversion (362), Subsurface Drain (606), and Underground Outlet (620).

Before Situation:

Animal mortality is done in a manner that results in non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Improper operation results in odors and spread of pathogens from incomplete composting, incineration, or interaction with predators. No plan was formulated for both normal and catastrophic mortality events.

After Situation:

Animal mortality is being done in a manner that prevents non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Proper operation results in little to no odors, complete composting, and protection from predators to minimize pathogen survival or spreading. An overall plan covers normal and catastrophic mortality events. Selected method for carcass treatment and disposal meet or are permitted by federal, state, and local laws, rules, regulation. Install facility on a 18' x 40' concrete pad with 4 bins (5' H x 10' W x 6' Length) along the front side and one 8'w by 40' long secondary bin. Bin wall consists of a 1' concrete curb and 4' of treated lumber. Roofed portion is addressed under Roofs and Covers (367). Site preparation includes topsoil removal, installing 4" of gravel, setting posts , installing concrete slab, installing wooden walls and doors. Piles turned to go through a second heat cycle prior to final land application.

Feature Measure: Total Bin Area

Scenario Unit:: Square Foot

Scenario Typical Size: 720.0

Scenario Total Cost: $9,966.05

Scenario Cost/Unit: $13.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formless, non reinforced	36	Non reinforced concrete cast-in-placed without forms by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$115.86	3	$347.58
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	14	$3,291.26
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$365.63	3	$1,096.89
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	40	$82.80
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$45.08	7	$315.56
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	$7.39	7	$51.73
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	80	$2,190.40
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	7	$151.97
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	$30.50	9	$274.50
Dimension Lumber, Treated	1044	Treated dimension lumber with nominal thickness equal or less than 2". Includes lumber and fasteners	Board Foot	$0.93	880	$818.40
Lumber, planks, posts and timbers, treated	1609	Treated dimension lumber with nominal thickness greater than 2". Includes lumber and fasteners. Does not include labor.	Board Foot	$1.54	448	$689.92
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	2	$141.74

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 317 - Composting Facility

Scenario #1 - Composter, with concrete under bins wood or concrete only

Scenario Description:

The composting facility, with concrete under bins only, is installed to address water quality concerns and disease vectors resulting from improper waste disposal by providing a dedicated facility for storage and treatment, and by creating a compost product that can be used in multiple ways including land application for enrichment of crop ground. All animal mortality composting shall be done using Practice Standard 316 - Animal Mortality Facility. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Structure for water control (587), Diversion (362), Pipeline (516), Subsurface Drain (606), Heavy Use Area Protection (561), Roofs and Covers (367), Roof Runoff Structure (558), Waste Storage Facility (313), Waste Recycling (633), Waste Transfer (634), Underground Outlet (620) and Vegetative Treatment Area (635).

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and groundwater, in addition to the use of excessive amounts of fertilizers.

After Situation:

Manure, litter and other agricultural by-products are being controlled, by the collection at the source, and stored properly, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. Install facility on a 18' x 40' concrete pad with 4 bins (5' H x 10' W x 6' Length) along the front side and one 8'w by 40' long secondary bin. Bin wall consists of a 1' concrete curb and 4' of treated lumber. Roofed portion is addressed under Roofs and Covers (367). Site preparation includes topsoil removal, installing 4" of gravel, setting posts , installing concrete slab, installing wooden walls and doors. Piles turned to go through a second heat cycle prior to final land application. The bins are constructed on a 5" concrete slab used to store and stabilize manure, litter and other agricultural by-products from a four house complex on any farm.

Feature Measure: Square Foot Floor Area

Scenario Unit:: Square Foot

Scenario Typical Size: 720.0

Scenario Total Cost: $9,866.49

Scenario Cost/Unit: $13.70

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formless, non reinforced	36	Non reinforced concrete cast-in-placed without forms by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$115.86	3	$347.58
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	14	$3,291.26
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$365.63	3	$1,096.89
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	40	$156.80
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$45.08	7	$315.56
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	$7.39	7	$51.73
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	$3.79	40	$151.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	80	$1,520.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	7	$151.97
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	$30.50	9	$274.50
Dimension Lumber, Treated	1044	Treated dimension lumber with nominal thickness equal or less than 2". Includes lumber and fasteners	Board Foot	$0.93	880	$818.40
Lumber, planks, posts and timbers, treated	1609	Treated dimension lumber with nominal thickness greater than 2". Includes lumber and fasteners. Does not include labor.	Board Foot	$1.54	448	$689.92
Mobilization						

Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	2	$141.74
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 319 - On-Farm Secondary Containment Facility

Scenario #4 - Concrete Containment Wall

Scenario Description:

This practice scenario includes the installation of a reinforced concrete wall containment with a concrete slab around an existing storage tank. The purpose of the practice is to address resource concerns related to water quality degradation due to the excessive release of organics into ground and surface waters or excessive sediment and turbidity in surface waters. Due to topography, limited site space and/or geological conditions a fabricated structure is needed. Structure will provide an environmentally safe facility for handling and storage of these products. Associated practices may include: Heavy Use Area Protection (561).

Before Situation:

Existing agricultural operation that has single walled fuel/oil storage tank(s) not protected. The producer has developed an SPCC plan in accordance with EPA requirements, that requires an above ground secondary containment facility for on-farm oil products, in order to control the excessive release of organics into ground and surface waters, or to control the excessive sediment and turbidity in surface water.

After Situation:

This scenario is based on containment for a 4,700 gallon tank. The containment volume is designed for 125% of the tank volume (4,700 gallons X 125% = 5,875 gallons). Structure will provide an environmentally safe facility for handling and storage of these products. Typical containment dimensions are 196 sqft bottom x 6" thick slab with 6" thick x 4' tall formed sidewalls. Tanks will be moved or raised to install base materials. The fabricated containment structure will be installed in conformance with the design and specifications. The on-farm oil products stored on the farm have secondary containment of accidental release that controls the excessive release of organics, suspended sediments, and turbidity. Structure will provide an environmentally safe facility for handling and storage of these products.

Feature Measure: Volume of concrete in the wall

Scenario Unit:: Cubic Yard

Scenario Typical Size: 4.0

Scenario Total Cost: $4,003.29

Scenario Cost/Unit: $1,000.82

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	4.2	$987.38
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$365.63	4.3	$1,572.21
Crane, truck mounted, hydraulic, 12 ton	1734	12 ton capacity truck mounted hydraulic crane. Equipment cost only.	Hour	$92.50	2	$185.00
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	2	$51.36
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	$30.50	4.2	$128.10
Pipe, PVC, 2", SCH 40	976	Materials: - 2" - PVC - SCH 40 - ASTM D1785	Foot	$1.39	30	$41.70
Fuel Containment Facility, Gate valve 2 inch diameter	1735	Metal 2 inch diameter gate valve. Materials only.	Each	$280.75	1	$280.75
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 325 - High Tunnel System

Scenario #18 - High Tunnel, Low Wind or Snow Load, Intensive Sun

Scenario Description:

Use in areas with low expected snow and wind loads. Quonset-style (round) manufactured frame of tubular steel (30 x 72 ft.) covered with 4-year 6 mil plastic. Because of extensive sun intensity, shade cloth is provided. Costs are based on purchase of manufactured kit and landowner installation of structure. Structure must be installed to manufacturer's specifications. Associated practices might include CPS Roof Runoff Structure (588), Underground Outlet (620), Critical Area Planting (342), Mulching (484)

Before Situation:

Cropland where extension of the growing season is needed. Primary resource concern addressed will be plant health and vigor. High sun intensity shortens growing season, or decreases crop quality.

After Situation:

High Tunnel structure has been installed and the growing season has been extended for 1-4 months on average. Shade cloth protects crops from high intensity of sun, allowing crop production and quality to continue into summer months. Plant health and vigor is improved.

Feature Measure: Area of Tunnel Installed

Scenario Unit:: Square Foot

Scenario Typical Size: 2,160.0

Scenario Total Cost: $9,440.60

Scenario Cost/Unit: $4.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	71	$1,349.00
Materials						
Hoop House, quonset style, with shade cloth	2636	Includes the framework complete with all predrilled steel, hardware and instructions. Includes 6 mil 4-year polyethylene film to cover tunnel, polylock for sides and ends, and knitted shade cloth for a quonset style (round top) hoop house in southern climates. Materials and shipping only, does not include labor.	Square Foot	$3.51	2160	$7,581.60
Mobilization						
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	$1.02	500	$510.00

Practice: 327 - Conservation Cover

Scenario #63 - Native Species

Scenario Description:

This practice applies on land to be retired from agricultural production and on other lands needing permanent protective cover. This practice typically involves conversion from a clean-tilled (conventional tilled) intensive cropping system to permanent native vegetation (scenario includes native grass). The typical size of the practice is 50 acres. This practice scenario is typically used to reduce soil erosion, reduce soil quality degradation, improve water quality, develop wildlife habitat, and reduce air quality impacts. Applies to conventional or organic systems

Before Situation:

Crops such as corn, soybeans, or cotton may be conventionally or organically grown and harvested. Full width tillage is utilized, weeds controlled by cultivation and/or chemical application. Soil surface residue amounts average 10% or less. Soil erosion exceeds allowable tolerance, and sediment may be moving offsite into surface water degrading water quality. Soil quality (soil organic matter) declines over time as a result of tillage practices, low residue, and long periods of bare soil. Air quality may be impacted during field operations by the creation of particulates. The system provides little to no wildlife habitat.

After Situation:

The 327 Implementation Requirements have been developed for the site and applied. The land is covered with permanent native grass vegetation which reduces soil erosion and water/sediment runoff, and eliminates dust emissions which improves air quality. Plants sown for conservation cover may provide cover for beneficial insects and wildlife. This scenario does not apply to plantings for forage production or to critical area plantings.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $9,406.50

Scenario Cost/Unit: $188.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	150	$1,689.00
Mechanical weed control, Vegetation termination	957	Mechanical operations, Includes: Roller/crimper, mower, shredder, etc. Includes equipment, power unit and labor costs.	Acre	$20.76	100	$2,076.00
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	50	$1,079.00
Materials						
Two Species Mix, Warm Season, Native Perennial Grass	2325	Native, warm season perennial grass. Includes material and shipping only.	Acre	$91.25	50	$4,562.50

Practice: 327 - Conservation Cover

Scenario #65 - Pollinator Species

Scenario Description:

Permanent vegetation, including a mix of native grasses, legumes, and forbs (mix may also include non-native species), established on any land needing permanent vegetative cover that provides habitat for pollinators. Typical practice size is variable depending on site; this scenario uses 1 ac as the typical size. In addition to providing pollinator habitat, this practice scenario may also reduce sheet, rill, and wind erosion, improve soil quality, improve water quality, and improve air quality. The practice may also provide wildlife habitat. Practice applicable on cropland, odd areas, corners, etc. Applies to conventional or organic systems.

Before Situation:

Crops such as corn, soybeans, or cotton may be conventionally or organically grown and harvested. Full width tillage is utilized, weeds controlled by cultivation and/or chemical application. Soil surface residue amounts average 10% or less. Erosion exceeds tolerable rates and sediment may be moving offsite into surface water degrading water quality. Soil quality (soil organic matter) declines over time as a result of tillage practices, low residue, and long periods of bare soil. Air quality may be impacted during field operations by the creation of particulates. The system provides little to no wildlife or pollinator habitat.

After Situation:

The 327 Implementation Requirements have been developed for the site and applied. Land is covered with permanent pollinator habitat including a mix of native grasses, legumes, forbs (mix may also include non-native species). This practice may also have reduced soil erosion, reduced water/sediment runoff, and improved air quality as a result of the elimination of dust emissions. Plants sown for pollinator habitat may also provide cover for beneficial insects and wildlife. This scenario does not apply to critical area plantings.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $1,048.89

Scenario Cost/Unit: $1,048.89

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	3	$33.78
Mechanical weed control, Vegetation termination	957	Mechanical operations, Includes: Roller/crimper, mower, shredder, etc. Includes equipment, power unit and labor costs.	Acre	$20.76	2	$41.52
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Materials						
Six Species Mix, Native Forb	2334	Native forb mix. Includes material and shipping only.	Acre	$952.01	1	$952.01

Practice: 327 - Conservation Cover

Scenario #66 - Monarch Species Mix

Scenario Description:

Establish permanent vegetative cover for pollinator habitat according to state specifications. Typically used for high quality nectar and pollen species. Assumes seed/plugs, equipment and labor for seed bed prep/planting, and weed management during establishment. Used for conventional or organic land on small, intensive areas that are central to specialty crop production. Not typically used for large-scale plantings. This is applicable to both organic and non-organic conditions.

Before Situation:

Old hayfields that are mowed typically in the fall lack milkweed needed for monarchs. Other crops such as corn, soybeans, or cotton are conventionally grown and harvested. The system provides little to no wildlife or pollinator habitat.

After Situation:

The 327 Implementation Requirements have been developed and applied for the site. Land covered with permanent monarch habitat including a mix of milkweed species, native grasses, legumes, and forbs. Plants sown for monarch habitat may also provide cover for beneficial insects and wildlife.

Feature Measure: area planted

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $1,482.47

Scenario Cost/Unit: $1,482.47

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	3	$33.78
Mechanical weed control, Vegetation termination	957	Mechanical operations, Includes: Roller/crimper, mower, shredder, etc. Includes equipment, power unit and labor costs.	Acre	$20.76	2	$41.52
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Materials						
Specialized native grass and forb mix	2619	A mix of native grass and forbs to be used for specialized purposes such as wildlife (including pollinators) or ecosystem restoration, requiring species not readility available and/or difficult to produce and harvest. Includes material and shipping only	Acre	$989.71	1.4	$1,385.59

Practice: 328 - Conservation Crop Rotation

Scenario #74 - Basic Rotation Organic and Non-Organic

Scenario Description:

In this region this practice may be part of a conservation management system on both organic and non-organic operations to: 1) Reduce sheet, rill and wind erosion, 2) Maintain or increase soil health and organic matter content, 3) Reduce water quality degradation due to excess nutrients, 4) Improve soil moisture efficiency, 5) Reduce the concentration of salts and other chemicals from saline seeps, 6) Reduce plant pest pressures, 7) Provide feed and forage for domestic livestock, and 8) Provide food and cover habitat for wildlife, including pollinator forage, and nesting. This practice payment is provided to the producer for the time needed to plan and implement the logistics of changing the rotation to effectively implement a conservation crop rotation on a typical 200 acre cropland farm. No foregone income. Cost represents typical situations for conventional and organic producers.

Before Situation:

The rotation consists primarily of low residue producing row crops. Fields range from nearly flat to C and D slopes. Erosion, soil quality, and pest management are the primary concerns.

After Situation:

A rotation is established that provides additional high residue and/or perennial crops that may treat one or more of the following purposes: reduce sheet, rill and wind erosion, maintain or increase soil health and organic matter content, reduce water quality degradation due to excess nutrients, improve soil moisture efficiency, reduce the concentration of salts and other chemicals from saline seeps, reduce plant pest pressures, provide feed and forage for domestic livestock, or provide food and cover habitat for wildlife, including pollinator forage, and nesting.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,085.40

Scenario Cost/Unit: $10.85

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	30	$1,085.40

Practice: 328 - Conservation Crop Rotation

Scenario #75 - Specialty Crops Organic and Non-Organic

Scenario Description:

In this region a rotation of organic or non-organic specialty crops (fruits and vegetable) are produced as part of a conservation management system to treat one or more of the following resource concerns: 1) Reduce sheet, rill and wind erosion, 2) Maintain or increase soil health and organic matter content, 3) Reduce water quality degradation due to excess nutrients, 4) Improve soil moisture efficiency, 5) Reduce the concentration of salts and other chemicals from saline seeps, 6) Reduce plant pest pressures, 7) Provide feed and forage for domestic livestock, and 8) Provide food and cover habitat for wildlife, including pollinator forage, and nesting. This practice payment is provided to acquire the technical knowledge and skills necessary to effectively implement a conservation crop rotation on a typical 50 acre specialty crop farm. No foregone income. Cost represents typical situations for organic and non-organic producers.

Before Situation:

This rotation consisted of growing specialty crops. Fields range from nearly flat to B and C slopes. Erosion, soil quality, and pest management are the primary concerns.

After Situation:

The rotation established adds higher residue crop(s) to the rotation that will treat one or more of the following resource concerns on organic and non- organic farms: 1) Reduce sheet, rill and wind erosion, 2) Maintain or increase soil health and organic matter content, 3) Reduce water quality degradation due to excess nutrients, 4) Improve soil moisture efficiency, 5) Reduce the concentration of salts and other chemicals from saline seeps, 6) Reduce plant pest pressures, 7) Provide feed and forage for domestic livestock, and 8) Provide food and cover habitat for wildlife, including pollinator forage, and nesting.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $1,447.20

Scenario Cost/Unit: $28.94

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	40	$1,447.20

Practice: 329 - Residue and Tillage Management, No-Till

Scenario #10 - No-Till/Strip-Till

Scenario Description:

This practice typically involves conversion from a clean-tilled (conventional tilled) system to no-till or strip-till system on 100 acres of cropland. This involves managing the amount, orientation and distribution of crop and other plant residue on the soil surface year round while limiting soil-disturbing activities used to establish and harvest crops. The practice is used to reduce sheet and rill erosion, reduce wind erosion, improve soil quality, reduce CO2 losses from the soil, reduce energy use, increase plant available moisture and provide food and escape cover for wildlife. The no-till/strip-till system includes non-tillage types of weed control and may also include a period of no till fallow. System is applicable in both irrigated and non-irrigated fields of organic and non-organic operations.

Before Situation:

Row crops or small grains are grown and harvested. Full width tillage is performed prior to planting and weed control during crop production is typically cultivation and chemical application. Fields are disked immediately following harvest, with additional operations in some fields to facilitate drainage, seedbed preparation or additional weed control. Residue amounts after tillage operations average 10% or less, resulting in bare soil being exposed to wind erosion and/or intense rainfall. Any crop residue that is present degrades and sediment/nutrient runoff from fields increases during rainfall events. Sheet and rill erosion occurs with visible rills by spring. Soil health (soil organic matter) declines over time as a result of tillage practices, low residue, and long periods of bare soil. This system will typically have a negative Soil Conditioning Index (SCI) and a high Soil Tillage Intensity Rating (STIR).

After Situation:

The Implementation Requirements for 329 Residue Management, No Till is prepared and installed. Managing crop residue on the surface of a field (typical 100 acre) year around according to the 329 practice plan while limiting soil disturbing activities to those which place nutrients, and plant crops that meet the minimum criteria in the 329 practice standard. All crops are seeded/planted with a no-till drill or no-till/strip-till planter, which minimizes soil disturbance while establishing good seed-soil contact. All residues are to be maintained on the soil surface in a uniform distribution over the entire field and not burned or removed. Crop residues provide soil surface cover throughout the year. Runoff and erosion are reduced and no rills are visible on the soil surface. Wind erosion is reduced by standing residues and surface cover. Over time, soil health is improved due to the additional biomass (crop residues), ground cover, and soil infiltration. Crop residues and/or cover crop residues left on the soil surface may maximize weed control by increasing allelopathic and mulching effect, and provides cover for wildlife. The practice would require reducing soil disturbance and erosion and increasing biomass returned to the soil in sufficient amounts to achieve increased SCI and decreased STIR.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $2,032.00

Scenario Cost/Unit: $20.32

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	50	$1,079.00
Seeding Operation, No Till/Strip Till Planter	1230	No Till/Strip Till row planters for seeding. Includes all costs for equipment, power unit, and labor.	Acre	$19.06	50	$953.00

Practice: 333 - Amending Soil Properties with Gypsum Products

Scenario #15 - Gypsum greater than 1 ton rate

Scenario Description:

Gypsum application of more than one ton/acre rate (typical average 1.5 tons/acre) to improve surface water quality due to phosphorus, pathogens, and soil health (Ca/Mg ratio). Scenario to be used in combination with an implemented nutrient management plan. The producer will use gypsum to improve soil surface structure and reduce concentration of dissolved reactive phosphorus (DRP) in runoff. Scenario includes the cost of material, application, and supervisor/management time to establish and manage new application methodology, including rates, timing, and sequence of application with other nutrient materials (i.e., manures, bio-solids, and fertilizers). The addressed resource concern is water quality and soil health. Associated practices are Nutrient Management (590), Conservation Crop Rotation (328), Cover Crop (340), Residue and Tillage Management, No-till (329) and Residue and Tillage Management, Reduced Till (345).

Before Situation:

Cropland in continuous production having relatively low soil organic matter and moderately high clay content with application of manure with a risk of pathogens. Soil in these fields has poor soil structure and a high risk of phosphorus and pathogen runoff. The soils are susceptible to soil crusting and as a result of long term tillage systems have a high concentration of phosphorous near the soil surface. The combination of poor soil structure and high nutrient levels at the soil surface results in runoff events with high concentrations of DRP that may contribute to degraded water quality.

After Situation:

A determination based on existing soil samples used in normal nutrient management has been made. The Implementation Requirements for Amending Soil Properties with Gypsum (333) has been developed for the site. The application of gypsum to the field based on the existing soil samples will result in reduced runoff and improved runoff water quality. This condition over time in combination with an implemented nutrient management plan and supporting practices to improve soil health will improve surface water quality.

Feature Measure: Acres with a gypsum product appli

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $2,543.98

Scenario Cost/Unit: $63.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$10.75	40	$430.00
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	1	$36.18
Materials						
Gypsum, Ground Ag Grade, Bulk	1224	Agricultural grade quarry ground gypsum (CaCO4) for dispersive soil treatment. Materials and delivery only.	Ton	$34.63	60	$2,077.80

Practice: 333 - Amending Soil Properties with Gypsum Products

Scenario #16 - Gypsum less than 1 ton per acre

Scenario Description:

Gypsum application of less than or equal to one ton/acre rate (typical average 1 tons/acre) to improve surface water quality due to phosphorus, pathogens, and soil health (Ca/Mg ratio). Scenario to be used in combination with an implemented nutrient management plan. The producer will use gypsum to improve soil surface structure and reduce concentration of dissolved reactive phosphorus (DRP) in runoff. Scenario includes the cost of material, application, and management time to establish and manage new application methodology, including rates, timing, and sequence of application with other nutrient materials (i.e., manures, bio-solids, and fertilizers). . The addressed resource concern is water quality and soil health. Associated practices are Nutrient Management (590), Conservation Crop Rotation (328), Cover Crop (340), Residue and Tillage Management, No-till (329) and Residue and Tillage Management, Reduced Till (345).

Before Situation:

Cropland in continuous production having relatively low soil organic matter and moderately high clay content. Soil in these fields have poor soil structure and a high risk of phosphorus and pathogen runoff. The soils are susceptible to soil crusting and as a result of long term tillage systems have high concentration of phosphorous near the soil surface. The combination of poor soil structure and high nutrient levels at the soil surface results in runoff events with high concentrations of DRP that may contribute to degraded water quality.

After Situation:

A determination based on existing soil samples used in normal nutrient management has been made. The Implementation Requirements for Amending Soil Properties with Gypsum (333) has been developed for the site. The application of gypsum to the field is based on the existing soil samples and will result in reduce runoff and improve runoff water quality. This condition over time in combination with the implemented nutrient management plan and supporting practices to improve soil health will improve surface water quality.

Feature Measure: Acres with a gypsum product appli

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $1,505.08

Scenario Cost/Unit: $37.63

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$10.75	40	$430.00
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	1	$36.18
Materials						
Gypsum, Ground Ag Grade, Bulk	1224	Agricultural grade quarry ground gypsum (CaCO4) for dispersive soil treatment. Materials and delivery only.	Ton	$34.63	30	$1,038.90

Practice: 338 - Prescribed Burning

Scenario #2 - Forest Light

Scenario Description:

Write site specific burn plan and apply a prescribed burn according to this designed burn plan and NRCS Prescribed Burning (338) standard and specifications. Typically this will not be the first burn to occur on the site. This prescribed burn will safely consume small debris, herbaceous material and/or leaf litter.

Before Situation:

A primary burn has occurred within the last 5 years. Site has accumulation of small debris, herbaceous material and/or leaf litter. Typically this occurs in a open forest stand.

After Situation:

Litter, small debris and slash are consumed; small seedlings may be killed. Residual larger trees have little to no scorching. Post treatment fire danger is significantly reduced with increased herbaceous material rejuvenated for wildlife and erosion control.

Feature Measure: Acres planned

Scenario Unit:: Acre

Scenario Typical Size: 80.0

Scenario Total Cost: $3,376.87

Scenario Cost/Unit: $42.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	16	$352.32
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	16	$457.28
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	$2.45	16	$39.20
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	32	$876.16
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	12	$434.16
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	12	$1,010.16
Materials						
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	$4.39	15	$65.85
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	2	$141.74

Practice: 338 - Prescribed Burning

Scenario #3 - Forest Heavy

Scenario Description:

Write site specific burn plan and apply a prescribed burn according to this designed burn plan and NRCS Prescribed Burning (338) standard and specifications in order to safely control undesirable species, reduce fuel load, improve wildlife habitat, improve plant productivity and/or quality, facilitate grazing distribution and maintain ecological processes.

Before Situation:

Area to be burned has a heavy fuel load, undesirable species and/or may be overstocked. Site has little to no herbaceous material.

After Situation:

Area has been burned to remove competing brush and undesirable species, adjust density and forest slash. Some bare ground is exposed to promote herbaceous growth.

Feature Measure: Acres planned

Scenario Unit:: Acre

Scenario Typical Size: 80.0

Scenario Total Cost: $4,820.55

Scenario Cost/Unit: $60.26

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Equipment Installation						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$66.84	8	$534.72
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	16	$352.32
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	16	$457.28
Trailer, water tank	1598	Mobile 5,000 gal water tank mounted on a trailer. Equipment only. Does not include towing equipment.	Hour	$19.95	8	$159.60
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	$2.45	8	$19.60
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	32	$876.16
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	16	$1,346.88
Materials						
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	$4.39	20	$87.80
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	2	$141.74
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	1	$490.01

Practice: 340 - Cover Crop

Scenario #22 - Cover Crop - Basic (Organic and Non-organic)

Scenario Description:

Typically a small grain or legume (may also use forage sorghum, radishes, turnips, buckwheat, etc.) will be planted as a cover crop immediately after harvest of a row crop, and will be followed by a row crop that will utilize the residue as a mulch. This scenario assumes that seed will be planted with a drill. The cover crop should be allowed to generate as much biomass as possible, without delaying planting of the following crop. The cover crop will be terminated using an approved herbicide prior to planting the subsequent crop.

Before Situation:

Row crops such as corn, soybeans, or cotton are grown and harvested in mid-late fall. Fields are disked immediately following harvest, with rows in some fields being hipped for drainage. Residue amounts after harvest average 30% or less, resulting in bare soil being exposed to wind erosion and/or intense rainfall during the fall, winter, and early spring. Over the winter residue degrades and sediment/nutrient runoff from fields increases. Erosion exceeds soil loss tolerances. Runoff from the fields flows into streams, water courses or other water bodies causing degradation to the receiving waters. Soil health (soil organic matter) declines over time as a result of tillage practices, low residue crops, and long periods of bare soil.

After Situation:

Implementation Requirements according to Cover Crop (340) are prepared and implemented. Within 30 days after harvest of the row crop, fields are planted with a small grain or legume cover crop (may also use forage sorghum, radishes, turnips, buckwheat, etc.), typically rye or clover. The average field size is 40 acres. The cover crop is seeded with a drill. No additional fertilizer is applied with the cover crop. The cover crop provides soil cover by late fall, throughout the winter, and into the early spring. Runoff and erosion are reduced. Wind erosion is reduced by standing residues. The cover crop is terminated with an approved herbicide prior to spring planting as late as feasible to maximize plant biomass production. Over time, soil health is improved due to the additional biomass, ground cover, soil infiltration, and plant diversity introduced to the cropping system. Cover crop residues left on the surface may maximize weed control by increasing allelopathic and mulching effect.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $3,382.80

Scenario Cost/Unit: $84.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	40	$248.00
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	40	$863.20
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	40	$754.80
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	40	$1,516.80

Practice: 340 - Cover Crop

Scenario #23 - Cover Crop - Adaptive Management

Scenario Description:

The practice scenario is for the implementation of cover crops in small replicated plots to allow the producer to learn how to manage cover crops on their operation. Scenario includes implementing replicated strip trials on a field plot to evaluate, identify and implement a particular cover crop management strategy (e.g., cover crop vs no cover crop, multiple species vs, single species, evaluate different termination methods or timings, using a legume vs no legume for nitrogen credits). This will be done following the guidance in the NRCS Technical Note 10 - Adaptive Management.

Before Situation:

Row crops such as corn, soybeans, or cotton are grown and harvested in mid-late fall. Fields are disked immediately following harvest, with rows in some fields being hipped for drainage. Residue amounts after harvest average 30% or less, resulting in bare soil being exposed to wind erosion and/or intense rainfall. Over the winter residue degrades and sediment/nutrient runoff from fields increases. Sheet and rill erosion occurs with visible rills by spring. Runoff from the fields flows into streams, water courses or other water bodies causing degradation to the receiving waters. Soil health (soil organic matter) declines over time as a result of tillage practices, low residue crops, and long periods of bare soil. The producer is considering the use of cover crops but is unsure how to manage on their unique operation or is seeking a way to better manage cover crops in the operation.

After Situation:

Implementation Requirements for Cover Crop (340) will be prepared along with the Adaptive Management plan for the replicated cover crop plots and implemented. Installation of this scenario will result in establishment of a cover crop replicated plots to compare to different management strategies for cover crop management following the guidance in the Agronomy Technical Note 10 - Adaptive Management. Implementation involves establishing the replicated plots to evaluate one or more cover crop management strategies. The plot will consist of at least 4 replicated plots designed, laid out, managed and evaluated with the assistance of a consultant knowledgeable in cover crop management. Results are used to make cover crop management decisions to address erosion and water quality issues. Yields will be measured and statistically summarized following the procedures in Agronomy Technical Note 10 - Adaptive Management. The yields for each plot will be adjusted to the appropriate moisture content. This would be repeated for 3 years.

Feature Measure: Area planted

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $2,296.20

Scenario Cost/Unit: $2,296.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	10	$62.00
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	10	$215.80
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	20	$547.60
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	40	$760.00
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	10	$188.70
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	$52.21	10	$522.10

Practice: 340 - Cover Crop

Scenario #24 - Cover Crop - Multiple Species (Organic and Non-organic)

Scenario Description:

Typically the multi-species cover crop (two or more species) mix includes a small grain, a legume, and may include other species such as forage sorghum, radishes, turnips, buckwheat, etc.). This mix will address all the purposes of the Cover Crop (340) standard. Typically the cover crop is seeded immediately after harvest of a row crop, but may be inter-seeded into a row crop using a broadcast seeder, drill, or similar device. The cover crop will be followed by another row crop and will utilize the residue as a mulch. The cover crop should be allowed to generate as much biomass as possible without delaying planting of the following crop. The cover crop will be terminated using an approved herbicide or tillage prior to planting the subsequent crop and terminated per the NRCS Cover Crop Termination Guidelines.

Before Situation:

Row crops such as corn, soybeans, or cotton are grown and harvested in mid-late fall. Fields are disked immediately following harvest with rows in some fields being hipped for drainage. Residue amounts after harvest average 30% or less resulting in bare soil being exposed to wind erosion and/or intense rainfall during the fall, winter, and early spring. Over the winter residue degrades and sediment/nutrient runoff from fields increases. Erosion exceeds soil loss tolerances. Runoff from the fields flows into streams, water courses or other water bodies causing degradation to the receiving waters. Soil health (soil organic matter) declines over time as a result of tillage practices, low residue crops, and long periods of bare soil.

After Situation:

Implementation Requirements according to Cover Crop (340) are prepared and implemented. Within 30 days after the harvest of row crop, fields are planted with a multi-species (2 or more species) cover crop mix that generally includes a small grain, a legume, and may include other species such as forage sorghum, radishes, turnips, buckwheat, etc. The average field size is 40 acres. The cover crop is seeded with a drill, broadcast seeder, aerial broadcast, or other method. No additional fertilizer is applied with the cover crop. The cover crop provides soil cover by late fall, throughout the winter, and into the early spring. Runoff and erosion are reduced. Wind erosion is reduced by standing residues. The cover crop is terminated with an approved herbicide prior to spring planting as late as feasible to maximize plant biomass production. Over time, soil health is improved due to the additional biomass, ground cover, soil infiltration, and plant diversity introduced to the cropping system. Cover crop residues left on the surface may maximize weed control by increasing allelopathic and mulching effect.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $3,954.40

Scenario Cost/Unit: $98.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	40	$248.00
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	40	$863.20
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	40	$754.80
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	$52.21	40	$2,088.40

Practice: 342 - Critical Area Planting

Scenario #32 - Native or Introduced Vegetation - Normal Tillage (Organic and Non-Organic)

Scenario Description:

Establishment of permanent vegetation (Native and Introduced) on a site (both organic and non-organic) that is void or nearly void of vegetation due to a natural occurrence or a newly constructed conservation practice. Costs include seedbed preparation with typical tillage implements, grass/legume seed, companion crop, and fertilizer and lime with application.

Before Situation:

Areas that are void or nearly void of vegetation, resulting in bare soil being exposed to erosive processes. The exposed areas may be caused from recent natural occurrences (fire, flood, wind, etc.) or due to newly constructed conservation practices such as waterways, terraces, water and sediment basins or dams. The exposed areas will be subject to wind and water erosion that exceed soil loss tolerances. Runoff from the area flows into streams, water courses or other water bodies causing degradation to the receiving waters. The soil typically has a pH imbalance and low fertility.

After Situation:

Implementation Requirements are prepared and implemented according to the Critical Area Planting (342) standard. This typical 1.0 acre critical area is stabilized by applying fertilizer, lime and seed. Soil amendments will be incorporated at a depth of four to six inches to improve fertility and ensure establishment of permanent vegetative cover. The site will be stabilized, erosion reduced, and offsite damages reduced/eliminated.

Feature Measure: area seeded

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $218.66

Scenario Cost/Unit: $218.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	2	$22.52
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	1	$6.69
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Materials						
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.42	30	$12.60
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	60	$28.80
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.36	60	$21.60
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	$32.76	2	$65.52
One Species, Cool Season, Introduced Perennial Grass	2313	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	$31.57	1	$31.57

Practice: 342 - Critical Area Planting

Scenario #33 - Native and Introduced Vegetation - Moderate Grading

Scenario Description:

Establishment of permanent vegetation (native and introduced) on a site that is void or nearly void of vegetation due to a natural or human disturbance. Costs include a dozer for grading and shaping of small gullies, seedbed preparation with typical tillage implements, grass/legume seed, companion crop, and fertilizer and lime with application.

Before Situation:

Areas that are void or nearly void of vegetation, resulting in bare soil being exposed to erosive processes. The exposed areas may be caused from natural occurrences (fire, flood, etc.) or human disturbance. The exposed areas have visible rills and small gullies averaging 1 foot in depth and 1 foot in width that requires some moderate grading to prepare a seedbed. Runoff from the area flows into streams, water courses or other water bodies causing degradation to the receiving waters. The soil typically has a pH imbalance and low fertility.

After Situation:

Implementation Requirements are prepared and implemented according to the Critical Area Planting (342) standard.. This typical 1.0 acre critical area is stabilized by grading and shaping the small gullies with a dozer and then applying fertilizer, lime and seed. The site will be stabilized, erosion reduced, and offsite damages reduced/eliminated.

Feature Measure: area seeded

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $595.09

Scenario Cost/Unit: $595.09

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$66.84	4	$267.36
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	2	$22.52
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	1	$6.69
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	4	$102.72
Materials						
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.42	30	$12.60
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	60	$28.80
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.36	60	$21.60
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	$32.76	2	$65.52
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	1	$37.92

Practice: 342 - Critical Area Planting

Scenario #34 - Native or Introduced Vegetation - Heavy Grading (Organic and Non-Organic)

Scenario Description:

Establishment of permanent vegetation on a site that is void or nearly void of vegetation due to a natural or human disturbance. Costs include a dozer for grading and shaping of moderate to severe gullies, seedbed preparation with typical tillage implements, grass/legume seed, companion crop, and fertilizer and lime with application.

Before Situation:

Areas that are void or nearly void of vegetation, resulting in bare soil being exposed to erosive processes. The exposed areas may be caused from natural occurrences (fire, flood, etc.) or human disturbance. The exposed areas have visible rills and moderate to severe gullies averaging 3 feet in depth and 3 feet in width. Runoff from the area flows into streams, water courses or other water bodies causing degradation to the receiving waters. The soil typically has a pH imbalance and low fertility.

After Situation:

Implementation Requirements are prepared and implemented according to the Critical Area Planting (342) standard. This typical 1.0 acre critical area is stabilized by grading and shaping the moderate to severe gullies with a dozer and then applying fertilizer, lime and seed. The site will be stabilized, erosion reduced, and offsite damages reduced/eliminated.

Feature Measure: area seeded

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $979.46

Scenario Cost/Unit: $979.46

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$66.84	8	$534.72
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	2	$22.52
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	1	$6.69
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	8	$205.44
Materials						
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.42	30	$12.60
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	60	$28.80
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.36	60	$21.60
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	$32.76	2	$65.52
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	$52.21	1	$52.21

Practice: 345 - Residue and Tillage Management, Reduced Till

Scenario #49 - Residue and Tillage Management, Reduced Till

Scenario Description:

Mulch-till is managing the amount, orientation and distribution of crop and other plant residue on the soil surface year round while limiting the soil-disturbing activities used to grow crops in systems where the entire field surface is tilled by the planter/drill or tillage tools prior to planting. This practice includes tillage methods commonly referred to as mulch tillage, vertical tillage, chiseling and disking, or the use of high disturbance drills without additional tillage. It applies to stubble mulching on summer-fallowed land, to tillage for annually planted crops, to tillage for planted crops and to tillage for planting perennial crops. All residue shall be uniformly spread or managed over the surface throughout the critical erosion period(s). All residue shall be uniformly distributed over the entire field and not burned or removed. These periods of intensive tillage have led to excessive soil loss, often above the soil loss tolerance (T), due to the loss of crop residue on the soil surface. The NRCS erosion prediction model(s) will be used to review the farming operations and determine the amount of surface residue to manage throughout the rotation to keep soil loss below T. The producer will adopt a reduced till system to meet one or more of the practice purposes.

Before Situation:

Crops such as corn, soybeans, small grains, or cotton are grown and harvested. Fields are tilled immediately following harvest, with rows in some fields being hipped for drainage. Residue amounts after harvest average 30% or less, resulting in bare soil being exposed to wind erosion and/or intense rainfall during the fall, winter, and early spring. Over the winter residue degrades and sediment/nutrient runoff from fields increase. Sheet, rill and wind erosion occurs. Spring tillage and seedbed preparation activities occur as early as possible in the late winter and early spring. Runoff from the fields flows into streams, water courses or other water bodies causing water quality degradation. Soil health (soil organic matter) declines over time as a result of tillage practices, low residue monocultures, and long periods of bare soil.

After Situation:

The Implementation Requirements are prepared following the criteria in the 345 Residue and Tillage Management, Reduced Till conservation practice standard. Reduced till applies to all cropland and other lands where crops are planted. This scenario includes the use of a reduce till systems and high disturbance drills, such as a hoe drill, air seeder, or no-till drill that disturbs a large percentage of soil surface during the planting operation. The residue that remains on the soil surface provides soil cover during late fall, throughout the winter, and into the early spring. Runoff and water/wind erosion are reduced and water quality improves. Over time, soil health is improved due to less tillage, the additional biomass, ground cover, soil infiltration, and plant diversity in the cropping system.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $2,158.00

Scenario Cost/Unit: $21.58

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	100	$2,158.00

Practice: 350 - Sediment Basin

Scenario #2 - Embankment earthen basin with no pipe

Scenario Description:

An low hazard class embankment earthen sediment basin in an existing drainage way on a farm for purpose of trapping sediment and preserving the capacity of reservoirs, ditches, canals, diversions, waterways and streams and to prevent undesirable deposition on bottom lands and other developed lands. An earthen embankment will be constructed with an earthen auxiliary spillway, as designed. Resource concerns addressed include excessive suspended sediment and turbidity in surface water, damage from sediment deposition, and reduced capacity of conveyances by sediment deposition. Surface water causes the sediment (and potentially pesticides and nutrients) to be transported into the riparian areas and water bodies downstream.

Before Situation:

Disturbed areas on all land uses that have excessive erosion lead to deterioration of receiving waters due to excessive sedimentation.

After Situation:

The typical sediment basin is constructed by excavating the pool area, constructing the auxiliary spillway, preparing the foundation as designed, and using 1500 cubic yards to create an embankment. The embankment will be designed and constructed according the pond standard (378). The product of the storage times the effective height of the dam is less than 3,000. The effective height of the dam is 35 feet or less. The sediment storage capacity should be a minimum of 900 cubic feet per acre of disturbed area. The detention storage should be a minimum of 3600 cubic feet per acre of drainage area. The earthen auxiliary spillway will be constructed as designed based on Pond standard (378). No principal spillway will be used. Associated practice(s): Other practices that may need to be implemented along with sediment basin to address all of the site specific resource concerns include: Critical Area Planting (342) and Mulching (484) where necessary to prevent erosion following construction activities, Structure for Water Control (587) if using a dewatering device, Pond Sealing or Lining (521A,521B,521C,521D).

Feature Measure: Embankment volume

Scenario Unit:: Cubic Yard

Scenario Typical Size: 1,500.0

Scenario Total Cost: $3,730.34

Scenario Cost/Unit: $2.49

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	$125.35	23	$2,883.05
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	23	$590.64
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 350 - Sediment Basin

Scenario #3 - Embankment earthen basin with pipe

Scenario Description:

An low hazard class embankment earthen sediment basin in an existing drainage way on a farm for purpose of trapping sediment and preserving the capacity of reservoirs, ditches, canals, diversions, waterways and streams and to prevent undesirable deposition on bottom lands and other developed lands. An earthen embankment will be constructed with a principal spillway conduit and earthen auxiliary spillway, as designed. Resource concerns addressed include excessive suspended sediment and turbidity in surface water, damage from sediment deposition, and reduced capacity of conveyances by sediment deposition. Surface water causes the sediment (and potentially pesticides and nutrients) to be transported into the riparian areas and water bodies downstream.

Before Situation:

Disturbed areas on all land uses that have excessive erosion lead to deterioration of receiving waters due to excessive sedimentation.

After Situation:

The typical sediment basin is constructed by excavating the pool area, constructing the auxiliary spillway, preparing the foundation as designed, and using 1500 cubic yards to create an embankment. The embankment will be designed and constructed according the Pond standard (378). The product of the storage times the effective height of the dam is less than 3,000. The effective height of the dam is 35 feet or less. The sediment storage capacity should be a minimum of 900 cubic feet per acre of disturbed area. The detention storage should be a minimum of 3600 cubic feet per acre of drainage area. The principal spillway is created using an approved conduit material and filter diaphragm. The earthen auxiliary spillway will be constructed as designed based on Pond standard (378). Associated practice(s): Other practices that may need to be implemented along with sediment basin to address all of the site specific resource concerns include: Critical Area Planting (342) and Mulching (484) where necessary to prevent erosion following construction activities, Structure for Water Control (587) if using a dewatering device, Pond Sealing or Lining (521A,521B,521C,521D).

Feature Measure: Embankment volume

Scenario Unit:: Cubic Yard

Scenario Typical Size: 1,500.0

Scenario Total Cost: $8,241.69

Scenario Cost/Unit: $5.49

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$365.63	3	$1,096.89
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	$125.35	23	$2,883.05
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	8	$219.04
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	23	$590.64
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	$30.09	19.6	$589.76
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	$30.50	1.6	$48.80
Pipe, PVC, 10", SCH 80	1351	Materials: - 10" - PVC - SCH 80 - ASTM D1785	Foot	$21.01	98	$2,058.98
Pipe, PVC, 12", SCH 80	1352	Materials: - 12" - PVC - SCH 80 - ASTM D1785	Foot	$28.90	8	$231.20
Trash Guard, metal	1608	Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport.	Pound	$2.26	118	$266.68
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 351 - Well Decommissioning

Scenario #1 - Shallow Well less than 20 feet deep

Scenario Description:

A licensed well driller will seal and permanently close an inactive, abandoned, or unusable water well to prevent excess nutrients in surface and groundwater and to eliminate pesticides transported to surface and ground water. Well will be cleared of all equipment and materials. Residual water column must be treated with chlorine concentration of >50 ppm or according to local, State, Tribal, or Federal regulations.

Before Situation:

Shallow or hand dug well that is less than 20 feet deep and inactive, abandoned, or unusable and provides a potential conduit for pesticides or nutrients to enter an aquifer. Assume 30 inch diameter casing.

After Situation:

Well is permanently sealed to prevent potential contamination of aquifer. Procedures and sealing materials shall conform to ASTM D5299 and be compatible with all local, State, Tribal, and Federal requirements. Backfill shall be placed and compacted in a manner that minimizes segregation and bulking to prevent surface subsidence. Associated practices: 342 Critical Area Seeding

Feature Measure: Length of well casing

Scenario Unit:: Foot

Scenario Typical Size: 15.0

Scenario Total Cost: $2,621.89

Scenario Cost/Unit: $174.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	$5.17	2.7	$13.96
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	1	$166.20
Grout pump	1334	Grout pump with tremie pipe. Equipment and power unit costs. Labor not included.	Hour	$15.71	2	$31.42
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Materials						
Grout, cement	1333	Cement grout meeting ASTM specifications for well sealing. Includes both neat-cement grout and bentonite gout mixtures. Includes materials, equipment and labor to place.	Cubic Yard	$681.27	2.7	$1,839.43
Chlorine	1335	Liquid chlorine bleach. Includes materials only.	Gallon	$2.82	1	$2.82
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 351 - Well Decommissioning

Scenario #2 - Shallow Well greater than 20 feet deep

Scenario Description:

A licensed well driller will seal and permanently close an inactive, abandoned, or unusable water well to prevent excess nutrients in surface and groundwater and to eliminate pesticides transported to surface and ground water. Well will be cleared of all equipment and materials. Residual water column must be treated with chlorine concentration of >50 ppm or according to local, State, Tribal, or Federal regulations.

Before Situation:

Shallow or hand dug well that is greater than 20 feet deep and inactive, abandoned, or unusable and provides a potential conduit for pesticides or nutrients to enter an aquifer. Assume 30 inch diameter casing.

After Situation:

Well is permanently sealed to prevent potential contamination of aquifer. Procedures and sealing materials shall conform to ASTM D5299 and be compatible with all local, State, Tribal, and Federal requirements. Backfill shall be placed and compacted in a manner that minimizes segregation and bulking to prevent surface subsidence. Associated practices: 342 Critical Area Seeding

Feature Measure: Length of well casing

Scenario Unit:: Foot

Scenario Typical Size: 30.0

Scenario Total Cost: $4,996.45

Scenario Cost/Unit: $166.55

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	$5.17	5.5	$28.44
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	3	$498.60
Grout pump	1334	Grout pump with tremie pipe. Equipment and power unit costs. Labor not included.	Hour	$15.71	3	$47.13
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	3	$82.14
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	3	$77.04
Materials						
Grout, cement	1333	Cement grout meeting ASTM specifications for well sealing. Includes both neat-cement grout and bentonite gout mixtures. Includes materials, equipment and labor to place.	Cubic Yard	$681.27	5.5	$3,746.99
Chlorine	1335	Liquid chlorine bleach. Includes materials only.	Gallon	$2.82	1	$2.82
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 351 - Well Decommissioning

Scenario #3 - Drilled well less than 300 feet deep with casing removed

Scenario Description:

A licensed well driller will seal and permanently close an inactive, abandoned, or unusable water well to prevent excess nutrients in surface and groundwater and to eliminate pesticides transported to surface and ground water. Well will be cleared of all equipment and materials. Residual water column must be treated with chlorine concentration of >50 ppm or according to local, State, Tribal, or Federal regulations.

Before Situation:

Drilled well that is less than 300 feet deep and inactive, abandoned, or unusable and provides a potential conduit for pesticides or nutrients to enter an aquifer. Typical well has 6 inch diameter casing.

After Situation:

Well is permanently sealed to prevent potential contamination of aquifer. Procedures and sealing materials shall conform to ASTM D5299 and be compatible with all local, State, Tribal, and Federal requirements. Backfill shall be placed and compacted in a manner that minimizes segregation and bulking to prevent surface subsidence. Associated practices: 342 Critical Area Seeding

Feature Measure: Length of well casing

Scenario Unit:: Foot

Scenario Typical Size: 200.0

Scenario Total Cost: $8,614.53

Scenario Cost/Unit: $43.07

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	8	$1,329.60
Grout pump	1334	Grout pump with tremie pipe. Equipment and power unit costs. Labor not included.	Hour	$15.71	8	$125.68
Hydrofracture Rig with Operator	1818	Equipment and power unit costs including mechanical packer equipment. Labor included.	Hour	$496.13	8	$3,969.04
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	8	$205.44
Materials						
Grout, cement	1333	Cement grout meeting ASTM specifications for well sealing. Includes both neat-cement grout and bentonite gout mixtures. Includes materials, equipment and labor to place.	Cubic Yard	$681.27	1.5	$1,021.91
Chlorine	1335	Liquid chlorine bleach. Includes materials only.	Gallon	$2.82	1	$2.82
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	4	$1,960.04

Practice: 351 - Well Decommissioning

Scenario #4 - Drilled well greater than 300 feet deep

Scenario Description:

A licensed well driller will seal and permanently close an inactive, abandoned, or unusable water well to prevent excess nutrients in surface and groundwater and to eliminate pesticides transported to surface and ground water. Well will be cleared of all equipment and materials. Residual water column must be treated with chlorine concentration of >50 ppm or according to local, State, Tribal, or Federal regulations.

Before Situation:

Drilled well that is greater than 300 feet deep and inactive, abandoned, or unusable and provides a potential conduit for pesticides or nutrients to enter an aquifer. Typical well has 6 inch diameter casing.

After Situation:

Well is permanently sealed to prevent potential contamination of aquifer. Procedures and sealing materials shall conform to ASTM D5299 and be compatible with all local, State, Tribal, and Federal requirements. Backfill shall be placed and compacted in a manner that minimizes segregation and bulking to prevent surface subsidence. Associated practices: 342 Critical Area Seeding

Feature Measure: Length of well casing

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: $12,933.84

Scenario Cost/Unit: $25.87

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	12	$1,994.40
Grout pump	1334	Grout pump with tremie pipe. Equipment and power unit costs. Labor not included.	Hour	$15.71	12	$188.52
Hydrofracture Rig with Operator	1818	Equipment and power unit costs including mechanical packer equipment. Labor included.	Hour	$496.13	12	$5,953.56
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	12	$308.16
Materials						
Grout, cement	1333	Cement grout meeting ASTM specifications for well sealing. Includes both neat-cement grout and bentonite gout mixtures. Includes materials, equipment and labor to place.	Cubic Yard	$681.27	3.7	$2,520.70
Chlorine	1335	Liquid chlorine bleach. Includes materials only.	Gallon	$2.82	3	$8.46
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	4	$1,960.04

Practice: 351 - Well Decommissioning

Scenario #5 - Decommissioning a drilled well less than 300 feet deep without casing removal

Scenario Description:

A well permit holder will seal and permanently close an inactive, abandoned, or unusable irrigation well to prevent excess nutrients in surface and groundwater and to eliminate pesticides transported to surface and ground water. Well will be cleared of all equipment and materials. Residual water column must be treated with chlorine concentration of >50 ppm or according to local, State, Tribal, or Federal regulations. Does not require removal of entire casing depth.

Before Situation:

Drilled irrigation well that is less than 300 feet deep and inactive, abandoned, or unusable and provides a potential conduit for pesticides or nutrients to enter an aquifer. Typical well has 6 inch diameter casing.

After Situation:

Irrigation well is permanently sealed to prevent potential contamination of aquifer. Procedures and sealing materials shall conform to ASTM D5299 and be compatible with all local, State, Tribal, and Federal requirements. Backfill shall be placed and compacted in a manner that minimizes segregation and bulking to prevent surface subsidence. Associated practices: 342 Critical Area Seeding

Feature Measure: Length of well casing

Scenario Unit:: Foot

Scenario Typical Size: 200.0

Scenario Total Cost: $1,402.83

Scenario Cost/Unit: $7.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	1	$56.65
Grout pump	1334	Grout pump with tremie pipe. Equipment and power unit costs. Labor not included.	Hour	$15.71	1	$15.71
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	1	$27.38
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	1	$21.71
Materials						
Grout, cement	1333	Cement grout meeting ASTM specifications for well sealing. Includes both neat-cement grout and bentonite gout mixtures. Includes materials, equipment and labor to place.	Cubic Yard	$681.27	1.5	$1,021.91
Chlorine	1335	Liquid chlorine bleach. Includes materials only.	Gallon	$2.82	1	$2.82
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 356 - Dike

Scenario #1 - Material haul Less Than 1 mile

Scenario Description:

Construction of a barrier, constructed of an earthen embankment, to control water level. Embankment structure to provide adequate freeboard, allowance for settlement, and foundation and embankment stability. Cost Estimate is based on an earthen dike assumed 1000 lineal feet, Class II (6 ft. in height, 8 ft. top width, 2H:1V side slopes) with a material haul distance of less than 1 mile. Associated practices include, but are not limited to: PS327 Conservation Cover, PS656 Constructed Wetland, PS342 Critical Area Planting, PS378 Ponds, PS382 Fence, PS464 Irrigation Land Levelling, PS500 Obstruction Removal, PS528 Prescribed Grazing, PS587 Structure for Water Control, PS620 Underground Outlet, PS645 Upland Wildlife Management, PS658 Wetland Creation, PS659 Wetland Enhancement, PS657 Wetland Restoration, PS644 Wetland Wildlife Habitat Management.

Before Situation:

Site is subject to flooding or inundation which poses a potential hazard to public safety, damage to land or property. Site may also require control of water level for purposes connected with crop production; fish and wildlife management; or wetland maintenance, improvement, restoration, or construction. An adequate quantity of soil suitable for constructing an earthen dike is available at an economical haul distance. Material haul < 1 mile.

After Situation:

Water level controlled by a stable earthen structure. Potential hazard to public safety, land or property mitigated; environmental benefit provided.

Feature Measure: Volume of Earthfill (including volu

Scenario Unit:: Cubic Yard

Scenario Typical Size: 4,500.0

Scenario Total Cost: $19,366.68

Scenario Cost/Unit: $4.30

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	4500	$17,640.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	3	$1,470.03

Practice: 356 - Dike

Scenario #2 - Material haul Greater Than 1 mile

Scenario Description:

Construction of a barrier, constructed of an earthen embankment, to control water level. Embankment structure to provide adequate freeboard, allowance for settlement, and foundation and embankment stability. Cost Estimate is based on an earthen dike assumed 1000 lineal feet, Class II (6 ft. in height, 8 ft. top width, 2H:1V side slopes) with a material haul distance of greater than 1 mile. Associated practices include, but are not limited to: PS327 Conservation Cover, PS656 Constructed Wetland, PS342 Critical Area Planting, PS378 Ponds, PS382 Fence, PS464 Irrigation Land Levelling, PS500 Obstruction Removal, PS528 Prescribed Grazing, PS587 Structure for Water Control, PS620 Underground Outlet, PS645 Upland Wildlife Management, PS658 Wetland Creation, PS659 Wetland Enhancement, PS657 Wetland Restoration, PS644 Wetland Wildlife Habitat Management.

Before Situation:

Site is subject to flooding or inundation which poses a potential hazard to public safety, damage to land or property. Site may also require control of water level for purposes connected with crop production; fish and wildlife management; or wetland maintenance, improvement, restoration, or construction. An adequate quantity of soil suitable for constructing an earthen dike is available at an economical haul distance. Material haul > 1 mile.

After Situation:

Water level controlled by a stable earthen structure. Potential hazard to public safety, land or property mitigated; environmental benefit provided.

Feature Measure: Volume of Earthfill (including volu

Scenario Unit:: Cubic Yard

Scenario Typical Size: 4,500.0

Scenario Total Cost: $22,336.68

Scenario Cost/Unit: $4.96

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	4500	$17,640.00
Hauling, bulk, highway truck	1615	Hauling of bulk earthfill, rockfill, waste or debris. One-way travel distance using fully loaded highway dump trucks (typically 16 CY or 20 TN capacity). Includes equipment and labor for truck only. Does not include cost for loading truck.	Cubic Yard Mile	$0.33	9000	$2,970.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	3	$1,470.03

Practice: 356 - Dike

Scenario #3 - Shallow Water Area

Scenario Description:

A barrier constructed of an earthen embankment, to control water level. Embankment structure to provide adequate freeboard, allowance for settlement, and foundation and embankment stability. Cost estimate is based on a 2,640 foot long 3 ft high earthen dike (Class III) with a top width of 10 ft and having 3H:1V side slopes used to create a wetland or other shallow water area. Associated practices include, but are not limited to: PS327 Conservation Cover, PS656 Constructed Wetland, PS 342 Critical Area Planting, (378) Ponds, (382) Fence, (464) Irrigation Land Levelling, (500) Obstruction Removal, (528) Prescribed Grazing, (587) Structure for Water Control, (620) Underground Outlet, (645) Upland Wildlife Management, (658) Wetland Creation, (659) Wetland Enhancement, (657) Wetland Restoration, (644) Wetland Wildlife Habitat Management.

Before Situation:

Site requires control of water level for purposes connected with crop production; fish and wildlife management; or wetland maintenance, improvement, restoration, or construction. An adequate quantity of soil suitable for constructing an earthen dike is available at an economical haul distance.

After Situation:

A 2,640 foot long Class III dike is constructed with an average height of 3 feet, top width of 10 feet, and 3:1 side slopes. The water level is controlled by a stable earthen structure, and environmental benefit provided.

Feature Measure: Volume of Earthfill (including volu

Scenario Unit:: Cubic Yard

Scenario Typical Size: 5,573.0

Scenario Total Cost: $23,572.84

Scenario Cost/Unit: $4.23

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	5573	$21,846.16
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	3	$1,470.03

Practice: 359 - Waste Treatment Lagoon

Scenario #1 - Waste Treatment Lagoon

Scenario Description:

A waste treatment lagoon is a component of a waste management system that provides biological treatment of manure and other byproducts of animal agricultural operations by reducing the pollution potential. Resource concern addressed is water quality by reducing the pollution potential to surface and groundwater by treating and storing liquid waste. Earthen lagoon liners are addressed with another standard. Potential Associated Practices: Pond Sealing or Lining, Bentonite Sealant (521C), Pond Sealing or Lining, Compacted Clay Treatment (521D), Pond Sealing or Lining, Flexible Membrane (521A), Pond Sealing or Lining, Soil Dispersant (521B), Fence (382), Critical Area Planting (342), Nutrient Management (590), Waste Transfer (634), Heavy Use Area Protection (561), and Solid/Liquid Waste Separation Facility (632).

Before Situation:

Operator presently has a confined animal feeding operation without a waste management system adequate to handle the waste stream leaving the animal production facilities. Manure and other agricultural waste by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or are being transported but not properly utilized or disposed of. This situation poses an environmental threat of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources.

After Situation:

A waste treatment lagoon constructed from on-site material provides an environmentally safe facility for storing manure and other agricultural waste by-products. This facility provides the landowner a means of storing and treating waste until it can be utilized in a proper manner in accordance with a nutrient management plan. Typical design size : Design Volume 439,440 ft3; 260' X 208' (top); 3:1 inside and outside side slopes; cut/fill ratio = 1.25; total depth = 13'; 1' freeboard (not included in design volume)

Feature Measure: Design Storage Volume

Scenario Unit:: Cubic Foot

Scenario Typical Size: 439,440.0

Scenario Total Cost: $98,359.04

Scenario Cost/Unit: $0.22

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	9102	$35,679.84
Earthfill, Dumped and Spread	51	Earthfill, dumped and spread without compaction effort, includes equipment and labor	Cubic Yard	$3.22	8101	$26,085.22
Stripping and stockpiling, topsoil	1199	Stripping and stockpiling of topsoil adjacent to stripping area. Includes equipment and labor.	Cubic Yard	$0.89	1389	$1,236.21
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	$3.79	9125	$34,583.75
Materials						
Structural steel tubing, 2" diameter	1120	Structural steel tubing, 2" diameter, 1/8" wall thickness, materials only	Foot	$3.42	8	$27.36
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	1	$490.01

Practice: 360 - Waste Facility Closure

Scenario #6 - Liquid Waste Impoundment Closure with 25percent Liquids and 75percent Solids

Scenario Description:

This practice scenario includes the decommissioning of an earthen liquid waste impoundment (embankment or excavated type) where the estimated volume of waste to be removed is approximately 25% liquid/slurry waste and 75% sludge/solid waste of the structural storage capacity of the structure. The purpose of the practice is to address resource concerns related to water quality degradation due to excess nutrient and pathogens in ground and/or surface waters and air quality impacts from greenhouse gases, particulate matter and associated precursors, and objectionable odors. Associated practices: Nutrient Management (590), Critical Area Planting (342)

Before Situation:

An existing lagoon or waste storage pond is no longer functioning correctly or is not being used for its intended purpose. It poses a safety hazard for humans and livestock and is a threat to environmental sustainability by the potential for impacts to water and air quality.

After Situation:

This scenario assumes a waste storage pond, with top dimensions of 110 ft x 110 ft, 8 ft total depth with 2:1 side slopes. The total structural storage volume equals 63,851 cubic feet. The volume of liquid waste to be pumped approximately equals 25% if the structural volume (25% X 63,851 CF = 15,9635 CF). The volume of solid waste to be removed approximately equals 75% of the structural volume (75% X 63,851 = 47,888 CF). The volume of earthwork (earthfill and excavation) required to breach the embankment and/or fill in the impoundment and perform final grading of the site is approximately 50% of the structural volume. The volume of earthwork will include 60% as excavation and 40% as compacted earthfill. Structural removal, as necessary, may include the removal and disposal of the synthetic liner, sealing or removal and disposal of waste transfer components and other appurtenances associated with closure of the facility. Decommissioning of a liquid waste storage impoundment includes agitating, removing, and spreading liquid/slurry waste material, removing solid/sludge waste remaining in the bottom. All waste material shall be land applied in accordance with Nutrient Management (590). If present, the synthetic liner will be removed and properly disposed of. All inflow devices and associated appurtenances will be removed and properly disposed of. The embankment will be breached and the excavation filled in with the embankment material or hauled in earthfill. The disturbed areas shall be vegetated in accordance with Critical Area Planting (342). Closure of the waste impoundment will address water quality degradation, air quality impacts and safety hazards by removing and properly utilizing the waste from the impoundment. The site will also become available for another use.

Feature Measure: Cubic feet of structural storage

Scenario Unit:: Cubic Foot

Scenario Typical Size: 63,851.0

Scenario Total Cost: $22,793.37

Scenario Cost/Unit: $0.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	709	$1,467.63
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	473	$1,854.16
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	12	$1,379.52
Manure, compost, injection	956	Loading, hauling and injecting manure/compost by ground equipment. Includes equipment, power unit and labor costs.	Gallon	$0.01	119401	$1,194.01
Spreading, manure sludge	1633	Loading, hauling and spreading manure solids/sludge by ground equipment on nearby fields. Includes equipment, power unit and labor costs.	Cubic Foot	$0.31	47888	$14,845.28
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	12	$228.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	12	$308.16
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	4	$1,026.60
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	1	$490.01

Practice: 362 - Diversion

Scenario #1 - Diversion

Scenario Description:

An earthen channel constructed across long slopes with supporting ridge on lower side, to divert runoff away from farmsteads, agricultural waste systems, gullies, critical erosion areas, construction areas or other sensitive areas. Outlet may be waterway, underground outlet. or other suitable outlet. Typical diversion is, 500 feet long installed on a field slope of 5 percent and requires 1 CY excavation per LF. Channel my be level or gradient and ridge may be vegetated or farmed. The quantity of excavation and fill is balanced.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Diversion is installed using a dozer. Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Underground Outlet (620), Mulching (484), and Subsurface Drainage (606).

Feature Measure: Diversion Fill Volume

Scenario Unit:: Cubic Yard

Scenario Typical Size: 500.0

Scenario Total Cost: $1,402.01

Scenario Cost/Unit: $2.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	500	$1,035.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 368 - Emergency Animal Mortality Management

Scenario #7 - In-House Composting

Scenario Description:

This scenario consists the emergency disposal of poultry mortality by composting in a static windrow. The cause of mortality is an event not related to disease. Additional carbon based bulking material is added to facilitate aeration and provide a proper C:N ratio. The windrow is turned at least once to go into another heat cycle prior to land application. Access is infrequent. This option may not be desirable for sites with limited area, karst topography, and not isolated from of public view. The purpose of the practice is to address resource concerns related to water quality degradation due to excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Air quality impacts due to odors will also be addressed. Potential Associated Practices: Pond Sealing or Lining, Bentonite Sealant (521C), Pond Sealing or Lining, Compacted Clay Treatment (521D), Pond Sealing or Lining, Soil Dispersant (521B), Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Diversion (362).

Before Situation:

Animal mortality is done in a manner that results in non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Improper operation results in odors and spread of pathogens from incomplete composting, or interaction with predators. No plan was formulated for catastrophic mortality events.

After Situation:

Animal mortality is being done in a manner that prevents non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Proper operation results in little to no odors, complete composting, and protection from predators to minimize pathogen survival or spreading. An overall plan covers normal and catastrophic mortality events. The typical scenario number of birds to be disposed of is 20,000, 4 pound birds which can be composted in-house. Composting requires 1.5 pounds of carbon per pound of bird. There is 0.5 pounds of litter per bird already on site. Wood chips (45 pcf) will be used as the additional carbon source. The composting windrow construction operation consists of 2 pieces of equipment and 2 add 'l laborers: 1) stockpiling birds and litter in center of house; 2) construct 2 windrow bases using carbon material; 3) place carcass/litter mix on bases; 4) cover with carbon material; 5) cap windrows with any remaining litter; 6) after first heat cycle remove windrow from house and reconstruct outside house for finishing. Site to be located out of drainage areas, off-site water diverted and any runoff to spread out into a grassed area.

Feature Measure: Number of 1000 lbs Animal Units

Scenario Unit:: Animal Unit

Scenario Typical Size: 80.0

Scenario Total Cost: $5,035.45

Scenario Cost/Unit: $62.94

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$45.08	28	$1,262.24
Aggregate, Wood Chips	1098	Includes materials, equipment and labor	Cubic Yard	$21.35	91	$1,942.85
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	28	$532.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	28	$607.88
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	4	$690.48

Practice: 368 - Emergency Animal Mortality Management

Scenario #8 - Burial

Scenario Description:

This scenario consists of the on-site burial of animal mortalities resulting from catastrophic events not related to disease. An earthen pit is excavated to contain the mortalities, and earth cover is placed over the mortalities to provide protection from predators to minimize pathogen survival or spreading. The purpose of the practice is to address resource concerns related to water quality degradation due to excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Air quality impacts due to odors will also be addressed. Potential Associated Practices: Pond Sealing or Lining, Bentonite Sealant (521C), Pond Sealing or Lining, Compacted Clay Treatment (521D), Pond Sealing or Lining, Soil Dispersant (521B), Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), and Diversion (362).

Before Situation:

Animal mortality disposal is done in a manner that results in non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Improper operation results in odors and spread of pathogens from incomplete composting, incineration, or interaction with predators. No plan was formulated for catastrophic mortality events.

After Situation:

Catastrophic Animal mortalities resulting from causes not related to disease are being disposed in a manner that prevents non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Proper operation results in little to no odors, and protection from predators to minimize pathogen survival or spreading. An overall plan covers the burial of animals as a result of catastrophic mortality events. This typical scenario was developed based on the disposal of 25 head of mature cattle located near the area where the cattle have been found. The scenario includes equipment time and labor to recover and transport carcasses to the burial location. The scenario also includes a burial trench 4' deep plus 3' additional cover over carcasses. Construct a 6' x 60' (surface dimensions) burial site with appropriate cover. Site can handle mortality for 25 mature beef cattle. On site soils can be re-compacted to meet required imperviousness. Include 3' overfill or mounding excavated material to provide for settlement of the burial site and divert or minimize offsite runoff. Site to be located out of drainage areas, off-site water diverted and any runoff to spread out into a grassed area.

Feature Measure: Number of 1000 lbs Animal Units

Scenario Unit:: Animal Unit

Scenario Typical Size: 25.0

Scenario Total Cost: $2,388.10

Scenario Cost/Unit: $95.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Dumped and Spread	51	Earthfill, dumped and spread without compaction effort, includes equipment and labor	Cubic Yard	$3.22	94	$302.68
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	$58.32	12	$699.84
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	$1.60	94	$150.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	12	$228.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	12	$260.52
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	1	$490.01

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #1 - Ventilation, Exhaust

Scenario Description:

Replacement of a conventional exhaust fan with high volume, low speed, efficient exhaust fan. Fans being installed should be models previously tested by BESS Lab or the Air Movement and Control Association and be in top 20 percentile of fans tested. Practice certification will be through receipts and pictures from the applicant. Typical scenario is replacement of old fan with 54" fan.

Before Situation:

Inefficient ventilation in an agricultural building.

After Situation:

High-efficiency ventilation system which reduces energy use. The new ventilation equipment will provide suitable air quality and reduce overall power requirements (kW) compared to the existing ventilation system as evidenced in an energy audit. Associated practices/activities: may include 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $1,199.88

Scenario Cost/Unit: $1,199.88

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	3	$82.14
Materials						
Fan, exhaust, 54" High Efficiency	1188	54 inch high efficiency exhaust fan, controls, wiring, and associated appurtenances. Materials only.	Each	$1,117.74	1	$1,117.74

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #2 - Ventilation, HAF

Scenario Description:

A system of fans are installed to create a horizontal air circulation pattern; the new system promotes efficient heat and moisture distribution. In a typical 10,000 square foot greenhouse, 10 HAF fans are needed. Fan performance meets Energy Audit efficiency criteria as tested by AMCA or BESS Labs.

Before Situation:

Inefficient air circulation system in a greenhouse.

After Situation:

High-efficiency air circulation system which reduces energy use. The new equipment will provide suitable air quality and reduce overall power requirements (kW) compared to the existing system as evidenced in an energy audit. Associated practices/activities: may include 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $214.99

Scenario Cost/Unit: $214.99

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Materials						
Fan, HAF, 1/10 to 1/15 HP	1189	High efficiency Horizontal Air Flow (HAF) fan, controls, wiring, and associated appurtenances. Materials only.	Each	$160.23	1	$160.23

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #3 - Plate Cooler

Scenario Description:

The installation of all stainless steel dual pass plate cooler, type 316 stainless steel. Practice certification will be through receipts and pictures from the applicant.

Before Situation:

Inefficient milk cooling (minimal pre-cooling of milk before entering the bulk tank).

After Situation:

High-efficiency milk cooling system which reduces energy use. The new milk cooling equipment will pre-cool the milk and reduce overall power requirements (kW) compared to the existing milk cooling system (where most of the cooling was accomplished in the bulk tank) as evidenced in an energy audit. Associated practices/activities: may include 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each Plate Cooler

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $7,175.70

Scenario Cost/Unit: $7,175.70

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	8	$219.04
Materials						
Plate Cooler, 750 - 999 gal/hr capacity	1178	Stainless Steel, dual pass plate cooler with 750 - 999 gallon/hour capacity. Includes materials and shipping only.	Each	$6,956.66	1	$6,956.66

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #4 - Scroll Compressor

Scenario Description:

Install a new scroll compressor, associated controls, wiring, and materials to retrofit an existing refrigeration system. A new condenser is not included in this typical scenario. Typical scenario includes a new 5 horsepower scroll compressor.

Before Situation:

Inefficient reciprocating compressor as a key component of the refrigeration system used to cool milk. The compressor is a critical part of a milk cooling system, affecting milk quality, system reliability, and system efficiency.

After Situation:

A more efficient scroll compressor, which will reduce energy use, is evidenced by the energy audit. A comparably sized scroll compressor provides refrigeration capacity at a higher efficiency than a reciprocating compressor. Newer scroll compressor systems typically reduce electricity use by 15 to 25 percent compared to reciprocating compressors. Associated practices/activities: may include 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Horse Power

Scenario Unit:: Horsepower

Scenario Typical Size: 5.0

Scenario Total Cost: $4,404.65

Scenario Cost/Unit: $880.93

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	4	$109.52
Materials						
Scroll Compressor - 5 HP	1183	Scroll compressor, 5 Horsepower, controls, wiring, and appurtenances. Materials only.	Each	$4,295.13	1	$4,295.13

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #5 - Variable Speed Drive, greater than 5 HP

Scenario Description:

The typical scenario consists of a variable speed drive (VSD) and appurtenances, such as hook-ups, control panels, wiring, control blocks, filters, switches, pads, etc. attached to an electric motor used to drive a ventilation fan, irrigation pumps, vacuum pump, or similar equipment involved with agricultural production. The motor size, on which the VSD is added, is larger than 5 HP.

Before Situation:

The system is inefficient when a motor operates at constant speed to satisfy a load which varies as to flow rate and/or pressure requirements.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a VSD to control electric motors. After the VSD is applied, the motor speed can be adjusted to reduce power requirements and better match varied flow or pressure requirements. Associated practices/activities: may include 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Nameplate Power of the Attached

Scenario Unit:: Horsepower

Scenario Typical Size: 50.0

Scenario Total Cost: $12,605.04

Scenario Cost/Unit: $252.10

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	8	$219.04
Materials						
Variable Speed Drive, 50 HP	1288	Variable speed drive for 50 Horsepower electric motor. Does not include motor. Materials only.	Horsepower	$247.72	50	$12,386.00

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #6 - Automatic Controller System

Scenario Description:

The typical scenario consists of an automatic control system installed on an existing manually controlled agricultural system. Typical components may include any of the following: wiring, sensors, data logger, logic controller, communication link, software, switches, and relay.

Before Situation:

A manually controlled system is existing in an agricultural facility that causes the inefficient use of energy, as evidenced by an on-farm energy audit.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of an automatic controller that helps regulates the energy consumption of the existing system. Associated practices/activities may include: 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each system

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $1,513.32

Scenario Cost/Unit: $1,513.32

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	8	$219.04
Materials						
Switches and Controls, temp sensors	1192	Temperature and soil moisture sensors installed as part of an electronic monitoring (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	$666.86	1	$666.86
Switches and Controls, programmable controller	1193	Programmable logic controller (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	$170.29	1	$170.29
Switches and Controls, Wi-Fi system and software	1194	Software with built-in cellular or Wi-Fi communication commonly used to control pumps and irrigation systems	Each	$457.13	1	$457.13

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #7 - Motor Upgrade, greater than 100 HP

Scenario Description:

The typical scenario consists of replacing an existing electric motor used to drive a ventilation fan, irrigation pumps, vacuum pump, or similar equipment involved with agricultural production with a new, high efficiency motor. The motor size is larger than 100 horsepower.

Before Situation:

The system is inefficient with a standard efficiency motor.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a NEMA premium efficiency motor. Associated practices/activities may include: 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Nameplate Power of Motor

Scenario Unit:: Horsepower

Scenario Typical Size: 150.0

Scenario Total Cost: $16,861.98

Scenario Cost/Unit: $112.41

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
Materials						
Motor, electric, NEMA Premium, 100 HP	1174	Premium NEMA approved electric motor, 100 Horsepower and all required appurtenances. Includes materials and shipping only.	Each	$8,121.33	0.5	$4,060.67
Motor, electric, NEMA Premium, 200 HP	1175	Premium NEMA approved electric motor, 200 Horsepower and all required appurtenances. Includes materials and shipping only.	Each	$24,726.47	0.5	$12,363.24

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #8 - Motor Upgrade, 10 to 100 HP

Scenario Description:

The typical scenario consists of replacing an existing electric motor used to drive a ventilation fan, irrigation pumps, vacuum pump, or similar equipment involved with agricultural production with a new, high efficiency motor. The motor size is equal to or larger than 10 and less than or equal to 100 horsepower.

Before Situation:

The system is inefficient with a standard efficiency motor.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a NEMA premium efficiency motor. Associated practices/activities may include: 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Nameplate Power of Motor

Scenario Unit:: Horsepower

Scenario Typical Size: 50.0

Scenario Total Cost: $6,720.34

Scenario Cost/Unit: $134.41

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	8	$219.04
Materials						
Motor, electric, NEMA Premium, 50 HP	1173	Premium NEMA approved electric motor, 50 Horsepower and all required appurtenances. Includes materials and shipping only.	Each	$6,501.30	1	$6,501.30

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #9 - Motor Upgrade, 1 to 10 HP

Scenario Description:

The typical scenario consists of replacing an existing electric motor used to drive a ventilation fan, irrigation pumps, vacuum pump, or similar equipment involved with agricultural production with a new, high efficiency motor. The motor size is larger than 1 and less than 10 horsepower.

Before Situation:

The system is inefficient with a standard efficiency motor.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a NEMA premium efficiency motor. Associated practices/activities may include: 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Nameplate Power of Motor

Scenario Unit:: Horsepower

Scenario Typical Size: 5.0

Scenario Total Cost: $923.43

Scenario Cost/Unit: $184.69

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	4	$109.52
Materials						
Motor, electric, NEMA Premium, 5 HP	1171	Premium NEMA approved electric motor, 5 Horsepower and all required appurtenances. Includes materials and shipping only.	Each	$813.91	1	$813.91

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #10 - Motor Upgrade, up to 1 HP

Scenario Description:

The typical scenario consists of replacing an existing electric motor used to drive a ventilation fan, irrigation pumps, vacuum pump, or similar equipment involved with agricultural production with a new, high efficiency motor. The motor size is less than or equal to 1 horsepower.

Before Situation:

The system is inefficient with a standard efficiency motor.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a NEMA premium efficiency motor. Associated practices/activities may include: 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Nameplate Power of Motor

Scenario Unit:: Horsepower

Scenario Typical Size: 1.0

Scenario Total Cost: $608.13

Scenario Cost/Unit: $608.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	4	$109.52
Materials						
Motor, electric, NEMA Premium, 1 HP	1169	Premium NEMA approved electric motor, 1 Horsepower and all required appurtenances. Includes materials and shipping only.	Each	$498.61	1	$498.61

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #11 - Heating, Radiant Heater

Scenario Description:

Replace "pancake" Brood Heaters in a poultry house with Radiant Tube Heaters, or similar. Replacement will require the materials and labor to remove existing heating system, re-plumb gas lines, cables and wench system to retrofit new radiant tube heaters, and miscellaneous items to complete the installation. Alternate acceptable radiant heating systems can include radiant brooders and quad radiant systems as evidenced by the energy audit. The typical scenario consists of the replacement of 28 brood heaters with 6 radiant tube heaters.

Before Situation:

Inefficient heat distribution equipment, such as conventional "pancake" brood heaters. The Pancake brooder, mounted at a low installation height, primarily warms the air. They provide a one-to-two foot perimeter at desired temperatures around each brooder. A large number of brooders are required to cover a significant percent of floor space. As the warmed air naturally rises it loses effectiveness for poultry on the ground.

After Situation:

Energy use is reduced through installation of a more efficient heater. Radiant tube heaters primarily warm objects within a direct line of sight (similar to the sun or an open fire). Air temperature is of relatively little importance for a radiant heating systems to be effective. As a result, radiant systems are typically installed 5' or more above the floor level. This height extends the distribution of the radiant heat over a larger area than is possible with pancake style heaters. A roughly 16' diameter radiant heat zone heats over twice that of a conventional pancake brooder. Associated practices/activities may include: 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Radiant Heating Capacity

Scenario Unit:: 1,000 BTU/Hour

Scenario Typical Size: 875.0

Scenario Total Cost: $11,197.64

Scenario Cost/Unit: $12.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
Materials						
Heater, radiant tube	1163	Radiant tube heater rated at 125,000 BTU/hour. Materials only.	Each	$1,537.08	7	$10,759.56

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #12 - Heating (Building)

Scenario Description:

Replace existing low efficiency heaters with new high efficiency heaters. High-efficiency heating systems include any heating unit with efficiency rating of 80%+ for fuel oil and 90%+ for natural gas and propane. Applications may be air heating/building environment and hydronic (boiler) heating for agricultural operations, including under bench, or root zone heating. An alternative to heater replacement might be the addition of climate control system and electronic temperature controls with +/- 1 degree F differential, to reduce the annual run time.

Before Situation:

Buildings heated with low efficiency heaters or heaters without proper electronic climate controls

After Situation:

Higher efficiency heaters reduce energy consumption, energy costs, and GHG emissions. These replacement systems can be fueled by natural gas, propane, or fuel oil. Associated practices/activities: 122-AgEMP - HQ and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Rated Heat Output

Scenario Unit:: 1,000 BTU/Hour

Scenario Typical Size: 750.0

Scenario Total Cost: $9,775.58

Scenario Cost/Unit: $13.03

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
Materials						
Heater, high efficiency	1165	Natural gas, propane, or fuel oil unit heater or boiler and venting materials. Based on input kBTU/hour. Includes materials and shipping only.	1,000 BTU/Hour	$12.45	750	$9,337.50

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #13 - Heating - Attic Heat Recovery vents

Scenario Description:

Install actuated inlets or automatic latching gravity inlets that draw warmer, drier air from the attic to assist with moisture and heat control when ventilation fans are being operated in poultry houses and swine barns. Other systems to transfer heat, as detailed in ASABE S612-compliant energy audit may also be used. Based on a 40' x 500' poultry house.

Before Situation:

Heated buildings with attic spaces but no means to transfer heat between the heated space, attic, and ambient (outside) air when relative conditions allow for reduced energy use.

After Situation:

Attic vents or inlets allow dry warm air from the attic to circulated through out the building. By using pre-warmed air from the attic less energy is needed for heating 122-AgEMP - HQ and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each inlet

Scenario Unit:: Each

Scenario Typical Size: 14.0

Scenario Total Cost: $2,198.10

Scenario Cost/Unit: $157.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	24	$657.12
Materials						
Inlet, Attic Ceiling	2414	Poultry house attic air inlets. Includes materials only.	Each	$110.07	14	$1,540.98

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #14 - Drying, Grain Dryer

Scenario Description:

A replacement continuous dryer rated for an appropriate rated bushel/per hour capacity for the operation that includes a microcomputer-based control system that adjusts the amount of time the crop remains in the dryer in order to achieve a consistent and accurate moisture content in the dried product. Alternate types of replacement dryers which reduce energy use are acceptable as evidenced by the energy audit. The typical operation requires a rated capacity of 860 bushels per hour.

Before Situation:

Wet crop is loaded in the top of a horizontal, continuous dryer. Dried crop is augured from the bottom of the dryer. The heated air from the unit's burners passes from the burner plenum through the grain. An on-farm energy audit has identified inefficient manual control of the dryer where the operator controls the plenum temperature and the discharge auger speed to achieve the desired final moisture content. Moisture content is based on measurement of grain leaving the dryer. The plenum temperature setting depends on the moisture content of crop with a typical value of 220 F. The burner cycles on and off, automatically, as necessary to maintain the plenum temperature selected by the operator.

After Situation:

Energy use is reduced through installation of a more efficient continuous dryer that uses a microcomputer-based controller to reduce over drying and total time of operation. Associated practices/activities may include: 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Rated capacity of the dryer

Scenario Unit:: Bushel per Hour

Scenario Typical Size: 860.0

Scenario Total Cost: $85,750.08

Scenario Cost/Unit: $99.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
Materials						
Grain dryer, Axial, 12'	1158	Grain dryer, 12 foot Axial with rated capacity of 460 bushels/hour. Materials only.	Bushel per Hour	$104.57	172	$17,986.04
Grain dryer, Axial, 16'	1159	Grain dryer, 16 foot Axial with rated capacity of 600 bushels/hour. Materials only.	Bushel per Hour	$90.29	172	$15,529.88
Grain dryer, Centrifugal, 20'	1160	Grain dryer, 20 foot Centrifugal with rated capacity of 785 bushels/hour. Materials only.	Bushel per Hour	$96.57	172	$16,610.04
Grain dryer, Centrifugal, 24'	1161	Grain dryer, 24 foot Centrifugal with rated capacity of 860 bushels/hr. Materials only.	Bushel per Hour	$103.43	172	$17,789.96
Grain dryer, Axial 28'	1162	Grain dryer, 28 foot Axial with rated capacity of 990 bushels/hr. Materials only.	Bushel per Hour	$101.14	172	$17,396.08

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #15 - Air Cooling, Evaporative Cooling System

Scenario Description:

A typical scenario is the addition of evaporative cooling to existing ventilation fans on poultry houses. The increased cooling from the evaporative cooling units will result in reduced cooling equipment operation and increased animal health.

Before Situation:

Cooling fans run very often and animal health suffers.

After Situation:

A more effective and efficient cooling system can be created through addition of an evaporative cooling system. Associated practices/activities: may include 122-AgEMP - HQ, 672-Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Typical house size is 24000 sq. feet. Scenario based on evaporation unit running 65 ft down both walls and 5.5 ft tall = 715 sf

Feature Measure: Square Feet of Cooling Surface

Scenario Unit:: Square Foot

Scenario Typical Size: 715.0

Scenario Total Cost: $17,098.75

Scenario Cost/Unit: $23.91

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	5	$136.90
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	5	$95.00
Materials						
Evaporative Cooling System, Large	2400	Energy efficient cooling systems installed in ventilated livestock confinement or greenhouses for temperature control. Complete system with cooling pads, aluminum distribution and end panels, 1/3 HP submersible sump pump and plumbing kit. Greater than 90 square feet. Includes material only.	Square Foot	$23.59	715	$16,866.85

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #16 - Air Cooling, Baffle Curtain

Scenario Description:

Installation of vertically-hanging curtains in the truss space (typically on the sides of the trusses) which effectively reduces the cross section for air flow during tunnel ventilation. Reducing the cross section for air flow reduces the needed tunnel fan capacity while achieving the minimum air speed. Curtains do not require any insulation value but must be durable in the broiler house environment. Curtains are typically installed 30 to 50 ft apart. Payment covers curtain material, fabrication, hanging accessories, and installation labor.

Before Situation:

A broiler house has open-truss construction. Nothing blocks the longitudinal air flow through the truss space during tunnel ventilation. The house requires a large total capacity of tunnel exhaust fans to achieve required minimum air speed during tunnel ventilation.

After Situation:

The broiler house has lower warm-season operational energy inputs and costs. Associated practices/activities may include: 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each Baffle Curtain

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $446.30

Scenario Cost/Unit: $446.30

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Curtain , 7-Layer, R3 Insulated	2427	Seven layer insulated curtain with an R-value of 3 for a livestock building. Typical curtain size is 4' x 270'. The curtain's two outer layers are vinyl and polyethylene and the five inner layers are composed of insulating materials with air trapping fibers and a vapor barrier. Does not include mounting accessories, assumes it is replacing a non-insulated curtain.	Square Foot	$2.18	135	$294.30

Practice: 378 - Pond

Scenario #1 - Excavated Pit

Scenario Description:

A low-hazard water impoundment structure on agricultural lands to improve water quality and to provide water for livestock, fish and wildlife, recreation, fire control, crop and orchard irrigation, and other related uses. Pond is created solely by excavation and impounds less than 3 feet against the embankment or spoil. Excavated material is spoiled, not placed in a designed embankment. Earthen spillway is constructed as needed. The resource concerns addressed include inadequate livestock water, excessive suspended sediment and turbidity in surface water, damage from sediment deposition, and reduced capacity of conveyances by sediment deposition.

Before Situation:

Area exists where water could naturally pool or run off to create a pond for livestock, wildlife, fire control or irrigation. Failure of the pond will not result in loss of life; damage to homes, commercial or industrial buildings, main highways, or railroads; or in interruption of the use or service of public utilities.

After Situation:

The typical pond is constructed by excavating 3100 cubic yards and spreading the spoil outside the pool area using a dozer or similar excavation equipment. Vegetation will be completed under critical area planting (342). Other associated practices include 382, 516, 521A, 533, 614, 587, 396.

Feature Measure: Excavated Volume

Scenario Unit:: Cubic Yard

Scenario Typical Size: 1,500.0

Scenario Total Cost: $5,591.55

Scenario Cost/Unit: $3.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	$125.35	15	$1,880.25
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	20	$2,299.20
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	35	$898.80
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 378 - Pond

Scenario #2 - Embankment Pond without Pipe

Scenario Description:

A water impoundment structure on agricultural land to improve water quality or to provide water for livestock, fish and wildlife, recreation, fire control, crop and orchard irrigation, and other related uses. An earthen embankment will be constructed with an earthen auxiliary spillway. The resource concerns addressed include inadequate livestock water, excessive suspended sediment and turbidity in surface water, damage from sediment deposition, and reduced capacity of conveyances by sediment deposition.

Before Situation:

Area exists where water could naturally pool or run off to create a pond for livestock, wildlife, fire control or irrigation. Failure of the embankment will not result in loss of life or damages of any kind.

After Situation:

The typical pond is constructed by excavating the pool area, constructing the auxiliary spillway, preparing the foundation as designed, and using 1500 cubic yards to create an embankment. The product of the storage times the effective height of the dam is less than 3,000. The effective height of the dam is 35 feet or less. The earthen auxiliary spillway will be constructed as designed. No principle spillway pipe will be used. Vegetation will be completed under critical area planting (342). Other associated practices include 382, 516, 521A, 533, 614, 587, 396.

Feature Measure: Embankment Volume

Scenario Unit:: Cubic Yard

Scenario Typical Size: 1,500.0

Scenario Total Cost: $6,288.65

Scenario Cost/Unit: $4.19

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	1500	$5,880.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 378 - Pond

Scenario #3 - Embankment Pond with Pipe

Scenario Description:

A low-hazard water impoundment structure on agricultural land to improve water quality and to provide water for livestock, fish and wildlife, recreation, fire control, crop and orchard irrigation, and other related uses. An earthen embankment will be constructed with a principle spillway conduit and earthen auxiliary spillway, as designed. The resource concerns addressed include inadequate livestock water, excessive suspended sediment and turbidity in surface water, damage from sediment deposition, and reduced capacity of conveyances by sediment deposition.

Before Situation:

Area exists where water could naturally pool or run off to create a pond for livestock, wildlife, fire control or irrigation. Failure of the embankment will not result in loss of life or damages of any kind.

After Situation:

The typical low hazard pond is constructed by excavating the pool area, constructing the auxiliary spillway, preparing the foundation as designed, and using 2000 cubic yards to create an embankment. The product of the storage times the effective height of the dam is less than 3,000. The effective height of the dam is 35 feet or less. The principle spillway is installed using an approved conduit material. The earthen auxiliary spillway will be constructed as designed. Vegetation will be completed under critical area planting (342). Other associated practices include 382, 516, 521A, 533, 614, 587, 396.

Feature Measure: Embankment Volume

Scenario Unit:: Cubic Yard

Scenario Typical Size: 2,000.0

Scenario Total Cost: $11,955.06

Scenario Cost/Unit: $5.98

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$365.63	3	$1,096.89
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	1.6	$3.31
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	2000	$7,840.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	8	$219.04
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	40	$760.00
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	$30.09	19.6	$589.76
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	$1.75	628	$1,099.00
Trash Guard, metal	1608	Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport.	Pound	$2.26	40	$90.40
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 381 - Silvopasture Establishment

Scenario #1 - Establish Trees

Scenario Description:

Establishment of trees into an existing pasture that contains adequate native or introduced forage.

Before Situation:

Pasture with suitable forage for livestock. There is very little protection from the elements (sun, wind, etc.) available to the livestock. Additionally, there are no long-term wood products being produced. Resource Concerns include Degraded Plant Condition - Undesirable Plant Productivity and Health, Inadequate Structure and Composition, Livestock Production Limitation - Inadequate Livestock Shelter.

After Situation:

The site will be prepared using Tree/Shrub Site Preparation (490), if needed, and then 200 to 400 pine trees per acre will be planted, providing shade and wind protection to livestock and wildlife, and, in time, producing a viable wood products crop. Per the conservation practice standard, livestock grazing will be deferred until the trees reach adequate height to resist damage, or use exclusion measures are established. All Resource Concerns listed above are addressed.

Feature Measure: Acres of silvopasture established

Scenario Unit:: Each

Scenario Typical Size: 4,000.0

Scenario Total Cost: $782.08

Scenario Cost/Unit: $0.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	8	$200.32
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	$7.01	8	$56.08
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	8	$173.68
Materials						
Tree, conifer, seedling, bare root, 1-0	1512	Bare root conifer trees, 1-0 (1 year old). Includes materials and shipping only.	Each	$0.05	4000	$200.00

Practice: 381 - Silvopasture Establishment

Scenario #3 - Establish Native Grass

Scenario Description:

Establishment of native grasses into an existing or planted stand of trees.

Before Situation:

Existing forest stand (pine or hardwood, native or planted) with 35 to 45 percent canopy cover or newly planted stand of trees with 200 to 400 trees per acre. There is very little available forage for livestock, due to undesirable species in the understory. Resource Concerns include Degraded Plant Condition - Undesirable Plant Productivity and Health, Inadequate Structure and Composition; Livestock Production Limitation - Inadequate Feed and Forage.

After Situation:

The soil is prepared for planting using chemical and mechanical means, then a mix of native warm-season grasses will be established, providing forage to livestock and wildlife. All Resource Concerns listed above are addressed.

Feature Measure: Acres of silvopasture established

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $4,206.50

Scenario Cost/Unit: $420.65

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	10	$112.60
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	10	$167.80
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	10	$62.00
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	10	$66.90
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$10.75	10	$107.50
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	10	$215.80
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	10	$77.80
Materials						
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	500	$240.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.36	500	$180.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	$32.76	20	$655.20
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	10	$188.70
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	$213.22	10	$2,132.20

Practice: 381 - Silvopasture Establishment

Scenario #4 - Establish Introduced Grass

Scenario Description:

Establishment of introduced grasses into an existing stand of trees that is already at an adequate density .

Before Situation:

Forest stand (pine or hardwood, native or planted) with 35 to 45 percent canopy cover for warm season introduced grasses or 60 percent canopy cover for cool season introduced grasses. There is very little available forage for livestock, due to undesirable species in the understory. Resource Concerns include Degraded Plant Condition - Undesirable Plant Productivity and Health, Inadequate Structure and Composition; Livestock Production Limitation - Inadequate Feed and Forage.

After Situation:

The soil is prepared for planting using chemical and mechanical means, then a mix of warm season introduced grasses or introduced cool-season grasses and legumes will be established, providing forage to livestock and wildlife. All Resource Concerns listed above are addressed.

Feature Measure: Acres of silvopasture established

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $2,692.90

Scenario Cost/Unit: $269.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	10	$112.60
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	10	$167.80
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	10	$62.00
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	10	$66.90
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$10.75	10	$107.50
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	$12.74	10	$127.40
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	10	$77.80
Materials						
Nitrogen (N), Ammonium Nitrate	69	Price per pound of N supplied by Ammonium Nitrate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.57	400	$228.00
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	500	$240.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.36	500	$180.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	$32.76	20	$655.20
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	10	$188.70
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	$47.90	10	$479.00

Practice: 382 - Fence

Scenario #1 - Barbed/Smooth Wire

Scenario Description:

Multi-strand, Barbed or Smooth Wire - Installation of fence will allow for implementation of grazing management that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds. Constructed using fencing materials rather than a pre-manufactured gate.

Before Situation:

On grazing lands health and vigor are negatively impacted by poor grazing distribution, timing of grazing and inadequate rest and recovery periods. Water quality is impacted by increased erosion and runoff, cattle access to water bodies is uncontrolled. Reduced vegetative cover increases the opportunity for encroachment of noxious and invasive weeds.

After Situation:

Installation of fence will allow for implementation of grazing management that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds. Fence includes posts, wire, fasteners, gates, etc... Four strand wire is commonly installed. Fence will be installed with wildlife friendly considerations.

Feature Measure: Length of Fence

Scenario Unit:: Foot

Scenario Typical Size: 2,640.0

Scenario Total Cost: $6,672.75

Scenario Cost/Unit: $2.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	$7.39	40	$295.60
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	20	$440.40
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	40	$1,001.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	96	$1,824.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	40	$868.40
Materials						
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	$72.51	8	$580.08
Post, Wood, CCA treated, 4" x 8'	10	Wood Post, Line 4" X 8', CCA Treated. Includes materials and shipping only.	Each	$8.21	6	$49.26
Post, Wood, CCA treated, 6" x 8'	12	Wood Post, End 6" X 8', CCA Treated. Includes materials and shipping only.	Each	$15.38	12	$184.56
Post, Steel T, 1.33 lbs, 6'	15	Steel Post, Studded 6' - 1.33 lb. Includes materials and shipping only.	Each	$6.81	130	$885.30
Gate, Pipe, 10'	1056	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	$150.03	2	$300.06
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: 382 - Fence

Scenario #2 - Woven Wire

Scenario Description:

Woven - Installation of fence will allow for implementation of a grazing management that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds. Woven wire is typically used in applications with sheep, goats, hogs, wildlife exclusion, shelterbelt/tree protection, etc. Constructed using fencing materials rather than a pre-manufactured gate.

Before Situation:

On grazing lands health and vigor are negatively impacted by poor grazing distribution, timing of grazing and inadequate rest and recovery periods. Water quality is impacted by increased erosion and runoff, livestock access to water bodies is uncontrolled. Reduced vegetative cover increases opportunity for encroachment of noxious and invasive weeds.

After Situation:

Installation of fence will allow for implementation of a rotational grazing plan that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds. Woven wire fence includes posts, wire, fasteners, gates, etc... Woven wire is typically used in applications with sheep, goats, hogs, wildlife exclusion, shelterbelt/tree protection, etc.

Feature Measure: Length of Fence

Scenario Unit:: Foot

Scenario Typical Size: 2,640.0

Scenario Total Cost: $8,198.27

Scenario Cost/Unit: $3.11

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	$7.39	40	$295.60
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	10	$220.20
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	40	$1,001.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	96	$1,824.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	40	$868.40
Materials						
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	$72.51	4	$290.04
Wire, Woven, Galvanized, 12.5 Gauge, 32"	3	Galvanized 12.5 gauge, 32" - 330' roll. Includes materials and shipping only.	Each	$179.23	8	$1,433.84
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	$6.38	6	$38.28
Post, Wood, CCA treated, 6" x 8'	12	Wood Post, End 6" X 8', CCA Treated. Includes materials and shipping only.	Each	$15.38	12	$184.56
Post, Steel T, 1.33 lbs, 6'	15	Steel Post, Studded 6' - 1.33 lb. Includes materials and shipping only.	Each	$6.81	220	$1,498.20
Gate, Pipe, 10'	1056	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	$150.03	2	$300.06
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: 382 - Fence

Scenario #3 - Electric

Scenario Description:

Electric - Installation of fence will allow for implementation of a grazing management that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds.

Before Situation:

On grazing lands health and vigor are negatively impacted by poor grazing distribution, timing of grazing and inadequate rest and recovery periods. Water quality is impacted by increased erosion and runoff, cattle access to water bodies is uncontrolled. Reduced vegetative cover increases the opportunity for encroachment of noxious and invasive weeds.

After Situation:

Installation of fence will allow for implementation of grazing management that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds. Fence includes posts, wire, fasteners, gates, fence charger, etc... Two strand wire is commonly installed. Fence will be installed with wildlife friendly considerations.

Feature Measure: Length of Fence

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: $1,951.89

Scenario Cost/Unit: $1.48

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	$7.39	2	$14.78
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	2	$50.08
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Wire, High Tensile, 12.5 Gauge, 4,000' roll	2	High Tensile 12.5 gauge, 4,000' roll. Includes materials and shipping only.	Each	$116.19	1	$116.19
Post, Wood, CCA treated, 5" x 8'	11	Wood Post, End 5" X 8', CCA Treated. Includes materials and shipping only.	Each	$11.47	4	$45.88
Post, Fiberglass, 7/8" X 6'	18	Fiberglass line post, 7/8"" diameter X 6' length. Includes materials and shipping only.	Each	$10.10	27	$272.70
Electric, Ground Rods	20	Electric, Ground Rod for electric fence. Includes materials and shipping only.	Each	$10.70	7	$74.90
Electric, Ground Rod Clamps	21	Electric, Ground Rod Clamps for electric fence. Includes materials and shipping only.	Each	$1.84	7	$12.88
Electric, Lightening Diverter	22	Electric, Lightening diverter for electric fence. Includes materials and shipping only.	Each	$10.46	1	$10.46
Electric, Insulated cable	23	Electric, Insulated cable for electric fence. Typically in spools of 100 to 200 feet. Includes materials and shipping only.	Each	$30.53	30	$915.90
Electric, Power Surge Protector	24	Electric, Power Surge Protector for electric fence. Includes materials and shipping only.	Each	$9.82	1	$9.82
Electric, Tester	26	Electric, Tester for electric fence. Includes materials and shipping only.	Each	$41.90	1	$41.90
Electric, Energizer, 3-4 joule	28	Electric, Energizer, 3-4 joule for electric fence. Includes materials and shipping only.	Each	$234.40	1	$234.40

Practice: 386 - Field Border

Scenario #37 - Field Border, Native Species, Forgone Income

Scenario Description:

A strip of permanent vegetation established at the edge or around the perimeter of an agricultural field. Practice includes seedbed prep and planting of native species. The area of the field border is taken out of production.

Before Situation:

Before practice conditions may vary widely. Fields may have erosion issues from wind or water, a field border may be needed to manage pest populations, protect soil and water quality, provide wildlife food and cover, provide pollinator habitat, or a field border may be used to increase carbon storage and improve air quality. Water quality, soil erosion and/or wildlife food and cover may all be primary resource concerns.

After Situation:

The 386 Implementation Requirements have been developed and applied for the site. This practice when applied around a field may support and connect other buffer practices within and between fields. Native grasses, legumes and forbs will be established in the field borders to the extent needed to meet the resource needs and producer objectives. Minimum field border widths shall be based on NRCS local design criteria specific to the purpose for installing the practice. Native species shall be selected that do not function as a host for diseases of a field crop and have physical characteristics necessary to control wind and water erosion to tolerable levels on the field border area.

Feature Measure: number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $424.44

Scenario Cost/Unit: $424.44

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	3	$33.78
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.5	$197.08
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.5	$103.56
Materials						
One Species, Warm Season, Native Perennial Grass	2322	Native, warm season perennial grass. Includes material and shipping only.	Acre	$68.44	1	$68.44

Practice: 386 - Field Border

Scenario #39 - Field Border, Pollinator, Forgone Income

Scenario Description:

A strip of permanent vegetation established at the edge or around the perimeter of an agricultural field. Practice includes seedbed prep and planting of pollinator friendly herbaceous species. The area of the field border is taken out of production.

Before Situation:

Before practice conditions may vary widely. Fields may have erosion issues from wind or water, a field border may be needed to manage pest populations, protect soil and water quality, provide wildlife food and cover, provide pollinator habitat, or a field border may be used to increase carbon storage and improve air quality. Water quality, soil erosion and/or wildlife food and cover may all be primary resource concerns.

After Situation:

The 386 Implementation Requirements have been developed and applied for the site. This practice when applied around a field may support and connect other buffer practices within and between fields. Pollinator herbaceous plantings will provide species which flower throughout the growing season. This provides a source of nectar for adult pollinators and a diversity of herbaceous material for immature pollinator life stages and for nesting. Minimum field border widths shall be based on NRCS local design criteria specific to the purpose for installing the practice. Species selected shall meet the pollinator habitat requirements of the state and be adapted to site; not function as a host for diseases of a field crop and; have physical characteristics necessary to control wind and water erosion to tolerable levels on the field border area.

Feature Measure: Number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $1,308.01

Scenario Cost/Unit: $1,308.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	3	$33.78
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.5	$197.08
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.5	$103.56
Materials						
Six Species Mix, Native Forb	2334	Native forb mix. Includes material and shipping only.	Acre	$952.01	1	$952.01

Practice: 386 - Field Border

Scenario #43 - Field Border, Pollinator

Scenario Description:

A strip of permanent vegetation established at the edge or around the perimeter of a field. This practice may also apply to recreation land or other land uses where agronomic crops including forages are grown. Practice includes seedbed prep and planting of pollinator friendly species.

Before Situation:

Before practice conditions may vary widely. Fields may have erosion issues from wind or water, a field border may be needed to manage pest populations, protect soil and water quality, provide wildlife food and cover, provide pollinator habitat, or a field border may be used to increase carbon storage and improve air quality. Water quality, soil erosion and/or wildlife food and cover may all be primary resource concerns.

After Situation:

The 386 Implementation Requirements have been developed and applied for the site. This practice when applied around a field may support and connect other buffer practices within and between fields. Pollinator herbaceous plantings will provide species which flower throughout the growing season. This provides a source of nectar for adult pollinators and a diversity of herbaceous material for immature pollinator life stages and for nesting. Minimum field border widths shall be based on NRCS local design criteria specific to the purpose for installing the practice. Species selected shall be adapted to site, will not function as a host for diseases of a field crop, and have physical characteristics necessary to control wind and water erosion to tolerable levels on the field border area.

Feature Measure: Number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $1,007.37

Scenario Cost/Unit: $1,007.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	3	$33.78
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Materials						
Six Species Mix, Native Forb	2334	Native forb mix. Includes material and shipping only.	Acre	$952.01	1	$952.01

Practice: 390 - Riparian Herbaceous Cover

Scenario #1 - Native Warm Season Grass

Scenario Description:

Native Warm Season Grasses with naturally regenerated Forbs: This scenario addresses inadequate herbaceous plant community function or diversity within the specific transitional zone between terrestrial and aquatic habitats in rangeland, pasture, cropland, and forest where natural seeding methods and/or management is unlikely to improve the plant community within a reasonable time period. This scenario applies to work not covered under NRCS Conservation Practice Range Planting (528), Forage and Biomass Planting (512), Critical Area Planting (342), Filter Strip (393), Restoration and Management of Rare and Declining Habitats (643), Streambank and Shoreline Protection (580), Vegetated Treatment Area (635), Wetland Enhancement (659), or Wetland Restoration (657). This practice can be used nation wide. The typical setting for this scenario is usually a narrow strip between the aquatic and terrestrial habitats subject to intermittent flooding and saturated soils where the existing plant community has been disturbed, destroyed, or the species diversity is unable to provide proper function and/or adequate habitat. Where the establishment of a diverse riparian herbaceous plant community is desired, an adapted mix of primarily native warm season grasses tolerant to the site conditions will be planted by broadcast and/or no-till or range drill seeding methods as necessary to accomplish the intended purpose(s) and legumes, and/or forbs are expected to naturally regenerate on-site. Where chemical control of undesirable vegetation, including invasive, is required to reduce competition for the desired plant community the Herbaceous Weed Control (315) practice should be used. Seedbed preparation may require LIGHT TILLAGE (disking). WHEN POLLINATOR HABITAT IS A CONSIDERATION: Include 5-10 adapted forb species that bloom sequentially throughout the growing season where feasible. To address the high diversity of riparian plant communities and their adjacent stream types that exist from the tropics to the tundra, and the deserts, prairies, mountains, and lowlands across the various regions and/or MLRA's, up to 20 adapted riparian plant community-specific scenarios may be required

Before Situation:

The riparian zone, the specific area between terrestrial and aquatic habitats, is currently an undesirable or inadequate stand of perennial or annual vegetation and natural reseeding or vegetation management is unlikely to improve the plant community within a reasonable amount of time to adequately address streambank and/or shoreline stability, dissipate stream energy and trap sediment, improve and/or maintain water quality, and/or provide adequate habitat corridors, food and/or cover for fish, wildlife, pollinators, and/or livestock resource concern(s). Existing conditions often require suppression or eradication of current vegetation by conventional mechanical or chemical (Herbaceous Weed Control (315)) methods to ensure establishment success of the new planting.

After Situation:

The riparian zone, the transitional zone between the terrestrial and aquatic habitats, is established to an adapted, diverse vegetative plant community and is under close management to insure long term survival and ecological succession. The quality and quantity of the riparian zone components are managed to support the species that depend on it for habitat as well as the functions it performs for stabilizing the streambank and/or shoreline, dissipating stream energy and trapping sediment, and improving and/or maintaining water quality. These functions include: stream temperature moderation through shading, recruitment of non-woody organic matter, habitat for terrestrial insects and other riparian dependent species, streambank integrity, and filtration of contaminants from surface run-off into the stream.

Feature Measure: Acres of Riparian Herbaceous Cove

Scenario Unit:: Acre

Scenario Typical Size: 0.0

Scenario Total Cost: $144.38

Scenario Cost/Unit: #Div/0!

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	1	$11.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	1	$21.71
Materials						
One Species, Native Forb, Low Cost	2329	Native forb. Includes material and shipping only.	Acre	$179.65	0.5	$89.83

Practice: 390 - Riparian Herbaceous Cover

Scenario #2 - Native Warm Season Grass w/ Forbs

Scenario Description:

Planting Native Warm Season Grasses with Forbs: This scenario addresses inadequate herbaceous plant community function or diversity within the specific transitional zone between terrestrial and aquatic habitats in rangeland, pasture, cropland, and forest where natural seeding methods and/or management is unlikely to improve the plant community within a reasonable time period. This scenario applies to work not covered under NRCS Conservation Practice Range Planting (528), Forage and Biomass Planting (512), Critical Area Planting (342), Filter Strip (393), Restoration and Management of Rare and Declining Habitats (643), Streambank and Shoreline Protection (580), Vegetated Treatment Area (635), Wetland Enhancement (659), or Wetland Restoration (657). This practice can be used nation wide. The typical setting for this scenario is usually a narrow strip between the aquatic and terrestrial habitats subject to intermittent flooding and saturated soils where the existing plant community has been disturbed, destroyed, or the species diversity is unable to provide proper function and/or adequate habitat. Where the establishment of a diverse riparian herbaceous plant community is desired, an adapted mix of primarily native warm season grasses, legumes, and/or forbs tolerant to the site conditions will be planted by broadcast and/or no-till or range drill seeding methods as necessary to accomplish the intended purpose(s). Where chemical control of undesirable vegetation, including invasive, is required to reduce competition for the desired plant community the Herbaceous Weed Control (315) practice should be used. Seedbed preparation may require LIGHT TILLAGE (disking). WHEN POLLINATOR HABITAT IS A CONSIDERATION: Include 5-10 adapted forb species that bloom sequentially throughout the growing season where feasible. To address the high diversity of riparian plant communities and their adjacent stream types that exist from the tropics to the tundra, and the deserts, prairies, mountains, and lowlands across the various regions and/or MLRA's, up to 20 adapted riparian plant community-specific scenarios may be required.

Before Situation:

The riparian zone, the specific area between terrestrial and aquatic habitats, is currently an undesirable or inadequate stand of perennial or annual vegetation and natural reseeding or vegetation management is unlikely to improve the plant community within a reasonable amount of time to adequately address streambank and/or shoreline stability, dissipate stream energy and trap sediment, improve and/or maintain water quality, and/or provide adequate habitat corridors, food and/or cover for fish, wildlife, pollinators, and/or livestock resource concern(s). Existing conditions often require suppression or eradication of current vegetation by conventional mechanical or chemical (Herbaceous Weed Control (315)) methods to ensure establishment success of the new planting.

After Situation:

The riparian zone, the transitional zone between the terrestrial and aquatic habitats, is established to an adapted, diverse vegetative plant community and is under close management to insure long term survival and ecological succession. The quality and quantity of the riparian zone components are managed to support the species that depend on it for habitat as well as the functions it performs for stabilizing the streambank and/or shoreline, dissipating stream energy and trapping sediment, and improving and/or maintaining water quality. These functions include: stream temperature moderation through shading, recruitment of non-woody organic matter, habitat for terrestrial insects and other riparian dependent species, streambank integrity, and filtration of contaminants from surface run-off into the stream.

Feature Measure: Acres of Riparian Herbaceous Cove

Scenario Unit:: Acre

Scenario Typical Size: 0.0

Scenario Total Cost: $231.04

Scenario Cost/Unit: #Div/0!

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	1	$11.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	1	$21.71
Materials						
One Species, Native Forb, Low/Moderate Cost	2330	Native forb. Includes material and shipping only.	Acre	$392.19	0.45	$176.49

Practice: 391 - Riparian Forest Buffer

Scenario #1 - Hardwood with Pasture Foregone Income

Scenario Description:

Establish a buffer of hardwood trees into a suitably prepared pasture site to restore riparian plant communities and associated benefits. The buffer will be located adjacent to and up-gradient from a watercourse or water body extending a minimum of 35 feet wide. The planting will consist of hand planted bare-root deciduous trees. Generally, planting spacing is at 12' x 12'; however, other spacing may be used depending on the objectives. Resource concerns to be addressed are Soil Erosion - excessive bank erosion; Water Quality - excess sediment and organics in surface waters and elevated temperature; Degraded Plant Condition - inadequate structure and composition; and Inadequate Habitat for Fish and Wildlife - habitat degradation.

Before Situation:

Typical sites include former riparian forests and habitat used for forage, cropland, speculation property, or other nonforest condition which contains undesirable amounts or types of vegetation. Active bank erosion is depositing sediment, nutrients and organics in the riparian area. Water temperature is high due to lack of shade. Habitat is not desirable for wildlife.

After Situation:

A buffer of trees will be established along the riparian corridor which will provide stability, filtration, shade, and desirable habitat to address the above mentioned resource concerns.

Feature Measure: Area of planting

Scenario Unit:: Acre

Scenario Typical Size: 5.0

Scenario Total Cost: $1,681.14

Scenario Cost/Unit: $336.23

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	8	$228.64
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	16	$197.76
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	10	$169.30
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Tree, hardwood, seedling or transplant, bare root, 6-18"	1509	Bare root hardwood trees 6-18" tall. Includes materials and shipping only.	Each	$0.26	1500	$390.00
Mobilization						
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	$1.02	100	$102.00

Practice: 391 - Riparian Forest Buffer

Scenario #2 - Hardwood with Row Crop Foregone Income

Scenario Description:

Establish a buffer of hardwood into a suitably prepared row crop site to restore riparian plant communities and associated benefits. The buffer will be located adjacent to and up-gradient from a watercourse or water body extending a minimum of 35 feet wide. The planting will consist of hand planted bare-root deciduous trees. Generally, planting spacing is at 12' x 12'; however, other spacing may be used depending on the objectives. Resource concerns to be addressed are Soil Erosion - excessive bank erosion; Water Quality - excess sediment and organics in surface waters and elevated temperature; Degraded Plant Condition - inadequate structure and composition; and Inadequate Habitat for Fish and Wildlife - habitat degradation.

Before Situation:

Typical sites include former riparian forests and habitat used for forage, cropland, speculation property, or other nonforest condition which contains undesirable amounts or types of vegetation. Active bank erosion is depositing sediment, nutrients and organics in the riparian area. Water temperature is high due to lack of shade. Habitat is not desirable for wildlife.

After Situation:

A buffer of trees will be established along the riparian corridor which will provide stability, filtration, shade, and desirable habitat to address the above mentioned resource concerns.

Feature Measure: Area of planting

Scenario Unit:: Acre

Scenario Typical Size: 5.0

Scenario Total Cost: $2,547.39

Scenario Cost/Unit: $509.48

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	8	$228.64
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	16	$197.76
Foregone Income						
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	5	$1,035.55
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Tree, hardwood, seedling or transplant, bare root, 6-18"	1509	Bare root hardwood trees 6-18" tall. Includes materials and shipping only.	Each	$0.26	1500	$390.00
Mobilization						
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	$1.02	100	$102.00

Practice: 391 - Riparian Forest Buffer

Scenario #3 - Hardwood Seedlings, Bare-root

Scenario Description:

Establish deciduous trees into a suitably prepared site to restore riparian plant communities and associated benefits. The tree planting will be located adjacent to a planned buffer of hardwood trees that is immediately adjacent to the stream and up-gradient from a watercourse or water body. The planting will consist of hand planted deciduous trees. Generally, spacing for deciduous tree planting is 12' x 12'; however, other spacing may be used depending on the objective. Resource concerns to be addressed are Soil Erosion - excessive bank erosion; Water Quality - excess sediment and organics in surface waters and elevated temperature; Degraded Plant Condition - inadequate structure and composition; and Inadequate Habitat for Fish and Wildlife - habitat degradation.

Before Situation:

Typical sites include former riparian forests and habitat used for forage, cropland, speculation property, or other nonforest condition which contains undesirable amounts or types of vegetation. Active bank erosion is depositing sediment, nutrients and organics in the riparian area. Water temperature is high due to lack of shade. Habitat is not desirable for wildlife.

After Situation:

A buffer of trees and shrubs will be established along the riparian corridor which will provide stability, filtration, shade, and desirable habitat to address the above mentioned resource concerns.

Feature Measure: Area of planting

Scenario Unit:: Each

Scenario Typical Size: 1,500.0

Scenario Total Cost: $1,095.04

Scenario Cost/Unit: $0.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	10	$123.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	10	$190.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Tree, hardwood, seedling or transplant, bare root, 6-18"	1509	Bare root hardwood trees 6-18" tall. Includes materials and shipping only.	Each	$0.26	1500	$390.00
Mobilization						
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	$1.02	100	$102.00

Practice: 391 - Riparian Forest Buffer

Scenario #4 - Pine Seedlings, Bare-root

Scenario Description:

Establish pine trees as part of a planned forest buffer into a suitably prepared site to restore riparian plant communities and associated benefits. The buffer will be located adjacent to and up-gradient from a watercourse or water body extending a minimum of 35 feet wide. The planting will consist of hand planted pine seedlings outside the 35' buffer immediately adjacent to the stream which must be hardwood. Planting spacing is generally at 6' x 12'; however, other spacing may be used depending on the objective. Resource concerns to be addressed are Soil Erosion - excessive bank erosion; Water Quality - excess sediment and organics in surface waters and elevated temperature; Degraded Plant Condition - inadequate structure and composition; and Inadequate Habitat for Fish and Wildlife - habitat degradation.

Before Situation:

Typical sites include former riparian forests and habitat used for forage, cropland, speculation property, or other nonforest condition which contains undesirable amounts or types of vegetation. Active bank erosion is depositing sediment, nutrients and organics in the riparian area. Water temperature is high due to lack of shade. Habitat is not desirable for wildlife.

After Situation:

A buffer of trees will be established along the riparian corridor which will provide stability, filtration, shade, and desirable habitat to address the above mentioned resource concerns.

Feature Measure: Number planted

Scenario Unit:: Each

Scenario Typical Size: 3,000.0

Scenario Total Cost: $855.04

Scenario Cost/Unit: $0.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	10	$123.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	10	$190.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Tree, conifer, seedling, bare root, 1-0	1512	Bare root conifer trees, 1-0 (1 year old). Includes materials and shipping only.	Each	$0.05	3000	$150.00
Mobilization						
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	$1.02	100	$102.00

Practice: 391 - Riparian Forest Buffer

Scenario #5 - Shrub Seedlings, Bare-root

Scenario Description:

Establish shrub seedlings as part of a planned forest buffer into a suitably prepared site to restore riparian plant communities and associated benefits. The buffer will be located adjacent to and up-gradient from a watercourse or water body extending a minimum of 35 feet wide. The planting will consist of hand planted shrub seedlings outside the 35' hardwood buffer immediately adjacent to the stream. Generally, planting for shrubs will be done at 6' x 6' spacing. However, other spacing may be used depending on the objective. Resource concerns to be addressed are Soil Erosion - excessive bank erosion; Water Quality - excess sediment and organics in surface waters and elevated temperature; Degraded Plant Condition - inadequate structure and composition; and Inadequate Habitat for Fish and Wildlife - habitat degradation.

Before Situation:

Typical sites include former riparian forests and habitat used for forage, cropland, speculation property, or other nonforest condition which contains undesirable amounts or types of vegetation. Active bank erosion is depositing sediment, nutrients and organics in the riparian area. Water temperature is high due to lack of shade. Habitat is not desirable for wildlife.

After Situation:

A buffer of trees and shrubs will be established along the riparian corridor which will provide stability, filtration, shade, and desirable habitat to address the above mentioned resource concerns.

Feature Measure: Number planted

Scenario Unit:: Each

Scenario Typical Size: 1,000.0

Scenario Total Cost: $1,165.04

Scenario Cost/Unit: $1.17

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	10	$123.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	10	$190.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Shrub, seedling or transplant, bare root, 6-18"	1506	Bare root hardwood trees 6-18" tall. Includes materials and shipping only.	Each	$0.46	1000	$460.00
Mobilization						
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	$1.02	100	$102.00

Practice: 393 - Filter Strip

Scenario #29 - Filter Strip, Native species, Forgone Income

Scenario Description:

A strip or area of herbaceous vegetation that removes contaminants from overland flow. Practice includes seedbed prep and planting of native species. The area of the filter strip is taken out of production.

Before Situation:

Annual cropland, grazing land, or disturbed land (including forestland) allows for runoff of suspended solids, dissolved and/or associated contaminants into environmentally-sensitive areas such as wetlands, riparian zones, critical habitat and neighboring non-ag properties. Water Quality resource concerns are associated with this practice.

After Situation:

The 393 Implementation Requirements are developed for the site and applied. The planned filter strip will be established and maintained per the practice plan that will meet the criteria for the planned purpose(s). The vegetation will consist of native species. The filter strip will have adequate width to filter the planned pollutants. The practice includes seedbed preparation, seeding, and seed. Species selected shall be able to withstand partial burial by sediment and tolerant of herbicides used on the contribution area while protecting environmentally-sensitive areas. The area of the filter strip is taken out of production.

Feature Measure: number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $490.12

Scenario Cost/Unit: $490.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	3	$33.78
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	1.5	$42.87
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.5	$197.08
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.5	$103.56
Materials						
Two Species Mix, Warm Season, Native Perennial Grass	2325	Native, warm season perennial grass. Includes material and shipping only.	Acre	$91.25	1	$91.25

Practice: 393 - Filter Strip

Scenario #30 - Filter Strip, Introduced species, Forgone Income

Scenario Description:

A strip or area of herbaceous vegetation that removes contaminants from overland flow. Practice includes seedbed prep and planting of introduced species. The area of the filter strip is taken out of production.

Before Situation:

Annual cropland, grazing land, or disturbed land (including forestland) allows for runoff of suspended solids, dissolved and/or associated contaminants into environmentally-sensitive areas such as wetlands, riparian zones, critical habitat and neighboring non-ag properties. Water Quality resource concerns are associated with this practice.

After Situation:

The 393 Implementation Requirements are developed for the site and applied. The planned filter strip will be established and maintained per the practice plan that will meet the criteria for the planned purpose(s). The vegetation will consist of introduced species. The filter strip will have adequate width to filter the planned pollutants. The practice includes seedbed preparation, seeding, and seed. Species selected shall be able to withstand partial burial by sediment and tolerant of herbicides used on contribution area while protecting environmentally-sensitive areas. The area of the filter strip is taken out of production.

Feature Measure: Number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $475.66

Scenario Cost/Unit: $475.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	3	$33.78
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	1	$6.69
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	1.5	$42.87
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.5	$197.08
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.5	$103.56
Materials						
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.42	30	$12.60
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	20	$9.60
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	$47.90	1	$47.90

Practice: 393 - Filter Strip

Scenario #32 - Filter Strip, Native species

Scenario Description:

A strip or area of herbaceous vegetation that removes contaminants from overland flow. Practice includes seedbed prep and planting of native species.

Before Situation:

Annual cropland, grazing land, or disturbed land (including forestland) allows for runoff of suspended solids, dissolved and/or associated contaminants into environmentally-sensitive areas such as wetlands, riparian zones, critical habitat and neighboring nonagricultural properties. Water Quality resource concerns are associated with this practice.

After Situation:

The 393 Implementation Requirements are developed for the site and applied. The planned filter strip will be established and maintained per the practice plan that will meet the criteria for the planned purpose(s). The vegetation will consist of native species. The filter strip will have adequate width to filter the planned pollutants. The practice includes seedbed preparation, seeding, and seed. Species selected shall be able to withstand partial burial by sediment and tolerant of herbicides used on contribution area while protecting environmentally-sensitive areas.

Feature Measure: number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $166.67

Scenario Cost/Unit: $166.67

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	3	$33.78
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	1.5	$42.87
Materials						
One Species, Warm Season, Native Perennial Grass	2322	Native, warm season perennial grass. Includes material and shipping only.	Acre	$68.44	1	$68.44

Practice: 393 - Filter Strip

Scenario #33 - Filter Strip, Introduced species

Scenario Description:

A strip or area of herbaceous vegetation that removes contaminants from overland flow. Practice includes seedbed prep and planting of introduced species.

Before Situation:

Annual cropland, grazing land, or disturbed land (including forestland) allows for runoff of suspended solids, dissolved and/or associated contaminants into environmentally-sensitive areas such as wetlands, riparian zones, critical habitat and neighboring nonagricultural properties. Water Quality resource concerns are associated with this practice.

After Situation:

The 393 Implementation Requirements are developed for the site and applied. The planned filter strip will be established and maintained per the practice plan that will meet the criteria for the planned purpose(s). The vegetation will consist of introduced species. The filter strip will have adequate width to filter the planned pollutants. The practice includes seedbed preparation, seeding, and seed. Species selected shall be able to withstand partial burial by sediment and tolerant of herbicides used on contribution area while protecting environmentally-sensitive areas.

Feature Measure: Number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $175.02

Scenario Cost/Unit: $175.02

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	3	$33.78
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	1	$6.69
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	1.5	$42.87
Materials						
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.42	30	$12.60
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	20	$9.60
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	$47.90	1	$47.90

Practice: 394 - Firebreak

Scenario #1 - Bare Soil - Light Equipment

Scenario Description:

Installation of a bare-ground firebreak of a minimum width of 10' around a 20 acre field/farm using farm equipment (2 passes). Generally water control devices such as water bars are not needed due either to the lack of steep terrain or the temporary nature of the firebreak. Resource concerns include Wildfire hazard from excessive biomass accumulation, Undesirable plant productivity and health, Inadequate plant structure and composition, and Habitat degradation.

Before Situation:

Tract, field, or farm lacks adequate firebreaks to either reduce the spread of wildfires or contain a prescribed burn. Installation will be accomplished by making two passes with the use of typical farm equipment such as tractors, plows, disks, or similar implements.

After Situation:

The property is adequately protected from wildfire or can be safely prescribe burned.

Feature Measure: Length of firebreak

Scenario Unit:: Foot

Scenario Typical Size: 3,000.0

Scenario Total Cost: $553.82

Scenario Cost/Unit: $0.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$66.84	6	$401.04
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	2	$22.52
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	6	$130.26

Practice: 394 - Firebreak

Scenario #4 - Vegetated - Light Equipment

Scenario Description:

Establishing a 30 - 50 foot wide strip of permanent vegetation that will serve as a green firebreak. Scenario includes clearing the site, preparing the seedbed, seeding (typically cool season grasses and/or legumes), and applying needed soil amendments. Clearing will be achieved with the use of a bush hog or similar equipment. Seedbed preparation and vegetation establishment will be accomplished with farm equipment. Soil amendments will be applied according to local FOTG guidance. This scenario does not include follow-up maintenance operations such as weed control. mowing, etc. Resource concerns include Wildfire hazard from excessive biomass accumulation, Soil erosion, and Excessive sediment in surface waters.

Before Situation:

Tract, field, or farm lacks adequate firebreaks to either reduce the spread of wildfires or contain a prescribed burn.

After Situation:

The property is adequately protected from wildfire or can be safely prescribe burned. Wildlife habitat will also be enhanced and the potential for erosion from the firebreak is minimized.

Feature Measure: Length of firebreak

Scenario Unit:: Foot

Scenario Typical Size: 4,000.0

Scenario Total Cost: $1,558.98

Scenario Cost/Unit: $0.39

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	4	$88.08
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	4	$209.84
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	4	$45.04
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	4	$67.12
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	4	$24.80
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	4	$26.76
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$10.75	4	$43.00
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	$12.74	4	$50.96
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	4	$86.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Nitrogen (N), Ammonium Nitrate	69	Price per pound of N supplied by Ammonium Nitrate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.57	160	$91.20
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	200	$96.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.36	200	$72.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	$32.76	4	$131.04
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.98	4	$75.92
One Species, Cool Season, Introduced Perennial Grass	2313	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	$31.57	4	$126.28
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: 395 - Stream Habitat Improvement and Management

Scenario #23 - Instream wood placement

Scenario Description:

This scenario involves placement of large wood (logs, root wads, log structures) into a stream channel in order to improve aquatic habitat that currently does not meet quality criteria for stream species habitat. A stream assessment (i.e. Stream Visual Assessment Protocol) should be conducted in order to document habitat components lacking for aquatic species (i.e. large wood, pools). A project design for wood placement will be based on assessment of the target stream reach characteristics and those of a suitable reference reach. These characteristics include channel geometry, channel slope, stream bottom substrate size and composition, and the geomorphic setting influencing the channel form, pattern and profile. Large wood and root wads placed into the stream will mimic genus, age, and size of mature trees found in intact, reference riparian areas in the MLRA where the project is located. Large wood/trees with root wads intact should be placed in streams to create pool habitat according to NRCS engineering specifications and with close review & approval of a fish habitat biologist. Boulders placed to provide ballast shall only be used if the geomorphic setting and project design demand this component. The planned activity will meet the current 395 standard, and facilitating practice standards utilized, including timing of work windows required for protected aquatic and riparian species, and protecting/restoring vegetation and substrates of/to areas impacted by heavy equipment. Implementation will result in the improvement of instream habitat complexity, hiding and resting cover, and/or increased food availability for fish and other stream species. Payment for implementation is to defray the costs of project implementation. Monitoring records demonstrating implementation of this scenario will address resource concerns for stream species of concern are required.

Before Situation:

In this stream reach, habitat for fish, aquatic insects and/or other stream species is sub-optimal as determined by the NRCS Stream Visual Assessment Protocol score of less than 5 overall. The site does not have adequate food, cover, and perhaps habitat connectivity for desired species. Riparian vegetation quality and/or quantity may also be compromised to the extent that the riparian area and floodplain are not functioning to provide necessary stream and riparian habitat components, such as large wood.

After Situation:

Stream habitat within the project reach is improving as a result of placing logs, root wads, and/or wood structures in the channel and/or along the stream bank. Pool habitat in the reach is improved, and hiding cover, food availability and refuge habitat for all stream species is improving.

Feature Measure: Bankfull width x reach length

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $20,853.78

Scenario Cost/Unit: $20,853.78

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	16	$2,659.20
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	8	$782.00
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	24	$616.32
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	$30.09	20	$601.80
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	$30.50	30	$915.00
Compost	265	A mixture of decaying organic matter, as from leaves and manure, used to improve soil structure and provide nutrients.	Ton	$41.44	1	$41.44
Cuttings, woody, large size	1309	Woody pole cuttings or posts 2" to 6" in diameter and 6' long. Includes materials and shipping only.	Each	$17.74	300	$5,322.00
Boulder	1761	Rock boulders (approximately 5 ft dia. 6.67 Tons) Inlcudes materials and delivery (up to 100 miles) only.	Ton	$34.95	40	$1,398.00
Steel, rebar	1832	Steel rebar, grade 60. Materials only.	Pound	$0.50	50	$25.00
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	$25.58	15	$383.70
Log, un-anchored	2035	Price of log picked up at the Mill. Includes material only.	Ton	$231.59	30	$6,947.70
Root Wad	2045	Tree stump buried into the streambank with the roots left exposed. Includes material only.	Ton	$9.08	20	$181.60
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 395 - Stream Habitat Improvement and Management

Scenario #24 - Instream rock placement

Scenario Description:

This scenario describes the implementation of a stream habitat improvement and management project that places individual boulders or boulder clusters, or rock structures in or adjacent to the stream channel as habitat components. A project design for boulder placement will be based on assessment of the target stream reach characteristics and those of a suitable reference reach. These characteristics include channel geometry, channel slope, stream bottom substrate size and composition, and the geomorphic setting influencing the channel form, pattern and profile. Large rocks/boulders placed in the stream channel will mimic geologic material sizes typically present in the watershed or observed in intact, reference stream reaches in the MLRA where the project is located. Boulders should be placed in streams to create pool habitat and hydraulic complexity according to NRCS engineering specifications and with close review & approval of a fish habitat biologist onsite during implementation of the project design. Spawning gravel placement should be placed to restore spawning area substrates potentially disturbed by rock placement. The planned activity will meet the current 395 standard, and facilitating practice standards utilized. Implementation will result in the improvement of instream habitat complexity, hiding and resting cover, spawning habitat, and/or increased food availability for fish and other stream species. Payment for implementation is to defray the costs of stream habitat assessment, and project implementation. Records demonstrating implementation of this scenario will address resource concerns for stream species of concern will be required.

Before Situation:

In this stream reach, habitat for fish, aquatic insects and other stream species is sub-optimal as determined by the NRCS Stream Visual Assessment Protocol score of less than 5 overall. The site does not have adequate food, cover, and perhaps habitat connectivity for desired species. Riparian vegetation quality and/or quantity may be also compromised to the extent that the riparian area and floodplain are not functioning to provide necessary stream and riparian habitat components, such as large wood, leaf matter, and shade.

After Situation:

Stream habitat within the project reach is improving as a result of placing boulders or constructing rock structures in the channel and/or along the stream bank. Hydraulic complexity of the habitat in the reach is increased, and hiding cover, food availability and refuge habitat for stream species is improving. Streambank vegetation is increasing and contributing to stability of the streambanks.

Feature Measure: Bankfull width x reach length

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $14,286.84

Scenario Cost/Unit: $14,286.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	16	$2,659.20
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	8	$782.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	24	$616.32
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	$30.09	30	$902.70
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	$30.50	120	$3,660.00
Cuttings, woody, large size	1309	Woody pole cuttings or posts 2" to 6" in diameter and 6' long. Includes materials and shipping only.	Each	$17.74	100	$1,774.00
Boulder	1761	Rock boulders (approximately 5 ft dia. 6.67 Tons) Inlcudes materials and delivery (up to 100 miles) only.	Ton	$34.95	60	$2,097.00
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	$25.58	20	$511.60
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 395 - Stream Habitat Improvement and Management

Scenario #25 - Rock and wood structures

Scenario Description:

This scenario describes the implementation of a stream habitat improvement and management project where practices are focused on instream habitat improvement with a combination of rock AND wood structures. This scenario involves placement of large wood and rock structures into a stream channel in order to improve aquatic habitat that currently does not meet quality criteria for stream species habitat. A stream assessment (i.e. Stream Visual Assessment Protocol) should be conducted in order to document habitat components (such as large wood, pools) are not currently present in the stream or are limited for aquatic species. A project design for placement of habitat structures (boulders, boulder clusters, wood, wood structures) will be based on assessment of (a) the target stream reach characteristics and (b) those of a suitable reference reach. These characteristics include channel geometry, channel slope, stream bottom substrate size and composition, and the geomorphic setting influencing the channel form, pattern and profile. Large rocks/boulders placed in the stream channel will mimic geologic material sizes typically present in the watershed or observed in intact, reference stream reaches in the MLRA where the project is located. Rock boulder sizes should also reflect the geomorphic setting of the stream reach. Large wood placed into the stream under this scenario should be similar in species, age, and size (diameter) as trees found in the surrounding riparian area, to the extent possible. Wood, boulders and/or boulder clusters will be placed in the stream to create pool habitat and hydraulic complexity according to NRCS engineering specifications and with close review & approval of a fish habitat biologist onsite during the planning and implementation of the project. This scenario involves restoring one acre of stream. The planned activity will meet the current 395 standard, and facilitating practice standards utilized. Implementation will result in the improvement of instream habitat complexity, hiding and resting cover, and/or increased food availability for fish and other stream species. Payment for implementation is to defray the costs of project implementation. Records demonstrating implementation of this scenario will address resource concerns for stream species of concern will be required.

Before Situation:

In this stream reach, habitat for fish, aquatic insects and/or other stream species is sub-optimal as determined by the NRCS Stream Visual Assessment Protocol score of less than 5. The site does not have adequate food, cover, and perhaps habitat connectivity for desired species. Riparian vegetation quality and/or quantity may also be compromised to the extent that the riparian area and floodplain are not functioning to provide necessary stream habitat components, such as large wood and off-channel refuge habitat.

After Situation:

Stream habitat within the project reach is improving as a result of placing logs, rocks, or constructing wood and rock structures in the channel and/or along the stream bank. Pool habitat in the reach is improved, and hiding cover, food availability and refuge habitat for all stream species is improving.

Feature Measure: stream length X bankfull width

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $32,667.03

Scenario Cost/Unit: $32,667.03

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	16	$2,659.20
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	8	$782.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	60	$1,642.80
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	24	$456.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	24	$616.32
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	180	$6,512.40
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	32	$2,693.76
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	$30.09	17	$511.53
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	$30.50	60	$1,830.00
Compost	265	A mixture of decaying organic matter, as from leaves and manure, used to improve soil structure and provide nutrients.	Ton	$41.44	1	$41.44

Cuttings, woody, large size	1309	Woody pole cuttings or posts 2" to 6" in diameter and 6' long. Includes materials and shipping only.	Each	$17.74	300	$5,322.00
Boulder	1761	Rock boulders (approximately 5 ft dia. 6.67 Tons) Inlcudes materials and delivery (up to 100 miles) only.	Ton	$34.95	40	$1,398.00
Steel, rebar	1832	Steel rebar, grade 60. Materials only.	Pound	$0.50	8	$4.00
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	$25.58	7	$179.06
Log, un-anchored	2035	Price of log picked up at the Mill. Includes material only.	Ton	$231.59	30	$6,947.70
Root Wad	2045	Tree stump buried into the streambank with the roots left exposed. Includes material only.	Ton	$9.08	10	$90.80
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 396 - Aquatic Organism Passage

Scenario #31 - Concrete Dam Removal

Scenario Description:

Full or partial removal of a concrete or earthen dam to restore aquatic organism passage, improve water quality, and promote functional river ecology and geomorphology. The extent of removal (full or partial) is determined through consultations with the dam owner in consideration of prevailing regulations and site historical status. Adjacent floodplain surfaces above and below the target dam are considered in the planning process to account for shifts in streamflow and geomorphic regime. Resulting channel dimensions and profile are determined on a site-specific basis to reflect--to the fullest extent possible--pre-dam conditions. Pre-removal sediment assays are completed to determine the toxicity of sediment stored behind the dam. Planning for the reclamation and management of stored sediments is completed according to geomorphic conditions, prevailing regulations, and the results of sediment toxicity investigations. Removal is done with an assortment of equipment, including tracked excavators outfitted with hydraulic chisels, hammers and/or buckets with "thumbs", bull dozers, skid steers, cranes, front-end loaders, and dump trucks. Alternative demolition techniques may include the use of high explosives, diamond-chain, or similar circular saws to remove the dam in a piecewise manner. Removed materials are trucked away and disposed or recycled off-site. Disturbed areas are revegetated with a mix of site-adapted species. Scenario does not include additional measures needed in the active channel and floodplain to account for post-removal changes to stream plan, pattern, or profile, or reclamation of any former impounded areas. Additional structural measures may be necessary to address constructed features associated with the removed dam including canals, raceways, adjacent spillways, navigation locks, access and maintenance roads, or similar civil works. RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE –Habitat degradation; EXCESS WATER – Ponding, flooding, seasonal high water table, seeps, and drifted snow; WATER QUALITY DEGRADATION – Elevated water temperature. Payments for these associated practices are made separately and are covered by other typical scenarios and payment schedules. See relevant CPS for additional information. ---Site Preparation and Reclamation associated with project footprint: (326) Clearing and Snagging, (342) Critical Area Planting, (382) Fence, (390) Riparian Herbaceous Cover, (391) Riparian Forest Buffer, (612) Tree/Shrub Establishment ---Reach Planning/Habitat Enhancement: (395) Stream Habitat Improvement and Management, ---Structural Measures Associated with Scenario but outside of project footprint: (410) Grade Stabilization Structure, (584) Channel Bed Stabilization, (580) Streambank and Shoreline Protection, (587) Structure for Water Control

Before Situation:

A channel-spanning concrete dam no longer has functional use, may be failing, or creates a hazard to downstream capital infrastructure or communities. The dam blocks upstream aquatic organism migration, and downstream migrants may be diverted into hydraulic structures that increase mortality or result in migration delays or dead-ends. The dam disrupts the downstream cycling and transport of sediment, woody material and nutrients. The pool created by the dam may impair water quality by increasing temperatures, capturing fine sediment--sometimes laden with heavy metals or other pollutants--later mobilized by high flow events, and creating slackwater habitat for invasive aquatic vegetation. Non-native or exotic fish species inhabit the pool and predate upon and/or displace native fish.

After Situation:

The existing dam is removed and reach geometry and slope are restored to pre-dam conditions to the fullest extent practicable. Aquatic organism passage and river ecology and geomorphic conditions are restored to pre-dam conditions to the fullest extent practicable. Resource Concerns are addressed within the context of the site.

Feature Measure: Cubic Yards of concrete in dam and

Scenario Unit:: Cubic Yard

Scenario Typical Size: 250.0

Scenario Total Cost: $36,702.02

Scenario Cost/Unit: $146.81

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Clearing and Grubbing	40	Clearing and Grubbing, includes materials, equipment and labor	Acre	$286.81	1.5	$430.22
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	$125.35	20	$2,507.00
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	60	$9,972.00
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$45.08	60	$2,704.80
Water management, Flooding & dewatering	969	Includes equipment and power unit. Labor not included.	Acre Foot	$139.03	6	$834.18
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	80	$7,820.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	80	$2,190.40
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	60	$1,140.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	220	$5,649.60
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	40	$1,447.20

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	4	$1,026.60
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 396 - Aquatic Organism Passage

Scenario #32 - Earthen Dam Removal

Scenario Description:

Full removal of an earthen dam to restore aquatic organism passage, improve water quality, and promote functional river ecology and geomorphology. The removal extent is determined through consultations with the dam owner in consideration of prevailing regulations and site historical status. Adjacent floodplain surfaces above and below the target dam are considered in the planning process to account for shifts in streamflow and geomorphic regime. Resulting channel dimensions and profile are determined on a site-specific basis to reflect, to the fullest extent possible, pre-dam conditions. Pre-removal sediment assays are be completed as necessary to determine the toxicity of sediment stored behind the dam. Planning for the reclamation and management of stored sediments is completed according to geomorphic conditions, prevailing regulations, and the results of sediment toxicity investigations. Removal is done with an assortment of equipment, including tracked excavators outfitted with hydraulic chisels, hammers and/or buckets with "thumbs", bull dozers, skid steers, cranes, front-end loaders, and dump trucks. Removed materials are trucked away and disposed or recycled off-site, unless native streambed material found in the embankment can be used in site reclamation. Disturbed areas are revegetated with a mix of site-adapted species. Scenario does not include additional measures needed in the active channel and floodplain to account for post-removal changes to stream plan, pattern, or profile, or reclamation of any former impounded areas. Additional structural measures may be necessary to address constructed features associated with the removed dam including head gates, canals, raceways, access and maintenance roads, or similar civil works. RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE –Habitat degradation; EXCESS WATER – Ponding, flooding, seasonal high water table, seeps, and drifted snow; WATER QUALITY DEGRADATION – Elevated water temperature. Payments for these associated practices are made separately and are covered by other typical scenarios and payment schedules. See relevant CPS for additional information. ---Site Preparation and Reclamation associated with project footprint: (326) Clearing and Snagging, (342) Critical Area Planting, (382) Fence, (390) Riparian Herbaceous Cover, (391) Riparian Forest Buffer, (612) Tree/Shrub Establishment ---Reach Planning/Habitat Enhancement: (395) Stream Habitat Improvement and Management, ---Structural Measures Associated with Scenario but outside of project footprint: (410) Grade Stabilization Structure, (584) Channel Bed Stabilization, (580) Streambank and Shoreline Protection, (587) Structure for Water Control

Before Situation:

A channel-spanning earthen dam no longer has functional use, may be failing, or creates a hazard to downstream capital infrastructure or communities. The dam blocks upstream aquatic organism migration, and downstream migrants may be diverted into hydraulic structures that increase mortality or result in migration delays or dead-ends. The dam disrupts the downstream cycling and transport of sediment, woody material and nutrients. The pool created by the dam may impair water quality by increasing temperatures, capturing fine sediment--sometimes laden with heavy metals or other pollutants--later mobilized by high flow events, and creating slackwater habitat for invasive aquatic vegetation. Non-native or exotic fish species inhabit the pool and predate upon and/or displace native fish.

After Situation:

The existing dam is removed and reach geometry and slope are restored to pre-dam conditions to the fullest extent practicable. Aquatic organism passage and river ecology and geomorphic conditions are restored to pre-dam conditions to the fullest extent practicable. Resource Concerns are addressed within the context of the site.

Feature Measure: Cubic Yards of earthen embankme

Scenario Unit:: Cubic Yard

Scenario Typical Size: 500.0

Scenario Total Cost: $31,966.63

Scenario Cost/Unit: $63.93

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Clearing and Grubbing	40	Clearing and Grubbing, includes materials, equipment and labor	Acre	$286.81	3	$860.43
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	$125.35	40	$5,014.00
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	60	$9,972.00
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$45.08	60	$2,704.80
Water management, Flooding & dewatering	969	Includes equipment and power unit. Labor not included.	Acre Foot	$139.03	6	$834.18
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	60	$5,865.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	40	$1,095.20
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	60	$1,140.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	40	$1,027.20
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	40	$1,447.20
Mobilization						

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	4	$1,026.60
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 396 - Aquatic Organism Passage

Scenario #33 - Blockage Removal

Scenario Description:

Removal of passage barriers, including small relict earthen diversions (e.g., splash dams), failing or undersized culverts, and sediment or large woody material (>10cm diameter and 2m length) from mass wasting or major flood events. Instream material associated with the previously mentioned circumstances or structures prevents aquatic organism passage by the creation of channel-spanning blockages, or areas of shallow depth, high velocities, or extensive changes in water surface elevation. In addition, these features may encourage abrupt channel changes that endanger adjacent capital infrastructure or transportation corridors. Excessive streambank erosion by flows deflected around or impounded behind these features may impair water quality by introducing fine sediment out of phase with the natural hydrograph and the life history requirements of native aquatic species. Removal is done with an assortment of equipment, including tracked excavators outfitted with buckets with "thumbs", bull dozers, skid steers, front-end loaders, and dump trucks. The channel and adjacent floodplain are restored to pre-blockage conditions to the fullest extent practicable. Removed materials are trucked away and disposed or recycled off-site, unless native streambed material found in the blockage can be used in site reclamation. Large woody material, if present, is used for instream reclamation, replaced in the channel downstream of the blockage, or trucked offsite for disposal or stockpiling for future projects. Disturbed areas are revegetated with a mix of site-adapted species. Scenario does not include additional measures needed in the active channel and floodplain. RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE –Habitat degradation; EXCESS WATER – Ponding, flooding, seasonal high water table, seeps, and drifted snow; WATER QUALITY DEGRADATION – Elevated water temperature; SOIL EROSION– Excessive bank erosion from streams shorelines or water conveyance channels Payments for these associated practices are made separately and are covered by other typical scenarios and payment schedules. See relevant CPS for additional information. ---Site Preparation and Reclamation associated with project footprint: (342) Critical Area Planting, (382) Fence, (390) Riparian Herbaceous Cover, (391) Riparian Forest Buffer, (612) Tree/Shrub Establishment; (643) Restoration and Management of Rare and Declining Habitats. ---Reach Planning/Habitat Enhancement: (395) Stream Habitat Improvement and Management, ---Structural Measures Associated with Scenario but outside of project footprint: (410) Grade Stabilization Structure, (584) Channel Bed Stabilization, (580) Streambank and Shoreline Protection

Before Situation:

An instream feature spanning the active channel creates hydraulic conditions that exceed the swimming or crawling abilities of native aquatic organisms. Event-driven mass wasting or instream deposits of coarse sediment create channel blockages or areas of shallow, fast-moving water. An instream plug of material transported to the site by flood flows or delivered to the channel from a hillslope failure not only blocks passage, but may deflect the stream toward a new course than endangers adjacent capital infrastructure or transportation corridors. Elevated risks associated with eventual over-topping or failure of the blockage to downstream features or communities are imminent in the event of a blockage that forms a temporary dam. Accelerated instream or lateral channel erosion may introduce fine sediment that impairs water quality.

After Situation:

The instream barrier is removed by a combination of methods and equipment and the channel and affected floodplain are restored to pre-blockage conditions to the fullest extent practicable. Resource Concerns are addressed within the context of the site.

Feature Measure: Cubic Yards of mineral sediment, fil

Scenario Unit:: Cubic Yard

Scenario Typical Size: 200.0

Scenario Total Cost: $20,572.98

Scenario Cost/Unit: $102.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	40	$2,266.00
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	$125.35	20	$2,507.00
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	20	$3,324.00
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$45.08	20	$901.60
Water management, Flooding & dewatering	969	Includes equipment and power unit. Labor not included.	Acre Foot	$139.03	2	$278.06
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	40	$3,910.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	20	$547.60
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	140	$3,595.20
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	20	$723.60
Mobilization						

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	6	$1,539.90
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 396 - Aquatic Organism Passage

Scenario #34 - Nature-Like Fishway

Scenario Description:

Nature-like fishways, also known as roughened channels, rock ramps, or bypass channels, are constructed features that provide passage around an instream barrier or in place of a removed barrier. Fishway design is based on simulating or mimicking adjacent stream characteristics, using natural materials, and providing suitable passage conditions over a range of flows for a wide variety of fish species and other aquatic organisms. Nature-like fishways provide enhanced passage conditions compared to concrete or aluminum (Alaskan Steeppass) ladders, and are not as susceptible to debris-related operational issues. When used to bypass an instream barrier, they require a larger footprint than instream structures, and may also require control structures to regulate flow through the fishway or address tailwater fluctuations affecting the fishway entrance (downstream end). Fishway design includes an assessment of adjacent stream characteristics, including channel geometry, slope, sediment texture and composition, and major geomorphic units that govern channel plan, pattern and profile. In the case of a fishway that bypasses an instream barrier, the design is tailored to these elements, the elevation required to ascend the barrier, and the known range of flow variation or operations. For fishways constructed in the place of a removed barrier, the design may be a hybrid approach that meets the same criteria, although in a smaller instream footprint. Nature-like fishways are constructed with an assortment of equipment used for excavation, placing material, and delivering and removing material. Construction elements generally include an assortment of rock used to create riffles, cascades, or riffle-pool sequences with between 6 to 12 inches of water surface elevation drop between adjacent structures. Large woody material is used to create channel structural elements in some settings, when available and where approved by oversight agencies. Removed materials are trucked away and disposed or recycled off-site, unless excavated native streambed material can be used in fishway construction. Large woody material or removed trees, if present, are used for fishway construction trucked offsite for disposal, or trucked offsite for stockpiling for future projects. Disturbed areas are revegetated with a mix of site-adapted species, and access control and signage are provided. Scenario does not include additional measures needed in the active channel and floodplain or at an existing dam necessary to control flow associated with nature-like fishway. RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE –Habitat degradation; EXCESS WATER – Ponding, flooding, seasonal high water table, seeps, and drifted snow; WATER QUALITY DEGRADATION – Elevated water temperature; EROSION– Excessive bank erosion from streams shorelines or water conveyance channels Payments for these associated practices are made separately and are covered by other typical scenarios and payment schedules. See relevant CPS for additional information. ---Site Preparation and Reclamation associated with project footprint: (326) Clearing and Snagging, (342) Critical Area Planting, (382) Fence, (390) Riparian Herbaceous Cover, (391) Riparian Forest Buffer, (612) Tree/Shrub Establishment ---Reach Planning/Habitat Enhancement: (395) Stream Habitat Improvement and Management, ---Structural Measures Associated with Scenario but outside of project footprint: (410) Grade Stabilization Structure, (582) Open Channel, (584) Channel Bed Stabilization, (580) Streambank and Shoreline Protection, (587) Structure for Water Control

Before Situation:

An instream barrier prevents upstream migration of native aquatic organisms and no support exists for removal. Similarly, an instream barrier is removed, and interested parties require maintenance of an upstream pool or pond. The subject stream contains a number of migrating aquatic organisms ranging in size from small to large with a range of propulsion abilities--weak to strong swimmers and animals that crawl along the bottom. In either case--barrier removal or bypassing an existing barrier--local sentiment to preserve existing or natural conditions and the desire to provide passage for a range of aquatic organisms indicate the use of a nature-like fishway. Adequate space for a bypass channel is available, and adjacent landowners approve.

After Situation:

A nature-like fishway is constructed in place of a removed barrier or around an existing barrier. The fishway is designed to mimic the adjacent natural stream, and is constructed of rock and/or large woody material that provides quality passage conditions for a number of species and geomorphic stability over a range of flows. Resource Concerns are addressed within the context of the site.

Feature Measure: Acres of constructed fishway (bank

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $98,506.91

Scenario Cost/Unit: $98,506.91

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Clearing and Grubbing	40	Clearing and Grubbing, includes materials, equipment and labor	Acre	$286.81	3	$860.43
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	$2.38	12000	$28,560.00
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	$5.17	100	$517.00
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	80	$4,532.00
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	80	$13,296.00
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$45.08	100	$4,508.00
Water management, Flooding & dewatering	969	Includes equipment and power unit. Labor not included.	Acre Foot	$139.03	2	$278.06
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	100	$9,775.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	80	$2,190.40

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	60	$1,140.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	280	$7,190.40
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	60	$2,170.80
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	240	$20,203.20
Materials						
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	$25.58	50	$1,279.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	4	$1,026.60
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 396 - Aquatic Organism Passage

Scenario #35 - CMP Culvert

Scenario Description:

A corrugated metal (galvanized steel or aluminum) pipe culvert (CMP) of any shape (round, elliptical, or squash) used at a road-stream crossing to provide aquatic organism passage (AOP) and promote stream ecological and geomorphic function. CMPs used for AOP are sized according to geomorphic analyses, not just an estimate of runoff and streamflow at the site from the contributing watershed. In addition, CMPs used for AOP are filled with a mixture of rock and gravel sized to emulate site stream conditions and geomorphic units in the channel. The simulated streambed material is continuous throughout the culvert barrel, and blended with the intact streambed at the culvert inlet and outlet. The first estimate of culvert size--diameter or span--is obtained by analyzing bankfull channel width on a reach of stream not affected by an existing road crossing or other conditions that alter self-formed conditions. In the case of a culvert replacement, bankfull investigations are begun at least 10-20 estimated bankfull channel widths above the existing stream crossing. Culvert diameter or span is then increased according to channel bed composition and texture, bank characteristics, channel alignment at the crossing section, and other parameters that may affect channel dynamics and stability. Once the CMP diameter or span is determined, culvert length will be determined by roadway geometry and loading requirements, and site stream conditions. Concrete headwalls and/or wing walls may be necessary in shorter installations and/or where fill/roadway cover is limited or the stream alignment is not perpendicular to the road axis. Culvert wall thickness and corrugations are determined by road loading requirements. Stream geomorphic characteristics, including the reach longitudinal profile, channel cross-sectional shape, substrate composition and arrangement, and bank shape and composition are determined. CMPs are installed with an assortment of equipment used for excavation, placing material, and delivering and removing material. Construction elements generally include an assortment of rock used to create riffles, cascades, or riffle-pool sequences with between 6 to 12 inches of water surface elevation drop between adjacent structures. Stream dewatering and diversion around the work site is often required, and temporary road closure or re-routing may also be required. . Channel bed material within the culvert barrel varies according to prevailing stream characteristics at the crossing site. The culvert is placed within the roadway on a subexcavated compacted bed, set at a slope that matches the design longitudinal profile, and backfilled with a bed mixture that mimics adjacent stream characteristics with special attention to channel pattern. Backfill depths are typically at least 20% of the culvert diameter or rise, but may deviate based on the shape of the culvert used, channel dimensions, substrate size, and the site longitudinal profile. Special equipment such as motorized wheelbarrows may be necessary to backfill smaller CMPs. Once the simulated streambed in the culvert barrel is complete, the roadway is replaced and any necessary armoring and revegetating material is placed at the culvert inlet and outlet where it intersects the road fill prism. Other actions include construction staking and signage, soil erosion and pollution control, removal and disposal of the old culvert, and topsoil conservation for site reclamation. Disturbed areas are revegetated with a mix of site-adapted species. Scenario does not include additional measures needed to address channel incision, bank stability, and other factors associated with the presence of the stream crossing. RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE –Habitat degradation; EXCESS WATER – Ponding, flooding, seasonal high water table, seeps, and drifted snow; WATER QUALITY DEGRADATION – Elevated water temperature; SOIL EROSION– Excessive bank erosion from streams shorelines or water conveyance channels Payments for these associated practices are made separately and are covered by other typical scenarios and payment schedules. See relevant CPS for additional information. ---Site Preparation and Reclamation associated with project footprint: (342) Critical Area Planting, (382) Fence, (390) Riparian Herbaceous Cover, (391) Riparian Forest Buffer, (612) Tree/Shrub Establishment; ---Reach Planning/Habitat Enhancement: (395) Stream Habitat Improvement and Management, ---Structural Measures Associated with Scenario but outside of project footprint: (410) Grade Stabilization Structure, (584) Channel Bed Stabilization, (580) Streambank and Shoreline Protection

Before Situation:

An existing undersized culvert as contributed to general bed and bank scour downstream of a road crossing, and may have contributed to the deposition of a wedge of sediment upstream of the road crossing. The road may be overtopped by high flows, resulting in outright failure, landowner accessibility problems, access by and to emergency services, and hamper post-flood recovery efforts. An upstream impoundment created by the undersized culvert has contributed to water quality problems including high water temperatures and the deposition and later mobilization of polluted fine sediment. Native aquatic organisms are unable to pass through the road crossing because the culvert outlet is perched above the downstream pool, and high velocities are not negotiable by animals that are able to leap into the culvert barrel.

After Situation:

The undersized culvert is replaced with a CMP sized, placed, and backfilled with material determined by geomorphic analyses performed in a reference reach upstream of the crossing location. Geomorphic and ecological functions are preserved through the crossing site, enhancing AOP, water quality, and culvert longevity. In addition, because the culvert is sized to promote the transport of streamflow and the materials it carries, it requires decreased maintenance activities over time. Landowners are able to access their holdings across a range of flows, and are able to seek and receive emergency and post-flood recovery services. Resource Concerns are addressed within the context of the site.

Feature Measure: CMP

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $29,808.85

Scenario Cost/Unit: $29,808.85

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	$2.38	900	$2,142.00
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	40	$6,648.00
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$45.08	60	$2,704.80
Water management, Flooding & dewatering	969	Includes equipment and power unit. Labor not included.	Acre Foot	$139.03	1	$139.03
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	40	$3,910.00
Labor						

Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	40	$1,095.20
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	60	$1,140.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	140	$3,595.20
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	40	$1,447.20
Materials						
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	$25.58	75	$1,918.50
Pipe, CMP, 96", 14 Gauge	1835	96" Corrugated Metal Pipe, Galvanized, Uncoated, 14 gage. Material cost only.	Foot	$89.39	40	$3,575.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 396 - Aquatic Organism Passage

Scenario #36 - Bottomless Culvert

Scenario Description:

A multi-plate galvanized steel or aluminum culvert (arch or box) used at a road-stream crossing to provide aquatic organism passage (AOP) and promote stream ecological and geomorphic function. They commonly attach to preformed reinforced or poured-in-place concrete footings. Bottomless culverts used for AOP are sized according to geomorphic analyses, not just an estimate of runoff and streamflow at the site from the contributing watershed. In addition, bottomless culverts used for AOP are filled with a mixture of rock and gravel sized to emulate site stream conditions and geomorphic units in the channel. The simulated streambed material is continuous throughout the culvert barrel, and blended with the intact streambed at the culvert inlet and outlet. The first estimate of culvert span is obtained by analyzing bankfull channel width on a reach of stream not affected by an existing road crossing or other conditions that alter self-formed conditions. In the case of a culvert replacement, bankfull investigations are begun at least 10-20 estimated bankfull channel widths above the existing stream crossing. Culvert span is then increased according to channel bed composition and texture, bank characteristics, channel alignment at the crossing section, and other parameters that may affect channel dynamics and stability. Once the culvert span is determined, culvert length will be dictated by roadway geometry and loading requirements, and site stream conditions. Concrete headwalls and/or wing walls may be necessary in shorter installations and/or where fill/roadway cover is limited or the stream alignment is not perpendicular to the road axis. Culvert wall thickness and footing requirements are determined by road loading requirements and site geotechnical investigations. Generally, the preferred footing is a T-design with a spread footing with stem wall. Connecting the culvert leg to the footing can be done by welding, grouting, bolting. Stream geomorphic characteristics, including the reach longitudinal profile, channel cross-sectional shape, substrate composition and arrangement, and bank shape and composition are determined. Bottomless arch or box culverts are commonly delivered in sections and bolted together in the field. Smaller arches can be delivered in one piece. They are installed with an assortment of equipment used for excavation, placing material, and delivering and removing material. Construction elements generally include an assortment of rock used to create riffles, cascades, or riffle-pool sequences with between 6 to 12 inches of water surface elevation drop between adjacent structures. Stream dewatering and diversion around the work site is often required, and temporary road closure or re-routing may also be required. Channel bed material within the culvert barrel varies according to prevailing stream characteristics at the crossing site. Footings are placed or poured, and the new streambed is set at a slope that matches the design longitudinal profile, and backfilled with a bed mixture that mimics adjacent stream characteristics with special attention to channel pattern. Once the simulated streambed between the footings is complete, the culvert sections are assembled and attached to the footings. Larger rock may be placed along the footing/culvert stemwall to project the connection from damage by transported bedload. The roadway is replaced and any necessary armoring and revegetating material is placed at the culvert inlet and outlet where it intersects the road fill prism. Other actions include construction staking and signage, soil erosion and pollution control, removal and disposal of the old culvert, and topsoil conservation for site reclamation. Disturbed areas are revegetated with a mix of site-adapted species. Scenario does not include additional measures needed to address channel incision, bank stability, and other factors associated with the presence of the stream crossing. Scenario does not include concrete for head or wing walls. RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE –Habitat degradation; EXCESS WATER – Ponding, flooding, seasonal high water table, seeps, and drifted snow; WATER QUALITY DEGRADATION – Elevated water temperature; SOIL EROSION– Excessive bank erosion from streams shorelines or water conveyance channels Payments for these associated practices are made separately and are covered by other typical scenarios and payment schedules. See relevant CPS for additional information. ---Site Preparation and Reclamation associated with project footprint: (342) Critical Area Planting, (382) Fence, (390) Riparian Herbaceous Cover, (391) Riparian Forest Buffer, (612) Tree/Shrub Establishment; ---Reach Planning/Habitat Enhancement: (395) Stream Habitat Improvement and Management, ---Structural Measures Associated with Scenario but outside of project footprint: (410) Grade Stabilization Structure, (584) Channel Bed Stabilization, (580) Streambank and Shoreline Protection

Before Situation:

An existing undersized culvert as contributed to general bed and bank scour downstream of a road crossing, and may have contributed to the deposition of a wedge of sediment upstream of the road crossing. The road may be overtopped by high flows, resulting in outright failure, landowner accessibility problems, access by and to emergency services, and hamper post-flood recovery efforts. An upstream impoundment created by the undersized culvert has contributed to water quality problems including high water temperatures and the deposition and later mobilization of polluted fine sediment. Native aquatic organisms are unable to pass through the road crossing because the culvert outlet is perched above the downstream pool, and high velocities are not negotiable by animals that are able to leap into the culvert barrel.

After Situation:

The undersized culvert is replaced with a bottomless arch or box culvert sized, placed, and backfilled with material determined by geomorphic analyses performed in a reference reach upstream of the crossing location. Geomorphic and ecological functions are preserved through the crossing site, enhancing AOP, water quality, and culvert longevity. In addition, because the culvert is sized to promote the transport of streamflow and the materials it carries, it requires decreased maintenance activities over time. Landowners are able to access their holdings across a range of flows, and are able to seek and receive emergency and post-flood recovery services. Resource Concerns are addressed within the context of the site.

Feature Measure: Multi-plate arch or box and rock fill

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $44,599.16

Scenario Cost/Unit: $44,599.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	$2.38	900	$2,142.00
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	$5.17	50	$258.50
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	40	$6,648.00
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$45.08	60	$2,704.80
Water management, Flooding & dewatering	969	Includes equipment and power unit. Labor not included.	Acre Foot	$139.03	1	$139.03
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	40	$3,910.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	40	$1,095.20
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	60	$1,140.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	140	$3,595.20
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	40	$1,447.20
Materials						
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	$25.58	75	$1,918.50
Footing, concrete, precast	1836	Precast spread footing with stemwall, T-shaped, with channel built to accept arched culvert leg. Includes materials only.	Foot	$59.95	80	$4,796.00
Geocell, 6"	1842	6-inch thick cellular confinement system, three-dimensional, expandable panels made from high-density polyethylene (HDPE), polyester or another polymer material. Includes materials, labor and equipment for the geocell only, does not include backfill.	Square Yard	$26.62	500	$13,310.00
Culvert, Multi-Plate arch	1979	Multi-plate arch culvert, typically 7 Gauge corrugated plate. Includes metal arch materials only, does not include footings.	Pound	$1.41	1	$1.41
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 396 - Aquatic Organism Passage

Scenario #37 - Concrete Box Culvert

Scenario Description:

A four-sided precast concrete box (square or rectangular) culvert used at a road-stream crossing to provide aquatic organism passage (AOP) and promote stream ecological and geomorphic function. Concrete box culverts are generally available in sections of 1-foot increments. Concrete box culverts used for AOP are sized according to geomorphic analyses, not just an estimate of runoff and streamflow at the site from the contributing watershed. In addition, concrete box culverts used for AOP are filled with a mixture of rock and gravel sized to emulate site stream conditions and geomorphic units in the channel. The simulated streambed material is continuous throughout the culvert barrel, and blended with the intact streambed at the culvert inlet and outlet. The first estimate of culvert width is obtained by analyzing bankfull channel width on a reach of stream not affected by an existing road crossing or other conditions that alter self-formed conditions. In the case of a culvert replacement, bankfull investigations are begun at least 10-20 estimated bankfull channel widths above the existing stream crossing. Culvert width is then increased according to channel bed composition and texture, bank characteristics, channel alignment at the crossing section, and other parameters that may affect channel dynamics and stability. Once the culvert width is determined, culvert length will be determined by roadway geometry and loading requirements, and site stream conditions. Concrete headwalls and/or wing walls may be necessary in shorter installations and/or where fill/roadway cover is limited or the stream alignment is not perpendicular to the road axis. Stream geomorphic characteristics, including the reach longitudinal profile, channel cross-sectional shape, substrate composition and arrangement, and bank shape and composition are determined. Concrete box culverts are delivered in sections and assembled onsite, and require adequate bed compaction throughout the crossing section. They are installed with an assortment of equipment used for excavation, placing material, and delivering and removing material. Construction elements generally include an assortment of rock used to create riffles, cascades, or riffle-pool sequences with between 6 to 12 inches of water surface elevation drop between adjacent structures. Stream dewatering and diversion around the work site is often required, and temporary road closure or re-routing may also be required. Channel bed material within the culvert barrel varies according to prevailing stream characteristics at the crossing site. The new streambed is set at a slope that matches the design longitudinal profile, and backfilled with a bed mixture that mimics adjacent stream characteristics with special attention to channel pattern. The roadway is replaced and any necessary armoring and revegetating material is placed at the culvert inlet and outlet where it intersects the road fill prism. Other actions include construction staking and signage, soil erosion and pollution control, removal and disposal of the old culvert, and topsoil conservation for site reclamation. Disturbed areas are revegetated with a mix of site-adapted species. Scenario does not include additional measures needed to address channel incision, bank stability, and other factors associated with the presence of the stream crossing. RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE –Habitat degradation; EXCESS WATER – Ponding, flooding, seasonal high water table, seeps, and drifted snow; WATER QUALITY DEGRADATION – Elevated water temperature; SOIL EROSION– Excessive bank erosion from streams shorelines or water conveyance channels Payments for these associated practices are made separately and are covered by other typical scenarios and payment schedules. See relevant CPS for additional information. ---Site Preparation and Reclamation associated with project footprint: (342) Critical Area Planting, (382) Fence, (390) Riparian Herbaceous Cover, (391) Riparian Forest Buffer, (612) Tree/Shrub Establishment; ---Reach Planning/Habitat Enhancement: (395) Stream Habitat Improvement and Management, ---Structural Measures Associated with Scenario but outside of project footprint: (410) Grade Stabilization Structure, (584) Channel Bed Stabilization, (580) Streambank and Shoreline Protection

Before Situation:

An existing undersized culvert as contributed to general bed and bank scour downstream of a road crossing, and may have contributed to the deposition of a wedge of sediment upstream of the road crossing. The road may be overtopped by high flows, resulting in outright failure, landowner accessibility problems, access by and to emergency services, and hamper post-flood recovery efforts. An upstream impoundment created by the undersized culvert has contributed to water quality problems including high water temperatures and the deposition and later mobilization of polluted fine sediment. Native aquatic organisms are unable to pass through the road crossing because the culvert outlet is perched above the downstream pool, and high velocities are not negotiable by animals that are able to leap into the culvert barrel.

After Situation:

The undersized culvert is replaced with a concrete box culvert sized, placed, and backfilled with material determined by geomorphic analyses performed in a reference reach upstream of the crossing location. Geomorphic and ecological functions are preserved through the crossing site, enhancing AOP, water quality, and culvert longevity. In addition, because the culvert is sized to promote the transport of streamflow and the materials it carries, it requires decreased maintenance activities over time. Landowners are able to access their holdings across a range of flows, and are able to seek and receive emergency and post-flood recovery services. Resource Concerns are addressed within the context of the site.

Feature Measure: Concrete box culvert and rock fill

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $53,399.00

Scenario Cost/Unit: $53,399.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	$2.38	1000	$2,380.00
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	$5.17	75	$387.75
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	40	$6,648.00
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$45.08	60	$2,704.80
Water management, Flooding & dewatering	969	Includes equipment and power unit. Labor not included.	Acre Foot	$139.03	1	$139.03
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	40	$3,910.00
Labor						

Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	40	$1,095.20
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	60	$1,140.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	140	$3,595.20
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	40	$1,447.20
Materials						
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	$25.58	75	$1,918.50
Culvert, box, 6' x 6'	1837	Precast concrete box culvert, 6'X6'. Typically in 4' sections. Includes materials only.	Foot	$330.75	40	$13,230.00
Geocell, 6''	1842	6-inch thick cellular confinement system, three-dimensional, expandable panels made from high-density polyethylene (HDPE), polyester or another polymer material. Includes materials, labor and equipment for the geocell only, does not include backfill.	Square Yard	$26.62	500	$13,310.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 396 - Aquatic Organism Passage

Scenario #42 - Low Water Crossing

Scenario Description:

Structure installed on low volume or on unimproved roads at watercourse crossings. Primary use is to allow livestock and equipment access to other parcels of land or operational units. Low-water crossings provide safe and stable stream crossings that don't negatively impact water and ecological quality while remaining stable across a wide range of flows. Variations exist, but a common application consists of an improved or hardened ford located above a hydraulic control (e.g., bedrock outcropping, riffle, or step composed of coarse substrates). Properly designed and installed low water crossings provide aquatic organism passage (AOP), promote stream ecological and geomorphic function, remain stable over time, and can pass sediment and woody debris. Conservation planning and interaction with the landowner is vital to determine if existing crossings can be consolidated into fewer, more reliable locations. Characterizing a site according to its watershed position and geomorphic function will aid design decisions. Optimal AOP conditions are usually realized when the backfill is composed of a mixture that mimics bed material as evaluated from a reference reach adjacent to the crossing—preferably at least 10-20 estimated bankfull channel widths above an existing crossing to avoid effects that alter channel geometry or bedform composition and spacing. Low water crossings are installed with an assortment of equipment used for excavation, placing material, and delivering and removing material. Low water crossings provide the best mix of function and longevity when they are designed and built to conform to existing channel geometry and slope, constructed to match the shape of the existing channel, and oriented to cross the stream at a 90 degree angle. Crossing width, measured along the downstream axis, should not exceed 2X bankfull width. Low water crossings are commonly constructed by over excavating the crossing section 6-12 inches below the existing streambed and backfilling the void with well-graded rock back to natural bed elevation. Geotextile lining may be required in some settings. Rock size and gradation is the smallest mix needed to remain stable under prevailing flow conditions—larger rock can endanger livestock and turbulence impairs passage. Sand or soil may be added into the mix to seal the section to ensure that the stream doesn't percolate into the crossing substrate. Smaller material increases bed diversity, chokes voids between bigger stones, and helps preserve passage quality. Smaller rock smaller (< 2 inches) at the finished surface may become lodged in livestock hooves. The road/trail surface of the crossing should be extended to an elevation that exceeds the known high water level on each side of the crossing. The downstream edge of the crossing should not produce a sharp drop in water surface to preserve AOP quality and discourage sediment deposition and debris accumulation. Other actions include construction staking and signage, soil erosion and pollution control, removal and disposal of the old culvert, and topsoil conservation for site reclamation. Disturbed areas are revegetated with a mix of site-adapted species. Scenario does not include additional measures needed to address channel incision, bank stability, and other factors associated with the presence of the stream crossing. Stream corridor fencing should be considered to control livestock access and preserve water and riparian quality. RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE –Habitat degradation Payments for these associated practices are made separately and are covered by other typical scenarios and payment schedules. See relevant CPS for additional information. ---Site Preparation and Reclamation associated with project footprint: (326) Clearing and Snagging, (342) Critical Area Planting, (382) Fence, (390) Riparian Herbaceous Cover, (391) Riparian Forest Buffer, (612) Tree/Shrub Establishment ---Reach Planning/Habitat Enhancement: (395) Stream Habitat Improvement and Management, ---Structural Measures Associated with Scenario but outside of project footprint: (410) Grade Stabilization Structure, (582) Open Channel, (584) Channel Bed Stabilization, (580) Streambank and Shoreline Protection, (587) Structure for Water Control

Before Situation:

A small farming operation has a mixture of pastures, hay meadows, and crops that all require seasonal movement of equipment and livestock between parcels. Four unimproved stream crossings provide unreliable access across the property and require yearly maintenance to clear debris and sediment. Farm equipment has gotten stuck in the past, and uncontrolled livestock access and frequent crossing or loafing in the stream contributes to chronic water quality problems associated with elevated fine sediment, high water temperatures, invasive aquatic vegetation, and fecal coliform bacteria. Livestock avoid three of the crossings when streamflow increases moderately. Two of the crossings are overwide and shallow, and impair AOP. The property and landowner's yearly operations are reviewed by conservation planners and—with the input and agreement of the landowner—it is decided that three of the four crossings can be eliminated and consolidated at one site above a cobble/boulder deposit in the stream.

After Situation:

An improved ford is constructed by excavating the channel just upstream of the boulder/cobble hydraulic control. The cut is lined with geotextile to control seepage and subsurface flow, and backfilled up to the existing bed elevation with a well-graded mix of rock sized to mimic the material in the channel upstream of the crossing. The finished crossing surface is at grade with the up and downstream channel elevation, and no drop exists along the downstream edge. Approaches on either side of the crossing are extended up to the adjacent floodplain surface, and the finished instream portion of the ford matches the existing channel cross section. Approach slopes are shallow enough for expected equipment traffic, including towed combinations, and armored as needed with larger rock to protect against erosion that may occur when the floodplain is inundated. The crossing is fenced and gated to control livestock access and provide greater flexibility to the landowner's grazing needs. AOP is provided, and the crossing remains stable across a range of flow and sediment and debris transport events. Resource Concerns are addressed within the context of the site.

Feature Measure: Cubic Yard

Scenario Unit:: Cubic Yard

Scenario Typical Size: 60.0

Scenario Total Cost: $39,634.23

Scenario Cost/Unit: $660.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Clearing and Grubbing	40	Clearing and Grubbing, includes materials, equipment and labor	Acre	$286.81	0.5	$143.41
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	$2.38	1000	$2,380.00
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	$5.17	50	$258.50
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	80	$4,532.00
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	60	$9,972.00
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$45.08	80	$3,606.40

Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	40	$3,910.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	60	$1,642.80
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	60	$1,140.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	260	$6,676.80
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	40	$1,447.20
Materials						
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	$25.58	75	$1,918.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	4	$1,026.60
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 397 - Aquaculture Ponds

Scenario #4 - Aquaculture Split Pond

Scenario Description:

Typical practice is 7 to 10 acre pond surface area, 3:1 side slopes, average 5' depth that will be split with a cross levee. The construction of a aquaculture split pond is to facilitate the efficient processing of nutrients, increase efficient use of water, increase energy use efficiency and the maintenance of water quality. The resource concerns addressed include excess nutrients in surface and ground waters, inefficient water use, inefficient energy use, and habitat degradation. Costs include all equipment necessary to excavate, grade and shape an cross levee for an aquaculture spilt pond. Water Control Structure, pumping plant, and Seeding not included.

Before Situation:

In the before situation, an aquaculture producer has an aquaculture pond system that one or more of the following concerns: excessive seepage or frequent release of nutrient laden aquaculture water, excessive energy consumption, excessive groundwater demand, and/or poor growing conditions for the current aquaculture species.

After Situation:

Aquaculture pond is typically 7 to10 acre in surface area, 5 feet deep with 3:1 side slopes with a ~330 ft cross levee constructed to split the pond (80/20). The practice is installed using a dozer or dirt buckets. Water control structure, Pumps, and Access Roads may also be needed and will be installed using those standards as appropriate.

Feature Measure: Acre of Aquaculture Pond

Scenario Unit:: Acre

Scenario Typical Size: 7.0

Scenario Total Cost: $9,593.94

Scenario Cost/Unit: $1,370.56

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	$3.79	2383	$9,031.57
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	1	$490.01

Practice: 410 - Grade Stabilization Structure

Scenario #1 - Check Dams

Scenario Description:

Typical setting is on a 40-acre pasture/hayland field having a slope of 5 to 10 percent where ephemeral gullies have formed. Typical installation consists of stabilizing/regrading the gully and installing six check dams with a top width of 3', average height of 2.5', 19' length, and 2:1 side slopes, ; containing an average of 21 tons of rock for a total of 126 tons. The check dams are underlain with geotextile fabric. Disturbed areas are protected with permanent vegetative cover. Addresses resource concerns such as water quality degradation and soil erosion-concentrated flow erosion.

Before Situation:

The operator presently has erosion gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed vegetation of disturbed areas use Critical Area Planting (342).

Feature Measure: Tons of rock installed

Scenario Unit:: Ton

Scenario Typical Size: 126.0

Scenario Total Cost: $7,309.50

Scenario Cost/Unit: $58.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	$1.60	160	$256.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	84	$6,388.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 410 - Grade Stabilization Structure

Scenario #13 - GSS lower cfs, lower fill

Scenario Description:

An earthen embankment with a principle spillway pipe < 15 inches in diameter with lower cfs (<=5 cfs)and lower fill (< 300 cu yds). Installed to stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon a typical amount of earthfill of 50 cubic yards, 12" smooth steel principle spillway with a 30 ft barrel. A small rock lined plunge pool protects the outlet channel. Disturbed areas are protected with permanent vegetative cover. Addresses resource concerns such as soil erosion-concentrated flow erosion and water quality degradation.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Pumping Plant (533), Watering Facility (614), and Livestock Pipeline (516) will use the corresponding Standard(s) as appropriate.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $1,542.80

Scenario Cost/Unit: $1,542.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	50	$196.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	1.25	$143.70
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	1	$27.38
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	1	$19.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	1.25	$32.10
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	2	$152.10
Pipe, Steel, 12", Std Wt, USED	1356	Materials: - USED - 12" - Steel Std Wt	Foot	$21.50	30	$645.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 410 - Grade Stabilization Structure

Scenario #14 - GSS lower cfs, med fill

Scenario Description:

An earthen embankment with a principle spillway pipe < 15 inches with lower cfs (<=5 cfs)and med fill (300 to 1200 cu yds). Installed to stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon a typical amount of earthfill of 1000 cubic yards, 12" smooth steel principle spillway with a 45 ft barrel. A rock lined plunge pool protects the outlet channel. Disturbed areas are protected with permanent vegetative cover. Addresses resource concerns such as soil erosion-concentrated flow erosion and water quality degradation.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Pumping Plant (533), Watering Facility (614), and Livestock Pipeline (516) will use the corresponding Standard(s) as appropriate.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $7,213.65

Scenario Cost/Unit: $7,213.65

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	1000	$3,920.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	5	$574.80
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	6	$164.28
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	6	$114.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	5	$128.40
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	10	$760.50
Pipe, Steel, 12", Std Wt, USED	1356	Materials: - USED - 12" - Steel Std Wt	Foot	$21.50	45	$967.50
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 410 - Grade Stabilization Structure

Scenario #15 - GSS lower cfs, higher fill

Scenario Description:

An earthen embankment with a principle spillway pipe <15 inches with lower cfs (<=5 cfs)and higher fill (>1200-2500). Installed to stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon a typical amount of earthfill of 2000 cubic yards, 12" smooth steel principle spillway with a 50 ft barrel. A rock lined plunge pool protects the outlet channel. Disturbed areas are protected with permanent vegetative cover. Addresses resource concerns such as soil erosion-concentrated flow erosion and water quality degradation.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Pumping Plant (533), Watering Facility (614), and Livestock Pipeline (516) will use the corresponding Standard(s) as appropriate.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $12,961.21

Scenario Cost/Unit: $12,961.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	2200	$8,624.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	7	$804.72
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	7	$191.66
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	7	$133.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	7	$179.76
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	18	$1,368.90
Pipe, Steel, 12", Std Wt, USED	1356	Materials: - USED - 12" - Steel Std Wt	Foot	$21.50	50	$1,075.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 410 - Grade Stabilization Structure

Scenario #16 - GSS med cfs, lower fill

Scenario Description:

An earthen embankment with a principle spillway pipe 15 to 22 inches with med cfs (>5-10 cfs)and lower fill (<300). Installed to stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon a typical amount of earthfill of 150 cubic yards, 18" smooth steel principle spillway with a 40 ft barrel. A rock lined plunge pool protects the outlet channel. Disturbed areas are protected with permanent vegetative cover. Addresses resource concerns such as soil erosion-concentrated flow erosion and water quality degradation.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Pumping Plant (533), Watering Facility (614), and Livestock Pipeline (516) will use the corresponding Standard(s) as appropriate.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $3,609.53

Scenario Cost/Unit: $3,609.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	150	$588.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	3	$344.88
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	3	$82.14
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	3	$57.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	3	$77.04
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	6	$456.30
Pipe, Steel, 18", Std Wt, USED	1358	Materials: - USED - 18" - Steel Std Wt	Foot	$35.50	40	$1,420.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 410 - Grade Stabilization Structure

Scenario #17 - GSS med cfs, med fill

Scenario Description:

An earthen embankment with a principle spillway pipe 15 to 22 inches with med cfs (>5-10 cfs)and med fill (300 - 1200). Installed to stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon a typical amount of earthfill of 1200 cubic yards, 18" smooth steel principle spillway with a 45 ft barrel. A rock lined plunge pool protects the outlet channel. Disturbed areas are protected with permanent vegetative cover. Addresses resource concerns such as soil erosion-concentrated flow erosion and water quality degradation.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Pumping Plant (533), Watering Facility (614), and Livestock Pipeline (516) will use the corresponding Standard(s) as appropriate.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $8,814.67

Scenario Cost/Unit: $8,814.67

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	1200	$4,704.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	6	$689.76
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	7	$191.66
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	7	$133.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	6	$154.08
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	10	$760.50
Pipe, Steel, 18", Std Wt, USED	1358	Materials: - USED - 18" - Steel Std Wt	Foot	$35.50	45	$1,597.50
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 410 - Grade Stabilization Structure

Scenario #18 - GSS med cfs, higher fill

Scenario Description:

An earthen embankment with a principle spillway pipe 15 to 22 inches with med cfs (>5-10 cfs)and higher fill (>1200-2500). Installed to stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon a typical amount of earthfill of 2500 cubic yards, 18" smooth steel principle spillway with a 80 ft barrel. A rock lined plunge pool protects the outlet channel. Disturbed areas are protected with permanent vegetative cover. Addresses resource concerns such as soil erosion-concentrated flow erosion and water quality degradation.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Pumping Plant (533), Watering Facility (614), and Livestock Pipeline (516) will use the corresponding Standard(s) as appropriate.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $16,289.21

Scenario Cost/Unit: $16,289.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	2500	$9,800.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	9	$1,034.64
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	6	$164.28
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	6	$114.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	9	$231.12
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	20	$1,521.00
Pipe, Steel, 18", Std Wt, USED	1358	Materials: - USED - 18" - Steel Std Wt	Foot	$35.50	80	$2,840.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 410 - Grade Stabilization Structure

Scenario #19 - GSS higher cfs, lower fill

Scenario Description:

An earthen embankment with a principle spillway pipe 22 to 34 inches with higher cfs (>10-20 cfs)and lower fill (<300). Installed to stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon a typical amount of earthfill of 275 cubic yards, 24" smooth steel principle spillway with a 45 ft barrel. A rock lined plunge pool protects the outlet channel. Disturbed areas are protected with permanent vegetative cover. Addresses resource concerns such as soil erosion-concentrated flow erosion and water quality degradation.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Pumping Plant (533), Watering Facility (614), and Livestock Pipeline (516) will use the corresponding Standard(s) as appropriate.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $5,288.12

Scenario Cost/Unit: $5,288.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	275	$1,078.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	4	$459.84
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	7	$191.66
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	7	$133.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	5	$128.40
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	7	$532.35
Pipe, Steel, 24", Std Wt, USED	1360	Materials: - USED - 24" - Steel Std Wt	Foot	$48.46	45	$2,180.70
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

USDA - Natural Resources Conservation Service

Mississippi

Practice: 410 - Grade Stabilization Structure

Scenario #20 - GSS higher cfs, med fill

Scenario Description:

An earthen embankment with a principle spillway pipe 22 to 34 inches with higher cfs (>10-20 cfs)and med fill (>300 to 1500). Installed to stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon a typical amount of earthfill of 1400 cubic yards, 24" smooth steel principle spillway with a 45 ft barrel. A rock lined plunge pool protects the outlet channel. Disturbed areas are protected with permanent vegetative cover. Addresses resource concerns such as soil erosion-concentrated flow erosion and water quality degradation.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Pumping Plant (533), Watering Facility (614), and Livestock Pipeline (516) will use the corresponding Standard(s) as appropriate.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $10,333.97

Scenario Cost/Unit: $10,333.97

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	1400	$5,488.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	6	$689.76
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	7	$191.66
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	7	$133.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	6	$154.08
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	12	$912.60
Pipe, Steel, 24", Std Wt, USED	1360	Materials: - USED - 24" - Steel Std Wt	Foot	$48.46	45	$2,180.70
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 410 - Grade Stabilization Structure

Scenario #21 - GSS higher cfs, higher fill

Scenario Description:

An earthen embankment with a principle spillway pipe 22 to 34 inches with higher cfs (>10-20 cfs)and higher fill (> 1500-2800). Installed to stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon a typical amount of earthfill of 2750 cubic yards, 24" smooth steel principle spillway with a 110 ft barrel. A rock lined plunge pool protects the outlet channel. Disturbed areas are protected with permanent vegetative cover. Addresses resource concerns such as soil erosion-concentrated flow erosion and water quality degradation.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Pumping Plant (533), Watering Facility (614), and Livestock Pipeline (516) will use the corresponding Standard(s) as appropriate.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $19,654.03

Scenario Cost/Unit: $19,654.03

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	2750	$10,780.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	4	$459.84
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	9	$246.42
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	9	$171.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	10	$256.80
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	24	$1,825.20
Pipe, Steel, 24", Std Wt, USED	1360	Materials: - USED - 24" - Steel Std Wt	Foot	$48.46	110	$5,330.60
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 410 - Grade Stabilization Structure

Scenario #22 - GSS xhigh cfs, xhigh fill

Scenario Description:

An earthen embankment with a principle spillway pipe greater than 34 inches with highest cfs (>20 cfs)and extra high fill (>2800). Installed to stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon a typical amount of earthfill of 3000 cubic yards, 36" smooth steel principle spillway with a 130 ft barrel. A rock lined plunge pool protects the outlet channel. Disturbed areas are protected with permanent vegetative cover. Addresses resource concerns such as soil erosion-concentrated flow erosion and water quality degradation.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Pumping Plant (533), Watering Facility (614), and Livestock Pipeline (516) will use the corresponding Standard(s) as appropriate.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $29,617.17

Scenario Cost/Unit: $29,617.17

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	3000	$11,760.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	15	$1,724.40
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	15	$410.70
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	15	$285.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	15	$385.20
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	24	$1,825.20
Pipe, Steel, 36", Std Wt, USED	1362	Materials: - USED - 36" - Steel Std Wt	Foot	$97.25	130	$12,642.50
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 412 - Grassed Waterway

Scenario #1 - Base Waterway

Scenario Description:

Typical practice is 1200 ' long, 12' bottom, 8:1 side slopes, 1.5' depth, half excavation. A grass waterway that is a shaped or graded channel and is established with suitable vegetation to carry surface water at a non-erosive velocity to a stable outlet. This practice addresses Concentrated Flow Erosion (Classic Gully & Ephemeral Erosion) and Excessive Sediment in surface waters. Waterway area measured from top of bank to top of bank. Seeding area is 20% greater than waterway area to account for disturbed areas. Costs include excavation and associated work to construct the overall shape and grade of the waterway.

Before Situation:

The field has a small gulley which is cutting deeper into the field as time goes on, so it needs to be stopped or controlled. Excessive sedimentation and soil erosion as a result from ephemeral or classic gully erosion. Gully has formed in field as a result of excessive runoff and poor cropping techniques. Grassed waterway is also commonly installed to covey runoff from concentrated flows, terraces, diversions, or water control structures or similar practices to a suitable, stable outlet.

After Situation:

Installed grassed waterway is 1200 ' long, 12' bottom, 8:1 side slopes, 1.5' depth. The practice is installed using a dozer. Use Critical Area Planting (342) for establishment of waterway vegetation. If erosion control blankets or mulching for seedbed establishment/protection are needed, use conservation practice Mulching (484). Drainage tile, if needed, will be installed according to Subsurface Drain (606). Outlets, if needed will be installed using Structure for Water Control (587). If inlet Structures are needed with the drainage tile, then those will be installed using Underground Outlet (620).

Feature Measure: Acre of Waterway

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $1,648.83

Scenario Cost/Unit: $1,648.83

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	$1.60	800	$1,280.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	4	$76.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	1	$36.18
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 412 - Grassed Waterway

Scenario #2 - Grass Waterway with Checks

Scenario Description:

Typical practice is 1200 ' long, 12' bottom, 8:1 side slopes, 1.5' depth, half excavation. A grass waterway that is a shaped or graded channel and is established with suitable vegetation to carry surface water at a non-erosive velocity to a stable outlet. Fabric or stone checks are installed every 100 feet along the length of the waterway perpendicular to waterflow and are 2/3 the waterway top width to reduce maintenance and provide temporary protection until vegetation is established. Fabric Checks are installed 18" deep with 12" laid over on the surface. (Alternatively, rock checks could be installed). This practice addresses Concentrated Flow Erosion (Classic Gully & Ephemeral Erosion) and Excessive Sediment in surface waters. Waterway area measured from top of bank to top of bank. Seeding area is 20% greater than waterway area to account for disturbed areas. Costs include excavation and associated work to construct the overall shape and grade of the waterway.

Before Situation:

The field has a small gulley which is cutting deeper into the field as time goes on, so it needs to be stopped or controlled. Excessive sedimentation and soil erosion as a result from ephemeral or classic gully erosion. Gully has formed in field as a result of excessive runoff and poor cropping techniques. Grassed waterway is also commonly installed to covey runoff from concentrated flows, terraces, diversions, or water control structures or similar practices to a suitable, stable outlet.

After Situation:

Installed grassed waterway is 1200 ' long, 12' bottom, 8:1 side slopes, 1.5' depth. Fabric checks are installed every 100 feet along the length of the waterway. The practice is installed using a dozer. Fabric or stone checks are installed with small backhoe and labor. Use Critical Area Planting (342) for establishment of waterway vegetation. If erosion control blankets or mulching for seedbed establishment/protection are needed, use conservation practice Mulching (484). Drainage tile, if needed, will be installed according to Subsurface Drain (606). Outlets, if needed will be installed using Structure for Water Control (587). If inlet Structures are needed with the drainage tile, then those will be installed using Underground Outlet (620).

Feature Measure: Acre of Waterway

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $2,484.42

Scenario Cost/Unit: $2,484.42

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	33	$68.31
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	$5.17	33	$170.61
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	$1.60	800	$1,280.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	12	$228.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Geotextile, non-woven, light weight	1209	Non-woven less than 8 ounce/square yard geotextile with staple anchoring. Materials and shipping only.	Square Yard	$1.25	132	$165.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 422 - Hedgerow Planting

Scenario #1 - Pollinator Habitat

Scenario Description:

Where pollinator habitat is an additional wildlife habitat concern this scenario addresses the resource concern of inadequate fish and wildlife habitat. It provides both physical habitat by providing areas that are not disturbed by annual tillage and provides pollen and nectar throughout the growing season by establishing a diverse mixture of flowering plants. Typically a mixture of 9 or more species is planted to improve diversity so that pollen and nectar are available as long as possible. Typical installation is in or at the edge of cropland or pasture. Typical installation involves tillage to prepare the site for planting. Flowering trees and shrubs adapted for local climatic and edaphic conditions are typically planted at eight - ten foot intervals (this will vary with species selection and density goals). Native grasses adapted to the local climatic and edaphic conditions will be drilled into the site at a rate that will achieve a minimum of 20 seeds per square foot. A locally adapted mixture of pollen and nectar producing plants will be drilled into the site. The species list in the component section of this scenario are strictly for deriving a cost. Species adapted to local climatic and edaphic conditions will be listed in the specification for the site. There is tremendous overlap between this practice and conservation practice 380 Windbreak/Shelterbelt establishment. The main difference is that conservation practice 380 is exclusively woody plants where practice 422 provides for the use of herbaceous materials. If a fence is needed to facilitate establishment use practice 382, Fence.

Before Situation:

Pollen and nectar sources are lacking or are only available for part of the growing season. Large cropland tracts lack undisturbed areas for ground nesting bees.

After Situation:

Flowering plants supply pollen and nectar throughout the growing season. Undisturbed areas provide nesting sites for bees and other native pollinators.

Feature Measure: Length and width of Hedgerow

Scenario Unit:: Foot

Scenario Typical Size: 660.0

Scenario Total Cost: $958.61

Scenario Cost/Unit: $1.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	0.33	$5.54
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	0.33	$7.12
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	$58.32	2	$116.64
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	2	$24.72
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	2	$43.42
Materials						
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.56	166	$92.96
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	66	$19.80
Tree shelter, solid tube type, 3-1/4" x 36"	1561	3-1/4" x 36" tree tube for protection from animal damage. Materials only.	Each	$2.37	166	$393.42
Two Species Mix, Warm Season, Native Perennial Grass	2325	Native, warm season perennial grass. Includes material and shipping only.	Acre	$91.25	0.33	$30.11
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	$566.31	0.33	$186.88

Practice: 422 - Hedgerow Planting

Scenario #3 - Wildlife, Trees - Shrubs only

Scenario Description:

Typically installed in or at the edge of cropland or pasture this scenario is used to address the Inadequate Habitat for Fish and Wildlife resource concern. Specifically, the establishment of dense vegetation in a linear design can be used to provide for several habitat elements depending on the needs identified in the habitat assessment. This scenario can provide: corridors for habitat connectivity, food, and cover for wildlife depending on design and plant species selection. The 422 standard for wildlife criteria calls for a minimum of two species of native plants. Typical installation involves tillage to prepare the site for planting. 2 Trees and/or shrubs adapted for local climatic and edaphic conditions are typically plant at eight - ten foot intervals (this will vary with species selection and density goals). The species list in the component section of this scenario are strictly for deriving a cost. Plant species adapted to the local climatic and edaphic conditions that address the resource concern will be stated in the specification for the site. There is tremendous overlap between this practice and conservation practice 380 Windbreak/Shelterbelt establishment. The main difference is that conservation practice 380 is exclusively woody plants where practice 422 provides for the use of herbaceous materials. If a fence is needed to facilitate establishment use practice 382, Fence.

Before Situation:

Habitat patches lack connectivity. Cover is inadequate to allow wildlife to exploit cropland food resources. Berries and mast are limited.

After Situation:

Inadequate habitat for fish and wildlife is addressed for needs identified in the resource assessment. Habitat patches are connected by corridors of dense hedgerow vegetation. Food resources in crop fields are made available by their proximity to hedgerow cover. Planting may include fruit and mast bearing species, improving food supply, depending on needs being addressed.

Feature Measure: Length and width of Hedgerow

Scenario Unit:: Foot

Scenario Typical Size: 660.0

Scenario Total Cost: $665.71

Scenario Cost/Unit: $1.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	1	$16.78
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	$58.32	1	$58.32
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	2	$24.72
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	1	$21.71
Materials						
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.56	166	$92.96
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	66	$19.80
Tree shelter, solid tube type, 3-1/4" x 36"	1561	3-1/4" x 36" tree tube for protection from animal damage. Materials only.	Each	$2.37	166	$393.42

Practice: 422 - Hedgerow Planting

Scenario #4 - Wildlife - Trees-Shrubs-NWSG

Scenario Description:

Typically installed in or at the edge of cropland or pasture this scenario is used to address the Inadequate Habitat for Fish and Wildlife resource concern. Specifically, the establishment of dense vegetation in a linear design can be used to provide for several habitat elements depending on the needs identified in the habitat assessment. This scenario can provide: corridors for habitat connectivity, food, and cover for wildlife depending on design and plant species selection. The 422 standard for wildlife criteria calls for a minimum of two species of native plants. Typical installation involves tillage to prepare the site for planting. 2 Trees and/or shrubs adapted for local climatic and edaphic conditions are typically plant at eight - ten foot intervals (this will vary with species selection and density goals). A mix of at least 3 native warm season grasses (NWSG) and forbs adapted to the local climatic and edaphic conditions will be drilled into the site at a rate that will achieve a minimum of 20 seeds per square foot. The species list in the component section of this scenario are strictly for deriving a cost. Plant species adapted to the local climatic and edaphic conditions that address the resource concern will be stated in the specification for the site. There is tremendous overlap between this practice and conservation practice 380 Windbreak/Shelterbelt establishment. The main difference is that conservation practice 380 is exclusively woody plants where practice 422 provides for the use of herbaceous materials. If a fence is needed to facilitate establishment use practice 382, Fence.

Before Situation:

Habitat patches lack connectivity. Cover is inadequate to allow wildlife to exploit cropland food resources. Berries and mast are limited.

After Situation:

Inadequate habitat for fish and wildlife is addressed for needs identified in the resource assessment. Habitat patches are connected by corridors of dense hedgerow vegetation. Food resources in crop fields are made available by their proximity to hedgerow cover. Planting may include fruit and mast bearing species, improving food supply, depending on needs being addressed.

Feature Measure: Length and width of Hedgerow

Scenario Unit:: Foot

Scenario Typical Size: 660.0

Scenario Total Cost: $794.32

Scenario Cost/Unit: $1.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	0.33	$5.54
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	0.33	$7.12
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	$58.32	2	$116.64
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	2	$24.72
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	2	$43.42
Materials						
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.56	166	$92.96
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	66	$19.80
Tree shelter, solid tube type, 3-1/4" x 36"	1561	3-1/4" x 36" tree tube for protection from animal damage. Materials only.	Each	$2.37	166	$393.42
One Species, Warm Season, Native Perennial Grass	2322	Native, warm season perennial grass. Includes material and shipping only.	Acre	$68.44	0.33	$22.59
Two Species Mix, Warm Season, Native Perennial Grass	2325	Native, warm season perennial grass. Includes material and shipping only.	Acre	$91.25	0.33	$30.11

Practice: 430 - Irrigation Pipeline

Scenario #1 - PVC, Iron Pipe Size, Less Than 2in Micro

Scenario Description:

Description: Below ground installation of PVC (Iron Pipe Size) pipeline. PVC (IPS) is manufactured in sizes (nominal diameter) from ½-inch to 36-inch; typical practice sizes range from 2-inch to 24-inch; and typical scenario size is 1 ½-inch. Construct 260' of 1-inch, Class 125 (SDR-32.5), PVC pipeline with appurtenances, installed below ground with a minimum of 2 feet of ground cover. 260' of 1 ½ inch, Class 125 (SDR-32.5) PVC pipe weighs 0.227 lb/ft, or a total of 59.02 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to micro-irrigation systems, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

Feature Measure: Length of Pipe

Scenario Unit:: Foot

Scenario Typical Size: 260.0

Scenario Total Cost: $1,285.68

Scenario Cost/Unit: $4.94

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trencher, 8"	936	Equipment and power unit costs. Labor not included.	Hour	$90.80	6	$544.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	6	$114.00
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	$1.75	64.9	$113.58
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 430 - Irrigation Pipeline

Scenario #2 - PVC, Iron Pipe Size, 2in - less than 4in Micro

Scenario Description:

Description: Below ground installation of PVC (Iron Pipe Size) pipeline. PVC (IPS) is manufactured in sizes (nominal diameter) from ½-inch to 36-inch; typical practice sizes range from 2-inch to 24-inch; and typical scenario size is 3-inch. Construct 260 feet of 3-inch, Class 125 (SDR-32.5), PVC pipeline with appurtenances, installed below ground with a minimum of 2 feet of ground cover. The unit is weight of pipe material in pounds. 260 feet of 3-inch, Class 125 (SDR-32.5) PVC pipe weighs .730 lb/ft, or a total of 189.8 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to micro-irrigation systems, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

Feature Measure: Length of Pipe

Scenario Unit:: Foot

Scenario Typical Size: 260.0

Scenario Total Cost: $1,537.47

Scenario Cost/Unit: $5.91

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trencher, 8"	936	Equipment and power unit costs. Labor not included.	Hour	$90.80	6	$544.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	6	$114.00
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	$1.75	208.78	$365.37
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 430 - Irrigation Pipeline

Scenario #3 - PVC, Iron Pipe Size, 4in - 6in Micro

Scenario Description:

Description: Below ground installation of PVC (Iron Pipe Size) pipeline. PVC (IPS) is manufactured in sizes (nominal diameter) from ½-inch to 36-inch; typical practice sizes range from 2-inch to 24-inch; and typical scenario size is 5-inch. Construct 260 feet of 5-inch, Class 125 (SDR-32.5), PVC pipeline with appurtenances, installed below ground with a minimum of 2 feet of ground cover. The unit is weight of pipe material in pounds. 260 feet of 5-inch, Class 125 (SDR-32.5) PVC pipe weighs 1.810 lb/ft, or a total of 470.6 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to micro-irrigation systems, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

Feature Measure: Length of Pipe

Scenario Unit:: Foot

Scenario Typical Size: 260.0

Scenario Total Cost: $2,078.01

Scenario Cost/Unit: $7.99

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trencher, 8"	936	Equipment and power unit costs. Labor not included.	Hour	$90.80	6	$544.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	6	$114.00
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	$1.75	517.66	$905.91
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 430 - Irrigation Pipeline

Scenario #4 - PVC, Iron Pipe Size, 8in Micro

Scenario Description:

Description: Below ground installation of PVC (Iron Pipe Size) pipeline. PVC (IPS) is manufactured in sizes (nominal diameter) from ½-inch to 36-inch; typical practice sizes range from 2-inch to 24-inch; and typical scenario size is 8-inch. Construct 260 feet of 8-inch, Class 125 (SDR-32.5), PVC pipeline with appurtenances, installed below ground with a minimum of 2 feet of ground cover. The unit is weight of pipe material in pounds. 260 feet of 8-inch, Class 125 (SDR-32.5) PVC pipe weighs 4.348 lb/ft, or a total of 1130.5 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to micro-irrigation systems, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

Feature Measure: Length of Pipe

Scenario Unit:: Foot

Scenario Typical Size: 260.0

Scenario Total Cost: $3,118.03

Scenario Cost/Unit: $11.99

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	$1.21	260	$314.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	6	$114.00
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	$1.75	1243.5	$2,176.13
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 430 - Irrigation Pipeline

Scenario #7 - PVC, Plastic Irrigation Pipe, less than or equal to 10in

Scenario Description:

Description: Below ground installation of PVC (Plastic Irrigation Pipe) pipeline. PVC (PIP) is manufactured in sizes (nominal diameter) from 4-inch to 27-inch; typical practice sizes range from 4-inch to 24-inch; and typical scenario size is 8-inch. Construct 1/4 mile (1,320 feet) of 8-inch, Class 50 (SDR-81.0), PVC PIP with appurtenances, installed below ground with a minimum of 2 feet of ground cover. The unit is weight of pipe in pounds. 1,320 feet of 8-inch, Class 50 (SDR-81.0) PVC PIP weighs 2.515 lb/ft, or a total of 3319.8 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

Feature Measure: Length of pipe

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: $9,413.15

Scenario Cost/Unit: $7.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	$1.21	1320	$1,597.20
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	48	$912.00
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	$1.75	3651.8	$6,390.65
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 430 - Irrigation Pipeline

Scenario #8 - PVC, Plastic Irrigation Pipe, 12in

Scenario Description:

Description: Below ground installation of PVC (Plastic Irrigation Pipe) pipeline. PVC (PIP) is manufactured in sizes (nominal diameter) from 4-inch to 27-inch; typical practice sizes range from 4-inch to 24-inch; and typical scenario size is 12-inch. Construct 1/4 mile (1,320 feet) of 12-inch, Class 80 (SDR-51.0) , PVC PIP with appurtenances, installed below ground with a minimum of 2 feet of ground cover. The unit is weight of pipe in pounds. 1,320 feet of 12-inch, Class 80 (SDR-51.0) PVC PIP weighs 5.654 lb/ft, or a total of 7,463 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

Feature Measure: Length of pipe

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: $19,473.85

Scenario Cost/Unit: $14.75

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	$2.79	1320	$3,682.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	48	$912.00
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	$1.75	8209	$14,365.75
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 430 - Irrigation Pipeline

Scenario #9 - PVC, Plastic Irrigation Pipe, 15in

Scenario Description:

Description: Below ground installation of PVC (Plastic Irrigation Pipe) pipeline. PVC (PIP) is manufactured in sizes (nominal diameter) from 4-inch to 27-inch; typical practice sizes range from 4-inch to 24-inch; and typical scenario size is 15-inch. Construct 1/4 mile (1,320 feet) of 15-inch, Class 80 (SDR-51.0) , PVC PIP with appurtenances, installed below ground with a minimum of 2 feet of ground cover. The unit is weight of pipe in pounds. 1,320 feet of 15-inch, Class 80 (SDR-51.0) PVC PIP weighs 8.874 lb/ft, or a total of 11,713.7 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

Feature Measure: Length of pipe

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: $27,656.85

Scenario Cost/Unit: $20.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	$2.79	1320	$3,682.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	48	$912.00
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	$1.75	12885	$22,548.75
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 430 - Irrigation Pipeline

Scenario #10 - PVC, Plastic Irrigation Pipe, 18in

Scenario Description:

Description: Below ground installation of PVC (Plastic Irrigation Pipe) pipeline. PVC (PIP) is manufactured in sizes (nominal diameter) from 4-inch to 27-inch; typical practice sizes range from 4-inch to 24-inch; and typical scenario size is 18-inch. Construct 1/4 mile (1,320 feet) of 18-inch, Class 80 (SDR-51.0) , PVC PIP with appurtenances, installed below ground with a minimum of 3 feet of ground cover. The unit is weight of pipe in pounds. 1,320 feet of 18-inch, Class 80 (SDR-51.0) PVC PIP weighs 13.67 lb/ft, or a total of 18,044.40 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

Feature Measure: Length of pipe

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: $39,843.85

Scenario Cost/Unit: $30.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	$2.79	1320	$3,682.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	48	$912.00
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	$1.75	19849	$34,735.75
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 430 - Irrigation Pipeline

Scenario #11 - PVC, Plastic Irrigation Pipe, 21in or Greater

Scenario Description:

Description: Below ground installation of PVC (Plastic Irrigation Pipe) pipeline. PVC (PIP) is manufactured in sizes (nominal diameter) from 4-inch to 27-inch; typical practice sizes range from 4-inch to 24-inch; and typical scenario size is 21-inch. Construct 1/4 mile (1,320 feet) of 21-inch, Class 80 (SDR-51.0), PVC PIP with appurtenances, installed below ground with a minimum of 2 feet of ground cover. The unit is weight of pipe in pounds. 1,320 feet of 21-inch, Class 80 (SDR-51.0) PVC PIP weighs 19.01 lb/ft, or a total of 25,009 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

Feature Measure: Length of pipe

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: $49,124.10

Scenario Cost/Unit: $37.22

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	$2.79	1320	$3,682.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	48	$912.00
Materials						
Pipe, steel, smooth wall, galvanized, weight priced	1381	Steel manufactured into galvanized smooth wall pipe	Pound	$1.60	27510	$44,016.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 430 - Irrigation Pipeline

Scenario #12 - Steel, IPS, Stream or Road Crossing Sleeve

Scenario Description:

Description: Steel (Iron Pipe Size) sleeve for PVC underground pipeline, either crossing a stream or crossing a county, city, state road. Steel (IPS) is manufactured in sizes (nominal diameter) from ½-inch to 36-inch; typical practice sizes range from 2-inch to 18-inch; and typical scenario size is 18-inch. Construct 60 ft of 18-inch, Schedule 10, Galvanized Steel Pipe across a stream as a sleeve for a PVC underground pipeline. The unit is the weight of pipe material in pounds. 60 feet of 18-inch, Schedule 10, Galvanized Steel Pipe weighs 47.39 lb/ft, for total of 2843.4 pounds. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline section needed to cross a stream or a road that is needing a steel sleeve for protection installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

Feature Measure: Length of Pipe

Scenario Unit:: Foot

Scenario Typical Size: 60.0

Scenario Total Cost: $6,082.78

Scenario Cost/Unit: $101.38

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	4	$226.60
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$66.84	4	$267.36
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Portable Welder	1407	Portable field welder. Equipment only. Labor not included.	Hour	$20.63	4	$82.52
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	4	$109.52
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	4	$102.72
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	4	$102.72
Materials						
Pipe, smooth steel, weight priced	1325	Smooth Steel pipe priced by the weight of the pipe materials. Materials only.	Pound	$1.72	2843.4	$4,890.65
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 430 - Irrigation Pipeline

Scenario #14 - Stand Pipe, Steel, IPS

Scenario Description:

Description: New or replacement of Steel (Iron Pipe Size) stand or manifold. Steel (IPS) is manufactured in sizes (nominal diameter) from ½-inch to 36-inch; typical practice sizes range from 16-inch to 36-inch; and typical scenario size is 30-inch. Fabricate and install 8 ft of 30-inch, Schedule 10, Galvanized Steel Pipe stand/manifold at a well, relift pump or within a pipeline . The unit is the weight of pipe material in pounds. 8 feet of 30-inch, Schedule 10, Galvanized Steel Pipe weighs 98.93 lb/ft, for total of 791.4 pounds. Appurtenances include: fittings, air vents, and pressure relief valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Before Situation:

An old undersized stand pipe/manifold in need of replacing or no stand pipe/manifold currently in place.

After Situation:

Stand pipe/Manifold installed either at a well, relift or at a junction of several underground pipelines.

Feature Measure: Length of Pipe

Scenario Unit:: Foot

Scenario Typical Size: 8.0

Scenario Total Cost: $2,599.65

Scenario Cost/Unit: $324.96

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	6	$339.90
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Portable Welder	1407	Portable field welder. Equipment only. Labor not included.	Hour	$20.63	6	$123.78
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	6	$164.28
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	6	$154.08
Materials						
Steel, Plate, 1/8"	1047	Flat Steel Plate, 1/8" thick, materials only.	Square Foot	$3.97	4.91	$19.49
Pipe, smooth steel, weight priced	1325	Smooth Steel pipe priced by the weight of the pipe materials. Materials only.	Pound	$1.72	870.6	$1,497.43
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 436 - Irrigation Reservoir

Scenario #1 - Embankment Dam with On-Site Borrow

Scenario Description:

The reservoir, created by an embankment built across a natural depression, with an 18" diameter principal spillway outlet through the embankment, is controlled by a canal-style gate. Outlet can also serve as overflow protection with a 12" diameter standpipe and tee to the 18" pipe. Any watershed runoff will be diverted around reservoir. It will be built with approximately 4,500 cubic yards of on-site material. It will be about 19.9 feet high and 200 feet long and hold approximately 1,000,000 gallons (3 acre-feet). The top of berm will be 10 feet wide and the embankment side slopes will be 2.5 H to 1 V up and down stream. Resource concern: Insufficient Water - Inefficient use of irrigation water. Associated practices include: 521 - Pond Sealing or Lining (various); 320 - Irrigation Canal or Lateral; 430 - Irrigation Pipeline; 428 - Irrigation Ditch Lining; 533 - Pumping Plant; 440 series - Irrigation Systems; 378 - Pond; 447 - Irrigation System, Tailwater Recovery; 484 - Mulching; and 342 - Critical Area Planting.

Before Situation:

Current system relies on an intermittent or low-flow rate water source. This results in untimely and/or inefficient water application. Divert water around - no spillway

After Situation:

This is an embankment, installed across a natural off-stream intermittent watercourse, used to store water for subsequent irrigation. It will be used to accumulate and store water for timely and efficient application of water through an irrigation system The water source could be a well, irrigation district pipeline, and/or a pump from a stream. It is designed to deliver water by gravity to an open ditch or non-pressurized pipeline, generally in excess of 5 cfs. All earthen materials will be from on-site sources.

Feature Measure: Volume of Compacted Eartfill

Scenario Unit:: Cubic Yard

Scenario Typical Size: 4,500.0

Scenario Total Cost: $23,204.68

Scenario Cost/Unit: $5.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, common earth, large equipment, 1500 ft	1221	Bulk excavation of common earth including sand and gravel with scrapers with average haul distance of 1500 feet. Includes equipment and labor.	Cubic Yard	$3.98	4500	$17,910.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Pipe, HDPE, CPT, Double Wall, Soil Tight, 12"	1244	Pipe, Corrugated HDPE Double Wall, 12" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	$7.04	36	$253.44
Pipe, HDPE, CPT, Double Wall, Soil Tight, 18"	1245	Pipe, Corrugated HDPE Double Wall, 18" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	$13.28	120	$1,593.60
Screw gate, cast iron, 18" diameter, 10/0 head	1917	18" diameter cast iron screw (canal) gate rated at 10 seating head 0 feet unseating head. Materials only.	Each	$1,075.90	1	$1,075.90
Coupling, HDPE CPT Dual Wall, Tee, 18"x18"x12"	1921	Tee, 18"x18"x12" - HDPE CPT Tee. Materials only.	Each	$284.98	1	$284.98
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 436 - Irrigation Reservoir

Scenario #5 - Reservoir Machine Compacted

Scenario Description:

Due to the nature of the alluvial soils in the area, especially the high clay content soils, extra compaction is required to work the material into a proper density and to avoid macrospores. This is an on-farm storage reservoir constructed from on-site borrow to construct levees above the natural grade. Water is pumped from on-farm drainage (storm runoff, irrigation return flows) into the structure. Typically, the runoff is temporarily stored in a adjacent tailwater channel. The levees are constructed with a 12 foot top and a 4 foot berm at full pool conditions to prevent wave action erosion. The levees are typically built 8 feet above ground with a two to three foot cut in the reservoir bottom. Typical size is 50,000 to 60,000 cu yds of earthfill. An auxiliary spillway is set at the berm elevation to prevent water level rises above the berm. Critical Area Planting and Mulching is required. 25 acres is typical size. Resource Concern: Aquifer Overdraft, Excess nutrients in surface water. Associated Practices: 521 - Pond Sealing or Lining (various); 320 - Irrigation Canal or Lateral; 430 - Irrigation Pipeline; 428 - Irrigation Ditch Lining; 533 - Pumping Plant; 440 series - Irrigation Systems; 447 - Irrigation System, Tailwater Recovery; 378 - Pond; 484 - Mulching; and 342 - Critical Area Planting.

Before Situation:

Current irrigation system relies on pumped groundwater from an aquifer that is being mined (aquifer overdraft). Farm runoff containing nutrients and sediments is not captured.

After Situation:

The on-farm storage reservoir will accumulate and store on-farm runoff during the winter and early spring for use as irrigation water during the growing season as irrigation water, reducing groundwater demand by 75%, reducing storm runoff from the farm by 50% and reducing nutrient delivery similarly.

Feature Measure: Volume of Compacted Earthfill

Scenario Unit:: Cubic Yard

Scenario Typical Size: 55,000.0

Scenario Total Cost: $243,099.81

Scenario Cost/Unit: $4.42

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	55000	$215,600.00
Foregone Income						
FI, Rice	1974	Rice is Primary Crop	Acre	$484.57	25	$12,114.25
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	16	$578.88
Materials						
Pipe, Steel, 18", Std Wt	1366	Materials: - 18" - Steel Std Wt	Foot	$127.76	100	$12,776.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	3	$1,470.03

Practice: 436 - Irrigation Reservoir

Scenario #6 - Delta Tailwater Pit

Scenario Description:

A new excavated pit is constructed to collect the excess irrigation water to create a pumping pool and storage area so the water can be recovered and reused. Typical pit cross section is trapezoidal with 20 ft bottom x 10 ft depth, with 2:1 side slopes, and 1575 ft length. The total yardage of earthwork is 21,613 cy. Resource concerns that will be addressed: Excess/Insufficient Water - inefficient use of irrigation water; Water Quality Degradation - excessive sediments in surface waters; Water Quality Degradation - Excess nutrients in surface and ground water; Degradation Plant Condition - undesirable plant productivity and health. Associated practices: 533 - Pumping Plants; 410 - Grade Stabilization Structure; 587 - Structure for water control; 449 - Irrigation Water Management

Before Situation:

Excess irrigation water collects at lower ends of field and backs up into crops and causes plant stress or causes erosion and travels off farm in a drainage ditch causing water quality issues in lower watersheds.

After Situation:

Excess irrigation water is collected and directed into a recovery system where the water can be recycled and reused for irrigation. Sedimentation has a chance to settle out of the water allowing for less sediment to travel down stream.

Feature Measure: Volume of Earth Excavated

Scenario Unit:: Cubic Yard

Scenario Typical Size: 21,613.0

Scenario Total Cost: $46,390.84

Scenario Cost/Unit: $2.15

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 200 HP	928	Track mounted Dozer with horsepower range of 160 to 250. Equipment and power unit costs. Labor not included.	Hour	$196.22	40	$7,848.80
Tractor, agricultural, 360 HP	1205	Agricultural tractor with horsepower range of 340 to 390. Equipment and power unit costs. Labor not included.	Hour	$158.22	145	$22,941.90
Scraper, pull, 15 CY	1207	Pull type earthmoving scraper with 15 CY capacity. Does not include pulling equipment or labor. Add Tractor or Dozer, 260 HP typically required for single scraper.	Hour	$23.31	290	$6,759.90
Foregone Income						
FI, Rice	1974	Rice is Primary Crop	Acre	$484.57	3.62	$1,754.14
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	40	$760.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	170	$4,365.60
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	40	$1,447.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 441 - Irrigation System, Microirrigation

Scenario #1 - Subsurface Drip Irrigation

Scenario Description:

A subsurface drip irrigation system (SDI) with a lateral spacing between 37-59 inches. This buried drip irrigation system utilizes a thinwall dripperline or tape with inline emitters at a uniform spacing for the system laterals. The dripperline or tape is normally installed by being plowed in approx. 10-14 inches deep with a chisel shank type plow equipped with tape reels. This type of drip irrigation system utilizes a buried supply manifold with automated zone control valves and a buried flush manifold with manual flush valves. This permanent micro-irrigation system includes an automated filter station, flow meter, backflow prevention device, automated control box or timer, the thinwall dipperline or tape for laterals, both a supply and a flushing manifold and numerous types of water control valves. This is an all-inclusive system starting with the filter station including all required system components out to the flush valves. The water supply line from the water source to the filter station is an irrigation pipeline (430) and is not included as part of this system Resource Concerns: Insufficient Water - Inefficient use of irrigation water, Degraded Plant Condition - Undesirable plant productivity and health, Water Quality Degradation - Excessive sediment in surface waters, and Inefficient Energy Use - Equipment and facilities. Associated Practices: 533-Pumping Plant, 449- Irrigation Water Management, 430 - Irrigation Pipeline, 610 - Salinity & Sodic Soil Management, 328-Conservation Crop Rotation, and 590 Nutrient Management.

Before Situation:

Typical before irrigation situation would normally be an existing inefficient surface or sprinkler irrigation system on a cropland or hayland field. The existing irrigation system would experience poor, non-uniform irrigation applications and significant water losses affecting both water quantity and water quality

After Situation:

A typical practice would be the installation of a subsurface drip irrigation system (SDI) on a 60 acre cropland or hayland field. The system lateral (thinwall dripperline or tape) spacing would 40 inches. This highly efficient SDI (buried) irrigation system provides irrigation water directly to the plant root zone eliminating application losses resulting in a very high water application efficiency and properly designed these SDI systems are capable of very uniform water applications. Typical field size is 60 acres.

Feature Measure: Acres in System

Scenario Unit:: Acre

Scenario Typical Size: 60.0

Scenario Total Cost: $113,813.37

Scenario Cost/Unit: $1,896.89

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Micro Irrigation, chemical injection equipment	1987	Chemical Injector Pump, plus chemigation check valve, injector ports, and appurtenances, Installation included.	Each	$1,508.81	1	$1,508.81
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	$1.75	4800	$8,400.00
Flow Meter, with Electronic Index	1452	10 inch Turbine Irrigation flow meter, with Electronic Index, Rate and Volume, permanently installed. Materials only.	Each	$3,747.37	1	$3,747.37
Micro Irrigation, Media Filter, 30" to 48" Dia. tank, Equipped for Automatic Flush	1482	Sand or media filter for Micro irrigation system. Includes plumbing, connections and automatic controller. Unit is complete and installed. Unit price per filter, not per filter station.	Each	$5,347.77	3	$16,043.31
Micro Irrigation, screen filter, => 100 gpm	1484	Screen filter for Micro irrigation system with 100 gpm or greater capacity. Includes plumbing, connections and automatic controller. Unit is complete and installed. Unit price per filter, not per filter station.	Each	$345.53	1	$345.53
Micro Irrigation, control valves and timers	1485	Automatic controller and timer, to turn on and off the sets for micro irrigation, installation and valves. Based on control unit, not number of valves controlled.	Each	$1,357.55	1	$1,357.55
Micro Irrigation, buried drip tape	2521	Tape that is installed underground for sub-surface drip irrigation, includes installation, and connections to the supply and flushing laterals. Tape is a minimum of 10 mil thick thick and has emitters built in. Includes labor and installtion.	Foot	$0.10	824108	$82,410.80

Practice: 441 - Irrigation System, Microirrigation

Scenario #2 - Surface PE Orchard or Vineyard

Scenario Description:

A micro-irrigation system, utilizing surface PE tubing (can be placed on trellis or above ground) with emitters (emitters are already installed in the pipe or will be purchased to be installed in the field into the pipe) to provide irrigation for vineyards and orchards grown in a grid pattern. The typical system is a permanent system, installed on a 60 acre field on the ground surface. The field has a tree spacing of 50 feet x 50 feet. PE tubing is laid on each side of the tree row. Lateral lengths are 630 feet and there are 156 laterals. This system utilizes emitters at each plant as the water application device. This system typically includes a filter system, PE tubing laterals, PVC manifolds, and submains, valves, fittings, emitters, etc. This practice applies to systems designed to discharge < 60 gal/hr at each individual lateral discharge point. Does not include Pump, Power source, Water source (well or reservoir). Resource Concerns: Insufficient Water - Inefficient use of irrigation water, Degraded Plant Condition - Undesirable plant productivity and health, Water Quality Degradation - Excessive sediment in surface waters, and Inefficient Energy Use - Equipment and facilities. Associated Practices: 533-Pumping Plant, 449- Irrigation Water Management, 430 - Irrigation Pipeline, 587 - Structure for Water Control, 610 - Salinity & Sodic Soil Management, 328-Conservation Crop Rotation, and 590 Nutrient Management.

Before Situation:

A field has an inefficient surface flood irrigation system causing irrigation water loss that impacts water quality and water quantity.

After Situation:

A surface placed microirrigation system is utilized to provide highly efficient irrigation to an vineyard. Water applications are reduced and runoff eliminated. Offsite water quality is improved, and on site water use is reduced.

Feature Measure: Acres in System

Scenario Unit:: Acre

Scenario Typical Size: 60.0

Scenario Total Cost: $75,177.37

Scenario Cost/Unit: $1,252.96

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	$1.21	8100	$9,801.00
Micro Irrigation, chemical injection equipment	1987	Chemical Injector Pump, plus chemigation check valve, injector ports, and appurtenances, Installation included.	Each	$1,508.81	1	$1,508.81
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	$1.75	2592	$4,536.00
Flow Meter, with Electronic Index	1452	10 inch Turbine Irrigation flow meter, with Electronic Index, Rate and Volume, permanently installed. Materials only.	Each	$3,747.37	1	$3,747.37
Micro Irrigation, Media Filter, 30" to 48" Dia. tank, Equipped for Automatic Flush	1482	Sand or media filter for Micro irrigation system. Includes plumbing, connections and automatic controller. Unit is complete and installed. Unit price per filter, not per filter station.	Each	$5,347.77	3	$16,043.31
Micro Irrigation, screen filter, => 100 gpm	1484	Screen filter for Micro irrigation system with 100 gpm or greater capacity. Includes plumbing, connections and automatic controller. Unit is complete and installed. Unit price per filter, not per filter station.	Each	$345.53	1	$345.53
Micro Irrigation, control valves and timers	1485	Automatic controller and timer, to turn on and off the sets for micro irrigation, installation and valves. Based on control unit, not number of valves controlled.	Each	$1,357.55	1	$1,357.55
Micro Irrigation, surface drip tubing	1488	Tubing is installed above ground for surface drip irrigation, includes installation, and connections to the supply and flushing laterals. Tubing has emitters built in.	Foot	$0.35	108108	$37,837.80

Practice: 441 - Irrigation System, Microirrigation

Scenario #3 - Surface Tape <5 acres

Scenario Description:

A micro-irrigation system using drip tape or similar type micro-irrigation material placed on the soil surface for vegetables or field crops. Spacing of drip tape or similar type micro irrigation material is based on soil type or row alignment but will typically vary from 18" to 36". This system typically includes a filter system, PE manifolds fittings, drip tape, etc. This practice applies to systems designed to discharge < 60 gal/hr at each individual discharge point. Does not include Pump, power source, water source. Surface placed drip tape will not meet the 441 practice life and will normally need replacement every year. After first installation drip tape will be replaced as operation and maintenance issue as required for proper operation of the system. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, Degraded Plant Condition - Undesirable plant productivity and health, Water Quality Degradation - Excessive sediment in surface waters, and Inefficient Energy Use - Equipment and Facilities. Associated Practices: 533-Pumping Plant, 449-Irrigation Water Management, 430 - Irrigation Pipeline, 610 - Salinity & Sodic Soil Management, 328-Conservation Crop Rotation, 590 Nutrient Management, and 595-Itegrated Pest Management.

Before Situation:

A typical before irrigation situation would normally be an existing inefficient sprinkler or surface irrigation system for vegetable or other crop production system. The existing irrigation system would experience poor, nonuniform irrigation applications and significant water losses affecting both water quantity and water quality.

After Situation:

A surface placed microirrigation system is utilized to provide highly efficient irrigation to a field. Water applications are reduced and runoff eliminated. Offsite water quality is improved, and on site water use is reduced. Drip tape will be replaced as operation and maintenance issue as required for proper operation of the system. A typical scenario consists of a 1 acre irrigated field with lateral spacing of 2 feet.

Feature Measure: Acres in System

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $2,357.00

Scenario Cost/Unit: $2,357.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	4	$76.00
Materials						
Pipe, HDPE, smooth wall, weight priced	1379	High Density Polyethylene (HDPE) compound manufactured into smooth wall pipe. Materials only.	Pound	$2.08	49	$101.92
Micro Irrigation, surface drip tape	2522	Tape is installed above ground for surface drip irrigation on annual crops, includes installation, and connections to the supply and flushing laterals. Tape is a minimum of 10 mil thick and has emitters built in.	Foot	$0.07	23958	$1,677.06
Micro Irrigation, screen or disc filter, < 3"	2524	Micro Irrigation, small manual flush screen or disc filter, <3 inch nominal size. Includes materials only.	Each	$156.78	1	$156.78
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24

Practice: 441 - Irrigation System, Microirrigation

Scenario #4 - Surface Tape > 5 acres

Scenario Description:

A micro-irrigation system using drip tape or similar type micro-irrigation material placed on the soil surface for vegetables or field crops. Spacing of drip tape or similar type micro irrigation material is based on soil type or row alignment but will typically vary from 18" to 36". This system typically includes a filter system, PE manifolds fittings, drip tape, etc. This practice applies to systems designed to discharge < 60 gal/hr at each individual discharge point. Does not include Pump, power source, water source. Surface placed drip tape will not meet the 441 practice life and will normally need replacement every year. After first installation drip tape will be replaced as operation and maintenance issue as required for proper operation of the system. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, Degraded Plant Condition - Undesirable plant productivity and health, Water Quality Degradation - Excessive sediment in surface waters, and Inefficient Energy Use - Equipment and Facilities. Associated Practices: 533-Pumping Plant, 449-Irrigation Water Management, 430 - Irrigation Pipeline, 610 - Salinity & Sodic Soil Management, 328-Conservation Crop Rotation, 590 Nutrient Management, and 595-Itegrated Pest Management.

Before Situation:

A typical before irrigation situation would normally be an existing inefficient sprinkler or surface irrigation system for vegetable or other crop production system. The existing irrigation system would experience poor, nonuniform irrigation applications and significant water losses affecting both water quantity and water quality.

After Situation:

A surface placed microirrigation system is utilized to provide highly efficient irrigation to a field. Water applications are reduced and runoff eliminated. Offsite water quality is improved, and on site water use is reduced. Drip tape will be replaced as operation and maintenance issue as required for proper operation of the system. A typical scenario consists of a 20 acre irrigated field with lateral spacing of 2 feet.

Feature Measure: Acres in System

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: $54,375.29

Scenario Cost/Unit: $2,718.76

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	$1.21	1320	$1,597.20
Micro Irrigation, chemical injection equipment	1987	Chemical Injector Pump, plus chemigation check valve, injector ports, and appurtenances, Installation included.	Each	$1,508.81	1	$1,508.81
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	32	$608.00
Materials						
Pipe, PVC, 3", SCH 40	977	Materials: - 3" - PVC - SCH 40 - ASTM D1785	Foot	$2.62	1320	$3,458.40
Valve, Air Vacuum Release, Manual	1041	Materials for <2" Manual Air/Vacuum Relief Valve	Each	$33.33	2	$66.66
Micro Irrigation, control valves and timers	1485	Automatic controller and timer, to turn on and off the sets for micro irrigation, installation and valves. Based on control unit, not number of valves controlled.	Each	$1,357.55	2	$2,715.10
Ball Valve, 4"	1726	4" ball valve, metal body. Materials only.	Each	$326.60	6	$1,959.60
Water Meter, Microirrigation, <= 2”, with Volume Totalizer	2437	Microirrigation water meter less than or equal to 2 inch diameter, with volume totalizer. Includes materials only.	Each	$293.51	1	$293.51
Micro Irrigation, Media Filter, 12” to 24” Dia. tank, Equipped for Auto Flush	2466	Sand or media filter for Micro irrigation system. Includes filter, plumbing, connections and automatic controller. Unit is complete and installed. Unit is each Filter in a filter station that normally includes 2 or more filters.	Each	$2,078.47	4	$8,313.88
Pressure Regulator	2468	Materials for pressure regulator less than or equal to 2" diameter.	Each	$14.07	4	$56.28
Micro Irrigation, surface drip tape	2522	Tape is installed above ground for surface drip irrigation on annual crops, includes installation, and connections to the supply and flushing laterals. Tape is a minimum of 10 mil thick and has emitters built in.	Foot	$0.07	479160	$33,541.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 441 - Irrigation System, Microirrigation

Scenario #5 - Microjet

Scenario Description:

A micro-irrigation system, utilizing micro-jets to provide irrigation and\or frost protection for an orchard or other specialty crops grown in a grid pattern. The system is installed with all fittings, control valves, pressure reducing/regulating valves, air/vacuum release, sand media/screen/disc filters, pressure gauges, submains, lateral lines, and micro-jet sprayers to deliver water to the trees. This practice applies to systems designed to discharge < 60 gal/hr at each individual lateral discharge point. Does not include Pump, Power source, Water source (well or reservoir). The typical installation is a permanent, microjet -irrigation system installed on a 60 acre orchard. Typical tree spacing is 20' x 20 feet. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, Degraded Plant Condition - Undesirable plant productivity and health, Water Quality Degradation - Excessive sediment in surface waters, and Inefficient Energy Use - Equipment and facilities. Associated Practices: 533-Pumping Plant, 449- Irrigation Water Management, 430 - Irrigation Pipeline, 610 - Salinity & Sodic Soil Management, 328-Conservation Crop Rotation, and 590 Nutrient Management.

Before Situation:

An orchard has an inefficient irrigation system causing irrigation water loss that impacts water quality and water quantity.

After Situation:

A micro-spray microirrigation system is utilized to provide highly efficient irrigation to an orchard. Water applications are reduced and runoff eliminated. Offsite water quality is improved, and on site water use is reduced.

Feature Measure: Acres in System

Scenario Unit:: Acre

Scenario Typical Size: 60.0

Scenario Total Cost: $178,025.53

Scenario Cost/Unit: $2,967.09

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Micro Irrigation, chemical injection equipment	1987	Chemical Injector Pump, plus chemigation check valve, injector ports, and appurtenances, Installation included.	Each	$1,508.81	1	$1,508.81
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	$1.75	4800	$8,400.00
Flow Meter, with Electronic Index	1452	10 inch Turbine Irrigation flow meter, with Electronic Index, Rate and Volume, permanently installed. Materials only.	Each	$3,747.37	1	$3,747.37
Micro Irrigation, Media Filter, 30" to 48" Dia. tank, Equipped for Automatic Flush	1482	Sand or media filter for Micro irrigation system. Includes plumbing, connections and automatic controller. Unit is complete and installed. Unit price per filter, not per filter station.	Each	$5,347.77	3	$16,043.31
Micro Irrigation, screen filter, => 100 gpm	1484	Screen filter for Micro irrigation system with 100 gpm or greater capacity. Includes plumbing, connections and automatic controller. Unit is complete and installed. Unit price per filter, not per filter station.	Each	$345.53	1	$345.53
Micro Irrigation, control valves and timers	1485	Automatic controller and timer, to turn on and off the sets for micro irrigation, installation and valves. Based on control unit, not number of valves controlled.	Each	$1,357.55	1	$1,357.55
Micro Irrigation, emitters or sprays and tubing	1489	Emitters or sprays that are installed above ground for micro or drip irrigation. Includes installation and connections to the supply and flushing laterals. Tubing for the emitters is included in this item.	Foot	$1.02	143748	$146,622.96

Practice: 441 - Irrigation System, Microirrigation

Scenario #6 - Hoop House System

Scenario Description:

A micro-irrigation system, utilizing surface PE tubing (can be placed on trellis or above ground) with emitters to provide irrigation for specialty crop grown in hoop houses. The typical system is a permanent system, installed in a 30' x 96' house with 24" rows with emitters on 12" spacing. This system typically includes a filter system, PE tubing laterals, PVC manifolds, and submains, valves, fittings, emitters, etc. This practice applies to systems designed to discharge < 60 gal/hr at each individual lateral discharge point. Does not include Pump, Power source, Water source (well or reservoir). Resource Concerns: Insufficient Water - Inefficient use of irrigation water, Degraded Plant Condition - Undesirable plant productivity and health, Water Quality Degradation - Excessive sediment in surface waters, and Inefficient Energy Use - Equipment and facilities. Associated Practices: 533-Pumping Plant, 449- Irrigation Water Management, 430 - Irrigation Pipeline, 610 - Salinity & Sodic Soil Management, 328-Conservation Crop Rotation, and 590 Nutrient Management.

Before Situation:

Irrigation of hoop house crops is done using manual irrigation methods such as a garden hose or water pail. Requires a great amount of time and many times plants are over watered in areas and underwater in others. Inefficient use of irrigation water is a concern.

After Situation:

A micro irrigation system is in place that provides uniform water distribution throughout the house so that all crops will receive adequate and timely irrigation water.

Feature Measure: Area of house

Scenario Unit:: Square Foot

Scenario Typical Size: 2,880.0

Scenario Total Cost: $472.19

Scenario Cost/Unit: $0.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	4	$76.00
Materials						
Micro Irrigation, screen filter, < 100 gpm	1617	Screen filter for Micro Irrigation used in small systems. Includes filter. No controls are included or needed.	Each	$50.59	1	$50.59
Micro Irrigation, drip irrigation system, small scale	2170	An above ground, small scale, micro-irrigation system. Includes miniature emitters, tubes, or applicators placed along a water delivery line. Includes materials and shipping only.	Square Foot	$0.12	2880	$345.60

Practice: 442 - Sprinkler System

Scenario #1 - Center Pivot System

Scenario Description:

Installation of a low pressure center pivot system. Resource concerns include: Soil Erosion (Concentrated flow erosion e.g. irrigation induced), Insufficient Water (Inefficient use of irrigation water), Water Quality Degradation (Excess nutrients in surface and ground waters, Excessive salts in surface and ground waters, Excess pathogens and chemicals from manure, bio-solids or compost applications). Associated Practices: Irrigation Pipeline (430), Pumping Plant (533), Irrigation Water Management (449)

Before Situation:

A 160 acre field is flood irrigated. Application of irrigation water is inefficient and non-uniform. Irrigation water is typically over applied in some parts of the field, and under applied in others. Deep percolation from the excess irrigation delivers excess nutrients salts, and chemicals to the ground water. Runoff from the field contains excess nutrients and degrades the receiving waters. Irrigated induced erosion is excessive.

After Situation:

The existing surface irrigation system is converted to a low pressure center pivot. Corners are converted to non-irrigated cropland. The pivot is 1300 feet in length with pressure regulators and low pressure sprinklers on drops. The new irrigation system has a coefficient of uniformity above 85%. Irrigation water is efficiently and uniformly applied to maintain adequate soil water for the desired level of plant growth. Deep percolation and field runoff is eliminated and there are no excess nutrients, salts or pathogens delivered to the receiving waters. Irrigation induced runoff is eliminated. This center pivot scenario includes all hardware from the pivot point, including the concrete pad the pivot is placed on.

Feature Measure: Length of Center Pivot Lateral

Scenario Unit:: Foot

Scenario Typical Size: 1,300.0

Scenario Total Cost: $101,358.63

Scenario Cost/Unit: $77.97

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Irrigation, Center pivot system with appurtenances, fixed cost portion	317	Fixed cost portion of the center pivot system with appurtenances. This portion includes the following items: pivot point, pipe, towers, pad, controls, sprinklers, installation.	Each	$6,609.59	1	$6,609.59
Irrigation, Center pivot system with appurtenances, variable cost portion	318	Variable cost portion of the center pivot system with appurtenances. This portion includes the following items: pivot point, pipe, towers, pad, controls, sprinklers, installation.	Foot	$72.38	1300	$94,094.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	2	$141.74
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 442 - Sprinkler System

Scenario #4 - Solid Set System

Scenario Description:

A solid set irrigation system. Resource concerns include: Soil Erosion (Concentrated flow erosion e.g. irrigation induced), Insufficient Water (Inefficient use of irrigation water), Water Quality Degradation (Excess nutrients in surface and ground waters, Excessive salts in surface and ground waters, Excess pathogens and chemicals from manure, bio-solids or compost applications) Associated Practices: Irrigation Pipeline (430), Pumping Plant (533), Irrigation Water Management (449)

Before Situation:

The typical installation will be on cropland with some existing inefficient irrigation. The farm is typically producing specialty crops, such as fresh vegetables.

After Situation:

The system is installed on 10 acres or less. The installed solid set system has 3-4 inch pipe sizes and sprinklers set 30 - 50 ft apart. Improved distribution uniformity and irrigation efficiency will result.

Feature Measure: Area of Irrigation System

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $49,308.44

Scenario Cost/Unit: $4,930.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Irrigation, Solid Set, w/Appurtenances	324	Solid Set irrigation system that includes pipe, sprinklers, connections, installation and appurtenances.	Acre	$4,916.67	10	$49,166.70
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	2	$141.74

Practice: 442 - Sprinkler System

Scenario #5 - Traveling Gun System, less than 2 inch Hose

Scenario Description:

A portable small gun system used to apply irrigation water on small fields. A small traveling gun irrigation system is installed to apply water uniformly and at an acceptable application rate operated under pressure to effectively irrigate less than 3 acres. The irrigation system is installed with all necessary appurtenances. Resource concerns: Soil Erosion (Concentrated flow erosion, e.g. overflowing waste storage) and Water Quality Degradation (Excess nutrients in surface and ground waters, Excessive salts in surface and ground waters, Excess pathogens and chemicals from liquid manure) Associated Practices: Irrigation Pipeline (430), Pumping Plant (533), Irrigation Water Management (449), Conservation Crop Rotation (328), Cover Crop (340), Nutrient Management (590), Waste Utilization (633), Manure Transfer (634)

Before Situation:

An existing traveling gun on a 5 acre field is inefficient and is not applying water uniformly or not at an acceptable application rate. Excess applied water causes irrigation induced erosion, runoff and deep percolation. The runoff and deep percolation degrade the receiving waters.

After Situation:

A small traveling gun irrigation system is installed to irrigate 5 acres based on the determined spacing needs. Irrigation is applied efficiently and uniformly to maintain adequate soil water for plant growth without causing excessive water loss, erosion, or water quality degradation The irrigation system is installed with all necessary appurtenances.

Feature Measure: Number of Traveling Gun Systems

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $12,257.34

Scenario Cost/Unit: $12,257.34

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Irrigation, Traveling Gun System with <= 2" Nominal size hose, and appurtenances light duty	1478	Irrigation, Traveling Gun System with <= 2" Nominal size hose with appurtenances. This includes the sprinkler gun, traveler cart, hard hose, reel, connections, controls, and installation. Normal hose length 500'	Inch Diameter	$12,257.34	1	$12,257.34

Practice: 442 - Sprinkler System

Scenario #6 - Traveling Gun System, 2 to 3 inch Hose

Scenario Description:

A portable big gun system used to apply waste water from animal feeding operations. This traveling big gun unit includes a sprinkler, towable cart, 1000’ or more of PE hard hose, a self propelled reel that moves the sprinkler toward the reel during operation. The reel attaches to a mainline with appropriately designed towpath width. The scenario describes an irrigation system that is typical to confined animal feeding operations. Resource concerns: Soil Erosion (Concentrated flow erosion, e.g. overflowing waste storage) and Water Quality Degradation (Excess nutrients in surface and ground waters, Excessive salts in surface and ground waters, Excess pathogens and chemicals from liquid manure) Associated Practices: Irrigation Pipeline (430), Pumping Plant (533), Irrigation Water Management (449), Conservation Crop Rotation (328), Cover Crop (340), Nutrient Management (590), Waste Utilization (633), Manure Transfer (634)

Before Situation:

A confined, animal operation has a waste management system that exceeds its capacity, or a operation that does not have a waste management system in place. The inefficiency of the existing system or the lack of a waste management system has an impact on the soil and water quality. Animal waste runs off and degrades the receiving waters.

After Situation:

The big gun applies animal manure in an appropriate quantity and location that eliminates both runoff of the manure and deep percolation of excess nutrients, salts, and pathogens. The big gun system is typically located on 50 acres or less of hay/pasture land, or 100 acres or less of cropland. The system includes a large irrigation gun with 1” to 1½” orifice mounted onto a movable cart. 1000’ or more flexible 3” PE pipe is attached to the cart on one end and a large reel on the other end. The reel serves as storage are for the pipe as the cart moves back to the reel. The reel is turned by a small engine which gradually pulls the flexible pipe and cart back to the reel/base.

Feature Measure: Number of Traveling Gun Systems

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $24,037.02

Scenario Cost/Unit: $24,037.02

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Irrigation, Traveling Gun System, > 2" to 3 " Nominal size hose	1479	Irrigation, Traveling Gun System with 2.3 to 3 " Nominal size hose with appurtenances. This includes the sprinkler gun, traveler cart, hard hose, reel, connections, controls, and installation. Normal hose length 1000'.	Inch Diameter	$8,012.34	3	$24,037.02

Practice: 442 - Sprinkler System

Scenario #7 - Traveling Gun System, greater than 3 inch Hose

Scenario Description:

A portable big gun system used to apply waste water from animal feeding operations. This traveling big gun unit includes a sprinkler, towable cart, 1200’ or more of PE hard hose, a self propelled reel that moves the sprinkler toward the reel during operation. The reel attaches to a mainline with appropriately designed towpath width. The scenario describes an irrigation system that is typical to confined animal feeding operations. Resource concerns: Soil Erosion (Concentrated flow erosion, e.g. overflowing waste storage) and Water Quality Degradation (Excess nutrients in surface and ground waters, Excessive salts in surface and ground waters, Excess pathogens and chemicals from liquid manure) Associated Practices: Irrigation Pipeline (430), Pumping Plant (533), Irrigation Water Management (449), Conservation Crop Rotation (328), Cover Crop (340), Nutrient Management (590), Waste Utilization (633), Manure Transfer (634)

Before Situation:

A confined, animal operation has a waste management system that exceeds its capacity, or a operation that does not have a waste management system in place. The inefficiency of the existing system or the lack of a waste management system has an impact on the soil and water quality. Animal waste runs off and degrades the receiving waters.

After Situation:

The big gun applies animal manure in an appropriate quantity and location that eliminates both runoff of the manure and deep percolation of excess nutrients, salts, and pathogens. The big gun system is typically located on 50 acres or less of hay/pasture land, or 100 acres or less of cropland. The system includes a large irrigation gun with 1” to 1½” orifice mounted onto a movable cart. 1200’ or more flexible 4” PE pipe is attached to the cart on one end and a large reel on the other end. The reel serves as storage are for the pipe as the cart moves back to the reel. The reel is turned by a small engine which gradually pulls the flexible pipe and cart back to the reel/base.

Feature Measure: Number of Traveling Gun Systems

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $47,558.92

Scenario Cost/Unit: $47,558.92

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Irrigation, Traveling Gun System, > 3" Nominal size hose	1762	Irrigation, Traveling Gun System with > 3" Nominal size hose with appurtenances. This includes the sprinkler gun, traveler cart, hard hose, reel, connections, controls, and installation. Normal hose length 1300'	Each	$47,558.92	1	$47,558.92

Practice: 442 - Sprinkler System

Scenario #33 - Renovation of Existing Sprinkler System- Alternating Drops

Scenario Description:

Center Pivot and Linear Move sprinkler systems are used in large crop fields with fairly regular field borders and flat topography. The scenario involves changing nozzles on center pivot or lateral move irrigation systems to re-nozzled, low-pressure systems to improve efficiency of water use and reduce energy use. This scenario is intended for cropland areas where the objective is water conservation. A typical scenario assumes a 1300 LF span, including end booms renozzled with low-pressure nozzles and drops, with drops mounted on trusses and alternating sides of the pivot. Resource concerns include: Soil Erosion (Concentrated flow erosion e.g. irrigation induced), Insufficient Water (Inefficient use of irrigation water), Water Quality Degradation (Excess nutrients in surface and ground waters, Excessive salts in surface and ground waters, Excess pathogens and chemicals from manure, bio-solids or compost applications), Inefficient Energy Use (Equipment and facilities e.g. pumping) Associated Practices: Irrigation Pipeline (430), Pumping Plant (533), Irrigation Water Management (449)

Before Situation:

A center pivot or lateral move system has high pressure sprinklers. The nozzles are worn and water is applied non-uniformly. Water runs off the field and degrades the receiving waters. Deep percolation in some parts of the field degrades the ground water quality. The runoff from the field causes soil erosion. The high pressure requirement for the system requires excess energy use.

After Situation:

A Center Pivot or Linear Move sprinkler system with a span of 1300 linear feet is re-nozzled with low-pressure nozzles and drops mounted on trusses and alternating sides of the system. The irrigation water is applied efficiently and uniformly to maintain adequate soil moisture for optimum plant growth. Runoff and deep percolation are eliminated, and the surface and ground water is no longer degraded. The irrigation induced soil erosion caused by runoff is also eliminated. The lower pressure requirements of the sprinklers reduces the energy used by the pump and alternating drops reduce instantaneous application rates.

Feature Measure: Length of Lateral Retrofitted

Scenario Unit:: Linear Foot

Scenario Typical Size: 1,300.0

Scenario Total Cost: $12,560.26

Scenario Cost/Unit: $9.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Aerial lift, telescoping bucket	1893	Aerial lift, bucket truck or cherry picker, typical 40' boom. Equipment only.	Hour	$42.64	16	$682.24
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	32	$608.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	32	$694.72
Materials						
Irrigation, Sprinkler Package, Renozzle or Retrofit, with drops and pressure regulators	1480	Sprinkler Package - Rennovation including sprinkler nozzle addition, and/or replacement, including new pressure regulators and drops.	Foot	$7.74	1300	$10,062.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 443 - Irrigation System, Surface and Subsurface

Scenario #1 - Surge Valve & Controller

Scenario Description:

This scenario would typically include installation and utilization of a 10-inch surge valve with automated controller (including all appurtenances) and installation labor needed to convert from a conventional surface irrigated system to a surge irrigation system. Typical field size is 80 acres. The surge valve will be used with PVC Gated Pipe or PE Gated Tubing to convey and distribute irrigation water to alternating irrigation sets in a timed surge cycle that results in a reduced surging irrigation application. The surging action increases rate of advance along set length, reduces deep percolation at upper end of field, increases uniformity of application along row length, and on lower intake soils can significantly reduce runoff losses. The result is improved irrigation efficiency, reduced leaching and erosion losses, and conserved energy. This scenario does not include gated pipe or associated practices. Units have been changed to inches to allow one to scale up or down the size of the valve. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, and Degraded Plant Condition - Undesirable plant productivity and health, Water Quality Degradation- Excess nutrients in surface and ground waters, Water Quality Degradation - Excessive sediment in surface waters, and Inefficient Energy Use - Equipment and facilities Associated Practices: 464-Irrigation Land leveling, 533-Pumping Plant, 449- Irrigation Water Management, 430 - Irrigation Pipeline, 328-Conservation Crop Rotation, and 590 Nutrient Management.

Before Situation:

Unacceptable irrigation application uniformity along existing surface irrigation system furrow or border length caused by excessive run length or soil infiltration rate when operated with continuous inflow on existing system. System is over irrigated in attempt to adequately irrigate low end of field.

After Situation:

A surge surface irrigation system is in place. After implementation, distribution uniformity and irrigation efficiency is improved, by reducing irrigation application volume and deep percolation losses. Runoff reductions, reduced energy use, and air quality improvements can also result.

Feature Measure: Number of Surge Valves

Scenario Unit:: Inch

Scenario Typical Size: 10.0

Scenario Total Cost: $2,274.31

Scenario Cost/Unit: $227.43

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00
Materials						
Surge Valve And Controller	1477	Surge Valve and Controller, with appurtenances. Material cost includes valve, controller, all appurtenances, and mobilization.	Each	$2,236.31	1	$2,236.31

Practice: 443 - Irrigation System, Surface and Subsurface

Scenario #4 - Poly Irrigation Tubing

Scenario Description:

This practice includes installation of thin wall Polyethylene (PE) irrigation tubing with 2½-inch gates, or gated pipe installed in shallow above ground trenches to replace above ground canals used to deliver water to individual basins within a contour levee or basin surface irrigation system. The typical scenario will use 1,320 feet of 15-inch, 10 mil, PE irrigation tubing (a 1,320-foot roll weighs 250 pounds) with 100 2½-inch gates spaced approximately 13 feet apart, installed in shallow above ground trenches to replace above ground canals used to deliver water to individual basins within a 40-acre irrigated field. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, and Degraded Plant Condition - Undesirable plant productivity and health, Water Quality Degradation- Excess nutrients in surface and ground waters, Water Quality Degradation - Excessive sediment in surface waters, and Inefficient Energy Use - Equipment and facilities Associated Practices: 464-Irrigation Land leveling, 533-Pumping Plant, 449- Irrigation Water Management, 430 - Irrigation Pipeline, 328-Conservation Crop Rotation, and 590-Nutrient Management.

Before Situation:

Typical before situation would include a contour levee or basin surface irrigation system. Irrigation water is delivered to individual basins in a 40-acre rice field split into paddies using irrigation canals and field ditches.

After Situation:

After implementation irrigation efficiency is improved, while reducing irrigation application volume, runoff, evaporation losses, and cold water damage to crops. Reduced energy use and air quality improvements can also result.

Feature Measure: Length of Pipe

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: $691.50

Scenario Cost/Unit: $0.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	10	$190.00
Materials						
Pipe, PE, collapsible, weight priced	1385	Polyethylene (PE) compound manufactured into collapsible tubing	Pound	$1.29	250	$322.50
Flap gate, plastic, 2½"	1424	2 1/2" plastic flap gate for poly irrigation tubing. Materials only.	Each	$1.79	100	$179.00

Practice: 447 - Irrigation System, Tailwater Recovery

Scenario #1 - Delta Tail Water Pit

Scenario Description:

A recovery pit is constructed to temporarily store the excess irrigation water and create a pumping pool so that the excess water can be recovered and reused. Typical pit size is trapezoidal ditch with 14ft bottom x 10ft depth x 1750 ft length with 2:1 side slopes. The total yardage of earthwork is 22,037 cy. Construction is typically done with either tractors and pans or with dozer and excavator. Resource concerns that will be addressed: Excess/Insufficient Water - inefficient use of irrigation water; Water Quality Degradation - excessive sediments in surface waters; Water Quality Degradation - Excess nutrients in surface and ground water; Degradation Plant Condition - undesirable plant productivity and health. Associated practices: 533 - Pumping Plants; 410 - Grade Stabilization Structure; 587 - Structure for water control; 449 - Irrigation Water Management; 436 - Irrigation Reservoir

Before Situation:

Excess irrigation water collects at lower ends of field and backs up into crops and causes plant stress or causes erosion and travels off farm in a drainage ditch causing water quality issues in lower watersheds. Excess irrigation water and runoff during the off season is not capture and unavailable for use.

After Situation:

Excess irrigation water is collected and directed into a recovery system where the water can be recycled and reused for irrigation. Sedimentation has a chance to settle out of the water allowing for less sediment to travel down stream. All runoff has an opportunity to be collected.

Feature Measure: Excavated Material

Scenario Unit:: Cubic Yard

Scenario Typical Size: 22,307.0

Scenario Total Cost: $38,222.55

Scenario Cost/Unit: $1.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$1.69	22037	$37,242.53
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 449 - Irrigation Water Management

Scenario #1 - Basic IWM 30 acres or less

Scenario Description:

A low Intensity irrigation water management system for producers using a checkbook method (crop grown, soil moisture conditions prior to irrigation, dates of irrigation start and stop, depths of irrigation applied, duration of irrigations, and amount of rainfall). For a typical scenario, soil moisture is determined by the feel method, volumes of irrigation water are based on energy or water district bills, records are kept on paper copies, and calculations are made by hand. Phaucet Program could be used where poly pipe is utilized. Resource Concerns: Insufficient Water Supply-Inefficient use of irrigation water; Degraded Plant Condition-Undesirable plant productivity and health, and Inefficient Energy Use-Equipment and facilities. Associated Practices: 441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface, 433-Irrigation Water Measurement, 434-Soil Moisture Measurement, 433- Irrigation Flow Measurement.

Before Situation:

The irrigator decides when to irrigate based on general crop or soil appearance or limited soil moisture monitoring. System run times are based on past apparent success. The typical irrigated field is a 30 acre corn field with a surface irrigation system.

After Situation:

Irrigations are scheduled based on measured crop water requirements. Records are used to evaluate results of past irrigation events and influence future irrigations. The irrigator keeps records of soil moisture, crop water use, rainfall amounts and irrigation timing and amounts. At the end of the irrigation season all the data has been reviewed and evaluated. Improvements planned for the next season have been determined.

Feature Measure: Irrigated Area Managed

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: $868.32

Scenario Cost/Unit: $28.94

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	24	$868.32

Practice: 449 - Irrigation Water Management

Scenario #2 - Basic IWM more than 30 acres

Scenario Description:

A low Intensity irrigation water management system for producers using a checkbook method (crop grown, soil moisture conditions prior to irrigation, dates of irrigation start and stop, depths of irrigation applied, duration of irrigations, and amount of rainfall). For a typical scenario, soil moisture is determined by the feel method, volumes of irrigation water are based on energy or water district bills, records are kept on paper copies, and calculations are made by hand. Phaucet Program could be used where poly pipe is utilized. Resource Concerns: Insufficient Water Supply-Inefficient use of irrigation water; Degraded Plant Condition-Undesirable plant productivity and health, and Inefficient Energy Use-Equipment and facilities. Associated Practices: 441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface, 433-Irrigation Water Measurement, 434-Soil Moisture Measurement, 433- Irrigation Flow Measurement.

Before Situation:

The irrigator decides when to irrigate based on general crop or soil appearance or limited soil moisture monitoring. System run times are based on past apparent success. The typical irrigated field is a 125 acre corn field with a sprinkler irrigation system.

After Situation:

Irrigations are scheduled based on measured crop water requirements. Records are used to evaluate results of past irrigation events and influence future irrigations. The irrigator keeps records of soil moisture, crop water use, rainfall amounts and irrigation timing and amounts. At the end of the irrigation season all the data has been reviewed and evaluated. Improvements planned for the next season have been determined.

Feature Measure: Irrigated Area Managed

Scenario Unit:: Acre

Scenario Typical Size: 125.0

Scenario Total Cost: $1,309.76

Scenario Cost/Unit: $10.48

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	32	$1,157.76

Practice: 449 - Irrigation Water Management

Scenario #3 - Intermediate IWM 30 acres or less

Scenario Description:

A medium intensity irrigation water management system for producers using a checkbook method (crop grown, soil moisture conditions prior to irrigation, dates of irrigation start and stop, depths of irrigation applied, duration of irrigations, and amount of rainfall). The use of programs such as Phaucet or Pipe Planner for poly pipe will be use for improving of irrigation application. For a typical scenario, soil moisture is determined by in-field moisture sensors with manual downloads. Irrigation amounts are recorded from a flow meter near the pump. Records are input manually into an irrigation scheduling computer program. Resource Concerns: Insufficient Water Supply-Inefficient use of irrigation water; Degraded Plant Condition-Undesirable plant productivity and health, and Inefficient Energy Use-Equipment and facilities. Associated Practices: 441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface, 433-Irrigation Water Measurement, 434-Soil Moisture Measurement, 433- Irrigation Flow Measurement.

Before Situation:

The farmer decides when to irrigate based on general crop or soil appearance or limited soil moisture monitoring. System run times are based on past apparent success. The typical irrigated field is a 30 acre corn field with a surface irrigation system.

After Situation:

Irrigations are scheduled based on measured crop water requirements. Records are used to evaluate results of past irrigation events and influence future irrigations. The irrigator keeps records of soil moisture, crop water use, rainfall amounts and irrigation timing and amounts. At the end of the irrigation season all the data has been reviewed and evaluated. Improvements planned for the next season have been determined.

Feature Measure: Irrigated Area Managed

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: $1,157.76

Scenario Cost/Unit: $38.59

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	32	$1,157.76

Practice: 449 - Irrigation Water Management

Scenario #4 - Intermediate IWM more than 30 acres

Scenario Description:

A medium intensity irrigation water management system for producers using a checkbook method (crop grown, soil moisture conditions prior to irrigation, dates of irrigation start and stop, depths of irrigation applied, duration of irrigations, and amount of rainfall). The use of programs such as Phaucet or Pipe Planner for poly pipe will be use for improving of irrigation application. For a typical scenario, soil moisture is determined by in field moisture sensors with manual downloads. Irrigation amounts are recorded from a flow meter near the pump. Records are input manually into an irrigation scheduling computer program. Resource Concerns: Insufficient Water Supply-Inefficient use of irrigation water; Degraded Plant Condition-Undesirable plant productivity and health, and Inefficient Energy Use-Equipment and facilities. Associated Practices: 441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface, 433-Irrigation Water Measurement, 434-Soil Moisture Measurement, 433- Irrigation Flow Measurement.

Before Situation:

The farmer decides when to irrigate based on general crop or soil appearance or limited soil moisture monitoring. System run times are based on past apparent success. The typical irrigated field is a 125 acre corn field with a sprinkler irrigation system.

After Situation:

Irrigations are scheduled based on measured crop water requirements. Records are used to evaluate results of past irrigation events and influence future irrigations. The irrigator keeps records of soil moisture, crop water use, rainfall amounts and irrigation timing and amounts. At the end of the irrigation season all the data has been reviewed and evaluated. Improvements planned for the next season have been determined.

Feature Measure: Irrigated Area Managed

Scenario Unit:: Acre

Scenario Typical Size: 125.0

Scenario Total Cost: $1,675.20

Scenario Cost/Unit: $13.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	12	$228.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	40	$1,447.20

Practice: 449 - Irrigation Water Management

Scenario #5 - Advanced IWM 30 acres or less

Scenario Description:

A high intensity irrigation water management system for producers using a checkbook method with advanced methods of determining irrigation water applied, and estimating crop evapotranspiration, monitoring field soil moisture, or monitoring crop temperature stress. The use of programs such as Phaucet or Pipe Planner for poly pipe will be use for improving of irrigation application. Typical methods include flow measurement, daily record keeping, and use of real-time evapotranspiration estimates (such as those provided dedicated weather stations) and/or soil moisture sensors with automated data logging to monitor field soil moisture content and/or crop temperature. For this scenario, soil moisture is determined by automated soil moisture monitoring stations equipped with telemetry data. Irrigation amounts are recorded from a flow meter near the pump. Telemetry data is automatically sent to a computer with irrigation software. Irrigator also receives real time data via mobile phone applications. Some data such as total water applied may be entered into computer software manually. Resource Concerns: Insufficient Water Supply-Inefficient use of irrigation water; Degraded Plant Condition-Undesirable plant productivity and health, and Inefficient Energy Use-Equipment and facilities. Associated Practices: 441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface, 433-Irrigation Water Measurement, 434-Soil Moisture Measurement, 433- Irrigation Flow Measurement.

Before Situation:

The farmer decides when to irrigate based on general crop or soil appearance or limited soil moisture monitoring. System run times are based on past apparent success. The typical irrigated field is a 30 acre corn field with a surface irrigation system.

After Situation:

Irrigations are scheduled based on measured crop water requirements. Records are used to evaluate results of past irrigation events and influence future irrigations. The irrigator keeps records of soil moisture, crop water use, rainfall amounts and irrigation timing and amounts. At the end of the irrigation season all the data has been reviewed and evaluated. Improvements planned for the next season have been determined.

Feature Measure: Irrigated Area Managed

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: $1,447.20

Scenario Cost/Unit: $48.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	40	$1,447.20

Practice: 449 - Irrigation Water Management

Scenario #6 - Advanced IWM more than 30 acres

Scenario Description:

A high intensity irrigation water management system for producers using a checkbook method with advanced methods of determining irrigation water applied, and estimating crop evapotranspiration, monitoring field soil moisture, or monitoring crop temperature stress. The use of programs such as Phaucet or Pipe Planner for poly pipe will be use for improving of irrigation application. Typical methods include flow measurement, daily record keeping, and use of real-time evapotranspiration estimates (such as those provided dedicated weather stations) and/or soil moisture sensors with automated data logging to monitor field soil moisture content and/or crop temperature. For this scenario, soil moisture is determined by automated soil moisture monitoring stations equipped with telemetry data. Irrigation amounts are recorded from a flow meter near the pump. Telemetry data is automatically sent to a computer with irrigation software. Irrigator also receives real time data via mobile phone applications. Some data such as total water applied may be entered into computer software manually. Resource Concerns: Insufficient Water Supply-Inefficient use of irrigation water; Degraded Plant Condition-Undesirable plant productivity and health, and Inefficient Energy Use-Equipment and facilities. Associated Practices: 441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface, 433-Irrigation Water Measurement, 434-Soil Moisture Measurement, 433- Irrigation Flow Measurement.

Before Situation:

The farmer decides when to irrigate based on general crop or soil appearance or limited soil moisture monitoring. System run times are based on past apparent success. The typical irrigated field is a 125 acre corn field with sprinkler irrigation.

After Situation:

Irrigations are scheduled based on measured crop water requirements. Records are used to evaluate results of past irrigation events and influence future irrigations. The irrigator keeps records of soil moisture, crop water use, rainfall amounts and irrigation timing and amounts. At the end of the irrigation season all the data has been reviewed and evaluated. Improvements planned for the next season have been determined.

Feature Measure: Irrigated Area Managed

Scenario Unit:: Acre

Scenario Typical Size: 125.0

Scenario Total Cost: $2,040.64

Scenario Cost/Unit: $16.33

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	48	$1,736.64

Practice: 449 - Irrigation Water Management

Scenario #7 - IWM Device_YR1

Scenario Description:

This practice includes the installation of an Irrigation Water Management device such as soil moisture sensors(tensiometers, gyp blocks, capacitance sensors etc.), atmometers, water level sensors, etc., that are installed and read to determine various information to be used by the cooperator in improving irrigator management. This level of instrumentation requires manual reading. Note: flowmeter (587) and surge valve (443) are separate practices and are not to be used as an IWM device under this practice. The installation includes the purchase of IWM device, installation of equipment, and labor to install and read sensors or device. Typical Scenario involves installation of resistance sensor blocks in a 80 acre field of irrigated cropland. In typical scenario, producer periodically monitors soil moisture sensors during the growing season. Meters used to read sensors may be portable. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, and Degraded Plant Condition - Undesirable plant productivity and health, and Inefficient Energy Use - Equipment and facilities. Associated Practices: 449- Irrigation Water Management, 587-Structure for water Control, 328-Conservation Crop Rotation, and 590-Nutrient Management.

Before Situation:

In the typical scenario, producer uses manual methods to evaluate parameter, such as feel method to estimate soil moisture for scheduling irrigation.

After Situation:

In typical scenario, producer uses instrumentation in lieu of manual methods and has installed four sensors at each monitoring site to a depth of four feet with one sensor representing each foot of depth. Producer uses periodic soil moisture measurements to schedule irrigation resulting in improved irrigation water management and reduced energy use.

Feature Measure: Number of Measuring Sites

Scenario Unit:: Each

Scenario Typical Size: 2.0

Scenario Total Cost: $2,350.93

Scenario Cost/Unit: $1,175.47

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	32	$1,157.76
Materials						
Weather Station, Basic	314	Basic Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, and temperature to a home weather console. Includes materials only.	Each	$304.96	1	$304.96
Soil Moisture Meter	1455	Soil Moisture Sensor Reader. Equipment only.	Each	$292.95	1	$292.95
Soil Moisture Sensor	1456	Soil moisture resistance sensor W/10' cables. Equipment only.	Each	$37.69	8	$301.52
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	2	$141.74

Practice: 449 - Irrigation Water Management

Scenario #8 - IWM Device with Data Recorder_YR1

Scenario Description:

This practice includes the installation of an Irrigation Water Management device such as soil moisture sensors(tensiometers, gyp blocks, capacitance sensors etc.), atmometers, water level sensors, etc., with built-in data recording capability that are installed and read by data logger/laptop to determine various information to be used by the cooperator in improving irrigator management. Note: flowmeter (587) and surge valve (443) are separate practices and are not to be used as an IWM device under this practice. The practice installation includes the purchase of IWM device, installation equipment (probe or auger), and a data logger to log continuous parameter data that can be downloaded to a personal computer and associated graphing software. Typical Scenario involves installation of resistance sensor blocks in a 80 acre field of irrigated cropland. Producer periodically monitors soil moisture sensors during the growing season. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, and Degraded Plant Condition - Undesirable plant productivity and health, and Inefficient Energy Use - Equipment and facilities. Associated Practices: 449-Irrigation Water Management, 587-Structure for water Control, 328-Conservation Crop Rotation, and 590-Nutrient Management.

Before Situation:

In the typical scenario, producer uses manual methods to evaluate parameter, such as feel method to estimate soil moisture for scheduling irrigation.

After Situation:

In typical scenario, producer uses recording instrumentation in lieu of manual methods and has installed four sensors at each monitoring site to a depth of four feet with one sensor representing each foot of depth. Producer periodically downloads continuously recorded soil moisture measurements that are used to schedule irrigation more effectively resulting in improved irrigation water management and reduced energy use.

Feature Measure: Number of Measuring Sites

Scenario Unit:: Each

Scenario Typical Size: 2.0

Scenario Total Cost: $3,984.38

Scenario Cost/Unit: $1,992.19

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	12	$228.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	40	$1,447.20
Materials						
Weather Station, Basic	314	Basic Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, and temperature to a home weather console. Includes materials only.	Each	$304.96	1	$304.96
Data Logger	1453	Data Logger W/Graphic Output for water management. Materials only.	Each	$780.48	2	$1,560.96
Soil Moisture Sensor	1456	Soil moisture resistance sensor W/10' cables. Equipment only.	Each	$37.69	8	$301.52
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	2	$141.74

Practice: 449 - Irrigation Water Management

Scenario #9 - IWM Device w. Telemetry_YR1

Scenario Description:

This practice includes the installation of an Irrigation Water Management device such as soil moisture sensors(tensiometers, gyp blocks, capacitance sensors etc.), atmometers, water level sensors, etc., with a telemetry system to transmit continuous parameter data that can be utilized on tablets, smartphones, laptops, or personal computer and associated graphing software to evaluate various parameters to be used by the cooperator in improving irrigation water management in real time. Note: flowmeter (587) and surge valve (443) are separate practices and are not to be used as an IWM device under this practice. The practice installation includes the purchase of IWM device, installation equipment (probe or auger), and a telemetry system to transmit continuous parameter data that can be utilized on an electronic device (tablet, smartphone, laptop, pc) and associated graphing software. Typical Scenario involves installation of resistance sensor blocks in a 80 acre field of irrigated cropland. Producer periodically monitors soil moisture sensors during the growing season. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, and Degraded Plant Condition - Undesirable plant productivity and health, and Inefficient Energy Use - Equipment and facilities. Associated Practices: 449- Irrigation Water Management, 587-Structure for water Control, 328-Conservation Crop Rotation, and 590-Nutrient Management.

Before Situation:

In the typical scenario, producer uses manual methods to evaluate parameter, such as feel method to estimate soil moisture for scheduling irrigation.

After Situation:

In typical scenario, producer uses instrumentation with real-time, continuous telemetry in lieu of manual methods and has installed four sensors at each monitoring site to a depth of four feet with one sensor representing each foot of depth. Producer utilizes continuously transmitted soil moisture measurements in analysis software that are used to schedule irrigation more effectively resulting in improved irrigation water management and reduced energy use.

Feature Measure: Number of Sensors in field

Scenario Unit:: Each

Scenario Typical Size: 2.0

Scenario Total Cost: $4,512.11

Scenario Cost/Unit: $2,256.06

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	48	$1,736.64
Materials						
Weather Station, Basic	314	Basic Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, and temperature to a home weather console. Includes materials only.	Each	$304.96	1	$304.96
Data Logger with Telemetry System	1454	Data Logger W/Graphic Output for water management and telemetry - data communication device with power supply in a weather proof enclosure. Equipment only.	Each	$1,723.25	1	$1,723.25
Soil Moisture Sensor	1456	Soil moisture resistance sensor W/10' cables. Equipment only.	Each	$37.69	8	$301.52
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	2	$141.74

Practice: 449 - Irrigation Water Management

Scenario #10 - Rice Intermittent Flood All Season

Scenario Description:

Managing water levels in rice fields for the entire growing season to minimize greenhouse gas production according to an irrigation water management plan developed in cooperation with university and/or water district personnel. Typical irrigation water management will include managing water levels in the field to “dry down” between full flood conditions to a saturated soil condition prior to re-flooding the field. Records are kept for flooding operations. Irrigation return flows will be reduced also, decreasing groundwater demand and decreasing exports improving water quality. Energy use should also be reduced. Resource Concerns: Excessive Greenhouse Gas – CH4 (methane); Excessive Greenhouse Gas – CO2 (carbon dioxide) or Excessive Greenhouse Gas – N2O (nitrous oxide). Insufficient Water Supply-Inefficient use of irrigation water; and Inefficient Energy Use-Equipment and facilities. Associated Practices: 410 - Grade Stabilization Structure; 430 - Irrigation Pipeline; 464 - Irrigation Land Leveling; 443 - Irrigation System, Surface and Subsurface; 587-Structure for water Control; and 590-Nutrient Management.

Before Situation:

Farmer maintains continuous flood on rice fields during the growing season. Significant greenhouse gases are produced. Water and nutrients are lost if rainfall occurs during the growing season.

After Situation:

Farmer floods fields and allows the fields to “dry-down” until little of no water is standing in the field but the soil is maintained in a saturated condition. The fields are then re-flooded and the cycle is repeated throughout the growing season. Greenhouse gas production is reduced. Water and nutrients are conserved.

Feature Measure: Irrigated Acres Managed

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $1,444.28

Scenario Cost/Unit: $36.11

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	25	$684.50
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	21	$759.78

Practice: 449 - Irrigation Water Management

Scenario #11 - Early Dry Down

Scenario Description:

Managing water levels in rice fields at the end of the growing season to minimize greenhouse gas production according to an irrigation water management plan developed in cooperation with university and/or water district personnel. Typical irrigation water management will include managing the field to an early “dry down” at the end of the growing season based on plant growth stage. Records are kept for end of season flooding operations. Irrigation return flows will be reduced also, decreasing groundwater demand and decreasing exports improving water quality. Energy use should also be reduced. Resource Concerns: Excessive Greenhouse Gas – CH4 (methane); Excessive Greenhouse Gas – CO2 (carbon dioxide) or Excessive Greenhouse Gas – N2O (nitrous oxide), Insufficient Water Supply-Inefficient use of irrigation water; and Inefficient Energy Use-Equipment and facilities. Associated Practices: 410 - Grade Stabilization Structure; 430 - Irrigation Pipeline; 464 - Irrigation Land Leveling; 443 - Irrigation System, Surface and Subsurface; 587-Structure for water Control; and 590-Nutrient Management.

Before Situation:

Farmer maintains continuous flood on rice fields during the growing season until rice is ready for harvest. Levees are cut and the fields are drained. Significant greenhouse gases are produced. Water and nutrients are lost if rainfall occurs during the growing season and at the end of the growing season.

After Situation:

Farmer floods fields and maintains flood during the growing season. Near the end of the growing season, no additional water is added and the field is allowed to dry down. Greenhouse gas production is reduced. Water and nutrients are conserved.

Feature Measure: Irrigated Acres Managed

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $690.36

Scenario Cost/Unit: $17.26

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	12	$328.56
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	10	$361.80

Practice: 450 - Anionic Polyacrylamide (PAM) Application

Scenario #1 - PAM Application

Scenario Description:

Control of irrigation induced erosion (typically in furrow irrigated fields) through the direct application of water-soluble Polyacrylamide (PAM) into the irrigation water supply (1 to 3 ounce sprinkled at 3-5 ft furrow inlet or metered at 10 ppm directly into the head ditch). PAM comes in granular, liquid oil emulsion, tablet, and block forms. This typical application is for an 80-acre furrow irrigated row crop field, with one PAM application (1-1.5 lb/ac, creating a 10 ppm concentration of the granular PAM in the head ditch metered via large fish feeder) at first irrigation followed by two additional applications (reduced rates of 0.5-1 lb/ac, or about 1-5 ppm in the inflow water) after cultivations. Resource Concern: Soil erosion. Associated Practices: 443-Irrigation System, Surface and Subsurface, 449-Irrigation Water Management.

Before Situation:

Irrigated lands susceptible to irrigation-induced erosion, excluding peat soils, and where the sodium adsorption ratio (SAR) of irrigation water is less than 15.

After Situation:

Erosion is minimized in furrow irrigated field.

Feature Measure: Weight of PAM Applied

Scenario Unit:: Pound

Scenario Typical Size: 240.0

Scenario Total Cost: $1,096.80

Scenario Cost/Unit: $4.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	12	$228.00
Materials						
Anionic Polyacrylamide (PAM)	1279	Water Soluble PAM, granular bulk, for mixing with irrigation water. Includes materials and shipping only.	Pound	$3.62	240	$868.80

Practice: 450 - Anionic Polyacrylamide (PAM) Application

Scenario #3 - Liquid Emulsion PAM for Surface Irrigation System

Scenario Description:

Polyacrylamide is a synthetic organic polymer derived from petroleum that can be used to reduce water quantity by improved infiltration and control of irrigation induced erosion through the direct application of water-soluble Polyacrylamide (PAM) into the irrigation water supply. PAM comes in granular, liquid oil emulsion, tablet, and block forms. The typical application is for an 120-acre f irrigated crop field. The emulsion form of PAM is generally injected directly into the irrigation water supply through canal or poly tubing at a rate of approximately 2.5 lbs. /ac per application. Subsequent applications are made every thirty days or following soil disturbance.

Before Situation:

Irrigation induced erosion allows for negative impacts on irrigation runoff water quality, water quantity, and soil erosion. Soil erosion, water quality and water quantity resource concerns are associated with this practice.

After Situation:

Water quantity justification derived from practice standard 450, Anionic Polyacrylamide (PAM) Application (September 2014) on fine to medium textured soils, PAM may result in an increase in surface irrigation infiltration of up to 60 % with 15% being typical on medium textured soils. Erosion is minimized in furrow irrigated field. Resource Concern: Soil erosion. water quality, reduced energy, water quantity Associated Practices: 443-Irrigation System, Surface and Subsurface, 449-Irrigation Water Management

Feature Measure: 2.5 lbs per acre

Scenario Unit:: Pound

Scenario Typical Size: 120.0

Scenario Total Cost: $7,635.00

Scenario Cost/Unit: $63.63

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	12	$228.00
Materials						
PAM - Liquid Emulsification, 30% active ingredient	2545	A liquid form of PAM that can be applied through a dispenser or a sprinkler. Includes materials and shipping only.	Gallon	$24.69	300	$7,407.00

Practice: 460 - Land Clearing

Scenario #2 - Heavy Equipment

Scenario Description:

Site preparation of a field with dozer or equivalent heavy equipment to achieve a conservation objective. Typical scenario is approximately 10 acres of trees and shrubs to be cleared. The resource concern is determined by the conservation objective met with the final practice applied to the field.

Before Situation:

Forested field of approximately 10 acres, with moderate density evenly spaced tree canopy.

After Situation:

Crew uses 200 HP dozer to clear trees and prepare field for conservation objective, includes on-site debris disposal as necessary. Associated practices, like plantings, other structures, or irrigation/drainage water management practices, would be contracted separately as needed.

Feature Measure: Area Cleared

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $10,126.01

Scenario Cost/Unit: $1,012.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 200 HP	928	Track mounted Dozer with horsepower range of 160 to 250. Equipment and power unit costs. Labor not included.	Hour	$196.22	40	$7,848.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	40	$760.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	40	$1,027.20
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	1	$490.01

Practice: 460 - Land Clearing

Scenario #3 - Clearing for GSS

Scenario Description:

Site preparation of a gully with track hoe, dozer or equivalent equipment to install a structural conservation practice, typically a 410 grade stabilization structure. Typical scenario is approximately 1 acres of trees and shrubs to be cleared on a high bank adjacent to a water body and/or gully. Woody debris removal often necessary. Does not address excavation required for practice installation. The resource concern is determined by the conservation objective met with the final practice applied to the field.

Before Situation:

Wooded field edge of approximately 1.0 acres, with moderate density evenly spaced tree canopy on a high bank adjacent to a gully or water body. Fallen trees must often be removed.

After Situation:

Crew uses 160 HP dozer or track hoe to clear trees and prepare site for conservation practice installation, includes on-site debris disposal as necessary. Associated practices, like plantings, other structures, or irrigation/drainage water management practices, would be contracted separately as needed.

Feature Measure: Area Cleared

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $2,204.03

Scenario Cost/Unit: $2,204.03

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	$125.35	7	$877.45
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$45.08	4	$180.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	7	$133.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	4	$86.84
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	7	$179.76
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	1	$490.01

Practice: 460 - Land Clearing

Scenario #42 - Non-Heavy Equipment

Scenario Description:

Site preparation of a field with a labor crew, chainsaws, chippers or similar equipment removing trees and shrubs to achieve a conservation objective. Typical scenario is approximately 1 acre of trees and shrubs to be cleared. The resource concern is determined by the conservation objective met with the final practice applied to the field.

Before Situation:

Forested field of approximately 1 acre, with moderate density evenly spaced tree canopy.

After Situation:

Labor crew uses chainsaws, chippers, or similar equipment to clear trees and prepare the field for a conservation objective, includes on-site disposal as necessary. Associated practices, like plantings, other structures, or irrigation/drainage water management practices, would be contracted separately as needed.

Feature Measure: Area Cleared

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $632.71

Scenario Cost/Unit: $632.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	24	$105.84
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	24	$456.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87

Practice: 462 - Precision Land Forming

Scenario #1 - Low Shaping

Scenario Description:

The land surface is shaped or leveled to a specific elevation and grade for various land uses. Cuts and fills are small. The resource concerns are EXCESS / INSUFFICIENT WATER -(Ponding, Flooding) and SOIL EROSION -(Sheet, Rill)

Before Situation:

The field has minor topographic issues or problems with surface drainage or erosion which can be corrected without land leveling or land smoothing. Site conditions require attention to elevation and grade. Typical situation is a 40 acre field. Material to be moved and or placed typically is between 60 - 124 cubic yards per acre.

After Situation:

Land has been shaped to the required elevations and grades. Resource concerns have been treated. Associated practices, like plantings or drainage water management practices, would be contracted separately as needed.

Feature Measure: Volume of Earth Moved

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $8,439.58

Scenario Cost/Unit: $210.99

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tractor, agricultural, 360 HP	1205	Agricultural tractor with horsepower range of 340 to 390. Equipment and power unit costs. Labor not included.	Hour	$158.22	36	$5,695.92
Scraper, pull, 15 CY	1207	Pull type earthmoving scraper with 15 CY capacity. Does not include pulling equipment or labor. Add Tractor or Dozer, 260 HP typically required for single scraper.	Hour	$23.31	36	$839.16
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	36	$924.48
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 468 - Lined Waterway or Outlet

Scenario #3 - Rock Lined - 24 inch

Scenario Description:

Install 300 ' long by 15' wide by 1.5' deep trapezoidal or parabolic shaped waterway lined with riprap (D100 = 18", Velocity ~ 11 ft/sec). 1/2 the channel is excavated, before excavation for riprap. Excess excavation is spoiled in the immediate area. Riprap is installed over 100% of the width of the waterway to prevent scour. Cost include excavation, spoiling of excess material, geotextile underlayment and installing 18" Rock Riprap. Lined waterway width is measured from top of bank to top of bank.

Before Situation:

Excessive sedimentation and soil erosion as a result of ephemeral or classic gully erosion. Velocities are generally too high or saturated soil conditions make it difficult to establish a grassed waterway.

After Situation:

Rock lined waterway is 300 ' long by 15' wide by 1.5' deep. Waterway is excavated and rock is placed using a hydraulic excavator. Geotextile underlayment is installed by laborers. Associated practices are Subsurface Drain (606), Underground Outlet (620), Structure for Water Control (587), and Critical Area Seeding (342).

Feature Measure: Square Foot of Waterway

Scenario Unit:: Square Foot

Scenario Typical Size: 4,500.0

Scenario Total Cost: $36,917.40

Scenario Cost/Unit: $8.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	555	$1,148.85
Foregone Income						
FI, Soybeans Irrigated	1962	Irrigated Soybeans is Primary Crop	Acre	$382.86	0.1	$38.29
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	465	$35,363.25
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 472 - Access Control

Scenario #1 - Cave Gate

Scenario Description:
Installing a barred metal gate to exclude human access to sensitive cave species in a karst area. Access control is needed to treat the wildlife resource concern.

Before Situation:
The cave is currently unprotected from human access, and bats are susceptible to white nose syndrome infection. T&E bat species could easily be impacted by this fungus.

After Situation:
Sensitive cave species are protected from human traffic and fungal infection.

Feature Measure: A 165 sq ft metal gate with bars 5.7

Scenario Unit:: Square Foot

Scenario Typical Size: 165.0

Scenario Total Cost: $13,511.00

Scenario Cost/Unit: $81.88

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	35	$958.30
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Materials						
Bat Gate	1129	Bat Gate Assembly, Includes materials, equipment and labor.	Square Foot	$72.38	165	$11,942.70
Mobilization						
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	$1.02	300	$306.00

Practice: 484 - Mulching

Scenario #1 - Natural Material - Full Coverage

Scenario Description:

Application of straw mulch or other state approved natural material to reduce erosion and facilitate the establishment of vegetative cover. Mulch provides full coverage and is typically used with critical area planting. Assumes 125 bales/acre (3 bales/1000 sq ft)

Before Situation:

Typical scenario ranges from a 0.1 to 1.0 acre disturbed site around a newly constructed structural practice. The potential for soil erosion is high and mulch is needed to stabilize the soil and facilitate the establishment of vegetative cover.

After Situation:

Straw mulch has been applied to areas needing mulch. Erosion and sedimentation is reduced, water and soil quality is protected, and vegetative cover is established.

Feature Measure: Area Covered by Mulch

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $527.26

Scenario Cost/Unit: $527.26

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	0.5	$11.01
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	10	$190.00
Materials						
Straw	1237	Small grain straw (non organic and certified organic). Includes materials only.	Ton	$130.50	2.5	$326.25

Practice: 484 - Mulching

Scenario #2 - Erosion Control Blanket

Scenario Description:

Installation of erosion control blanket on critical areas with steep slopes, grassed waterways or diversions.. Blanket is typically made of coconut coir, wood fiber, straw and is typically covered on both sides with polypropylene netting. Used to help control erosion and establish vegetative cover.

Before Situation:

There are areas of concentrated flow or very steep eroding areas needing a high level of erosion protection. Soil erosion is a concern and there is little to no vegetation.

After Situation:

The erosion control blanket is placed on concentrated flow or steep areas and secured with ground stables. Soil erosion is minimized and vegetative cover is established.

Feature Measure: Area Covered by Mulch

Scenario Unit:: Square Foot

Scenario Typical Size: 5,000.0

Scenario Total Cost: $884.60

Scenario Cost/Unit: $0.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Erosion Control Blanket, biodegradable	1213	Biodegradable erosion control blanket, typically a composite of natural fibers with reinforcing polymer netting. Materials and shipping only.	Square Yard	$1.32	555	$732.60

Practice: 484 - Mulching

Scenario #3 - Synthetic Material

Scenario Description:

Installation of geotextile, biodegradable plastic, polyethylene plastic, or other state approved synthetic mulch to conserve soil moisture, moderate soil temperature, and provide erosion control. Payment based on actual area covered by mulching material.

Before Situation:

Site conditions very. Typically scenarios include annual and perennial specialty crops. Water quantity and soil moisture is a concern.

After Situation:

Synthetic mulch is applied in rows with a mulch layer or by other mechanized means. Soil moisture is conserved and energy use associated with irrigation is decreased.

Feature Measure: Area Covered by Mulch

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $1,866.36

Scenario Cost/Unit: $1,866.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	1.5	$37.56
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00
Materials						
Mulch, polyethylene plastic, 1.0 mil	1303	1.0 mil polyethylene plastic mulch, with anchoring. Includes materials and shipping only.	Square Yard	$0.37	4840	$1,790.80

Practice: 490 - Tree/Shrub Site Preparation

Scenario #1 - Chemical - Ground Application on Open Field

Scenario Description:

This practice involves the use of various herbicides applied using ground-based machinery (farming equipment) in order to remove undesirable vegetation and improve site conditions for establishing trees and/or shrubs. Typical sites include abandoned fields, pastures, rangelands, or agricultural fields. This practice is typically used to address the following resource concerns: degraded plant condition - undesirable plant productivity and health and inadequate structure and composition. Treatment can be done before or after planting.

Before Situation:

Undesirable vegetation is present on the site including herbaceous plants and woody vegetation. Noxious and invasive species may also be present on the site. If left uncontrolled, undesirable vegetation will inhibit successful establishment of target species of trees and/or shrubs.

After Situation:

Undesirable vegetation has been treated using appropriate herbicides, reducing competition for target trees and/or shrubs. Site conditions are favorable for successful establishment of trees and/or shrubs.

Feature Measure: Area of Treatment

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $1,908.89

Scenario Cost/Unit: $47.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$9.96	40	$398.40
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	40	$52.40
Herbicide, Sulfometuron methyl & Hexazinone	1282	Broad spectrum herbicide for residual weed control for christmas trees and other trees. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$22.80	40	$912.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 490 - Tree/Shrub Site Preparation

Scenario #2 - Chemical - Ground Band Spray

Scenario Description:

This practice involves the use of various herbicides applied using ground-based machinery (farming equipment & ATV's) in order to remove undesirable vegetation and improve site conditions for establishing trees and/or shrubs by spraying strips and not the whole tract. (Whole field is counted, but approximately one third of the field is treated). Typical sites include abandoned fields, pastures, rangelands, or agricultural fields. This practice is typically used to address the following resource concerns: degraded plant condition - undesirable plant productivity and health and inadequate structure and composition. Treatment can be done before or after planting.

Before Situation:

Undesirable vegetation is present on the site including herbaceous plants and woody vegetation. Noxious and invasive species may also be present on the site. If left uncontrolled, undesirable vegetation will inhibit successful establishment of target species of trees and/or shrubs.

After Situation:

Undesirable vegetation has been treated using appropriate herbicides, reducing competition for target trees and/or shrubs in strips (usually 2 ft on each side of planted row). Site conditions are favorable for successful establishment of trees and/or shrubs.

Feature Measure: Area of Treatment

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $1,699.66

Scenario Cost/Unit: $42.49

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	8	$228.64
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	13	$491.79
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	13	$348.14
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	13	$17.03
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: 490 - Tree/Shrub Site Preparation

Scenario #4 - Chemical - Aerial Application

Scenario Description:

This practice involves the use of herbicides applied by helicopter in order to remove undesirable vegetation and improve site conditions for establishing trees and/or shrubs. This typical scenario includes open land such as abandoned fields, pastures or forestlands that were recently harvested. This practice is typically used to address the following resource concerns: degraded plant condition - undesirable plant productivity and health and inadequate structure and composition. Treatment can be done before or after planting.

Before Situation:

Undesirable vegetation is present on the site including herbaceous plants and woody competition. Noxious and invasive species may also be present on the site. If left uncontrolled, undesirable vegetation will inhibit successful establishment of target species of trees and/or shrubs.

After Situation:

Undesirable vegetation has been treated using appropriate herbicides, reducing competition for target trees and/or shrubs. Site conditions are favorable for successful establishment of trees and/or shrubs.

Feature Measure: Area of Treatment

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $3,921.04

Scenario Cost/Unit: $98.03

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, aerial application, helicopter	1991	Chemical application performed by helicopter on forest only. Includes equipment, mobilization, and labor.	Acre	$32.78	40	$1,311.20
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	40	$754.80
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	40	$1,513.20
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	40	$52.40

Practice: 490 - Tree/Shrub Site Preparation

Scenario #6 - Mechanical - Heavy, shearing and windrowing

Scenario Description:

This practice involves the use of heavy machinery (usually bull dozers & not typical farming equipment) to treat an area in order to improve site conditions for establishing trees and/or shrubs. Usually vegetation and/or debris is sheared and raked or pushed to form piles or windrows. Typical sites include trees and brush cover that is not appropriate to the site or does not provide the desired condition for the landowner. This practice is typically used to address the following resource concerns: degraded plant condition - undesirable plant productivity and health and inadequate structure and composition and soil quality degradation - soil erosion - sheet and rill. Treatment must be done before planting.

Before Situation:

The site is dominated by undesirable vegetation including herbaceous plants and significant amounts of woody vegetation (trees and brush) occupying the site. There is also a significant component of woody debris on site. Noxious and invasive species may also be present on the site. Adequate planter access is impossible with existing conditions. If left untreated, seedlings can not be planted properly at the proper density. Existing competition will cause poor survival or reduced growth of trees/shrubs to be established on the site.

After Situation:

Undesirable vegetation has been removed using mechanical methods reducing competition for target trees and/or shrubs. Woody debris has been removed to facilitate tree/shrub planting operations. Site conditions are favorable for successful establishment of trees and/or shrubs.

Feature Measure: Area of Treatment

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $18,288.82

Scenario Cost/Unit: $457.22

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Heavy mechanical site prep, shearing, V-blade, K-G blading	1314	Mechanical operations that shear trees and vegetation. Requires heavy equipment such as dozers, Includes equipment, power unit and labor costs.	Acre	$222.29	40	$8,891.60
Heavy mechanical site prep, raking	1317	Mechanical operations that pushing and raking trees and vegetation. Requires heavy equipment such as dozers. Includes equipment, power unit and labor costs.	Acre	$192.34	40	$7,693.60
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	20	$723.60
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 490 - Tree/Shrub Site Preparation

Scenario #7 - Mechanical-Ripping/chopping

Scenario Description:

This practice involves the use of heavy machinery (usually bull dozers & not typical farming equipment) to rip/cut/lift underground root systems to improve site conditions for establishing trees and/or shrubs. Typical sites include trees and brush cover that is not appropriate to the site or does not provide the desired condition for the landowner. This practice is typically used to address the following resource concerns: degraded plant condition - undesirable plant productivity and health and inadequate structure and composition and soil quality degradation - soil erosion - sheet and rill. Treatment must be done before planting.

Before Situation:

Undesirable vegetation is present on the site including herbaceous plants and sparse woody competition. Noxious and invasive species may also be present on the site. If left uncontrolled, undesirable vegetation will inhibit successful establishment of target species of trees and/or shrubs. Soils are compacted as a result of harvesting heavy equipment activities or other land uses.

After Situation:

Undesirable vegetation has been knocked down with heavy tillage equipment used to breakup and lift root systems, breakup compaction (<18" deep), thus enhancing the conditions for planting and survival of trees and/or shrubs. Soil compaction has been alleviated, allowing penetration of moisture and allowing roots to grow properly. Site conditions are favorable for successful establishment of trees and/or shrubs.

Feature Measure: Area of Treatment

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $7,233.85

Scenario Cost/Unit: $180.85

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Heavy mechanical site prep, drum chopping	1316	Mechanical operations that pushing trees and vegetation and crushing them with a water filled roller chopper. Requires heavy equipment such as dozers. Includes equipment, power unit and labor costs.	Acre	$161.36	40	$6,454.40
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	1	$490.01

Practice: 490 - Tree/Shrub Site Preparation

Scenario #9 - Mechanical - Light, Mow/Disk

Scenario Description:

This practice involves the use of light/moderate machinery(typically tractors used in normal farming operations) to clear above ground vegetation (disk or bush hog) in order to improve site conditions for establishing trees and/or shrubs. Typical sites include abandoned fields, pastures, rangelands, or agricultural fields. This following resource concerns: soil quality degradation - compaction, soil erosion - sheet and rill, and degraded plant condition - undesirable plant productivity and health and inadequate structure and composition. Treatment can be done before or after planting.

Before Situation:

Undesirable vegetation is present on the site including herbaceous plants and sparse woody competition. Noxious and invasive species may also be present on the site. If left uncontrolled, undesirable vegetation will inhibit successful establishment of target species of trees and/or shrubs.

After Situation:

Undesirable vegetation has been removed using a bush hog and/or disk to cut and/or knock down existing vegetation, thus enhancing the conditions for planting and survival of trees and/or shrubs. Site conditions are favorable for successful establishment of trees and/or shrubs.

Feature Measure: Area of Treatment

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $1,740.05

Scenario Cost/Unit: $43.50

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	20	$1,049.20
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	20	$434.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 511 - Forage Harvest Management

Scenario #1 - Perennial Crops - Delayed Mowing

Scenario Description:

In perennial forage crops, the delaying the harvest of the first cutting to promote the reproduction of ground nesting birds. Delaying the harvest of the first cutting will benefit ground nesting birds; research at the University of Vermont showed that breeding success for declining grassland songbirds went from 0 on a regularly harvested hay field to 2.8 fledglings per female per year when the first harvest on a hayfield was delayed until August 1st. Eastern Meadowlarks, and Savannah Sparrows require a nesting period to fledge young that lasts through the end of July in most parts of the eastern US. The delayed harvest results in a decrease in overall forage quality. Farmers could see as much as a 50% reduction in market value due to declines in protein (~50%) and digestibility (~20%), making the forage crop less palatable and lower in relative feed value. The selected fields should be large enough to promote ground nesting birds. After young have fledged the field will be harvested for dry forages.

Before Situation:

Perennial forage crops are produced and harvested; ground nesting birds are disturbed and/or fledgling birds are killed in the process.

After Situation:

Annual crops are harvested with a delayed mowing; forage quality is compromised, however, the survival of ground nesting birds is promoted.

Feature Measure: Increased grassland bird populatio

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: $625.31

Scenario Cost/Unit: $20.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	30	$507.90
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	1	$27.38
Materials						
Test, Plant Tissue Test	301	Tissue analysis for crops. Includes materials and shipping only.	Each	$25.03	1	$25.03

USDA - Natural Resources Conservation Service

Mississippi

Practice: 512 - Forage and Biomass Planting

Scenario #1 - Native Perennial Grass (1 species)

Scenario Description:

Establish or reseed adapted perennial native grasses to improve or maintain livestock/wildlife nutrition and health, extend the length of the grazing season, and provide soil cover to reduce erosion. Used for either conventional or no-till seeding of native grasses for pasture, hayland, and wildlife openings. This practice may be utilized for organic or regular production. This scenario assumes fertilizer, seed, equipment and labor for seed bed prep, tillage, seeding ,and spreading.

Before Situation:

Poorly managed/degraded pasture land or cropland being converted to pasture and/or hay.

After Situation:

Suitable species are established to improve forage quality and quantity and reduce soil erosion on cropland ,hayland, pasture, and/or biomass production.

Feature Measure: Acres of Forage and Biomass Planti

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: $8,186.46

Scenario Cost/Unit: $272.88

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	30	$186.00
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	30	$200.70
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$10.75	30	$322.50
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	30	$647.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	1500	$720.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.36	1500	$540.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	$32.76	60	$1,965.60
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	1	$10.21
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	30	$566.10
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	30	$566.10
One Species, Warm Season, Native Perennial Grass	2322	Native, warm season perennial grass. Includes material and shipping only.	Acre	$68.44	30	$2,053.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 512 - Forage and Biomass Planting

Scenario #3 - Native Perennial 2 or more species

Scenario Description:

Establish or reseed with 2 or more adapted perennial native warm season grasses to improve or maintain livestock/wildlife nutrition and health, extend the length of the grazing season, and provide soil cover to reduce erosion. Used for either conventional or no-till seeding of perennial native warm season grasses for pasture, hayland, and wildlife openings. This practice may be utilized for organic or regular production. This scenario assumes fertilizer, seed, equipment and labor for seed bed prep, tillage, seeding ,and spreading.

Before Situation:

Existing stand of perennial grasses or monoculture or no grasses present. Resource concerns may include undesirable plant productivity and health, inadequate feed and forage for livestock, soil erosion and soil quality.

After Situation:

Suitable NWSG species are established to improve forage quality and quantity and reduce soil erosion on cropland, hayland, pasture and/or biomass production.

Feature Measure: Acres of Forage and Biomass Planti

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: $12,666.96

Scenario Cost/Unit: $422.23

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	30	$337.80
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	30	$186.00
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$10.75	30	$322.50
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	30	$647.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	1500	$720.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.36	1500	$540.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	$32.76	60	$1,965.60
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	1	$10.21
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	30	$566.10
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	30	$566.10
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	$213.22	30	$6,396.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 512 - Forage and Biomass Planting

Scenario #4 - Native Perennial 2 or more species with Low Input

Scenario Description:

Establish or reseed with two or more adapted perennial native warm season grasses to improve or maintain livestock/wildlife nutrition and health, extend the length of the grazing season, and provide soil cover to reduce erosion. Used for either conventional or no-till seeding of perennial native warm season grasses for pasture, hayland, and wildlife openings. This practice may be utilized for organic or regular production. This scenario assumes fertility and pH are not needed. Seed, equipment and labor for seed bed prep, tillage, seeding ,and spreading are included.

Before Situation:

Existing stand of perennial grasses or monoculture or no grasses present. Resource concerns may include undesirable plant productivity and health, inadequate feed and forage for livestock, soil erosion and soil quality.

After Situation:

Suitable NWSG species are established to improve forage quality and quantity and reduce soil erosion on cropland, hayland, pasture and/or biomass production.

Feature Measure: Acres of Forage and Biomass Planti

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: $8,552.76

Scenario Cost/Unit: $285.09

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	30	$337.80
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	30	$186.00
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	30	$647.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	1	$10.21
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	30	$566.10
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	$213.22	30	$6,396.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 512 - Forage and Biomass Planting

Scenario #5 - Introduced Cool Season Grasses

Scenario Description:

Establish or reseed adapted perennial introduced cool season grasses and legumes to improve or maintain livestock/wildlife nutrition and health, extend the length of the grazing season, and provide soil cover to reduce erosion. Used for either conventional or no-till seeding of perennial introduced cool season grasses for pasture, hayland, and wildlife openings. This practice may be utilized for organic or regular production. This scenario assumes fertilizer, seed, equipment and labor for seed bed prep, tillage, seeding ,and spreading.

Before Situation:

Poor or nonexistent stand of grass species. Resource concerns may include undesirable plant productivity and health, inadequate feed and forage for livestock, soil erosion and soil quality.

After Situation:

Suitable species are established to improve forage quality and quantity and reduce soil erosion on cropland ,hayland, pasture, and/or biomass production.

Feature Measure: Acres of Forage and Biomass Planti

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: $6,886.26

Scenario Cost/Unit: $229.54

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	30	$337.80
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	30	$186.00
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	30	$200.70
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	30	$647.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Nitrogen (N), Ammonium Nitrate	69	Price per pound of N supplied by Ammonium Nitrate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.57	1200	$684.00
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	1500	$720.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.36	1500	$540.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	$32.76	60	$1,965.60
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	1	$10.21
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	30	$566.10
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2319	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	$20.66	30	$619.80
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 512 - Forage and Biomass Planting

Scenario #7 - Introduced Warm Season Grasses

Scenario Description:

Establish or reseed adapted introduced warm season grasses to improve or maintain livestock/wildlife nutrition and health, extend the length of the grazing season, and provide soil cover to reduce erosion. Used for either conventional or no-till seeding of perennial introduced warm season grasses for pasture, hayland, and wildlife openings. This practice may be utilized for organic or regular production. This scenario assumes fertilizer, seed, equipment and labor for seed bed prep, tillage, seeding ,and spreading.

Before Situation:

Existing stand of perennial grasses or monoculture or no grasses present. Resource concerns may include undesirable plant productivity and health, inadequate feed and forage for livestock, soil erosion and soil quality.

After Situation:

Suitable species are established to improve forage quality and quantity and reduce soil erosion on cropland ,hayland, pasture, and/or biomass production.

Feature Measure: Acres of Forage and Biomass Planti

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: $8,121.66

Scenario Cost/Unit: $270.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	30	$337.80
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	30	$186.00
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	30	$200.70
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	30	$647.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Nitrogen (N), Ammonium Nitrate	69	Price per pound of N supplied by Ammonium Nitrate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.57	1200	$684.00
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	1500	$720.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.36	1500	$540.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	$32.76	60	$1,965.60
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	1	$10.21
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	30	$566.10
One Species, Warm Season, Introduced Perennial Grass (seed or sprigs)	2323	Introduced, warm season perennial grass seed or sprig. Includes material and shipping only.	Acre	$61.84	30	$1,855.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 512 - Forage and Biomass Planting

Scenario #8 - Introduced Warm Season Grasses with Low Input

Scenario Description:

Establish or reseed adapted introduced warm season grasses to improve or maintain livestock/wildlife nutrition and health, extend the length of the grazing season, and provide soil cover to reduce erosion. Used for either conventional or no-till seeding of perennial introduced warm season grasses for pasture, hayland, and wildlife openings. This practice may be utilized for organic or regular production. This scenario assumes fertility and pH are not needed. Seed, equipment and labor for seed bed prep, tillage, seeding ,and spreading are included.

Before Situation:

Existing stand of perennial grasses or monoculture or no grasses present. Resource concerns may include undesirable plant productivity and health, inadequate feed and forage for livestock, soil erosion and soil quality.

After Situation:

Suitable species are established to improve forage quality and quantity and reduce soil erosion on cropland ,hayland, pasture, and/or biomass production.

Feature Measure: Acres of Forage and Biomass Planti

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: $4,011.36

Scenario Cost/Unit: $133.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	30	$337.80
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	30	$186.00
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	30	$647.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	1	$10.21
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	30	$566.10
One Species, Warm Season, Introduced Perennial Grass (seed or sprigs)	2323	Introduced, warm season perennial grass seed or sprig. Includes material and shipping only.	Acre	$61.84	30	$1,855.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 512 - Forage and Biomass Planting

Scenario #9 - Sprigging

Scenario Description:

Sprigging new grasses with sprigging application for the purpose of providing forage, increasing plant diversity, soil quality and fertility, and plant health. This practice may be utilized for organic or regular production. This scenario assumes fertilizer, sprigs, equipment and labor for seed bed prep, tillage, sprigging ,and spreading.

Before Situation:

Poor or nonexistent stand of grass species. Resource concerns may include undesirable plant productivity and health, inadequate feed and forage for livestock, soil erosion and soil quality.

After Situation:

Suitable species are established to improve forage quality and quantity and reduce soil erosion on cropland ,hayland, pasture, and/or biomass production.

Feature Measure: Acres of Forage and Biomass Planti

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: $9,700.86

Scenario Cost/Unit: $323.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	30	$337.80
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	30	$186.00
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	30	$200.70
Ground sprigging	1101	Includes costs for equipment, power unit and labor.	Acre	$74.22	30	$2,226.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Nitrogen (N), Ammonium Nitrate	69	Price per pound of N supplied by Ammonium Nitrate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.57	1200	$684.00
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	1500	$720.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.36	1500	$540.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	$32.76	60	$1,965.60
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	1	$10.21
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	30	$566.10
One Species, Warm Season, Introduced Perennial Grass (seed or sprigs)	2323	Introduced, warm season perennial grass seed or sprig. Includes material and shipping only.	Acre	$61.84	30	$1,855.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 512 - Forage and Biomass Planting

Scenario #10 - Overseeding Legumes with low input

Scenario Description:

Establishment of legumes for the purpose of increasing plant diversity, soil quality and fertility, and plant health and enhancing the quality of forage. This practice may be utilized for organic or regular production. This scenario assumes fertilizer, seed, equipment and labor for seed bed prep, tillage, seeding ,and spreading.

Before Situation:

Existing stand of perennial grasses or monoculture with no legumes present .

After Situation:

Legumes will be maintained through proper grazing management and improve plant diversity and soil quality.

Feature Measure: Acres of Forage and Biomass Planti

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: $3,050.76

Scenario Cost/Unit: $101.69

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	30	$337.80
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	30	$186.00
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	30	$200.70
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	30	$647.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	1500	$720.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.36	1500	$540.00
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	1	$10.21
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

USDA - Natural Resources Conservation Service

Mississippi

Practice: 512 - Forage and Biomass Planting

Scenario #43 - Overseeding Legumes

Scenario Description:

Establishment of legumes for the purpose of increasing plant diversity, soil quality and fertility, and plant health and enhancing the quality of forage. This practice may be utilized for organic or regular production. This scenario assumes fertilizer, seed, equipment and labor for seed bed prep, tillage, seeding ,and spreading.

Before Situation:

Existing stand of perennial grasses or monoculture with no legumes present .

After Situation:

Legumes will be maintained through proper grazing management and improve plant diversity and soil quality.

Feature Measure: Acres of Forage and Biomass Planti

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: $5,016.36

Scenario Cost/Unit: $167.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	30	$337.80
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	30	$186.00
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	30	$200.70
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	30	$647.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.48	1500	$720.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.36	1500	$540.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	$32.76	60	$1,965.60
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	1	$10.21
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 516 - Livestock Pipeline

Scenario #1 - PVC IPS Less than 1.5 inches

Scenario Description:

Description: Below ground installation of PVC (Iron Pipe Size) pipeline. PVC (IPS) is manufactured in sizes (nominal diameter) from ½-inch to 36-inch; typical practice sizes range from 1-inch to 4-inch; and typical scenario size is 1-inch. Construct 1,320 feet of 1-inch, Schedule 40, PVC Pipeline with appurtenances, installed below ground with a minimum 1.5 feet of ground cover. The scenario unit is weight of pipe material in pounds. 1,320 feet of 1-inch, Schedule 40, PVC pipe weighs 0.240 lb/ft, or a total of 317 pounds. Appurtenances include: couplings, fittings, thrust blocks, gate valves (2), air release valves (2), drain valve (1), and pressure relief valve (1), and are included in the cost of pipe material (additional 10% of pipe material quantity). Revegetation is not included. Resource Concerns: Inadequate Livestock Water, Inefficient Energy Use. Associated Practices: Critical Area Planting (342), Pumping Plant (533), Watering Facility (614), and Water Harvesting Catchment (636).

Before Situation:

Water supplies need to be conveyed through pipelines for use by livestock or wildlife.

After Situation:

Pipeline(s) convey and/or distribute water to storage and/or watering facilities, for use by livestock or wildlife.

Feature Measure: Length of Pipe

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: $2,947.50

Scenario Cost/Unit: $2.23

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	$1.21	1320	$1,597.20
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	12	$228.00
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	$1.75	348	$609.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 528 - Prescribed Grazing

Scenario #5 - PCS Moderate Mgmt (Year 1)

Scenario Description:

A baseline pasture condition assessment will be completed by the participant with the assistance of a conservationist using the pasture condition score card. A grazing mgmt plan will be implemented. Participant will monitor the health of the pastures by conducting at least quarterly pasture condition assessment (transects). Participant will record the number of days grazed and rested, stubble heights of forage before and after grazing, number & size of grazing animals, nutrients/herbicides applied. Participant has 3 years to bring score from 26-35 to 36-45. Year 1

Before Situation:

Pasture is not deferred/rested from grazing. Spot grazing is 10-30%. Desirable species 40-60% of the stand. 25-50% of the stand meets the minimum residual grazing height of the desirable species. Yields may be below site potential. Moderate compaction evident throughout. Some service ponding. Pasture contains two to four species, two functional groups and one legume.

After Situation:

A prescribed grazing schedule, contingency plan that details potential climatic problems and monitoring plan is being followed. Removal of herbage by the grazing animals is in accordance with production limitations, plant sensitivities and management goals. Frequency of defoliations and season of grazing is based on the rate of growth and physiological condition of the plants.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $2,033.72

Scenario Cost/Unit: $50.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Rangeland/grassland field monitoring kit	967	Miscellaneous tools needed to complete rangeland/grassland monitoring. Materials may include camera, clippers, plot frame, scale, tape measure, etc. Includes materials and shipping only.	Each	$51.08	1	$51.08
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	28	$766.64
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	64	$1,216.00

Practice: 528 - Prescribed Grazing

Scenario #9 - Pasture Deferment - Long Term

Scenario Description:

Defer the pasture for 210 days and up to a growing season to provide rest to specific plants such as native grasses. The rest is needed to provide long-term rest to specific plants that would typically decline in plant health, vigor, and availability due to overgrazing. The importance of long-term deferment is critical to the long term success of the plants and meeting the desired life span.

Before Situation:

The producer will typically graze the plants before they have sufficient time to become established. Therefore, any plants that emerges will be susceptible to early grazing pressure and possibly overgrazing. Existing herbaceous vegetation will compete against the desired plants and become dominant. The lack of cover reduces the wildlife habitat. No monitoring or record keeping is currently being completed. Plants not adapted or suited, inadequate wildlife cover, soil erosion, and inadequate plant productivity and vigor are common resource concerns.

After Situation:

Scenario describes activities completed to restrict grazing for a defined period during the normal grazing period to provide rest to targeted plants. Activities include moving livestock to alternate locations, sampling and analyzing pasture condition, recordkeeping. Forgone Income used represents the acreage of usable forage not utilized during the deferment period as a proportion of the grazing season. Typical size of 120 acre pasture operation with 30 animal units where 50% of the acreage (or 60 acres) is deferred from grazing for 210 days. Costs and activities are typical for conventional and organic producers. Associated Practices: (511) Forage Harvest Management, (512) Forage and Biomass Planting, (590) Nutrient Management, (595) Integrated Pest Management, (561) Heavy Use Area Protection, (382) Fence, (614) Watering Facility, (378) Pond, (642) Water Well, (314) Brush Management, (315) Herbaceous Weed Control, (338) Prescribed Burning.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 60.0

Scenario Total Cost: $4,666.62

Scenario Cost/Unit: $77.78

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	8	$176.16
Trucking, moving livestock to new paddock	961	Livestock transportation costs to implement a grazing rotation using a gooseneck trailer 6'8" x 24'. Includes equipment, power unit and labor costs.	Mile	$2.84	50	$142.00
Rangeland/grassland field monitoring kit	967	Miscellaneous tools needed to complete rangeland/grassland monitoring. Materials may include camera, clippers, plot frame, scale, tape measure, etc. Includes materials and shipping only.	Each	$51.08	1	$51.08
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	210	$3,555.30
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00

Practice: 533 - Pumping Plant

Scenario #1 - Electric-Powered Pump Less than or Equal to 5 HP , no pressure tank

Scenario Description:

A 2.5 hp submersible electric-powered pump is installed in a well or structure; or a close-coupled 2.5 hp electric-powered centrifugal pump is mounted on a platform. It is used for watering livestock as part of a prescribed grazing system; or for pressurizing a small irrigation system; or for transferring liquid waste in a waste transfer system. Resource Concerns: Livestock Production Limitation - Inadequate livestock water; Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 449 - Irrigation Water Management; 516 - Livestock Pipeline; 313 - Waste Storage Facility; 634 - Waste Transfer; and 614 - Watering Facility.

Before Situation:

Livestock: The present gravity flow system is inadequate to provide the proper flow rate for a prescribed grazing system. Irrigation: Available water is at an insufficient pressure to allow for even distribution of water. Waste Transfer: Contaminated water needs to be moved to a containment facility.

After Situation:

Livestock: Water is transferred at a sufficient rate and pressure to meet the requirements of a prescribed grazing system. Irrigation: A properly designed pump is installed to improve irrigation efficiency and reduce energy usage. Waste Transfer: Liquid wastes that have been collected through a waste transfer system are now efficiently transferred to an appropriate treatment or storage facility.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 2.0

Scenario Total Cost: $2,423.43

Scenario Cost/Unit: $1,211.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	1	$235.09
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	1	$22.02
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	6	$114.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	6	$217.08
Materials						
Pump, <= 5 HP, pump and motor, fixed cost portion	1009	Fixed cost portion of a pump less than or equal to 5 HP pump and motor. This portion is a base cost and is not dependant on horsepower. The total cost of any pump will include this fixed cost plus a variable cost portion. The completed pump and motor will include the motor and controls. Includes Includes material and shipping only.	Each	$564.23	2.5	$1,410.58
Pump, <= 5 HP, pump and motor, variable cost portion	1010	Variable cost portion of a pump less than or equal to 5 HP pump and motor. This portion IS dependent on the total horsepower for the pump. The total cost of any pump will include this variable cost plus the fixed cost portion. The completed pump and motor will include the motor and controls. Includes material and shipping only.	Horsepower	$424.66	1	$424.66

Practice: 533 - Pumping Plant

Scenario #2 - Electric-Powered Pump Less than or Equal to 5 HP, with pressure tank

Scenario Description:

A 1 hp submersible electric-powered pump is installed in a well or structure; or a close-coupled 1 hp electric-powered centrifugal pump is mounted on a platform. It is used for watering livestock as part of a prescribed grazing system; or for pressurizing a small irrigation system. Resource Concerns: Livestock Production Limitation - Inadequate livestock water; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 449 - Irrigation Water Management; 516 - Livestock Pipeline.

Before Situation:

Livestock: The present gravity flow system is inadequate to provide the proper flow rate for a prescribed grazing system. Irrigation: Available water is at an insufficient pressure to allow for even distribution of water.

After Situation:

Livestock: Water is transferred at a sufficient rate and pressure to meet the requirements of a prescribed grazing system. Irrigation: A properly designed pump is installed to improve irrigation efficiency and reduce energy usage.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 1.0

Scenario Total Cost: $1,898.54

Scenario Cost/Unit: $1,898.54

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	0.25	$58.77
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	6	$114.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	6	$217.08
Materials						
Pump, <= 5 HP, pump and motor, fixed cost portion	1009	Fixed cost portion of a pump less than or equal to 5 HP pump and motor. This portion is a base cost and is not dependant on horsepower. The total cost of any pump will include this fixed cost plus a variable cost portion. The completed pump and motor will include the motor and controls. Includes Includes material and shipping only.	Each	$564.23	1	$564.23
Pump, <= 5 HP, pump and motor, variable cost portion	1010	Variable cost portion of a pump less than or equal to 5 HP pump and motor. This portion IS dependent on the total horsepower for the pump. The total cost of any pump will include this variable cost plus the fixed cost portion. The completed pump and motor will include the motor and controls. Includes material and shipping only.	Horsepower	$424.66	1	$424.66
Pressure Tank, 40 gallon	1038	Pressure Tank, 40 gallon. Includes materials and shipping only.	Each	$475.76	1	$475.76

Practice: 533 - Pumping Plant

Scenario #3 - Electric-Powered Pump >5 HP<=30 hp, with L-pipe

Scenario Description:

This is a close-coupled, 3-phase, 20 hp electric-powered mixed-flow pump mounted in a steel L-pipe for large microirrigation (1,000 gpm and 30 psi) system or a large-sized surface irrigation system (1,200 gpm) or a medium-sized (1,000 gpm and 25 psi) waste transfer system. . The pump lifts water out of a stream, bayou, or tailwater pit through a discharge pipe into an irrigation reservoir directly or irrigation pipeline with either a dog-leg or closed stand pipe connection. Resource Concerns: Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 449 - Irrigation Water Management; 313 - Waste Storage Facility; and 634 - Waste Transfer.

Before Situation:

Irrigation: An existing irrigation system employs an inefficient, improperly sized pump that prevents efficient water application resulting in water loss and high energy use or is currently using ground water wells as irrigation supply.

After Situation:

Irrigation: A properly designed and efficient pumping plant is installed, reducing energy use and improving irrigation efficiency.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 20.0

Scenario Total Cost: $17,634.68

Scenario Cost/Unit: $881.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	2	$470.18
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	8	$919.68
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	56	$1,233.12
Portable Welder	1407	Portable field welder. Equipment only. Labor not included.	Hour	$20.63	16	$330.08
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	8	$219.04
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	56	$1,064.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	8	$205.44
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	56	$2,026.08
Materials						
Pump, > 5 HP to 30 HP, pump and motor, fixed cost portion	1011	Fixed cost portion of a pump between 5 and 30 HP, including the pump and motor. This portion is a base cost for the pump and is not dependant on horsepower. The total cost will include this fixed cost plus a variable cost portion. Includes material and shipping only.	Each	$2,020.31	1	$2,020.31
Pump, > 5 HP to 30 HP, pump and motor, variable cost portion	1012	Variable cost portion of a pump between 5 and 30 HP, including the pump and motor. This portion is dependent on the total horsepower for the pump. The total cost will include this variable cost plus a fixed cost portion. Includes material and shipping only.	Horsepower	$128.60	20	$2,572.00
Pipe, Steel, 12", Std Wt, USED	1356	Materials: - USED - 12" - Steel Std Wt	Foot	$21.50	20	$430.00
Pipe, Steel, 20", Std Wt, USED	1359	Materials: - USED - 20" - Steel Std Wt	Foot	$40.30	40	$1,612.00
Pipe, Steel, 24", Std Wt, USED	1360	Materials: - USED - 24" - Steel Std Wt	Foot	$48.46	14	$678.44
Swing Check Valve, metal, 12"	2082	12" swing check valve for back flow prevention, ductile iron metal body with flange mount and lever shaft. Materials only.	Each	$3,597.66	1	$3,597.66
Mobilization						

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 533 - Pumping Plant

Scenario #4 - Electric-Powered Pump >30 hp <=75, with L-pipe

Scenario Description:

This is a close-coupled, 3-phase, 50 hp electric-powered mixed-flow pump mounted in a steel L-pipe for large microirrigation (2,000 gpm and 30 psi) system or a very large-sized surface irrigation system (3,000 gpm) or a large-sized (2,000 gpm and 25 psi) waste transfer system. The pump lifts water out of a stream, bayou, or tailwater pit through a discharge pipe into an irrigation reservoir directly or irrigation pipeline with either a dog-leg or closed stand pipe connection. This is a close-coupled, 3-phase, 50 hp electric-powered centrifugal pump mounted on a platform for pressurizing a large-sized 1,000 gpm and 50 psi) sprinkler or very large microirrigation (2,000 gpm and 30 psi) system or a very large-sized surface irrigation system (3,000 gpm) or a large-sized (2,000 gpm and 25 psi) waste transfer system. Resource Concerns: Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 449 - Irrigation Water Management; 313 - Waste Storage Facility; and 634 - Waste Transfer.

Before Situation:

Irrigation: An existing irrigation system employs an inefficient, improperly sized pump that prevents efficient water application resulting in water loss and high energy use or is currently using ground water wells as irrigation supply.

After Situation:

A properly designed and efficient pumping plant is installed, reducing energy use and improving irrigation efficiency

Feature Measure: Pump Power Requirement

Scenario Unit:: Horsepower

Scenario Typical Size: 50.0

Scenario Total Cost: $30,056.18

Scenario Cost/Unit: $601.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	2	$470.18
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	16	$1,839.36
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	56	$1,233.12
Portable Welder	1407	Portable field welder. Equipment only. Labor not included.	Hour	$20.63	16	$330.08
Crane, truck mounted, hydraulic, 12 ton	1734	12 ton capacity truck mounted hydraulic crane. Equipment cost only.	Hour	$92.50	16	$1,480.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	56	$1,533.28
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	24	$616.32
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	56	$2,026.08
Materials						
Pump, > 30 HP, pump and motor, fixed cost portion	1013	Fixed cost portion of a pump greater than 30 HP, including the pump and motor. This portion is a base cost for the pump and is not dependant on horsepower. The total cost will include this fixed cost plus a variable cost portion. Includes material and shipping only.	Each	$4,779.04	1	$4,779.04
Pump, >30 HP, Pump and motor, variable cost portion	1014	Variable cost portion of a pump greater than 30 HP, including the pump and motor. This portion is dependent on the total horsepower for the pump. The total cost will include this variable cost plus a fixed cost portion. IIncludes material and shipping only.	Horsepower	$98.11	50	$4,905.50
Pipe, Steel, 16", Std Wt, USED	1357	Materials: - USED - 16" - Steel Std Wt	Foot	$28.35	20	$567.00
Pipe, Steel, 24", Std Wt, USED	1360	Materials: - USED - 24" - Steel Std Wt	Foot	$48.46	40	$1,938.40
Pipe, Steel, 30", Std Wt, USED	1361	Materials: - USED - 30" - Steel Std Wt	Foot	$76.17	14	$1,066.38

Swing Check Valve, metal, 16"	2084	16" swing check valve for back flow prevention, ductile iron metal body with flange mount and lever shaft. Materials only.	Each	$6,710.79	1	$6,710.79
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 533 - Pumping Plant

Scenario #5 - Electric-Powered Pump >75 HP, with L-Pipe

Scenario Description:

This is a close-coupled, 3-phase, 100 hp electric-powered mixed-flow pump mounted in a steel L-pipe for a very large-sized surface irrigation system (5,000 gpm) . The pump lifts water out of a stream, bayou, or tailwater pit through a discharge pipe into an irrigation reservoir directly or irrigation pipeline with either a dog-leg or closed stand pipe connection. Resource Concerns: Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 449 - Irrigation Water Management; 313 - Waste Storage Facility; and 634 - Waste Transfer.

Before Situation:

Irrigation: An existing irrigation system employs an inefficient, improperly sized pump that prevents efficient water application resulting in water loss and high energy use or is currently using ground water wells as irrigation supply.

After Situation:

Irrigation: A properly designed and efficient pumping plant is installed, reducing energy use and improving irrigation efficiency.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 100.0

Scenario Total Cost: $43,919.92

Scenario Cost/Unit: $439.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	4	$940.36
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	8	$919.68
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	56	$1,233.12
Portable Welder	1407	Portable field welder. Equipment only. Labor not included.	Hour	$20.63	16	$330.08
Crane, truck mounted, hydraulic, 12 ton	1734	12 ton capacity truck mounted hydraulic crane. Equipment cost only.	Hour	$92.50	16	$1,480.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	12	$328.56
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	56	$1,064.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	12	$308.16
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	56	$2,026.08
Materials						
Pump, > 30 HP, pump and motor, fixed cost portion	1013	Fixed cost portion of a pump greater than 30 HP, including the pump and motor. This portion is a base cost for the pump and is not dependant on horsepower. The total cost will include this fixed cost plus a variable cost portion. Includes material and shipping only.	Each	$4,779.04	1	$4,779.04
Pump, >30 HP, Pump and motor, variable cost portion	1014	Variable cost portion of a pump greater than 30 HP, including the pump and motor. This portion is dependent on the total horsepower for the pump. The total cost will include this variable cost plus a fixed cost portion. IIncludes material and shipping only.	Horsepower	$98.11	100	$9,811.00
Pipe, Steel, 20", Std Wt, USED	1359	Materials: - USED - 20" - Steel Std Wt	Foot	$40.30	20	$806.00
Pipe, Steel, 36", Std Wt, USED	1362	Materials: - USED - 36" - Steel Std Wt	Foot	$97.25	50	$4,862.50
Pipe, Steel, 42", Std Wt, USED	1363	Materials: - USED - 42" - Steel Std Wt	Foot	$111.90	14	$1,566.60
Swing Check Valve, metal, 20"	2086	20" swing check valve for back flow prevention, ductile iron metal body with flange mount and lever shaft. Materials only.	Each	$13,208.09	1	$13,208.09
Mobilization						

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 533 - Pumping Plant

Scenario #6 - Electric-Powered Pump >5 HP<=30 hp

Scenario Description:

This is a close-coupled, 3-phase, 20 hp electric-powered centrifugal pump mounted on a platform for pressurizing a medium-sized (500 gpm and 50 psi) sprinkler or large microirrigation (1,000 gpm and 30 psi) system or a large-sized surface irrigation system (1,500 gpm) or a medium-sized (1,000 gpm and 25 psi) waste transfer system. Resource Concerns: Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 449 - Irrigation Water Management; 313 - Waste Storage Facility; and 634 - Waste Transfer.

Before Situation:

Irrigation: An existing irrigation system employs an inefficient, improperly sized pump that prevents efficient water application resulting in water loss and high energy use.

After Situation:

Irrigation: A properly designed and efficient pumping plant is installed, reducing energy use and improving irrigation efficiency.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 20.0

Scenario Total Cost: $10,520.02

Scenario Cost/Unit: $526.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	2	$470.18
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	8	$453.20
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	56	$1,233.12
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	8	$219.04
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	56	$1,064.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	8	$205.44
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	56	$2,026.08
Materials						
Pump, > 5 HP to 30 HP, pump and motor, fixed cost portion	1011	Fixed cost portion of a pump between 5 and 30 HP, including the pump and motor. This portion is a base cost for the pump and is not dependant on horsepower. The total cost will include this fixed cost plus a variable cost portion. Includes material and shipping only.	Each	$2,020.31	1	$2,020.31
Pump, > 5 HP to 30 HP, pump and motor, variable cost portion	1012	Variable cost portion of a pump between 5 and 30 HP, including the pump and motor. This portion is dependent on the total horsepower for the pump. The total cost will include this variable cost plus a fixed cost portion. Includes material and shipping only.	Horsepower	$128.60	20	$2,572.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 533 - Pumping Plant

Scenario #7 - Electric-Powered Pump >30 hp <=75

Scenario Description:

This is a close-coupled, 3-phase, 50 hp electric-powered centrifugal pump mounted on a platform for pressurizing a large-sized 1,000 gpm and 50 psi) sprinkler or very large microirrigation (2,000 gpm and 30 psi) system or a very large-sized surface irrigation system (3,000 gpm) or a large-sized (2,000 gpm and 25 psi) waste transfer system. Resource Concerns: Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 449 - Irrigation Water Management; 313 - Waste Storage Facility; and 634 - Waste Transfer.

Before Situation:

Irrigation: An existing irrigation system employs an inefficient, improperly sized pump that prevents efficient water application resulting in water loss and high energy use.

After Situation:

A properly designed and efficient pumping plant is installed, reducing energy use and improving irrigation efficiency

Feature Measure: <Unknown>

Scenario Unit:: Horsepower

Scenario Typical Size: 50.0

Scenario Total Cost: $17,030.57

Scenario Cost/Unit: $340.61

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	2	$470.18
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	16	$906.40
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	56	$1,233.12
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	56	$1,533.28
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	24	$616.32
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	56	$2,026.08
Materials						
Pump, > 30 HP, pump and motor, fixed cost portion	1013	Fixed cost portion of a pump greater than 30 HP, including the pump and motor. This portion is a base cost for the pump and is not dependant on horsepower. The total cost will include this fixed cost plus a variable cost portion. Includes material and shipping only.	Each	$4,779.04	1	$4,779.04
Pump, >30 HP, Pump and motor, variable cost portion	1014	Variable cost portion of a pump greater than 30 HP, including the pump and motor. This portion is dependent on the total horsepower for the pump. The total cost will include this variable cost plus a fixed cost portion. IIncludes material and shipping only.	Horsepower	$98.11	50	$4,905.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 533 - Pumping Plant

Scenario #8 - Electric-Powered Pump >75hp

Scenario Description:

This is a close-coupled, 3-phase, 100 hp electric-powered centrifugal pump mounted on a platform for pressurizing a medium-sized (500 gpm and 50 psi) sprinkler or large microirrigation (1,000 gpm and 30 psi) system or a large-sized surface irrigation system (1,500 gpm) or a medium-sized (1,000 gpm and 25 psi) waste transfer system. Resource Concerns: Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 449 - Irrigation Water Management; 313 - Waste Storage Facility; and 634 - Waste Transfer.

Before Situation:

Irrigation: An existing irrigation system employs an inefficient, improperly sized pump that prevents efficient water application resulting in water loss and high energy use.

After Situation:

Irrigation: A properly designed and efficient pumping plant is installed, reducing energy use and improving irrigation efficiency.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 100.0

Scenario Total Cost: $21,200.17

Scenario Cost/Unit: $212.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	4	$940.36
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	8	$453.20
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	56	$1,233.12
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	12	$328.56
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	56	$1,064.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	12	$308.16
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	56	$2,026.08
Materials						
Pump, > 30 HP, pump and motor, fixed cost portion	1013	Fixed cost portion of a pump greater than 30 HP, including the pump and motor. This portion is a base cost for the pump and is not dependant on horsepower. The total cost will include this fixed cost plus a variable cost portion. Includes material and shipping only.	Each	$4,779.04	1	$4,779.04
Pump, >30 HP, Pump and motor, variable cost portion	1014	Variable cost portion of a pump greater than 30 HP, including the pump and motor. This portion is dependent on the total horsepower for the pump. The total cost will include this variable cost plus a fixed cost portion. IIncludes material and shipping only.	Horsepower	$98.11	100	$9,811.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 533 - Pumping Plant

Scenario #9 - Variable Frequency Drive

Scenario Description:

This is an installation of electrical and electronic components designed to vary the frequency of the voltage to an electric motor and thus the ability to vary the speed of the motor. This directly affects pressure and flowrate. This also could give the operator the flexibility to operate several systems separately or at the same time. Resource concerns: Insufficient water - Inefficient use of irrigation water; Inefficient energy use - Equipment and facilities and Farming/ranching practices and field operations. Associated Practices: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 449 - Irrigation Water Management; 516 - Livestock Pipeline; and 614 - Watering Facility.

Before Situation:

Standard electrical connection from electrical utility to pump motor. No capability to match pump output pressure and/or flowrate to field(s) need(s). Result is over/under pressure(s) and/or flow rate(s), possible hydraulic anomalies, energy loss, and or inefficient water application in the irrigation system.

After Situation:

VFD Modifications are implemented at the pump site to allow for varying the speed of a 40 hp electric motor to match the pressure and flow requirements for a center pivot irrigation system.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 50.0

Scenario Total Cost: $12,386.00

Scenario Cost/Unit: $247.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Variable Speed Drive, 50 HP	1288	Variable speed drive for 50 Horsepower electric motor. Does not include motor. Materials only.	Horsepower	$247.72	50	$12,386.00

Practice: 533 - Pumping Plant

Scenario #10 - Internal Combustion-Powered Pump less than or equal to 50 HP with L-pipe

Scenario Description:

The typical scenario supports installation of a pump in an existing irrigation system or installation of a new pump on cropland with a 30 BHP pump. Size of pump is determined by required GPM and pressure derived from a design for specific irrigation system on cropland. The combination of higher solids content and volume require a larger horse power pump. This liquid manure pump is used to transfer semi-solid manure from a small reception pit located either below a barnyard or at the end of a free-stall barn or scrape alley. Resource Concerns: Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 449 - Irrigation Water Management; 313 - Waste Storage Facility; 634 - Waste Transfer; 436 - Irrigation Reservoir; and 447 - Irrigation System, Tailwater Recovery; and 614 - Watering Facility.

Before Situation:

Irrigation: Either an existing irrigation system employs an inefficient, improperly-sized pump that leads to inefficient water delivery resulting in high energy costs, or Waste Transfer: various types of semi-solid or liquid waste at the headquarters is uncollected causing surface and ground water issues.

After Situation:

Irrigation Setting: For irrigation system, a properly designed pump is installed, reducing water and energy usage. or Waste Transfer Setting: For semi-solid or liquid waste, wastes that have been collected through a waste transfer system are now efficiently transferred to appropriate treatment or storage facilities or crop application. Due to topography, gravity transfer is not possible and a properly sized pump is needed to transfer waste as part of a waste transfer system.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 30.0

Scenario Total Cost: $28,992.79

Scenario Cost/Unit: $966.43

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	0.25	$58.77
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	$125.35	8	$1,002.80
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	8	$919.68
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Portable Welder	1407	Portable field welder. Equipment only. Labor not included.	Hour	$20.63	8	$165.04
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	4	$109.52
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	4	$76.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	16	$410.88
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	4	$144.72
Materials						
Pump, < 50 HP, Pump & ICE power unit	1027	Materials, labor, controls: < 50 HP Pump & ICE power unit	Horsepower	$631.52	30	$18,945.60
Pipe, Steel, 24", Std Wt, USED	1360	Materials: - USED - 24" - Steel Std Wt	Foot	$48.46	40	$1,938.40
Pipe, Steel, 30", Std Wt, USED	1361	Materials: - USED - 30" - Steel Std Wt	Foot	$76.17	14	$1,066.38
Swing Check Valve, metal, 12"	2082	12" swing check valve for back flow prevention, ductile iron metal body with flange mount and lever shaft. Materials only.	Each	$3,597.66	1	$3,597.66
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 533 - Pumping Plant

Scenario #11 - Internal Combustion-Powered Pump greater than 50 to 70 HP, with L-pipe

Scenario Description:

The typical scenario supports installation of a pump in an existing irrigation system or installation of a new pump on cropland with a 60 BHP pump. Size of pump is determined by required GPM and pressure derived from a design for specific irrigation system on cropland. The combination of higher solids content and volume require a larger horse power pump. This liquid manure pump is used to transfer semi-solid manure from a small reception pit located either below a barnyard or at the end of a free-stall barn or scrape alley. Resource Concerns: Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 449 - Irrigation Water Management; 313 - Waste Storage Facility; 634 - Waste Transfer; 436 - Irrigation Reservoir; and 447 - Irrigation System, Tailwater Recovery; and 614 - Watering Facility.

Before Situation:

Irrigation: Either an existing irrigation system employs an inefficient, improperly-sized pump that leads to inefficient water delivery resulting in high energy costs, or Waste Transfer: various types of semi-solid or liquid waste at the headquarters is uncollected causing surface and ground water issues.

After Situation:

Irrigation Setting: For irrigation system, a properly designed pump is installed, reducing water and energy usage. Waste Transfer Setting: For semi-solid or liquid waste, wastes that have been collected through a waste transfer system are now efficiently transferred to appropriate treatment or storage facilities or crop application. Due to topography, gravity transfer is not possible and a properly sized pump is needed to transfer waste as part of a waste transfer system.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 60.0

Scenario Total Cost: $42,897.15

Scenario Cost/Unit: $714.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	1	$235.09
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	8	$453.20
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	$125.35	4	$501.40
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	8	$919.68
Portable Welder	1407	Portable field welder. Equipment only. Labor not included.	Hour	$20.63	8	$165.04
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	32	$608.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	16	$410.88
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	16	$578.88
Materials						
Pump, > 50 to 70 HP, Pump & ICE power unit	1028	Materials, labor, controls: > 50 to 70 HP Pump & ICE power unit	Horsepower	$497.91	60	$29,874.60
Pipe, Steel, 24", Std Wt, USED	1360	Materials: - USED - 24" - Steel Std Wt	Foot	$48.46	40	$1,938.40
Pipe, Steel, 30", Std Wt, USED	1361	Materials: - USED - 30" - Steel Std Wt	Foot	$76.17	14	$1,066.38
Swing Check Valve, metal, 14"	2083	14" swing check valve for back flow prevention, ductile iron metal body with flange mount and lever shaft. Materials only.	Each	$5,194.22	1	$5,194.22
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 533 - Pumping Plant

Scenario #12 - Internal Combustion-Powered Pump greater than 70 HP, with L-pipe

Scenario Description:

The typical scenario supports replacement of a pump in an existing irrigation system or installation of a new pump on cropland that is 80 BHP pump or larger. Size of pump is determined by required GPM and pressure derived from a design for specific irrigation system on cropland. Scenario could also be used for a pump for silage leachate, barnyard runoff, and milk house waste (as part of a waste transfer system) at farm headquarters. Resource Concerns: Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 449 - Irrigation Water Management; 313 - Waste Storage Facility; 634 - Waste Transfer; and 614 - Watering Facility.

Before Situation:

Irrigation: Either an existing irrigation system employs an inefficient, improperly-sized pump that leads to inefficient water delivery resulting in high energy costs, or Waste Transfer: various types of semi-solid or liquid waste at the headquarters is uncollected causing surface and ground water issues.

After Situation:

Irrigation Setting: For irrigation system, a properly designed pump is installed, reducing water and energy usage. Waste Transfer Setting: For semi-solid or liquid waste, wastes that have been collected through a waste transfer system are now efficiently transferred to appropriate treatment or storage facilities or crop application. Due to topography, gravity transfer is not possible and a properly sized pump is needed to transfer waste as part of a waste transfer system.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 80.0

Scenario Total Cost: $47,509.73

Scenario Cost/Unit: $593.87

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	2	$470.18
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$66.84	8	$534.72
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	8	$919.68
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	6	$132.12
Portable Welder	1407	Portable field welder. Equipment only. Labor not included.	Hour	$20.63	8	$165.04
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	8	$219.04
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	48	$912.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	8	$205.44
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	24	$868.32
Materials						
Pump, > 70 HP, Pump & ICE power unit	1029	Materials, labor, controls: > 70 HP Pump & ICE power unit	Horsepower	$384.26	80	$30,740.80
Pipe, Steel, 18", Std Wt, USED	1358	Materials: - USED - 18" - Steel Std Wt	Foot	$35.50	20	$710.00
Pipe, Steel, 30", Std Wt, USED	1361	Materials: - USED - 30" - Steel Std Wt	Foot	$76.17	40	$3,046.80
Pipe, Steel, 36", Std Wt, USED	1362	Materials: - USED - 36" - Steel Std Wt	Foot	$97.25	14	$1,361.50
Swing Check Valve, metal, 16"	2084	16" swing check valve for back flow prevention, ductile iron metal body with flange mount and lever shaft. Materials only.	Each	$6,710.79	1	$6,710.79
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 533 - Pumping Plant

Scenario #13 - Internal Combustion-Powered Well Pump 50 HP and less, no L-pipe

Scenario Description:

The typical scenario supports installation of a pump in an existing irrigation system or installation of a new pump on cropland with a 30 BHP pump. Size of pump is determined by required GPM and pressure derived from a design for specific irrigation system on cropland. The combination of higher solids content and volume require a larger horse power pump. This liquid manure pump is used to transfer semi-solid manure from a small reception pit located either below a barnyard or at the end of a free-stall barn or scrape alley. Resource Concerns: Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 449 - Irrigation Water Management; 313 - Waste Storage Facility; 634 - Waste Transfer; 436 - Irrigation Reservoir; and 447 - Irrigation System, Tailwater Recovery; and 614 - Watering Facility.

Before Situation:

Irrigation: Either an existing irrigation system employs an inefficient, improperly-sized pump that leads to inefficient water delivery resulting in high energy costs, or Waste Transfer: various types of semi-solid or liquid waste at the headquarters is uncollected causing surface and ground water issues.

After Situation:

Irrigation Setting: For irrigation system, a properly designed pump is installed, reducing water and energy usage. or Waste Transfer Setting: For semi-solid or liquid waste, wastes that have been collected through a waste transfer system are now efficiently transferred to appropriate treatment or storage facilities or crop application. Due to topography, gravity transfer is not possible and a properly sized pump is needed to transfer waste as part of a waste transfer system.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 30.0

Scenario Total Cost: $21,846.63

Scenario Cost/Unit: $728.22

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	1	$235.09
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	8	$453.20
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	4	$88.08
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	8	$219.04
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	32	$608.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	8	$205.44
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	16	$578.88
Materials						
Pump, < 50 HP, Pump & ICE power unit	1027	Materials, labor, controls: < 50 HP Pump & ICE power unit	Horsepower	$631.52	30	$18,945.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 533 - Pumping Plant

Scenario #14 - Internal Combustion-Powered Well Pump Greater than 50 to 70 HP, no L-pipe

Scenario Description:

The typical scenario supports installation of a well pump in an existing irrigation system or installation of a new well pump on cropland with a 60 BHP pump. Size of pump is determined by required GPM and pressure derived from a design for specific irrigation system on cropland. The combination of higher solids content and volume require a larger horse power pump. This liquid manure pump is used to transfer semi-solid manure from a small reception pit located either below a barnyard or at the end of a free-stall barn or scrape alley. The well will be drilled using 642 Water Well. Resource Concerns: Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 449 - Irrigation Water Management; 313 - Waste Storage Facility; 634 - Waste Transfer; 436 - Irrigation Reservoir; and 447 - Irrigation System, Tailwater Recovery; and 614 - Watering Facility.

Before Situation:

Irrigation: Either an existing irrigation system employs an inefficient, improperly-sized pump that leads to inefficient water delivery resulting in high energy costs, or Waste Transfer: various types of semi-solid or liquid waste at the headquarters is uncollected causing surface and ground water issues.

After Situation:

Irrigation Setting: For irrigation system, a properly designed pump is installed, reducing water and energy usage. Waste Transfer Setting: For semi-solid or liquid waste, wastes that have been collected through a waste transfer system are now efficiently transferred to appropriate treatment or storage facilities or crop application. Due to topography, gravity transfer is not possible and a properly sized pump is needed to transfer waste as part of a waste transfer system.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 60.0

Scenario Total Cost: $32,775.63

Scenario Cost/Unit: $546.26

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	1	$235.09
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	8	$453.20
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	4	$88.08
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	8	$219.04
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	32	$608.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	8	$205.44
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	16	$578.88
Materials						
Pump, > 50 to 70 HP, Pump & ICE power unit	1028	Materials, labor, controls: > 50 to 70 HP Pump & ICE power unit	Horsepower	$497.91	60	$29,874.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 533 - Pumping Plant

Scenario #15 - Internal Combustion-Powered Well Pump Greater than 70 HP, no L-pipe

Scenario Description:

The typical scenario supports replacement of a pump in an existing irrigation system or installation of a new pump on cropland that is 80 BHP pump or larger. Size of pump is determined by required GPM and pressure derived from a design for specific irrigation system on cropland. Scenario could also be used for a pump for silage leachate, barnyard runoff, and milk house waste (as part of a waste transfer system) at farm headquarters. Resource Concerns: Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 449 - Irrigation Water Management; 313 - Waste Storage Facility; 634 - Waste Transfer; and 614 - Watering Facility.

Before Situation:

Irrigation: Either an existing irrigation system employs an inefficient, improperly-sized pump that leads to inefficient water delivery resulting in high energy costs, or Waste Transfer: various types of semi-solid or liquid waste at the headquarters is uncollected causing surface and ground water issues.

After Situation:

Irrigation Setting: For irrigation system, a properly designed pump is installed, reducing water and energy usage. Waste Transfer Setting: For semi-solid or liquid waste, wastes that have been collected through a waste transfer system are now efficiently transferred to appropriate treatment or storage facilities or crop application. Due to topography, gravity transfer is not possible and a properly sized pump is needed to transfer waste as part of a waste transfer system.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 100.0

Scenario Total Cost: $42,199.60

Scenario Cost/Unit: $422.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	2	$470.18
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	8	$453.20
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	6	$132.12
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	8	$219.04
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	48	$912.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	8	$205.44
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	24	$868.32
Materials						
Pump, > 70 HP, Pump & ICE power unit	1029	Materials, labor, controls: > 70 HP Pump & ICE power unit	Horsepower	$384.26	100	$38,426.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 533 - Pumping Plant

Scenario #16 - Tractor Power Take Off (PTO) Pump

Scenario Description:

This scenario involves a PTO driven pump to either transfer water for an irrigation system from a Pond - 378 (includes backflow prevention as appropriate) to cropland or; to transfer semi-solid/ liquid manure (as part of a waste transfer system) at the farm headquarters from a Waste Storage Facility - 313, to an irrigation system or waste treatment facility. In both cases, a PTO driven pump is selected because the landowner has equipment available to supply power to the pump. Electricity is not readily available and/or a stationary engine is not a practical alternative. Resource Concerns: Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 430 - Irrigation Pipeline; 442 - Irrigation System, Sprinkler; 449 - Irrigation Water Management; 590 - Nutrient Management; 378 - Pond; 313 - Waste Storage Facility; and 634 - Waste Transfer.

Before Situation:

Irrigation Setting: An existing surface irrigation system employs an inefficient, improperly sized pump that leads to inefficient water delivery resulting in high energy costs; Waste Transfer Setting: various types of semi-solid or liquid waste at the headquarters are uncollected causing surface and ground water issues. A transfer method for waste is needed. Due to topography, gravity transfer is not possible and a properly sized pump is needed to transfer waste as part of a waste transfer system.

After Situation:

Irrigation Setting: A properly designed PTO-driven pump is installed, to transfer water to an Irrigation Pipeline (430) or Irrigation Canal or Lateral (320). Waste Transfer Setting: Wastes that have been collected through a waste transfer system are now efficiently transferred from a Waste Storage Facility (313) to an appropriate treatment facility or to an irrigation system. The pump typically will move 2,000 gallons per minute and is portable so that it can be used at several locations.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 60.0

Scenario Total Cost: $11,556.19

Scenario Cost/Unit: $192.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	2	$470.18
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	16	$352.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	16	$578.88
Materials						
Pump, Ag Water PTO, 1,000 GPM	1923	Materials, labor, controls: Ag Water PTO Pump 1,000 GPM - 8"	Each	$9,850.81	1	$9,850.81

Practice: 533 - Pumping Plant

Scenario #18 - Photovoltaic-Powered Pump

Scenario Description:

The typical scenario assumes installation of a submersible solar-powered pump in a well or a live stream. The installation includes the pump, wiring, drop pipe, solar panels, mounts, inverter, and all appurtenances. Note: It is generally not advisable to use a storage battery for a number of reasons. A storage tank is generally the most efficient method to store energy. Grazing - Livestock exclusion from surface water will result in improved surface water quality and reduced erosion. Irrigation - energy consumption will be reduced and the increased pressure and flow rates will improve irrigation efficiency. Resource Concerns: Insufficient stockwater. Associated Practices include: 374 - Farmstead Energy Improvement; 382 - Fence; 430 - Irrigation Pipeline; 436 - Irrigation Reservoir; 516 - Livestock Pipeline; 561 - Heavy Use Area Protection; and, 614 - Watering Facility.

Before Situation:

Livestock: Inadequate supply or location of water for a prescribed grazing system. Eroded stream banks and degraded water quality due to livestock access to stream. Cattle are not well-distributed because of remote water location. Irrigation: Pressure and flow rate is insufficient for uniform irrigation.

After Situation:

The typical scenario assumes installation of a 746-watt photovoltaic (PV) panel, capable of operating a 1 hp solar-powered submersible pump in a well or other water source (Notes: 1) A PV panel is rated under standard and ideal conditions which will most likely not be replicated in the field; 2) 1 hp is defined as 746 watts; 3) It is reasonable to expect a 1/4 hp solar-powered submersible pump to deliver about 1.5 gpm and develop a pressure at the pump outlet of about 60 psi.). The installation includes the pump, wiring, pipeline in the well, solar panels, frame mounts, inverter, and all appurtenances. Water will be pumped to an existing storage tank at a higher elevation from which it will be used to pressurize the Livestock Pipeline (516) or Irrigation Pipeline (430). Grazing - Livestock exclusion from surface water will result in improved surface water quality and reduced erosion. Grazing has potential to be well distributed. Irrigation: Improved pressure and flow rate will improve irrigation efficiency.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 1.0

Scenario Total Cost: $9,475.84

Scenario Cost/Unit: $9,475.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	16	$352.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	16	$578.88
Materials						
Pump, <= 5 HP, pump and motor, fixed cost portion	1009	Fixed cost portion of a pump less than or equal to 5 HP pump and motor. This portion is a base cost and is not dependant on horsepower. The total cost of any pump will include this fixed cost plus a variable cost portion. The completed pump and motor will include the motor and controls. Includes Includes material and shipping only.	Each	$564.23	1	$564.23
Pump, <= 5 HP, pump and motor, variable cost portion	1010	Variable cost portion of a pump less than or equal to 5 HP pump and motor. This portion IS dependent on the total horsepower for the pump. The total cost of any pump will include this variable cost plus the fixed cost portion. The completed pump and motor will include the motor and controls. Includes material and shipping only.	Horsepower	$424.66	1	$424.66
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will include all materials (electrical, controllers, service drops and etc). This cost will include material, labor and equipment.	Each	$472.52	1	$472.52
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all materials (electrical, controllers, and service drop, etc). This cost will include material, labor and equipment.	Kilowatt	$8,474.04	0.8	$6,779.23

Practice: 533 - Pumping Plant

Scenario #19 - Pump Conversion to Low Pressure

Scenario Description:

This scenario involves converting an existing pump which is set up to operate any high pressure system to a pump set up to operate a low pressure system, when the existing high pressure system is being converted to low pressure system. Resource Concerns: Excess/Insufficient Water - Inefficient Use of Irrigation Water & Water Quality Degradation; Energy Conservation Associated Practices: 449 - Irrigation Water Management, 442 - Irrigation System, Sprinkler

Before Situation:

An existing irrigation pump is operating a high pressure center pivot system and needs to be converted to a low pressure pump to efficiently operate a center pivot system converted to low pressure.

After Situation:

The existing high pressure pump is pulled and stages are removed in order to reduce the pressure which the pump will produce, this will cause a more energy efficient system and a system which is more efficiently distributing water.

Feature Measure: conversion of pump

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $6,236.16

Scenario Cost/Unit: $6,236.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Crane, truck mounted, hydraulic, 12 ton	1734	12 ton capacity truck mounted hydraulic crane. Equipment cost only.	Hour	$92.50	6	$555.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	6	$114.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Pump, Bowl replacement, 30 to 100 HP	1984	Includes all material and shop labor to replace/service the entire set of bowls for a vertical turbine pump, install new bowls as necessary, and all appurtenances and materials to connect to the existing well column. Typical of 100 to 300 feet of column depth, 400 to 800 gpm discharge at 30 to 50 psi. Does not include labor and equipment to remove and install the assembled pump from the well.	Horsepower	$99.63	50	$4,981.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 533 - Pumping Plant

Scenario #20 - Basic Pump Automation

Scenario Description:

Typical: a diesel or electrical pump is set up with basic capabilities to shut off the pump based upon time, water levels, or other sensor or device to prevent excess run-time and unnecessary pumping. Resource Concerns: Excess/Insufficient Water - Inefficient Use of Irrigation Water & Water Quality Degradation Associated Practices: 449 - Irrigation Water Management

Before Situation:

Pumps are manually stopped. Oil, fuel, and water level in reservoir/tailwater pit are manually read. Requires a person to physically be on site to manipulate the pump and to take readings. Excess irrigation water is allowed to run off the crops and farmland when situations occur where farm labor is unable to operate the pump when irrigation is needed or needs have been met.

After Situation:

Pump has an automatic pump stop based upon a timer, water level sensor or other device. This prevents the landowner from being physically at the site when sufficient water is available or not for irrigation. Crops are supplied the required water needs and excess is not allowed to leave the farm, thus preventing damage to the pumping system, increased labor of the overall farm operation and increasing efficiency, preventing sediment loss, reducing turbidity, over saturation of the plants, water quality turbidity or excess water use in critical ground water areas.

Feature Measure: automation of a pump cut-off

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $366.33

Scenario Cost/Unit: $366.33

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Switches and Controls, programmable controller	1193	Programmable logic controller (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	$170.29	1	$170.29

Practice: 533 - Pumping Plant

Scenario #21 - Intermediate Pump Automation

Scenario Description:

Typical: a diesel or electrical pump is set up with a intermediate automation component that controls the pump via remote access in order to prevent excess run-time and unnecessary pumping. Resource Concerns: Excess/Insufficient Water - Inefficient Use of Irrigation Water & Water Quality Degradation Associated Practices: 449 - Irrigation Water Management

Before Situation:

Pumps are manually stopped. Oil, fuel, and water level in reservoir/tailwater pit are manually read. Requires a person to physically be on site to manipulate the pump and to take readings. Excess irrigation water is allowed to run off the crops and farmland when situations occur where farm labor is unable to operate the pump when irrigation is needed or needs have been met.

After Situation:

By use of a smartphone or tablet, the pump can be remoted started or stopped. Alerts can be sent to operator of interruptions in the system or can be preset to shut off at specified time. This prevents the landowner from being physically at the site when sufficient water is available or not for irrigation. Crops are supplied the required water needs and excess is not allowed to leave the farm, thus preventing damage to the pumping system, increased labor of the overall farm operation and increasing efficiency, preventing sediment loss, reducing turbidity, over saturation of the plants, water quality turbidity or excess water use in critical ground water areas.

Feature Measure: automation of a pump start and st

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $3,053.52

Scenario Cost/Unit: $3,053.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	4	$76.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	4	$336.72
Materials						
Switches and Controls, temp sensors	1192	Temperature and soil moisture sensors installed as part of an electronic monitoring (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	$666.86	1	$666.86
Switches and Controls, programmable controller	1193	Programmable logic controller (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	$170.29	1	$170.29
Switches and Controls, Wi-Fi system and software	1194	Software with built-in cellular or Wi-Fi communication commonly used to control pumps and irrigation systems	Each	$457.13	1	$457.13
Switches and Controls, radio system	1195	Output radio, field transmitter, and receiver commonly used to control pumps and irrigation systems	Each	$815.09	1	$815.09
Safety Camera on Automated Pump	2474	Waterproof outdoor wireless IP Network security camera with housing. Includes materials only.	Each	$480.73	1	$480.73
Engine/Fuel Tank Sensor	2487	Transducer and sensors to monitor the oil pressure, oil and water temperatures, fuel flow meter with digital pulse output and fuel levels in a tank. Includes the conduit and cabling.	Each	$50.70	1	$50.70

Practice: 533 - Pumping Plant

Scenario #23 - Pump without power unit, with L-pipe

Scenario Description:

The typical scenario supports installation of a pump and support typically used with pumping from a tailwater recovery channel or reservoir on cropland with a 35 BHP pump without a power unit (3000gpm x 30 ft)/(3960*.65) = 35 BHP. Size (BHP) of pump is determined by required GPM and pressure derived from a design for specific irrigation system on cropland. Typical scenario is 3000 gpm with 30 ft of head (lift, line friction, pressure, etc.). Also may apply to a pump for wastewater. Cooperator has existing motor, will rent motor, or buy used motor. Resource Concerns: Water Quality degradation - Excess nutrients in surface and ground waters; Insufficient water - Inefficient use of irrigation water. Associated Practices include: 374 - Farmstead Energy Improvement; 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 449 - Irrigation Water Management; 313 - Waste Storage Facility; 634 - Waste Transfer; 436 - Irrigation Reservoir; and 447 - Irrigation System, Tailwater Recovery; and 614 - Watering Facility.

Before Situation:

Irrigation: Implementation of a tailwater recovery system or on-farm storage system requires a transfer pump w/o a power plant. Either an existing irrigation system employs an inefficient, improperly-sized pump that leads to inefficient water delivery resulting in high energy costs, or Waste Transfer: various types of semi-solid or liquid waste at the headquarters is uncollected causing surface and ground water issues.

After Situation:

Irrigation Setting: For irrigation system, a properly designed pump is installed, reducing water and energy usage and allowing proper utilization of captured water. or Waste Transfer Setting: For semi-solid or liquid waste, wastes that have been collected through a waste transfer system are now efficiently transferred to appropriate treatment or storage facilities or crop application. Due to topography, gravity transfer is not possible and a properly sized pump is needed to transfer waste as part of a waste transfer system.

Feature Measure: Pump Power Requirement

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 35.0

Scenario Total Cost: $14,774.79

Scenario Cost/Unit: $422.14

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	0.25	$58.77
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	8	$1,329.60
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Portable Welder	1407	Portable field welder. Equipment only. Labor not included.	Hour	$20.63	8	$165.04
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	4	$76.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	16	$410.88
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	4	$144.72
Materials						
Pipe, Steel, 24", Std Wt, USED	1360	Materials: - USED - 24" - Steel Std Wt	Foot	$48.46	40	$1,938.40
Pipe, Steel, 30", Std Wt, USED	1361	Materials: - USED - 30" - Steel Std Wt	Foot	$76.17	14	$1,066.38
Swing Check Valve, metal, 12"	2082	12" swing check valve for back flow prevention, ductile iron metal body with flange mount and lever shaft. Materials only.	Each	$3,597.66	1	$3,597.66
Pump, 40-80 hp axial flow/mixed flow	2215	Propeller pump to handle 10,000 - 20,000gpm axial flow/ mixed flow; 12" - 24" discharge, head (<20' to 25'), propeller type pump. Materials and shipping only.	Gallon per Minute	$1.81	3000	$5,430.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 533 - Pumping Plant

Scenario #65 - PAM surface irrigation injector pump

Scenario Description:

Polyacrylamide is a synthetic organic polymer derived from petroleum that can be used to reduce water quantity by improved infiltration and control of irrigation induced erosion (typically in furrow irrigated row crop fields) through the direct application of water-soluble Polyacrylamide (PAM) into the irrigation water supply. PAM comes in granular, liquid oil emulsion, tablet, and block forms. The typical application is for an 80-acre furrow or flood irrigated crop field. The emulsion form of PAM is generally injected directly into the irrigation water supply through canal or poly tubing at a rate of approximately 2-3 lbs. /ac per application. Subsequent applications are made every thirty days or following soil disturbance.

Before Situation:

Irrigation induced erosion allows for negative impacts on irrigation runoff water quality, water quantity, and soil erosion. Soil erosion, water quality and water quantity resource concerns are associated with this practice.

After Situation:

Water quantity justification derived from practice standard 450, Anionic Polyacrylamide (PAM) Application (September 2014) on fine to medium textured soils, PAM may result in an increase in surface irrigation infiltration of up to 60 % with 15% being typical on medium textured soils. Erosion is minimized in furrow irrigated field. Resource Concern: water quantity, soil erosion, reduce energy use, improve water quality Associated Practices: 443-Irrigation System, Surface and Subsurface, 449-Irrigation Water Management

Feature Measure: 1 per system

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $607.09

Scenario Cost/Unit: $607.09

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Pump, Transfer, 1 HP, Pump and Motor	2472	Transfer pump with a 1 horsepower, 3 phase motor. Includes materials, labor, and controls.	Each	$607.09	1	$607.09

Practice: 554 - Drainage Water Management

Scenario #1 - Drainage Water Management (DWM)

Scenario Description:

This scenario is the process of managing water discharges from surface and/or subsurface agricultural drainage systems by reducing nutrient loading into surface waters. Typical systems consist of a 75 acre field with existing drainage tile lines and installed water control structures. The operator goes to the field in order to adjust water control structures (riser boards). While on site the date and adjustment information is recorded/logged. The number of yearly adjustments is based on 6 trips to a field 5 miles from headquarters. The field time to make and record each adjustment is 0.5 hours per structure (including travel time). The typical field will contain 5 water control structures; 3 structures control field water levels and 2 structures control a single denitrifying bioreactor. Resource Concern: Water Quality - Excess Nutrients in surface and ground waters. Associated Practices: 606-Subsurface Drain; 607-Surface Drain, Field Ditch; 608-Surface Drain, Main or Lateral; 587-Structure for Water Control; 590-Nutrient Management .

Before Situation:

Existing drainage systems are in place and water flows uncontrolled.

After Situation:

Existing drainage systems are managed to reduce flow of field drainage waters from the site and reduce nitrate loading by denitrification.

Feature Measure: Number of Control Structures

Scenario Unit:: Each

Scenario Typical Size: 5.0

Scenario Total Cost: $432.15

Scenario Cost/Unit: $86.43

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	0.33	$21.45
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	15	$410.70

Practice: 560 - Access Road

Scenario #2 - New 6 Inch gravel road in wet, level terrain

Scenario Description:

Newly Constructed gravel road with min. 6 inch thick compacted gravel surface in relatively level ground in wet areas. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, and all equipment, labor and incidental materials necessary to install the practice.

Before Situation:

An agricultural enterprise which requires, but does not have, a fixed travel way for equipment and vehicles for various resource activities and where use of equipment and vehicles within the enterprise without a defined access road would result in compaction, excessive sediment and turbidity in surface water, reduced visibility, and emissions of fugitive dust. This scenario is applicable where the resource activity areas consist of relatively wet and swampy but level terrain lands.

After Situation:

The road will be 14 feet wide with 6 inch gravel surfacing at the top. It is mostly in embankment less than 3 feet in height, (average 2 ft) typical side slopes 2:1. A properly constructed, well defined access road will greatly reduce sheet, rill and wind erosion, eliminate compaction in land use areas where it is harmful, reduce emissions of particulate matter (PM) and PM precursors and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). When seeding or revegetation is required, use Critical Area Planting (342). Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).

Feature Measure: Length of Roadway

Scenario Unit:: Foot

Scenario Typical Size: 1,000.0

Scenario Total Cost: $20,567.15

Scenario Cost/Unit: $20.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	$2.38	2000	$4,760.00
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	1330	$5,213.60
Earthfill, Dumped and Spread	51	Earthfill, dumped and spread without compaction effort, includes equipment and labor	Cubic Yard	$3.22	1330	$4,282.60
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	10	$273.80
Materials						
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic Yard	$21.02	275	$5,780.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 561 - Heavy Use Area Protection

Scenario #1 - Reinforced Concrete with sand or gravel foundation

Scenario Description:

The stabilization of areas around facilities that are frequently and intensively used by people, animals or vehicles by surfacing with reinforced concrete on a sand or gravel foundation to provide a stable, non-eroding surface. Installation includes all materials, equipment, and labor to install this practice, The stabilized area will address the resource concerns soil erosion and water quality degradation.

Before Situation:

This practice applies to agricultural, urban, recreational and other frequently and/or intensively used areas requiring treatment to address soil erosion and water quality degradation.

After Situation:

The stabilized area is surfaced with approximately 630 square feet of approximately 8 cubic yards of welded wire mesh reinforced concrete with 8 cubic yards of sand or gravel foundation material for surfacing areas around facilities that are frequently and intensively used by people, animals or vehicles and will address soil erosion and water quality degradation. All needed roads must use Access Road (560). Any needed treatment of stream crossings must use Stream Crossing (578). Any needed vegetation of disturbed areas must use Critical Area Planting (342). Provisions to collect, store, utilize, and or treat contaminated runoff must use Sediment Basin (350), Waste Storage Facility (313), or Waste Treatment (629) as appropriate. To reduce the potential for air quality problems from particulate matter associated with heavy use areas, consider the use of Windbreak/Shelterbelt Establishment (380) or Herbaceous Wind Barriers (603).

Feature Measure: Area

Scenario Unit:: Square Foot

Scenario Typical Size: 630.0

Scenario Total Cost: $2,386.37

Scenario Cost/Unit: $3.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	8	$1,880.72
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	4	$8.28
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	$30.09	8	$240.72
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 561 - Heavy Use Area Protection

Scenario #3 - Rock/Gravel on Geotextile, 6 inch thick

Scenario Description:

The stabilization of areas around facilities that are frequently and intensively used by people, animals or vehicles by surfacing with rock and or gravel on a geotextile fabric foundation to provide a stable, non-eroding surface. Installation includes all materials, equipment, and labor to install this practice, The stabilized area will address the resource concerns of soil erosion and water quality degradation.

Before Situation:

This practice applies to agricultural, urban, recreational and other frequently and/or intensively used areas requiring treatment to address soil erosion and water quality degradation.

After Situation:

The stabilized area is surfaced with approximately 630 square feet of rock, (6" deep) and or gravel on approximately 70 square yards of geotextile fabric foundation material for surfacing areas around facilities that are frequently and intensively used by people, animals or vehicles and will address soil erosion and water quality degradation. All needed roads must use Access Road (560). Any needed treatment of stream crossings must use Stream Crossing (578). Any needed vegetation of disturbed areas must use Critical Area Planting (342). Provisions to collect, store, utilize, and or treat contaminated runoff must use Sediment Basin (350), Waste Storage Facility (313), or Waste Treatment (629) as appropriate. To reduce the potential for air quality problems from particulate matter associated with heavy use areas, consider the use of Windbreak/Shelterbelt Establishment (380) or Herbaceous Wind Barriers (603).

Feature Measure: Area of Rock and or Gravel

Scenario Unit:: Square Foot

Scenario Typical Size: 630.0

Scenario Total Cost: $814.09

Scenario Cost/Unit: $1.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	$2.38	70	$166.60
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	12	$24.84
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	$30.50	12	$366.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 576 - Livestock Shelter Structure

Scenario #1 - Portable Shade Structure

Scenario Description:

A flexible membrane or fabric-like roof placed on a steel or wood portable frame used to promote animal health where prescribed grazing practices have limited livestock access to shade. Cost estimate is based upon a 25 ft x 40 ft portable structure. Associated practices include Fence (382), Prescribed Grazing (528), and Watering Facility (614).

Before Situation:

Livestock are being managed using a prescribed grazing plan resulting in a lack of shade during the summer months. The livestock are stressed and eat less frequently.

After Situation:

Livestock shade structures are rotated and sized according to NRCS plans and specifications. Livestock access to water, shade, and forage are dispersed to decrease animal stress and promote a better grazing and nutrient spreading.

Feature Measure: Area of Roof Frame

Scenario Unit:: Square Foot

Scenario Typical Size: 1,000.0

Scenario Total Cost: $4,023.75

Scenario Cost/Unit: $4.02

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	8	$176.16
Portable Welder	1407	Portable field welder. Equipment only. Labor not included.	Hour	$20.63	16	$330.08
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Materials						
Pipe, PVC, 2", SCH 40	976	Materials: - 2" - PVC - SCH 40 - ASTM D1785	Foot	$1.39	25	$34.75
Steel, Plate, 3/16"	1048	Flat Steel Plate, 3/16" thick, materials only.	Square Foot	$5.95	2	$11.90
Pipe, Steel, 1 ¼", SCH 40	1103	Materials: - 1 1/4" - Steel SCH 40	Foot	$4.09	94	$384.46
Pipe, Steel, 2", SCH 40	1105	Materials: - 2" - Steel SCH 40	Foot	$6.57	185	$1,215.45
Synthetic Liner, 60 mil	2109	Synthetic 60 mil HDPE, LLDPE, EPDM, etc membrane liner material. Includes materials and shipping only.	Square Foot	$1.21	1000	$1,210.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87

Practice: 578 - Stream Crossing

Scenario #2 - Hard armored low water crossing

Scenario Description:

Stabilize the bottom and slope of a stream channel using rock riprap or cast in place concrete. The typical scenario includes site preparation, dewatering, acquiring and installing gravel or geotextile with rock riprap or cast in place concrete on channel bottom and approaches. Final travel surface shall be the rocks or concrete. If a different travel surface is needed, refer to another appropriate standard for the surfacing. The cost estimate is based on a typical stream that has 30 foot bottom width and approaches. Width is 14 feet for a total area as 420sf. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

Before Situation:

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

After Situation:

Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

Feature Measure: Crossing dimensions

Scenario Unit:: Square Foot

Scenario Typical Size: 420.0

Scenario Total Cost: $1,902.83

Scenario Cost/Unit: $4.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	2	$195.50
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$1.69	18	$30.42
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	2	$51.36
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	18	$1,368.90
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 578 - Stream Crossing

Scenario #4 - Low water crossing using prefabricated products

Scenario Description:

To install a stable crossing medium on channel bottom and approaches. Medium includes but not limited to precast concrete blocks, geocells, pavers, and gabions. If a different travel surface is needed, refer to another appropriate standard for the surfacing. This cost estimate is based on a typical stream that has a 30 foot bottom width and approaches. Width is 14 feet for a total area as 420sf. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

Before Situation:

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

After Situation:

Access road and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

Feature Measure: low water crossing

Scenario Unit:: Square Foot

Scenario Typical Size: 420.0

Scenario Total Cost: $3,022.32

Scenario Cost/Unit: $7.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	2	$195.50
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$1.69	18	$30.42
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	40	$760.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	2	$51.36
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	$30.09	6	$180.54
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	$30.50	18	$549.00
GeoCell, 4"	1054	4-inch thick cellular confinement system, three-dimensional, expandable panels made from high-density polyethylene (HDPE), polyester or another polymer material. Includes materials, labor and equipment for the geocell only, does not include backfill	Square Yard	$25.11	50	$1,255.50

Practice: 578 - Stream Crossing

Scenario #5 - Steam Crossing, Concrete Bottom

Scenario Description:

Stabilize the bottom and slope of a stream channel using cast in place concrete with gravel approaches. This scenario includes site preparation, dewatering, acquiring and installing gravel or geotextile with gravel and cast in place concrete on channel bottom and approaches. Final travel surface shall be the rocks above normal high-water mark and concrete below the normal high-water mark. If a different travel surface is needed, refer to another appropriate standard for the surfacing. Typical stream used for cost estimate has 30 linear feet of concrete (bottom width and approaches) with 10 foot gravel approaches on either side above the normal high-water mark. Width is 14 feet for a total area as 420sf. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

Before Situation:

An unimproved stream crossing has rill and gully erosion causing excessive sediments and excess nutrient potential. Erosion is made worse by vehicle traffic through the stream or rutting has progressed to the point that access to the field on the other side is no longer possible. Stream flow/velocity during storm events is such that culverts or a less ridged ford type crossing is not anticipated to last its design life. Access is difficult to the field across the stream and water quality is negatively impacted.

After Situation:

Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

Feature Measure: Crossing dimensions

Scenario Unit:: Square Foot

Scenario Typical Size: 420.0

Scenario Total Cost: $5,547.20

Scenario Cost/Unit: $13.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	18	$4,231.62
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	2	$195.50
Excavation, common earth, wet, side cast, large equipment	1228	Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$4.33	50	$216.50
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	2	$51.36
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	$30.09	5	$150.45
Geotextile, non-woven, heavy weight	1210	Non-woven greater than 8 ounce/square yard geotextile with staple anchoring. Materials and shipping only.	Square Yard	$4.41	32	$141.12
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 580 - Streambank and Shoreline Protection

Scenario #3 - Structural, Standard

Scenario Description:

Protection of streambanks using structural measures such as riprap, concrete block, piling revetments, with wire or geotextile fencing; with slotted fencing; jacks or jack fields, etc. to stabilize and protect banks of streams or excavated channels against scour and erosion. The purpose of this practice is to maintain, improve, or restore physical, chemical, and biological functions of a stream to provide diverse aquatic communities to improve habitat for desired aquatic species. Payment cost include shaping bank, critical area vegetation, geotextile, and rock rip rap; a 8-foot high bank at 3(H):1(V) slope for 1000 linear feet (0.46 acres) is used for estimation purposes. The rock toe will be 3' thick and 5' high and have a bed key 3 ft deep and extending 6 ft out. The bank above the riprap will be graded to a stable slope and revegetated. Resource Concerns: Soil Erosion - Excessive Bank Erosion from Streams, Shoreline and Water Conveyance Channels; Water Quality Degradation - Excessive Sediment in Surface Waters; Water Quality Degradation - Elevated Water Temperature; Excess/Insufficient Water - Excessive Sediment in Surface Waters; Inadequate Habitat for Fish and Wildlife- Habitat Degradation. Associated Practices include: 560 - Access Road; 342 - Critical Area Planting; 382 - Fence; 391 - Riparian Forest Buffer; 390 - Riparian Herbaceous Cover; 395 - Stream Habitat Improvement and Management; 614 - Watering Facility; 484-Mulching; and 570-Stormwater Runoff Control

Before Situation:

A stream bisects the agricultural property and has had all of the woody vegetation removed due to overgrazing or human manipulation; the stream has severely degraded streambanks that are unstable and show signs of active erosion. Soil Erosion: The streambank is unstable. Water Quality Degradation: The sediment load has increased in the stream resulting in elevated water temperatures. Excess/Insufficient Water: The excessive sediment load has reduced the water conveyance capacity, storage capacity and flow within the stream. Inadequate Habitat for Fish and Wildlife: The deficiencies in the stream's habitat limit survival, growth, reproduction, and/or diversity of aquatic organisms within the stream.

After Situation:

The streambank is stable against further erosion and encourages natural sediment transport and deposition. Loss of riparian areas and sediment load is reduced in the stream. For Soil Erosion: The streambank is stable. For Water Quality Degradation: The sediment load has decreased in the stream resulting in improved aquatic habitat. For Excess/Insufficient Water: The water conveyance capacity, storage capacity and flow within the stream has been stabilized. For Inadequate Habitat for Fish and Wildlife: The reduction in the sediment load promotes survival, growth, reproduction, and/or diversity of aquatic organisms within the stream's habitat.

Feature Measure: Linear Feet of Streambank/Shoreli

Scenario Unit:: Foot

Scenario Typical Size: 1,000.0

Scenario Total Cost: $214,897.59

Scenario Cost/Unit: $214.90

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	3167	$12,414.64
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$66.84	16	$1,069.44
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	0.46	$7.72
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	0.46	$3.08
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$10.75	0.46	$4.95
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	$12.74	0.12	$1.53
Excavation, common earth, wet, side cast, large equipment	1228	Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$4.33	3167	$13,713.11
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	320	$6,080.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	16	$347.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	80	$2,894.40
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	2333	$177,424.65
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	0.46	$17.44
Mobilization						

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	1	$490.01

Practice: 580 - Streambank and Shoreline Protection

Scenario #4 - Structural, Site Specific

Scenario Description:

Protection of actively eroding streambanks using structural measures such as riprap, concrete block, gabions, etc. to stabilize and protect banks of streams or excavated channels against scour and erosion. Depending on site conditions, protection is extended from the streambank toe to 80% of the top bank height, or all the way to the top bank if overland flow or field runoff creates a need for such protection. The purpose of this practice is to maintain, improve, or restore physical, chemical, and biological functions of a stream to provide diverse aquatic communities to improve habitat for desired aquatic species. Payment cost include shaping bank, critical area vegetation, geotextile, and rock rip rap; a 15-foot high bank at 2(H):1(V) slope for 125 linear feet is used for estimation purposes. The rock will be keyed in 2' below the streambed at the toe. The rock will extend 80% of the slope distance up the bank, or 12 feet high. The bank above the riprap will be graded to a stable slope and revegetated. Resource Concerns: Soil Erosion - Excessive Bank Erosion from Streams, Shoreline and Water Conveyance Channels; Water Quality Degradation - Excessive Sediment in Surface Waters; Water Quality Degradation - Elevated Water Temperature; Excess/Insufficient Water - Excessive Sediment in Surface Waters; Inadequate Habitat for Fish and Wildlife- Habitat Degradation. Associated Practices include: 560 - Access Road; 342 - Critical Area Planting; 382 - Fence; 391 - Riparian Forest Buffer; 390 - Riparian Herbaceous Cover; 395 - Stream Habitat Improvement and Management; 614 - Watering Facility; 484-Mulching; and 570-Stormwater Runoff Control

Before Situation:

A stream bisects the agricultural property and has had all of the woody vegetation removed due to overgrazing or human manipulation; the stream has severely degraded streambanks that are unstable and show signs of active erosion. Soil Erosion: The streambank is unstable. Water Quality Degradation: The sediment load has increased in the stream resulting in elevated water temperatures. Excess/Insufficient Water: The excessive sediment load has reduced the water conveyance capacity, storage capacity and flow within the stream. Inadequate Habitat for Fish and Wildlife: The deficiencies in the stream's habitat limit survival, growth, reproduction, and/or diversity of aquatic organisms within the stream.

After Situation:

The streambank is stable against further erosion and encourages natural sediment transport and deposition. Loss of riparian areas and sediment load is reduced in the stream. For Soil Erosion: The streambank is stable. For Water Quality Degradation: The sediment load has decreased in the stream resulting in improved aquatic habitat. For Excess/Insufficient Water: The water conveyance capacity, storage capacity and flow within the stream has been stabilized. For Inadequate Habitat for Fish and Wildlife: The reduction in the sediment load promotes survival, growth, reproduction, and/or diversity of aquatic organisms within the stream's habitat.

Feature Measure: Cubic Yards of riprap

Scenario Unit:: Cubic Yard

Scenario Typical Size: 306.0

Scenario Total Cost: $43,797.84

Scenario Cost/Unit: $143.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	890	$3,488.80
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$66.84	16	$1,069.44
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	16	$1,839.36
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	0.46	$7.72
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	0.46	$3.08
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$10.75	0.46	$4.95
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	$12.74	0.08	$1.02
Excavation, common earth, wet, side cast, large equipment	1228	Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$4.33	890	$3,853.70
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	320	$6,080.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	16	$347.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	80	$2,894.40
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	306	$23,271.30

One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	0.46	$17.44
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	1	$490.01

Practice: 580 - Streambank and Shoreline Protection

Scenario #5 - Vegetative with Willow Staking

Scenario Description:

Protection of streambanks consisting of conventional plantings of vegetation to stabilize and protect against scour and erosion. The purpose of this practice is to maintain, improve, or restore physical, chemical, and biological functions of a stream to provide diverse aquatic communities to improve habitat for desired aquatic species. Payment cost include shaping bank, staking of willow cuttings, critical area vegetation, and erosion control fabric; a 6-foot high bank at 3(H):1(V) slope for 1000 linear feet (0.46 acres) where the lower 3 feet are staked with willows is used for estimation purposes. Resource Concerns: Soil Erosion - Excessive Bank Erosion from Streams, Shoreline and Water Conveyance Channels; Water Quality Degradation - Excessive Sediment in Surface Waters; Water Quality Degradation - Elevated Water Temperature; Excess/Insufficient Water - Excessive Sediment in Surface Waters; Inadequate Habitat for Fish and Wildlife- Habitat Degradation. Associated Practices include: 560 - Access Road; 342 - Critical Area Planting; 382 - Fence; 391 - Riparian Forest Buffer; 390 - Riparian Herbaceous Cover; 395 - Stream Habitat Improvement and Management; 614 - Watering Facility; 484-Mulching; and 570-Stormwater Runoff Control

Before Situation:

A stream bisects the agricultural property and has had all of the woody vegetation removed due to overgrazing or human manipulation; the stream has marginally degraded streambanks that are unstable with little hydraulic roughness near the toe and show signs of active erosion. Soil Erosion: The streambank is unstable. Water Quality Degradation: The sediment load has increased in the stream resulting in elevated water temperatures. Excess/Insufficient Water: The excessive sediment load has reduced the water conveyance capacity, storage capacity and flow within the stream. Inadequate Habitat for Fish and Wildlife: The deficiencies in the stream's habitat limit survival, growth, reproduction, and/or diversity of aquatic organisms within the stream.

After Situation:

The streambank is stabilized against further erosion by the roots of planted willows and encourages natural sediment transport and deposition. The stream bank's toe is further stabilized by the addition of hydraulic roughness, via growing brushy vegetation, at the toe of the slope. Loss of riparian areas and sediment load is reduced in the stream. For Soil Erosion: The streambank is stable. For Water Quality Degradation: The sediment load has decreased in the stream resulting in improved aquatic habitat. For Excess/Insufficient Water: The water conveyance capacity, storage capacity and flow within the stream has been stabilized. For Inadequate Habitat for Fish and Wildlife: The reduction in the sediment load promotes survival, growth, reproduction, and/or diversity of aquatic organisms within the stream's habitat.

Feature Measure: Linear Feet of Streambank/Shoreli

Scenario Unit:: Foot

Scenario Typical Size: 1,000.0

Scenario Total Cost: $19,918.84

Scenario Cost/Unit: $19.92

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$66.84	16	$1,069.44
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	0.46	$7.72
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	0.46	$3.08
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$10.75	0.46	$4.95
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	$12.74	0.46	$5.86
Excavation, common earth, wet, side cast, large equipment	1228	Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$4.33	2500	$10,825.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	234	$4,446.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	16	$347.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	56	$2,026.08
Materials						
Cuttings, woody, medium size	1308	Woody cuttings, live stakes or whips typically 1/4" to 1" diameter and 24" to 48" long. Includes materials and shipping only.	Each	$0.48	1000	$480.00
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	0.46	$17.44
Mobilization						

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

USDA - Natural Resources Conservation Service

Mississippi

Practice: 580 - Streambank and Shoreline Protection

Scenario #7 - Longitudinal Peak Stone Toe, 4 foot high or less

Scenario Description:

Protection of streambanks using Longitudinal Peak Stone Toe protection (LPST) having a height of 4' or less. Use "Structural" where additional structural measures such as tree revetments; log, rootwad and boulder revetments; dormant post plantings; piling revetments with wire or geotextile fencing; piling revetments with slotted fencing; jacks or jack fields; rock riprap; stream jetties; stream barbs; and gabions are used. The purpose of this practice is to maintain, improve, or restore physical, chemical, and biological functions of a stream to provide diverse aquatic communities to improve habitat for desired aquatic species. The typical scenario involves the stabilization of 1,000 linear feet of a stream bank having 12 foot high near vertical banks. Estimated cost is based on the installation of LPST, as described in NEH 654, TS14K-13, having a height of 3 ft, 1.5:1 front slope and 1.5:1 back slope. The area between the sloped bank and LPST is a 19 foot wide bench planted with shrub type vegetation (willow stakes). Material used to make the bench are taken from excavated material taken to achieve the 3(H):1(V) slope. The bank above the riprap will be graded to a stable slope and revegetated in accordance with Critical Area Planting (382). Resource Concerns: Soil Erosion - Excessive Bank Erosion from Streams, Shoreline and Water Conveyance Channels; Water Quality Degradation - Excessive Sediment in Surface Waters; Water Quality Degradation - Elevated Water Temperature; Excess/Insufficient Water - Excessive Sediment in Surface Waters; Inadequate Habitat for Fish and Wildlife- Habitat Degradation. Associated Practices include: 560 - Access Road; 342 - Critical Area Planting; 382 - Fence; 391 - Riparian Forest Buffer; 390 - Riparian Herbaceous Cover; 395 - Stream Habitat Improvement and Management; 614 - Watering Facility; 484-Mulching; and 570-Stormwater Runoff Control

Before Situation:

A stream bisects the agricultural property and has had all of the woody vegetation removed due to overgrazing or human manipulation; the stream has severely degraded streambanks that are unstable and show signs of active erosion. Soil Erosion: The streambank is unstable. Water Quality Degradation: The sediment load has increased in the stream resulting in elevated water temperatures. Excess/Insufficient Water: The excessive sediment load has reduced the water conveyance capacity, storage capacity and flow within the stream. Inadequate Habitat for Fish and Wildlife: The deficiencies in the stream's habitat limit survival, growth, reproduction, and/or diversity of aquatic organisms within the stream.

After Situation:

The streambank is stable against further erosion and encourages natural sediment transport and deposition. Loss of riparian areas and sediment load is reduced in the stream. For Soil Erosion: The streambank is stable. For Water Quality Degradation: The sediment load has decreased in the stream resulting in improved aquatic habitat. For Excess/Insufficient Water: The water conveyance capacity, storage capacity and flow within the stream has been stabilized. For Inadequate Habitat for Fish and Wildlife: The reduction in the sediment load promotes survival, growth, reproduction, and/or diversity of aquatic organisms within the stream's habitat.

Feature Measure: Linear Feet of Streambank/Shoreli

Scenario Unit:: Foot

Scenario Typical Size: 1,000.0

Scenario Total Cost: $80,816.99

Scenario Cost/Unit: $80.82

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	2100	$8,232.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	186	$21,382.56
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	0.06	$1.01
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	0.06	$0.40
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$10.75	0.06	$0.65
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	$12.74	0.06	$0.76
Hauling, bulk, highway truck	1615	Hauling of bulk earthfill, rockfill, waste or debris. One-way travel distance using fully loaded highway dump trucks (typically 16 CY or 20 TN capacity). Includes equipment and labor for truck only. Does not include cost for loading truck.	Cubic Yard Mile	$0.33	40500	$13,365.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	320	$6,080.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	44	$1,591.92
Materials						
Rock Riprap, graded, angular, material and shipping	1200	Graded Rock Riprap for all gradation ranges. Includes materials and delivery only.	Ton	$34.84	810	$28,220.40
Cuttings, woody, medium size	1308	Woody cuttings, live stakes or whips typically 1/4" to 1" diameter and 24" to 48" long. Includes materials and shipping only.	Each	$0.48	2000	$960.00

One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	0.06	$2.28
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 580 - Streambank and Shoreline Protection

Scenario #8 - Longitudinal Peak Stone Toe, higher than 4 feet

Scenario Description:

Protection of streambanks using Longitudinal Peak Stone Toe protection (LPST) having a height of 4.5' or more. Use "Structural" where additional structural measures such as tree revetments; log, rootwad and boulder revetments; dormant post plantings; piling revetments with wire or geotextile fencing; piling revetments with slotted fencing; jacks or jack fields; rock riprap; stream jetties; stream barbs; and gabions are used. The purpose of this practice is to maintain, improve, or restore physical, chemical, and biological functions of a stream to provide diverse aquatic communities to improve habitat for desired aquatic species. The typical scenario involves the stabilization of 1,000 linear feet of a stream bank having 12 foot high near vertical banks. Estimated cost is based on the installation of LPST, as described in NEH 654, TS14K-13, having a height of 6 ft, 1.5:1 front slope and 1.5:1 back slope. The area between the sloped bank and LPST is a 19 foot wide bench planted with shrub type vegetation (willow stakes). Material used to make the bench are taken from excavated material taken to achieve the 3(H):1(V) slope. The bank above the riprap will be graded to a stable slope and revegetated in accordance with Critical Area Planting (382). Resource Concerns: Soil Erosion - Excessive Bank Erosion from Streams, Shoreline and Water Conveyance Channels; Water Quality Degradation - Excessive Sediment in Surface Waters; Water Quality Degradation - Elevated Water Temperature; Excess/Insufficient Water - Excessive Sediment in Surface Waters; Inadequate Habitat for Fish and Wildlife- Habitat Degradation. Associated Practices include: 560 - Access Road; 342 - Critical Area Planting; 382 - Fence; 391 - Riparian Forest Buffer; 390 - Riparian Herbaceous Cover; 395 - Stream Habitat Improvement and Management; 614 - Watering Facility; 484-Mulching; and 570-Stormwater Runoff Control

Before Situation:

A stream bisects the agricultural property and has had all of the woody vegetation removed due to overgrazing or human manipulation; the stream has severely degraded streambanks that are unstable and show signs of active erosion. Soil Erosion: The streambank is unstable. Water Quality Degradation: The sediment load has increased in the stream resulting in elevated water temperatures. Excess/Insufficient Water: The excessive sediment load has reduced the water conveyance capacity, storage capacity and flow within the stream. Inadequate Habitat for Fish and Wildlife: The deficiencies in the stream's habitat limit survival, growth, reproduction, and/or diversity of aquatic organisms within the stream.

After Situation:

The streambank is stable against further erosion and encourages natural sediment transport and deposition. Loss of riparian areas and sediment load is reduced in the stream. For Soil Erosion: The streambank is stable. For Water Quality Degradation: The sediment load has decreased in the stream resulting in improved aquatic habitat. For Excess/Insufficient Water: The water conveyance capacity, storage capacity and flow within the stream has been stabilized. For Inadequate Habitat for Fish and Wildlife: The reduction in the sediment load promotes survival, growth, reproduction, and/or diversity of aquatic organisms within the stream's habitat.

Feature Measure: Linear Feet of Streambank/Shoreli

Scenario Unit:: Foot

Scenario Typical Size: 1,000.0

Scenario Total Cost: $232,858.05

Scenario Cost/Unit: $232.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	2100	$8,232.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	310	$35,637.60
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	0.06	$1.01
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	0.06	$0.40
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$10.75	0.06	$0.65
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	$12.74	0.06	$0.76
Hauling, bulk, highway truck	1615	Hauling of bulk earthfill, rockfill, waste or debris. One-way travel distance using fully loaded highway dump trucks (typically 16 CY or 20 TN capacity). Includes equipment and labor for truck only. Does not include cost for loading truck.	Cubic Yard Mile	$0.33	186900	$61,677.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	480	$9,120.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	93	$3,364.74
Materials						
Rock Riprap, graded, angular, material and shipping	1200	Graded Rock Riprap for all gradation ranges. Includes materials and delivery only.	Ton	$34.84	3240	$112,881.60
Cuttings, woody, medium size	1308	Woody cuttings, live stakes or whips typically 1/4" to 1" diameter and 24" to 48" long. Includes materials and shipping only.	Each	$0.48	2000	$960.00

One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	0.06	$2.28
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 587 - Structure for Water Control

Scenario #1 - Inlet Flashboard Riser, Metal

Scenario Description:

A Flashboard Riser fabricated of metal and used in a water management system that maintains a desired water surface elevation, controls the direction or rate of flow, or conveys water to address the resource concerns: Inadequate Water - Inefficient use of Irrigation Water and Inadequate habitat for Fish and Wildlife. The water surface elevation is controlled by addition or removal of slats or "stoplogs". This scenario is applicable to variable crest weir structures where the elevation is controlled at the inlet (Half-Rounds). They are often fabricated from half pipes (i.e. half-rounds) or sheet steel in a box shape. Payment rate is based upon the Flashboard Weir Length in inches multiplied by the outlet length in feet (Inch-Foot). Cost estimate is based on a "Half-Round" flashboard riser shop fabricated using a longitudinal cut 36" smooth steel pipe, a 50' long - 30" outlet pipe passing through an embankment.

Before Situation:

The operator presently flood irrigates his field and has no means to accurately maintain a constant water level at varying elevations resulting in a lack of flexibility, and inefficient use of water and energy during pumping. The operator also desires to maintain a permanent pool for water fowl during the winter.

After Situation:

The operator has the capability to more efficiently control and maintain a range of water surface elevations thereby reducing the flow rate needed. Less water is wasted and both water and energy is conserved. The operator is now able to maintain adequate water during the winter as a benefit to waterfowl. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Irrigation Water Management (449), Irrigation Land Leveling (464), Irrigation Canal or Lateral (320), Irrigation System, Tailwater Recovery (447), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

Feature Measure: Flashboard Weir Length (in) x barre

Scenario Unit:: Diameter Inch Foot

Scenario Typical Size: 1,800.0

Scenario Total Cost: $6,117.66

Scenario Cost/Unit: $3.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	190	$744.80
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	$5.17	10	$51.70
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	$63.41	2	$126.82
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	5	$136.90
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	6	$114.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	2	$51.36
Materials						
Pipe, Steel, 30", Std Wt, USED	1361	Materials: - USED - 30" - Steel Std Wt	Foot	$76.17	50	$3,808.50
Pipe, Steel, 36", Std Wt, USED	1362	Materials: - USED - 36" - Steel Std Wt	Foot	$97.25	6	$583.50
Steel, Angle, 2 1/2" x 2 1/2" x 1/4"	1372	Materials: Angle, 2 1/2" x 2 1/2" x 1/4", Meets ASTM A36	Foot	$3.30	24	$79.20
Steel, Plate, 3/8"	1375	Flat steel plate, 3/8" thickness. Materials only.	Square Foot	$11.02	4	$44.08
Lumber, planks, posts and timbers, treated	1609	Treated dimension lumber with nominal thickness greater than 2". Includes lumber and fasteners. Does not include labor.	Board Foot	$1.54	32	$49.28
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 587 - Structure for Water Control

Scenario #2 - Inline Flashboard Riser, Metal

Scenario Description:

A Flashboard Riser fabricated of metal and used in a water management system that maintains a desired water surface elevation, controls the direction or rate of flow, or conveys water to address the resource concerns: Inadequate Water - Inefficient use of Irrigation Water and Inadequate habitat for Fish and Wildlife. The water surface elevation is controlled by addition or removal of slats or "stoplogs". This scenario is applicable to variable crest weir structures where the elevation is controlled at the embankment. They are often fabricated from vertical pipes with the stoplogs are located in the middle (i.e. Full-Rounds) or sheet steel in a box shape. Payment rate is based upon the Flashboard Weir Length in inches multiplied by the outlet length in feet (Inch-Foot). Cost estimate is based on a "Half-Round" flashboard riser shop fabricated using a longitudinal cut 36" smooth steel pipe, a 50' long - 30" outlet pipe passing through an embankment.

Before Situation:

The operator presently flood irrigates his field and has no means to accurately maintain a constant water level at varying elevations resulting in a lack of flexibility, and inefficient use of water and energy during pumping. The operator also desires to maintain a permanent pool for water fowl during the winter.

After Situation:

The operator has the capability to more efficiently control and maintain a range of water surface elevations thereby reducing the flow rate needed. Less water is wasted and both water and energy is conserved. The operator is now able to maintain adequate water during the winter as a benefit to waterfowl. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Irrigation Water Management (449), Irrigation Land Leveling (464), Irrigation Canal or Lateral (320), Irrigation System, Tailwater Recovery (447), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

Feature Measure: Flashboard Weir Length (in) x Barre

Scenario Unit:: Diameter Inch Foot

Scenario Typical Size: 1,800.0

Scenario Total Cost: $6,475.45

Scenario Cost/Unit: $3.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	190	$744.80
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	$5.17	15	$77.55
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	$63.41	4	$253.64
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	7	$191.66
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	10	$190.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	4	$102.72
Materials						
Pipe, Steel, 30", Std Wt, USED	1361	Materials: - USED - 30" - Steel Std Wt	Foot	$76.17	50	$3,808.50
Pipe, Steel, 36", Std Wt, USED	1362	Materials: - USED - 36" - Steel Std Wt	Foot	$97.25	6	$583.50
Steel, Angle, 2 1/2" x 2 1/2" x 1/4"	1372	Materials: Angle, 2 1/2" x 2 1/2" x 1/4", Meets ASTM A36	Foot	$3.30	24	$79.20
Steel, Plate, 3/8"	1375	Flat steel plate, 3/8" thickness. Materials only.	Square Foot	$11.02	10	$110.20
Lumber, planks, posts and timbers, treated	1609	Treated dimension lumber with nominal thickness greater than 2". Includes lumber and fasteners. Does not include labor.	Board Foot	$1.54	4	$6.16
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 587 - Structure for Water Control

Scenario #7 - Slide Gate

Scenario Description:

This scenario is the installation of a permanent slide gate structure to control the conveyance of water. The typical size is a 4' diameter opening. The slide gate may be installed on an open channel or pipeline. The slide gate is made of steel and has a hand operated mechanical lifting system, i.e. screw. This scenario assists in addressing the resource concerns: water management. Conservation practices that may be associated are: 533-Pumping Plant.

Before Situation:

A channel or pipeline is in need of a head gate to control the flow of water.

After Situation:

A 4' slide gate is installed and operated by hand is installed.

Feature Measure: diameter

Scenario Unit:: Foot

Scenario Typical Size: 4.0

Scenario Total Cost: $8,086.86

Scenario Cost/Unit: $2,021.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	6	$339.90
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	12	$328.56
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	12	$228.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	6	$154.08
Materials						
Screw gate, cast iron, 4' diameter, 10/0 head	1746	4' diameter cast iron screw (canal) gate rated at 10 seating head 0 feet unseating head. Includes materials only.	Each	$6,779.67	1	$6,779.67
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 587 - Structure for Water Control

Scenario #8 - Flap Gate

Scenario Description:

This scenario is the installation of a permanent flap (tide) gate structure to control the direction of flow resulting from tides or high water or back-flow from flooding. The typical size is a 4' diameter opening. The gate may be installed on an open channel or pipeline. It is made of steel and operates automatically. This scenario assists in addressing the resource concerns: water management. Conservation practices that may be associated are:

Before Situation:

A wetland or other area is in need of a flap gate to control the direction of the water.

After Situation:

A flap gate 4' wide is installed.

Feature Measure: Feet Diameter (of Gate)

Scenario Unit:: Foot

Scenario Typical Size: 4.0

Scenario Total Cost: $6,976.77

Scenario Cost/Unit: $1,744.19

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	6	$339.90
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	12	$328.56
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	12	$228.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	6	$154.08
Materials						
Flap Gate, cast iron, 4' diameter	1745	4' diameter cast iron flap gate. Materials only.	Each	$5,669.58	1	$5,669.58
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 587 - Structure for Water Control

Scenario #15 - Fabricated Metal Water Control Structure

Scenario Description:

A Water Control Structure fabricated of metal and used in a water management system that maintains a desired water surface elevation, controls the direction or rate of flow, or conveys water to address the resource concerns: Inadequate Water - Inefficient use of Irrigation Water and Inadequate habitat for Fish and Wildlife. This scenario is applicable to large fabricated structures used locally or not covered by other scenarios for the control of water surface elevation. The Cost estimate is based on a structure fabricated from a used Tank Car, having a diameter of 9 ft and length of 60 ft (9ft x 60ft = 540 Square Feet). The top half of the tank car is cut away 7 ft from one end, and a steel endplate is welded onto the cut end to form a three sided weir (7ft deep x 9ft wide). A 24 inch steel pipe having a screw valve, accessible topside, is welded through the plate allowing drawdown or further water surface elevation control. The structure passes through an embankment and regulates flow between the two sides. Payment rate is based upon the steel structure's plan view dimensions (Length x Width) in Square Feet (SF).

Before Situation:

Fields are irrigate but excess irrigation water runs off into ditches and streams due to inefficiencies in irrigation. The excess water is carrying sediment and nutrients with it which are flowing into to the basins and causing water quality issues throughout the watershed.

After Situation:

Excess irrigation water is captured and able to be stored at a consistent level to allow for adequate pumping in order to relift the excess water back into the system either directly to the field or to a surface storage reservoir. The water control structure allows the excess water to be stored so that it is not running down the basin and so excess nutrients or sediments have a chance to settle out of the water. Less water is wasted and both water and energy is conserved. The operator is now able to maintain adequate water during the winter as a benefit to waterfowl. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Irrigation Water Management (449), Irrigation Land Leveling (464), Irrigation Canal or Lateral (320), Irrigation System, Tailwater Recovery (447), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

Feature Measure: Structure Length (ft) x Structure Wi

Scenario Unit:: Square Foot

Scenario Typical Size: 540.0

Scenario Total Cost: $18,205.70

Scenario Cost/Unit: $33.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$365.63	4	$1,462.52
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	$3.92	304	$1,191.68
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	$5.17	15	$77.55
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	16	$1,839.36
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	20	$547.60
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	40	$760.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	16	$410.88
Materials						
Pipe, Steel, 24", Std Wt, USED	1360	Materials: - USED - 24" - Steel Std Wt	Foot	$48.46	20	$969.20
Steel, Angle, 2 1/2" x 2 1/2" x 1/4"	1372	Materials: Angle, 2 1/2" x 2 1/2" x 1/4", Meets ASTM A36	Foot	$3.30	8	$26.40
Steel, Plate, 3/8"	1375	Flat steel plate, 3/8" thickness. Materials only.	Square Foot	$11.02	40.5	$446.31
Steel Tank Car	1826	Materials: - USED Rail Road Tank Car	Each	$9,219.05	1	$9,219.05
Slide gate, steel, 2' diameter, low head	1829	2' diameter steel slide gate for low head installations	Each	$418.00	1	$418.00
Welded Bar Grate, metal	1980	Heavy duty vertical bar welded grating, typically 1-1/4"x 3/16" bars on 1" spacing with cross rod on 4" spacing. Materials only.	Square Foot	$12.90	45	$580.50
Mobilization						

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 587 - Structure for Water Control

Scenario #16 - Flow Meter with Mechanical Index

Scenario Description:

Installed water flow meter with mechanical, cumulative volume and rate index. Meters can be any flow measurement device that meets CPS 433, (i.e. meters: turbine, propeller, acoustic, magnetic, venturi, orifice, etc.) with or without straightening vanes. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, and Degraded Plant Condition - Undesirable plant productivity and health, and Inefficient Energy Use - Equipment and facilities Associated Practices: 533-Pumping Plant, 449-Irrigation Water Management, 441-Irrigation System, Microirrigation, 443-Irrigation System Surface and Subsurface, 442-Irrigation System, Sprinkler, 328-Conservation Crop Rotation, 634-Waste Transfer, and 590-Nutrient Management.

Before Situation:

Producer estimates seasonal and individual irrigation application flow rate and volumes based on energy costs, system operating pressure, or other means.

After Situation:

Producer is able to access instantaneous rate and cumulative flow volume data at the meter location. The information gained will enable the irrigator to improve irrigation water management, recognize system performance issues before they become critical, and reduce energy use.

Feature Measure: Nominal Diameter of Meter

Scenario Unit:: Inch

Scenario Typical Size: 10.0

Scenario Total Cost: $2,043.98

Scenario Cost/Unit: $204.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Flow Meter, with mechanical Index	1450	10 inch, Turbine Type Flow Meter with Mechanical Index, permanently installed. Includes material, labor and installation.	Each	$1,902.24	1	$1,902.24
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	2	$141.74

Practice: 587 - Structure for Water Control

Scenario #17 - Flow Meter with Electronic Index

Scenario Description:

Installed water flow meter with an electronic index . Meters can be any flow measurement device that meets CPS 433, (i.e., meters: turbine, propeller, acoustic, magnetic, venturi, orifice, etc.) with or without straightening vanes or data logging capability. Meter nominal diameter for insert type turbine meters will be installation pipe size. Typical installation would include installation of a 10 inch turbine flow meter, with electronic index output. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, and Degraded Plant Condition - Undesirable plant productivity and health, and Inefficient Energy Use - Equipment and facilities Associated Practices: 533-Pumping Plant, 449-Irrigation Water Management, 441-Irrigation System, Microirrigation, 443-Irrigation System Surface and Subsurface, 442-Irrigation System, Sprinkler, 328-Conservation Crop Rotation, 634-Waster Transfer, and 590-Nutrient Management.

Before Situation:

Producer estimates seasonal and individual irrigation application flow rate and volumes based on energy costs, system operating pressure, or other means.

After Situation:

Producer is able to access instantaneous rate and cumulative flow volume data at the meter location. The information gained will enable the irrigator to improve irrigation water management, recognize system performance issues before they become critical, and reduce energy use.

Feature Measure: Nominal Diameter of Meter

Scenario Unit:: Inch

Scenario Typical Size: 10.0

Scenario Total Cost: $3,889.11

Scenario Cost/Unit: $388.91

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Flow Meter, with Electronic Index	1452	10 inch Turbine Irrigation flow meter, with Electronic Index, Rate and Volume, permanently installed. Materials only.	Each	$3,747.37	1	$3,747.37
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	2	$141.74

Practice: 587 - Structure for Water Control

Scenario #18 - Flow Meter with Electronic Index & Telemetry

Scenario Description:

Installed water flow meter with an electronic flow rate and volume index and data telemetry transmission system. Meters can be any flow measurement device that meets CPS 433, (i.e. meters: turbine, propeller, acoustic, magnetic, venturi, orifice, etc.) with or without straightening vanes. Meter nominal diameter for insert type turbine meters will be installation pipe size. Typical installation would include installation of a 10 inch magnetic flow meter, with electronic index output and telemetry data transfer system for monitoring irrigation system flow rate. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, and Degraded Plant Condition - Undesirable plant productivity and health, and Inefficient Energy Use - Equipment and facilities Associated Practices: 533-Pumping Plant, 449-Irrigation Water Management, 441-Irrigation System, Microirrigation, 443-Irrigation System Surface and Subsurface, 442-Irrigation System, Sprinkler, 328-Conservation Crop Rotation, 634-Waste Transfer, and 590-Nutrient Management.

Before Situation:

Producer estimates seasonal and individual irrigation application flow rate and volumes based on energy costs, system operating pressure, or other means.

After Situation:

Producer is able to access instantaneous rate and cumulative flow volume data from a personal computer or cell phone at any time. The information gained will enable the irrigator to improve irrigation water management, recognize system performance issues before they become critical, and reduce energy use.

Feature Measure: Nominal Diameter of Meter

Scenario Unit:: Inch

Scenario Typical Size: 10.0

Scenario Total Cost: $5,402.48

Scenario Cost/Unit: $540.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Flow Meter, with electronic Index and telemetry	1451	10 inch Magnetic Irrigation Flow Meter, with electronic index and equipped for telemetry, permanently installed. Includes material, meter appurtenances, and installation.	Each	$5,260.74	1	$5,260.74
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	2	$141.74

Practice: 590 - Nutrient Management

Scenario #278 - Basic NM (Non-Organic/Organic)

Scenario Description:

This scenario describes the implementation of a basic nutrient management system on > = 40 acres of cropland or hayland where there is no manure application. Scenario is applicable on non-organic and organic land. The planned NM system will meet the current Nutrient Management (590) CPS. Implementation will result in the proper rate, source, method of placement, and timing of nutrient application. Payment for implementation is to defray the costs of soil testing, analysis, and implementation of the nutrient management plan and recordkeeping. Records demonstrating implementation of the 4 R's of NM will be required.

Before Situation:

In this geographic area, a fertility program is either nonexistent or does not meet the Nutrient Management (590) CPS. Soil testing is not completed on a regular basis and applications of fertilizers are not based on land grant university recommendations or a nutrient budget. An environmental evaluation or risk assessment is not completed. Nutrients are transported to surface waters through runoff, drainage tile, or soil erosion, or to ground water from leaching in quantities that degrade water quality and limit use of intended purposes. Soil quality may be degraded by excess or inadequate nutrients. Fields have little or no erosion protection during critical periods often times resulting in sheet, rill, and ephemeral erosion.

After Situation:

A nutrient management system will be developed to meet the current Nutrient Management (590) CPS, when applicable system will also meet NOP regulations. Development and implementation of a nutrient management plan (NMP) will benefit plant productivity while also reducing potential for off-site degradation. A nutrient management budget will be developed for each field(s) based on soil test analysis and land grant university recommendations or crop removal rates. On planning units typically 40 acres or larger, soil testing is completed according to LGU recommendations. Records will be provided annually of the current soil test, analysis, application rates, forms and rates of nutrients for each field, including crop yields. Nutrient applications will be completed according to the Nutrient Management Plan that minimizes nutrient runoff and leaching or buildup of excess nutrient concentrations.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $286.80

Scenario Cost/Unit: $7.17

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	1	$22.02
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	4	$76.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	2	$20.42

Practice: 590 - Nutrient Management

Scenario #280 - Small Farm NM (Non-Organic/Organic)

Scenario Description:

Scenario is applicable on non-organic and organic land. Scenario implementation of a basic nutrient management system on small, often diversified farm systems typically between 0.5-10 acres where manure and/or compost may be utilized either alone or in conjunction with commercial fertilizer. The planned NM system will meet the current Nutrient Management (590) CPS. Implementation will result in the proper rate, source, method of placement, and timing of nutrient application. Payment for implementation is to defray the costs of soil testing, manure and/or compost analysis, and implementation of the nutrient management plan and recordkeeping. Records demonstrating implementation of the 4 R's of NM will be required. Scenario is designed to encourage producers to effectively utilize commercial fertilizers, organic fertilizers, manure, and/or compost appropriately improving soil quality and minimizing runoff of nutrients from fields to surface waters. The basis for nutrient applications will be recommendations based on soil, manure, and compost analyses.

Before Situation:

In this geographic area, a fertility program is either nonexistent or does not meet the Nutrient Management (590). Soil testing is not completed on a regular basis and applications of fertilizers are not based on land grant university recommendations or a nutrient budget. An environmental evaluation or risk assessment is not completed. Nutrients are transported to surface waters through runoff, drainage tile, or soil erosion, or to ground water from leaching in quantities that degrade water quality and limit use of intended purposes. Soil quality may be degraded by excess or inadequate nutrients. Fields have little or no erosion protection during critical periods often times resulting in sheet, rill, and ephemeral erosion.

After Situation:

A nutrient management system will be developed to meet the current Nutrient Management (590), when applicable system will also meet NOP regulations. Development and implementation of a nutrient management plan (NMP) will benefit plant productivity while also reducing potential for off-site degradation. A nutrient management budget will be developed for each field, crop block, or crop rotation within a block/field based on soil test analysis and land grant university recommendations or crop removal rates. Application of nutrients will be completed at the proper rate, timing, and methods, and sources per the NMP. Records will be provided annually of current soil test, analysis, application timing, nutrient source, application method, application rate, and crop yields for each block. Nutrient applications will be completed according to the NMP that minimizes nutrient runoff and leaching or buildup of excess nutrient concentrations.

Feature Measure: <Unknown>

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $257.14

Scenario Cost/Unit: $257.14

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	3	$57.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	1	$84.18
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	2	$20.42
Test, Manure Analysis	306	Moisture, Total N, P, K. Includes materials and shipping only.	Each	$45.54	1	$45.54
Test, Compost Analysis	307	Moisture, Total N, P, K. Includes materials and shipping only.	Each	$50.00	1	$50.00

Practice: 590 - Nutrient Management

Scenario #281 - Basic NM with Manure and/or Compost (Non-Organic/Organic)

Scenario Description:

This scenario describes the implementation of a basic nutrient management system on > = 40 acres of cropland or hayland where manure and/or compost is utilized either alone or in conjunction with commercial fertilizer. Scenario is applicable on non-organic and organic land. The planned NM system will meet the current Nutrient Management (590) CPS. Implementation will result in the proper rate, source, method of placement, and timing of nutrient application. Payment for implementation is to defray the costs of soil testing, manure and/or compost analysis, and implementation of the nutrient management plan and recordkeeping. Records demonstrating implementation of the 4 R's of NM will be required. Scenario is designed to encourage producers to effectively utilize commercial fertilizers, organic fertilizers, manure, and/or compost appropriately improving soil quality and minimizing runoff of nutrients from fields to surface waters. The basis for nutrient applications will be recommendations based on soil, manure, and compost analyses.

Before Situation:

In this geographic area, a fertility program is either nonexistent or at a basic level. Application of fertilizers, including manures, composts, and amendments, are completed annually based upon tradition that does not specifically consider the detrimental effects of improper timing or rates of nutrients, or excess nutrient buildup in the soil. Fields are overwintered with little or no erosion protection often times resulting in sheet, rill, and ephemeral erosion by spring. Soil testing is not completed on a regular basis and applications of fertilizers are not based on land grant university recommendations or a nutrient budget. An environmental evaluation or risk assessment is not completed. Nutrients are transported to surface waters through runoff, drainage tile, or soil erosion, or to ground water from leaching in quantities that degrade water quality and limit use of intended purposes. Soil quality may be degraded by excess or inadequate nutrients. Fields have little or no erosion protection during critical periods often times resulting in sheet, rill, and ephemeral erosion.

After Situation:

A nutrient management system will be developed to meet the current Nutrient Management (590) CPS, when applicable system will also meet NOP regulations. Development and implementation of a nutrient management plan (NMP) will benefit plant productivity while also reducing potential for off-site degradation. A nutrient management budget will be developed for each field(s) based on soil test analysis and land grant university recommendations or crop removal rates. On planning units typically 40 acres or larger, soil testing is completed according to LGU recommendations. Records will be provided annually of the current soil test, analysis, application rate, forms and rates of nutrients for each field, including crop yields. Nutrient applications will be completed according to the Nutrient Management Plan that minimizes nutrient runoff and leaching or buildup of excess nutrient concentrations.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $626.70

Scenario Cost/Unit: $15.67

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	1	$22.02
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	4	$336.72
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	2	$20.42
Test, Manure Analysis	306	Moisture, Total N, P, K. Includes materials and shipping only.	Each	$45.54	1	$45.54
Test, Compost Analysis	307	Moisture, Total N, P, K. Includes materials and shipping only.	Each	$50.00	1	$50.00

Practice: 591 - Amendments for the Treatment of Agricultural Waste

Scenario #2 - Litter Amendments for Water Quality With Partially Treated Brood Chamber

Scenario Description:

This practice scenario includes the application of a litter treatment amendment that is approved by NRCS to the entire poultry house to reduce ammonia emissions and water-soluble phosphorous in the poultry litter. An entire poultry house is treated year round for air and water quality impacts. In the winter, the producer or integrator treats the brood chamber between flocks with litter amendments solely for bird health and production. The amount being applied by the producer or integrator in winter months does not meet the air and water quality resource concerns. Additional litter amendments are added in winter for Air Quality benefits not being applied by the integrator. Litter amendments are applied spring through fall for entire flocks. NRCS is not responsible for the litter amendments already being applied by the integrator for the purposes of production and bird health. The purpose of the practice is to address resource concerns related to water quality degradation due to excess nutrients and pathogens and air quality impacts due to particulate matter and associated precursors, and objectionable odors. Associated practices: Nutrient Management (590).

Before Situation:

No litter amendments are being applied during the spring through fall months. An amendment is being applied at a lower application rate during the winter months, typically half the house and only two flocks. Partial winter application is solely for production purposes and the lower application rate is not enough to address resource concerns from existing nutrient levels which may contribute to water quality degradation from nutrient runoff and leaching from fields fertilized with poultry litter and cause adverse air quality impacts such as objectionable odors and ammonia emissions.. The operation raises 4 flocks per year and the integrator partially treats 2 flocks in the winter months. Approximately 18.7% of the needed litter amendments are being applied and only during the winter months.

After Situation:

An NRCS approved amendment is applied between each flock. All flocks are optimally treated with litter amendments year-round. A typical broiler operation with 4 flocks in a 42’ x 500’ house (21,000 square feet) is treated to reduce the impacts on air and water quality. Typically 100 pounds of litter amendments per 1000 square feet are applied 4 times annually. The total amendment applied is adjusted by 81.3% to account for the portion of the brood chamber that is receiving partial application during the winter months. The amendment is proven to reduce ammonia emissions and soluble phosphorus in the litter. The selected amendment is applied in conformance with the manufacturer’s recommendations and the rates required. The resulting litter contains higher levels of nutrients and nutrient management plans must account for this. Nutrient level testing of the litter and nutrient planning shall be in conformance with CPS Nutrient Management, Code 590. The amendment successfully addresses water quality degradation from nutrients in surface and ground water and air quality impacts due to objectionable odors, ammonia emissions, PM and PM precursors and bird health resource concerns. Formula to calculate the number of 1000 SF units: (Square Feet of house) / 1000 SF X (Number of houses) X (Number of applications/year) = Number of 1000SF/year. 21,000 SF / 1000 SF X 1 house X 4 app/yr = 84 units of 1000SF

Feature Measure: Number of 1000SF applications per

Scenario Unit:: 1,000 Square Foot

Scenario Typical Size: 84.0

Scenario Total Cost: $3,300.72

Scenario Cost/Unit: $39.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Application of ag waste amendment for poultry litter	2020	Litter amendment application performed in house. Includes equipment, power unit and labor costs.	Ton	$58.85	3.4	$200.09
Materials						
Ag Waste Amendment, aluminum sulfate, alum	1684	Aluminum sulfate, alum, poultry Litter amendment. NRCS approved for air and water quality concerns to reduce ammonia emissions and soluble phosphorus in the litter. Materials only.	Ton	$911.95	3.4	$3,100.63

Practice: 595 - Integrated Pest Management (IPM)

Scenario #1 - Basic IPM Field 1RC

Scenario Description:

A basic IPM plan with LGU-approved pest monitoring techniques and pest thresholds (where available) is applied in Large Scale Field/Forage Crops to address one identified resource concern (e.g. Water Quality - Impacts to Human Drinking Water) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concern) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to an identified resource concern (e.g. Water Quality – Impacts to Human Drinking Water).

After Situation:

After implementing the 595 practice, a basic IPM system has been implemented with Land Grant University approved pest monitoring techniques and pest thresholds (where available) to help meet the minimum criteria for one identified resource concern (e.g. Water Quality - Impacts to Human Drinking Water) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concern) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $559.84

Scenario Cost/Unit: $14.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	6	$505.08

Practice: 595 - Integrated Pest Management (IPM)

Scenario #2 - Basic IPM Field >1RC

Scenario Description:

A basic IPM plan with LGU-approved pest monitoring techniques and pest thresholds (where available) is applied in Large Scale Field/Forage Crops to address multiple identified resource concerns (e.g. Water Quality – Impacts to Human Drinking Water and Pollinator Impacts) with either risk prevention (e.g. planned pesticides have no risks to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for "Intermediate", "High" or "Extra High" WIN-PST Final Hazard Ratings).

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to two or more identified resource concerns (e.g. Water Quality – Impacts to Human Drinking Water and Impacts on Pollinators).

After Situation:

After implementing the 595 practice, a basic IPM system has been implemented with Land Grant University approved pest monitoring techniques and pest thresholds (where available) to help meet the minimum criteria for two or more identified resource concerns (e.g. Water Quality - Impacts to Human Drinking Water and Impacts on Pollinators) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for "Intermediate", "High" or "Extra High" WIN-PST Final Hazard Ratings).

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $755.58

Scenario Cost/Unit: $18.89

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	3	$82.14
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	8	$673.44

Practice: 595 - Integrated Pest Management (IPM)

Scenario #3 - Advanced Field All RCs

Scenario Description:

A comprehensive IPM plan with LGU-approved pest prevention, avoidance and monitoring techniques and pest thresholds (where available) is applied in Large Scale Field/Forage Crops to address all identified resource concerns with either risk prevention (e.g. planned pesticides have no risk to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to an identified resource concern (e.g. Water Quality – Impacts to Human Drinking Water).

After Situation:

After implementing the 595 practice, a comprehensive IPM plan with Land Grant University approved pest prevention, avoidance and monitoring techniques and pest thresholds (where available) is applied to help meet the minimum criteria for all identified resource concerns with either risk prevention (e.g. planned pesticides have no risk to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $1,119.68

Scenario Cost/Unit: $27.99

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	4	$109.52
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	12	$1,010.16

Practice: 595 - Integrated Pest Management (IPM)

Scenario #4 - Basic IPM Fruit/Veg 1RC

Scenario Description:

A basic IPM plan with LGU-approved pest monitoring techniques and pest thresholds (where available) is applied in Large Scale Small Fruit/Vegetable Crops to address one identified resource concern (e.g. Water Quality - Impacts to Human Drinking Water) with either risk prevention (e.g. planned pesticides no risk to the identified resource concern) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to an identified resource concern (e.g. Water Quality – Impacts to Human Drinking Water).

After Situation:

After implementing the 595 practice, a basic IPM system has been implemented with Land Grant University approved pest monitoring techniques and pest thresholds (where available) to help meet the minimum criteria for at least one identified resource concern (e.g. Water Quality - Impacts to Human Drinking Water) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concern) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $782.96

Scenario Cost/Unit: $78.30

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	4	$109.52
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	8	$673.44

Practice: 595 - Integrated Pest Management (IPM)

Scenario #5 - Basic IPM Fruit/Veg >1RC

Scenario Description:

A basic IPM plan with LGU-approved pest monitoring techniques and pest thresholds (where available) is applied in Large Scale Small Fruit/Vegetable Crops to address multiple identified resource concerns (e.g. Water Quality - Impacts to Human Drinking Water and Pollinator Impacts) with either risk prevention (e.g. planned pesticides have no risk to identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to two or more identified resource concerns (e.g. Water Quality – Impacts to Human Drinking Water and Impacts on Pollinators).

After Situation:

After implementing the 595 practice, a basic IPM system has been implemented with Land Grant University approved pest monitoring techniques and pest thresholds (where available) to help meet the minimum criteria for two or more identified resource concerns (e.g. Water Quality - Impacts to Human Drinking Water and Impacts on Pollinators) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $1,006.08

Scenario Cost/Unit: $100.61

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	6	$164.28
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	10	$841.80

Practice: 595 - Integrated Pest Management (IPM)

Scenario #6 - Advanced IPM Fruit/Veg All RCs

Scenario Description:

A comprehensive IPM plan with LGU-approved pest prevention, avoidance and monitoring techniques and pest thresholds (where available) is applied in Large Scale Small Fruit/Vegetable Crops to address all identified resource concerns with either risk prevention (e.g. planned pesticides have no risk to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to an identified resource concern (e.g. Water Quality – Impacts to Human Drinking Water).

After Situation:

After implementing the 595 practice, a comprehensive IPM plan with Land Grant University approved pest prevention, avoidance and monitoring techniques and pest thresholds (where available) is applied to help meet the minimum criteria for all identified resource concerns with either risk prevention (e.g. planned pesticides have no risk to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $1,536.50

Scenario Cost/Unit: $153.65

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	10	$273.80
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	15	$1,262.70

Practice: 595 - Integrated Pest Management (IPM)

Scenario #10 - IPM S-Farm 1RC

Scenario Description:

A basic IPM plan with LGU-approved pest monitoring techniques and pest thresholds (where available) is applied in Small Farm/Diversified Systems (e.g. CSA, organic, etc.) to address one identified resource concern (e.g. Water Quality - Impacts to Human Drinking Water) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concern) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings). This scenario attempts to capture the higher cost/acre of planning and implementing IPM techniques on smaller acreages with very diverse cropping systems.

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to an identified resource concern (e.g. Water Quality – Impacts to Human Drinking Water).

After Situation:

After implementing the 595 practice, a basic IPM system has been implemented with Land Grant University approved pest monitoring techniques and pest thresholds (where available) to help meet the minimum criteria for at least one identified resource concern resource concern (e.g. Water Quality - Impacts to Human Drinking Water) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concern) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Feature Measure: <Unknown>

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $475.66

Scenario Cost/Unit: $475.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90

Practice: 595 - Integrated Pest Management (IPM)

Scenario #11 - IPM S-Farm >1RC

Scenario Description:

A basic IPM plan with LGU-approved pest monitoring techniques and pest thresholds (where available) is applied in Small Farm/ Diversified Systems (e.g. CSA, organic, etc.) to address multiple identified resource concerns (e.g. Water Quality - Impacts to Human Drinking Water and Pollinator Impacts) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings). This scenario attempts to capture the higher cost/acre of planning and implementing IPM techniques on smaller acreages with very diverse cropping systems.

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to two or more identified resource concerns (e.g. Water Quality – Impacts to Human Drinking Water and Impacts on Pollinators).

After Situation:

After implementing the 595 practice, a basic IPM system has been implemented with Land Grant University approved pest monitoring techniques and pest thresholds (where available) to help meet the minimum criteria for two or more identified resource concerns (e.g. Water Quality - Impacts to Human Drinking Water and Impacts on Pollinators) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Feature Measure: <Unknown>

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $614.60

Scenario Cost/Unit: $614.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	4	$109.52
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	6	$505.08

Practice: 595 - Integrated Pest Management (IPM)

Scenario #12 - Advanced IPM S-Farm All RCs

Scenario Description:

A comprehensive IPM plan with LGU-approved pest prevention, avoidance and monitoring techniques and pest thresholds (where available) is applied in Small Farm/Diversified Systems (e.g. CSA, Organic, etc.) to address all identified resource concerns with either risk prevention (e.g. planned pesticides have no risk to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings. This scenario attempts to capture the higher cost/acre of planning and implementing IPM techniques on smaller acreages with very diverse cropping systems.

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to an identified resource concern (e.g. Water Quality – Impacts to Human Drinking Water).

After Situation:

After implementing the 595 practice, a comprehensive IPM plan with Land Grant University approved pest prevention, avoidance and monitoring techniques and pest thresholds (where available) is applied to help meet the minimum criteria for all identified resource concerns with either risk prevention (e.g. planned pesticides have no risk to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Feature Measure: <Unknown>

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $921.90

Scenario Cost/Unit: $921.90

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	6	$164.28
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	9	$757.62

Practice: 600 - Terrace

Scenario #1 - Broadbased

Scenario Description:

An earthen embankment with channel constructed across the field slope as part of a system to shorten slope lengths and reduce sheet, rill, and gully erosion in a cropped field. The typical installation is a broadbased terrace having 5:1 upstream and 5:1 downstream slopes measuring 2,500 feet in a field with slopes from 2% to 8% constructed in loam soils or similar in regards to workability. Channel and berm are farmed. A stable outlet is provided in the form of a Grassed Waterway or Underground Outlet. Costs include all equipment and forces necessary to excavate, shape, and compact terrace. This practice addresses Concentrated Flow Erosion and Excessive Sediment in surface waters.

Before Situation:

Long slope lengths contribute to excessive sedimentation and soil erosion in cropped fields as a result of gully, rill, and sheet erosion. The excessive erosion may lead to deterioration of receiving waters due to excessive sedimentation and nutrient transport.

After Situation:

A system of broadbased terraces measuring 2,500 feet in length, 2.5 height, and 5:1 front and back slopes is installed with spacing designed to intercept flow of water and shorten slope length to reduce erosion to acceptable levels. Work is done with dozer, scraper, or road grader. The installed terrace is typically farmed. Associated practices are Critical Area Planting (342), Grassed Waterway (412), and Underground Outlet (620).

Feature Measure: Length of Terrace

Scenario Unit:: Foot

Scenario Typical Size: 2,500.0

Scenario Total Cost: $5,608.75

Scenario Cost/Unit: $2.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	$125.35	34	$4,261.90
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	34	$873.12
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	6	$217.08
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 600 - Terrace

Scenario #4 - Narrow Base Less Than 8%

Scenario Description:

An earthen embankment with channel constructed across the field slope as part of a system to shorten slope lengths and reduce sheet, rill, and gully erosion in a cropped field. The typical installation is a system of narrow base terraces with 2:1 slopes, 2,500' length, and 2.5' height in a field with slopes from 3% to 8% constructed in loam soils or similar in regards to workability. A stable outlet is provided in the form of a Grassed Waterway or Underground Outlet. Costs include all equipment and forces necessary to excavate, shape, and compact terrace. Permanent vegetation is established. Seeding is not included. This practice addresses Concentrated Flow Erosion and Excessive Sediment in surface waters.

Before Situation:

Long slope lengths contribute to excessive sedimentation and soil erosion in cropped fields as a result of gully, rill, and sheet erosion. The excessive erosion may lead to deterioration of receiving waters due to excessive sedimentation and nutrient transport.

After Situation:

A system of narrow base terraces with approximately 2:1 front and back slopes measuring 2,500 feet in length and 2.5 feet height is constructed with spacing designed to intercept flow of water and shorten slope length to reduce erosion to acceptable levels. Work is done with dozer, scraper, or road grader. Associated practices are Critical Area Planting (342), Grassed Waterway (412), and Underground Outlet (620).

Feature Measure: Length of Terrace

Scenario Unit:: Foot

Scenario Typical Size: 2,500.0

Scenario Total Cost: $3,989.91

Scenario Cost/Unit: $1.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	$125.35	24	$3,008.40
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	24	$616.32
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	3	$108.54
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 601 - Vegetative Barrier

Scenario #14 - Vegetative Planting

Scenario Description:

Permanent strips of stiff, dense vegetation established along the general contour of slopes.

Before Situation:

Significant erosion is occurring resulting in substantial transport of sediment across the slope. A large amount of sediment is subsequently delivered to the edge of the field and/or waterways.

After Situation:

Implementation Requirements are prepared and implemented for the site according to the Vegetative Barrier (601) standard. A strip or strips of stiff, dense vegetation such as Vetiver Grass is/are established along the general contour of the slope that effectively settles a significant amount of sediment above the leading edge of the vegetative barrier. Barrier may also help to connect green areas to provide shelter for wildlife.

Feature Measure: Per 100 foot Linear feet of practice

Scenario Unit:: Foot

Scenario Typical Size: 100.0

Scenario Total Cost: $755.60

Scenario Cost/Unit: $7.56

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	0.01	$0.06
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.69	0.01	$0.07
Ground sprigging	1101	Includes costs for equipment, power unit and labor.	Acre	$74.22	0.01	$0.74
Materials						
Nitrogen (N), Ammonium Sulfate	70	Price per pound of N supplied by Ammonium Sulfate. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.88	0.46	$0.40
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	0.01	$0.19
One Species, Warm Season, Introduced Perennial Rhizome	2324	Cool season introduced perennial rhizome. Includes material and shipping only.	100 Foot	$754.14	1	$754.14

Practice: 606 - Subsurface Drain

Scenario #10 - Corrugated Plastic Pipe (CPP), Single-Wall, <= 6 inch

Scenario Description:

Description: Below ground installation of perforated HDPE (Corrugated Plastic Pipe) pipeline, using a drainage plow. HDPE (CPP) Single-Wall is manufactured in sizes (nominal diameter) from 3-inch to 24-inch; typical practice sizes range from 3-inch to 12-inch; and typical scenario size is 5-inch. Construct 2,000 feet of 5-inch, Single-Wall, perforated HDPE Corrugated Plastic Pipe (CPP), installed below ground to a minimum depth 5 feet. The unit is in weight of pipe material in pounds. 2,000 feet of 5-inch, Single-Wall, perforated HDPE CPP weighs 0.50 lb/ft, or a total of 1,000 pounds. The typical number of mainline connections for 2,000 feet of subsurface drain line is a total of 3 each. Resource Concerns: Excess Water (Seasonal High Water Table); Degraded Plant Condition; Water Quality Degradation (Nutrients). Associated Practices: 608 - Surface Drain, Main or Lateral; 587 - Structure for Water Control, 533 - Pumping Plant; and 554 - Drainage Water Management.

Before Situation:

Before installation soil conditions are excessively wet in the spring due to poor internal soil drainage. Excess soil water is causing crop stress and delay of field operations (seed bed preparation, planting, etc.).

After Situation:

The drainage modifications result in reduced plant stress due to excessive wetness caused by a seasonal high water table, or improved drainage water quality due to system retrofit enabling drainage water management.

Feature Measure: Weight of Pipe

Scenario Unit:: Pound

Scenario Typical Size: 1,000.0

Scenario Total Cost: $7,992.00

Scenario Cost/Unit: $7.99

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, tile line plowing, earth, 60"	1457	Plowing in 3"-15" CPP drain line into earth, 60" depth, includes equipment and labor for trenching, laying, and backfilling.	Foot	$2.41	2000	$4,820.00
Materials						
Pipe, HDPE, corrugated single wall, <= 12" weight priced Compound	1380	High Density Polyethylene (HDPE) compound manufactured into single wall corrugated pipe or tubing. Materials only.	Pound	$1.59	1000	$1,590.00
Drainage Lateral Connection	1458	Connect 3"-6" drainage lateral to main drain, includes excavation to 6' depth, install tee on main line, connect lateral, and backfill. Includes material cost for tee.	Each	$29.56	3	$88.68
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 606 - Subsurface Drain

Scenario #11 - Enveloped Corrugated Plastic Pipe (CPP), Single-Wall, <= 6 inch

Scenario Description:

Description: Below ground installation of perforated HDPE (Corrugated Plastic Pipe) pipeline with Sand-Gravel envelope, using a drainage trencher. HDPE (CPP) Single-Wall is manufactured in sizes (nominal diameter) from 3-inch to 24-inch; typical practice sizes range from 3-inch to 12-inch; and typical scenario size is 5-inch. Construct 2,000 feet of 5-inch, Single-Wall, perforated HDPE Corrugated Plastic Pipe (CPP), installed below ground to a minimum depth of 5 feet, and surrounded with a sand-gravel envelope. The unit is in weight of pipe material in pounds. 2,000 feet of 5-inch, Single-Wall, perforated HDPE CPP weighs 0.50 lb/ft, or a total of 1,000 pounds. The typical volume sand-gravel for 2,000 feet of 12"wide x 12" high envelope is 64 cubic yards. The typical number of mainline connections for 2,000 feet of subsurface drain line is a total of 3 each. Resource Concerns: Excess Water (seasonal High Water Table); Degraded Plant Condition; Water Quality Degradation (Nutrients). Associated Practices: 608 - Surface Drain, Main or Lateral; 587 - Structure for Water Control, 533 - Pumping Plant; and 554 - Drainage Water Management.

Before Situation:

Before installation soil conditions are excessively wet in the spring due to poor internal soil drainage. Excess soil water is causing crop stress and delay of field operations (seed bed preparation, planting, etc.).

After Situation:

The drainage modifications result in reduced plant stress due to excessive wetness caused by a seasonal high water table, or improved drainage water quality due to system retrofit enabling drainage water management.

Feature Measure: Weight of Pipe

Scenario Unit:: Pound

Scenario Typical Size: 1,000.0

Scenario Total Cost: $9,942.24

Scenario Cost/Unit: $9.94

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Track Loader, 95HP	935	Equipment and power unit costs. Labor not included.	Hour	$89.10	8	$712.80
Trenching, Earth, 12" x 60"	1459	Trenching, earth, 12" wide x 60" depth, includes equipment and labor for trenching, laying 3"-6" CPP drain line with envelope, and backfilling.	Foot	$1.95	2000	$3,900.00
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	8	$205.44
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	$30.50	64	$1,952.00
Pipe, HDPE, corrugated single wall, <= 12" weight priced Compound	1380	High Density Polyethylene (HDPE) compound manufactured into single wall corrugated pipe or tubing. Materials only.	Pound	$1.59	1000	$1,590.00
Drainage Lateral Connection	1458	Connect 3"-6" drainage lateral to main drain, includes excavation to 6' depth, install tee on main line, connect lateral, and backfill. Includes material cost for tee.	Each	$29.56	3	$88.68
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	2	$980.02

Practice: 607 - Surface Drain, Field Ditch

Scenario #1 - Field Drainage Ditch

Scenario Description:

A new field ditch is constructed to collect the excess irrigation water of a single field and direct it to a collection system so that the water can be recovered and reused. Typical ditch size is trapezoidal ditch with 4ft bottom x 3ft depth x 1760 ft length with 2:1 side slopes. The total yardage of earthwork is 1956 cy. Resource concerns that will be addressed: Excess/Insufficient Water - inefficient use of irrigation water; Water Quality Degradation - excessive sediments in surface waters; Water Quality Degradation - Excess nutrients in surface and ground water; Degradation Plant Condition - undesirable plant productivity and health. Associated practices: 533 - Pumping Plants; 410 - Grade Stabilization Structure; 587 - Structure for water control; 449 - Irrigation Water Management

Before Situation:

Excess irrigation water collects at lower ends of field and backs up into crops and causes plant stress or causes erosion and travels off farm in a drainage ditch causing water quality issues in lower watersheds.

After Situation:

Excess irrigation water is collected and directed into a recovery system where the water can be recycled and reused for irrigation. Sedimentation has a chance to settle out of the water allowing for less sediment to travel down stream.

Feature Measure: Volume of Earth Excavated

Scenario Unit:: Cubic Yard

Scenario Typical Size: 1,956.0

Scenario Total Cost: $4,221.54

Scenario Cost/Unit: $2.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	1956	$4,048.92
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: 612 - Tree/Shrub Establishment

Scenario #1 - Pine, Bare root

Scenario Description:

Tree seedlings will be hand planted in the forested area where few or no forest trees are growing, the existing stand of trees needs under planting, or the previously planted seedling tree stocking level is below desirable conditions. Wildlife habitat is degraded by loss of forest conditions. This resource concern addressed is degraded plant condition -- and inadequate structure and composition, and inadequate wildlife & fish habitat.

Before Situation:

The stocking level of the forest does not meet the minimum recommended number of trees per acre. The existing condition of the forest stand does not meet the landowners objectives. To be a viable forest additional seedlings need planting. Wildlife habitat is rated poor.

After Situation:

The prescribed number of trees are hand planted on 20 acres, and the objectives of the landowner are met. The forest will provide wildlife habitat, provide a long term ground cover, and capture atmospheric carbon.

Feature Measure: Number planted

Scenario Unit:: Each

Scenario Typical Size: 10,000.0

Scenario Total Cost: $1,750.32

Scenario Cost/Unit: $0.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	8	$98.88
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	40	$760.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Tree, conifer, seedling, bare root, 1-0	1512	Bare root conifer trees, 1-0 (1 year old). Includes materials and shipping only.	Each	$0.05	10000	$500.00
Mobilization						
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	$1.02	100	$102.00

Practice: 612 - Tree/Shrub Establishment

Scenario #2 - Hardwood, bare root

Scenario Description:

Establishing a hardwood forest setting by hand planting hardwood tree seedlings. Resource concerns are degraded plant condition - undesirable productivity and health, and Inadequate structure and composition; inadequate habitat for fish and wildlife - habitat degradation.

Before Situation:

In an existing upland forest the present trees are poor quality, at low stocking levels, or are undesirable species. Existing conditions do not meet landowner objectives of growing high quality trees. Wildlife habitat is poor due to the above described conditions. Resource concerns are degrade plant condition - undesirable productivity and health, and Inadequate structure and composition; inadequate habitat for fish and wildlife - habitat degradation. Prior to planting any needed vegetation control will be conducted first.

After Situation:

The area of treatment is 20 acres. Bare root hardwood seedlings are planted by hand in the best locations for seedling survival. Solid tree tubes are installed to protect seedlings from animal browsing damage. Post planting vegetation control is planned to ensure seedling survival.

Feature Measure: Number planted

Scenario Unit:: Each

Scenario Typical Size: 6,000.0

Scenario Total Cost: $2,709.32

Scenario Cost/Unit: $0.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	8	$98.88
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	32	$608.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Tree, hardwood, seedling or transplant, bare root, 6-18"	1509	Bare root hardwood trees 6-18" tall. Includes materials and shipping only.	Each	$0.26	6000	$1,560.00
Mobilization						
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	$1.02	150	$153.00

Practice: 612 - Tree/Shrub Establishment

Scenario #3 - Shrub, bare root

Scenario Description:

Shrubs are planted to provide a more diverse habitat. Plantings are in either uplands or bottomlands. The site lacks ground level habitat structure and diversity for wildlife. Resource concern is inadequate habitat for fish and wildlife - habitat fragmentation.

Before Situation:

No shrubbery vegetation, or very little, is present under the forest overstory. Wildlife species that need shrub cover are not present. An adequate stand of overstory trees is present, but it is a single level, not multi-level.

After Situation:

A 10 acre area is planted with shrubs. Shrubs are not planted over the entire 10 acres. They are planted in groups or motts. The motts, more or less circular in shape, are 50 feet in diameter, with 50 shrubs planted within each mott. 4 motts are planted per acre for a total of 200 shrubs per acre. Motts are randomly established to take advantage of site conditions and shrub species being planted.

Feature Measure: Number planted

Scenario Unit:: Each

Scenario Typical Size: 2,000.0

Scenario Total Cost: $2,315.08

Scenario Cost/Unit: $1.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	24	$296.64
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	24	$456.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.56	2000	$1,120.00
Mobilization						
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	$1.02	150	$153.00

Practice: 612 - Tree/Shrub Establishment

Scenario #4 - Pine, containerized

Scenario Description:

Tree seedlings will be hand planted in the forested area where few or no forest trees are growing, the existing stand of trees needs under planting, or the previously planted seedling tree stocking level is below desirable conditions. Typically, containerized seedlings are used for special species such as longleaf or to help insure survival in droughty areas. Wildlife habitat is degraded by loss of forest conditions. This resource concern addressed is degraded plant condition -- and inadequate structure and composition, and inadequate wildlife & fish habitat.

Before Situation:

The stocking level of the forest does not meet the minimum recommended number of trees per acre. The existing condition of the forest stand does not meet the landowners objectives. To be a viable forest additional seedlings need planting. Wildlife habitat is rated poor.

After Situation:

The prescribed number of trees are hand planted on 20 acres, and the objectives of the landowner are met. The forest will provide wildlife habitat, provide a long term ground cover, and capture atmospheric carbon.

Feature Measure: Number planted

Scenario Unit:: Each

Scenario Typical Size: 10,000.0

Scenario Total Cost: $3,651.44

Scenario Cost/Unit: $0.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	40	$760.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Tree, conifer, seedling, containerized, 4 cu. in.	1516	Containerized conifer stock, 4 cubic inches (e.g., "4a" plug), 1.1" x 5.2". Includes materials and shipping only.	Each	$0.25	10000	$2,500.00
Mobilization						
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	$1.02	100	$102.00

Practice: 614 - Watering Facility

Scenario #1 - Permanent Drinking/Storage <500 Gallons

Scenario Description:

A permanent watering facility for livestock and or wildlife constructed of approved materials with less than 500 gallons of capacity that stores adequate quantity and quality of water for storage and or direct drinking access. All watering facilities will be constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation. This watering facility will address the resource concerns of inadequate supply of water for livestock and or wildlife, habitat degradation, water quality, and undesirable plant productivity and health.

Before Situation:

This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water is not available in sufficient quantities at specific locations, and habitat, water quality, plant productivity and health needs to be improved.

After Situation:

A permanent watering facility with a capacity of less than 500 gallons is installed with all tank materials, tank plumbing and float valve, to provide adequate water storage capacity to ensure an adequate supply and quality of water for livestock or wildlife for storage and or direct drinking access and provides improved plant productivity and health, water quality, and habitat. All watering facilities are constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation and placed on a properly prepared foundation with required plumbing. All needed pipelines are installed using Livestock Pipeline (516). Any needed vegetation of disturbed areas will use Critical Area Planting (342). All collectors or catchments for collecting precipitation will be addressed by using Water Harvesting Catchment (636). Any needed water source installation will use Water Well (642), Pumping Plant (533), Spring Development (574), or Livestock Pipeline (516) as appropriate. Areas around watering facilities where animal concentrations or overflow from the watering facility will cause resource concerns will be protected by using Heavy Use Area Protection (561) as appropriate.

Feature Measure: Capacity in Gallons

Scenario Unit:: Gallon

Scenario Typical Size: 250.0

Scenario Total Cost: $869.12

Scenario Cost/Unit: $3.48

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	0.5	$1.04
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	2	$113.30
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2.5	$47.50
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	2	$43.42
Materials						
Wildlife Escape Ramp	242	Pool size 15' x 30', for small mammals less than one pound	Each	$25.16	1	$25.16
Tank, Galvanized Steel Livestock, >75 - 300 gallon	1067	Includes tank materials and float valve	Gallon	$1.31	250	$327.50
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic Yard	$21.02	0.5	$10.51
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 614 - Watering Facility

Scenario #2 - Permanent Drinking/Storage 500-1000 Gallons

Scenario Description:

A permanent watering facility for livestock and or wildlife constructed of approved materials with 500 to 1,000 gallons of capacity that stores adequate quantity and quality of water for storage and or direct drinking access. All watering facilities will be constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation. This watering facility will address the resource concerns of inadequate supply of water for livestock and or wildlife, habitat degradation, water quality, and undesirable plant productivity and health.

Before Situation:

This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water is not available in sufficient quantities at specific locations, and habitat, water quality, plant productivity and health needs to be improved.

After Situation:

A permanent watering facility with a capacity of 500 to 1,000 gallons is installed with all tank materials, tank plumbing and float valve, to provide adequate water storage capacity to ensure an adequate supply and quality of water for livestock or wildlife for storage and or direct drinking access and provides improved plant productivity and health, water quality, and habit. All watering facilities are constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation and placed on a properly prepared foundation with required plumbing. All needed pipelines are installed using Livestock Pipeline (516). Any needed vegetation of disturbed areas will use Critical Area Planting (342). All collectors or catchments for collecting precipitation will be addressed by using Water Harvesting Catchment (636). Any needed water source installation will use Water Well (642), Pumping Plant (533), Spring Development (574), or Livestock Pipeline (516) as appropriate. Areas around watering facilities where animal concentrations or overflow from the watering facility will cause resource concerns will be protected by using Heavy Use Area Protection (561) as appropriate.

Feature Measure: Capacity in Gallons

Scenario Unit:: Gallon

Scenario Typical Size: 750.0

Scenario Total Cost: $1,800.30

Scenario Cost/Unit: $2.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	2	$4.14
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	6	$339.90
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	6	$132.12
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	6	$164.28
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	6.75	$128.25
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	6	$130.26
Materials						
Wildlife Escape Ramp	242	Pool size 15' x 30', for small mammals less than one pound	Each	$25.16	1	$25.16
Tank, Galvanized Steel Livestock, > 300 - 1,000 gallon	1068	Includes tank materials and float valve	Gallon	$0.77	750	$577.50
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic Yard	$21.02	2	$42.04
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 614 - Watering Facility

Scenario #4 - Permanent Drinking/Storage Greater Than 5000 Gallons

Scenario Description:

A permanent watering facility for livestock and or wildlife constructed of approved materials with more than 5,000 gallons of capacity that stores adequate quantity and quality of water for storage and or direct drinking access All watering facilities will be constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation. This watering facility will address the resource concerns of inadequate supply of water for livestock, habitat degradation, water quality, and undesirable plant productivity and health.

Before Situation:

This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water is not available in sufficient quantities at specific locations, and habitat, water quality, plant productivity and health needs to be improved.

After Situation:

A permanent watering facility with a capacity of more than 5,000 gallons is installed with all tank materials, tank plumbing and float valve, to provide adequate water storage capacity to ensure an adequate supply and quality of water for livestock or wildlife for storage and or direct drinking access and provides improved plant productivity and health, water quality, and habitat. All watering facilities are constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation and placed on a properly prepared foundation with required plumbing. All needed pipelines are installed using Livestock Pipeline (516). Any needed vegetation of disturbed areas will use Critical Area Planting (342). All collectors or catchments for collecting precipitation will be addressed by using Water Harvesting Catchment (636). Any needed water source installation will use Water Well (642), Pumping Plant (533), Spring Development (574), or Livestock Pipeline (516) as appropriate. Areas around watering facilities where animal concentrations or overflow from the watering facility will cause resource concerns must be protected by using Heavy Use Area Protection (561) as appropriate.

Feature Measure: Capacity in Gallons

Scenario Unit:: Gallon

Scenario Typical Size: 10,000.0

Scenario Total Cost: $6,478.80

Scenario Cost/Unit: $0.65

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	7	$1,645.63
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	13	$26.91
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	12	$679.80
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	12	$264.24
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	12	$328.56
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	14	$266.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	12	$260.52
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	12	$434.16
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	$30.09	13	$391.17
Wildlife Escape Ramp	242	Pool size 15' x 30', for small mammals less than one pound	Each	$25.16	1	$25.16
Tank, Galvanized Steel Bottomless Livestock, > 6,000 gallon	1070	Includes tank materials, shipping, and float valve, no liner	Gallon	$0.19	10000	$1,900.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 614 - Watering Facility

Scenario #6 - Fountain

Scenario Description:

This scenario is for the installation of a livestock watering fountain in a pasture; typically near headquarters. The fountain is a manufactured valve type fountain with a capacity of less than 200 gallons. The cost includes all field preparation, excavation, concrete or gravel pad, and plumbing as needed to install the fountain. It does not include the pipeline to deliver the drinking water to the fountain or the heavy use are around the fountain. The unit cost will be based on each (ea.) structure installed. This watering facility will address the resource concerns of inadequate supply of water for livestock and or wildlife, habitat degradation, water quality, and undesirable plant productivity and health.

Before Situation:

The typical location of this practice is near headquarters or other winter grazing area which has limited or no access to water. This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water is not available in sufficient quantities at specific locations, and habitat, water quality, plant productivity and health needs to be improved.

After Situation:

A permanent watering facility, typically a single livestock watering fountain with two ball type access ports, with a capacity of less than 200 gallons is installed with all tank materials, tank plumbing and float valve, to provide adequate water storage capacity to ensure an adequate supply and quality of water for livestock or wildlife for storage and or direct drinking access and provides improved plant productivity and health, water quality, and habitat. All watering facilities are constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation and placed on a properly prepared foundation with required plumbing. All needed pipelines are installed using Livestock Pipeline (516). Any needed vegetation of disturbed areas will use Critical Area Planting (342). All collectors or catchments for collecting precipitation will be addressed by using Water Harvesting Catchment (636). Any needed water source installation will use Water Well (642), Pumping Plant (533), Spring Development (574), or Livestock Pipeline (516) as appropriate. Areas around watering facilities where animal concentrations or overflow from the watering facility will cause resource concerns will be protected by using Heavy Use Area Protection (561) as appropriate.

Feature Measure: Each Fountain

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $1,222.42

Scenario Cost/Unit: $1,222.42

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$235.09	0.5	$117.55
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	2	$113.30
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	2	$43.42
Materials						
Wildlife Escape Ramp	242	Pool size 15' x 30', for small mammals less than one pound	Each	$25.16	1	$25.16
Tank, Freeze Proof, 2 hole	280	Tank, Freeze Proof with 2 drinking holes. Includes materials and shipping.	Each	$712.37	1	$712.37
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

USDA - Natural Resources Conservation Service

Mississippi

Practice: 620 - Underground Outlet

Scenario #2 - UO Less than 6inches, w Riser

Scenario Description:

Install 500 feet of 6" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench is excavated approximately 54"" deep and 15" wide by trencher. Costs include 6" HDPE corrugated single wall plastic tubing, 8" Perforated PVC Riser Inlet, trench excavation, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Feature Measure: Length of Conduit

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: $3,172.85

Scenario Cost/Unit: $6.35

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	$2.51	105	$263.55
Trencher, wheel type	1259	Wheel type Trencher, typically 350 HP with 6' max depth. Equipment only.	Hour	$267.38	5	$1,336.90
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	$2.17	2	$4.34
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	5	$108.55
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	1	$76.05
Pipe, HDPE, 6", CPT, Single Wall	1242	Pipe, Corrugated Plastic Tubing, Single Wall, 6" diameter - ASTM F405. Material cost only.	Foot	$1.15	500	$575.00
Inlet, riser, 8"	1262	Riser, polymer, complete vertical perforated UGO inlet with Tee, orifice plate if needed, 8" diameter. Materials only.	Each	$111.40	2	$222.80
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 620 - Underground Outlet

Scenario #4 - Greater Than 6 and Less Than or Equal To 12 inches, with Riser

Scenario Description:

Install 500 feet of 10" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench Excavation is 58" deep and 28" wide. Costs include 10" HDPE pipe, 12" Perforated PVC Riser Inlet, trench excavation, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Feature Measure: Length of Conduit

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: $6,133.06

Scenario Cost/Unit: $12.27

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	$2.51	210	$527.10
Trencher, wheel type	1259	Wheel type Trencher, typically 350 HP with 6' max depth. Equipment only.	Hour	$267.38	5	$1,336.90
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	$2.17	2	$4.34
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	5	$108.55
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	4	$144.72
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	$76.05	1	$76.05
Pipe, HDPE, CPT, Double Wall, Soil Tight, 10"	1243	Pipe, Corrugated HDPE Double Wall, 10" diameter with soil tight joints - AASHTO M252. Material cost only.	Foot	$6.24	500	$3,120.00
Inlet, riser, 10"	1263	Riser, polymer, complete vertical perforated UGO inlet with Tee, orifice plate if needed, 10" diameter. Materials only.	Each	$151.05	2	$302.10
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: 629 - Waste Treatment

Scenario #11 - Litter Windrow Pasteurization

Scenario Description:

This practice scenario includes the in house windrowing of poultry litter to promote pasteurization between flocks. The purpose of the practice is to address resource concerns related to water quality degradation due to (excess nutrient and pathogens) and air quality impacts (PM & PM precursors, and objectionable odors). Associated practices: Amendments for Treatment of Agricultural Waste (591), Waste Storage Facility (313), & Nutrient Management (590)

Before Situation:

A poultry operation typically removes part of the litter and bedding between flocks, called a cakeout. A full cleanout of litter and bedding is typically done once every 1-3 years depending on the operation. Over time, the accumulation of poultry waste in the litter contributes to an increase in odors and high ammonia emissions in the house contribute to impacts on bird health.

After Situation:

This scenario assumes 4 flocks per year in an operation with 2 - 42 x 500 square foot houses. Three (3) in-house pasteurization events will be performed annually. There will be a full cleanout after the 4th flock. Formula to calculate the total number of pasteurization events per year on a 1000 SF basis: (Square Feet of house) / 1000 SF X (Number of houses) X (Number of pasteurization events) = Number of 1000SF. 21,000 SF / 1000 SF X 2 houses X 3 events = 126 units of 1000SF In house pasteurization of poultry litter is achieved by windrowing the litter in the house. The process takes approximately one week. This process successfully addresses the air quality impacts (ammonia emissions, PM and PM precursors) and bird health resource concerns. This process also improves the quality of poultry litter that must be spread on farmland. Bird health is improved and bird mortality is reduced.

Feature Measure: Surface Area of housing floor windr

Scenario Unit:: 1,000 Square Foot

Scenario Typical Size: 126.0

Scenario Total Cost: $5,581.08

Scenario Cost/Unit: $44.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	$58.32	66	$3,849.12
Aerator Attachment, 8", PTO	1707	Aerator attachment for mounting to tractor and PTO, 8" diameter. Equipment cost only with out tractor. Brown Bear R24C-8' or equivalent	Hour	$9.97	30	$299.10
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	66	$1,432.86

Practice: 633 - Waste Recycling

Scenario #1 - Export Ag Waste By-products Recycled for Use Off Farm

Scenario Description:

Agricultural by-products on the farm are in excess of the ability of the farm and limited crop land base to utilize. These waste materials are accumulating in such a manner that the water, soil and/or air quality have resource concerns. The application of a waste management plan will recycle these by-products such that the quality of the natural resources will be improved and the environment protected. The agricultural by-products are tested and exported off the farm operation for external uses. Records are kept detailing disposition of the waste, including date, amount, and receiver of the waste. Results of the agricultural by-product laboratory analysis is also provided to the receiver. Associated practices: 313-Waste Storage Facility, 317-Composting Facility, 590-Nutrient Management

Before Situation:

Agricultural by-products are produced or accumulated on the farm in amounts that cannot be utilized by the farm without causing resource concerns such as degradation of water quality, soil health and/or air quality.

After Situation:

Twice a year the excess agricultural by-products that have been collected at the farm are sampled and laboratory tested to determine the characteristics of the waste material that is recycled. The results of this analysis will determine the basis of its use. The agricultural by-products are then handled according to the waste management system plan. The intended off-farm use of the recycled agricultural waste by-products will refer to the laboratory analysis. Records shall be kept of the analysis, dates and quantities of recycled waste exported.

Feature Measure: Farm

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $404.16

Scenario Cost/Unit: $404.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	4	$144.72
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Test, Manure Analysis	306	Moisture, Total N, P, K. Includes materials and shipping only.	Each	$45.54	2	$91.08

Practice: 642 - Water Well

Scenario #4 - Small Plastic Farm Well, Less Than 6 in

Scenario Description:

Installation of a well with PVC casing diameter of 4 inches or less; typical farm well has 4 inch diameter PVC casing. Note that doubling the diameter of water well casings only increases specific capacity by 10%. Increasing the length of the screened interval in a well is much more cost-effective at increasing yield. A well is drilled, dug, driven, bored, jetted or otherwise constructed to an aquifer for water supply. A PVC cap and grouting are installed to prevent a direct conduit to ground water, and the well is disinfected in accordance with state and local regulations. The purpose of the practice is to provide water for livestock or small irrigation systems, such as, micro-irrigation. Cost estimate is based on a well depth of 100 feet, with well casing 4 inches in diameter, PVC casing installed to a depth of 50 feet, and typical yield of less than or equal to 250 gpm.

Before Situation:

Livestock have insufficient water or are fenced from their water source or there is insufficient water for use in micro-irrigation/small irrigation systems.

After Situation:

Sufficient water is available for livestock or irrigation. Utilize Pumping Plant (533) and Pipeline (516) or Irrigation water conveyance (430) as associated practices. Use Critical Area Seeding (342) where necessary to prevent erosion following construction activities.

Feature Measure: Linear Foot of well depth

Scenario Unit:: Foot

Scenario Typical Size: 100.0

Scenario Total Cost: $2,894.91

Scenario Cost/Unit: $28.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Rotary Drill Rig	1595	Rotary drill rig including equipment and power unit costs. Labor not included.	Hour	$343.07	4	$1,372.28
Materials						
Test, Standard Water Test, Well Water	309	Well Water Suitability test. Includes materials and shipping only.	Each	$44.74	1	$44.74
Grout, cement	1333	Cement grout meeting ASTM specifications for well sealing. Includes both neat-cement grout and bentonite gout mixtures. Includes materials, equipment and labor to place.	Cubic Yard	$681.27	1	$681.27
Chlorine	1335	Liquid chlorine bleach. Includes materials only.	Gallon	$2.82	1	$2.82
Well Cap, 4"	1785	Well cap, 4". Materials only.	Each	$26.15	1	$26.15
Well Casing, Plastic, 4"	1803	PVC or ABS non-threaded well casing, 4". Materials only.	Foot	$3.71	50	$185.50
Well Screen, plastic, 4"	1998	4" PVC well screen. Materials only.	Foot	$6.51	50	$325.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 643 - Restoration of Rare or Declining Natural Communities

Scenario #3 - Rare or Declining Habitat Monitoring and Management, Medium Intensity and Complexity

Scenario Description:

This scenario is applied to all land use types including those with wildlife as a modifier, where any resource concern is identified related to rare or declining habitats, and where medium intensity and complexity of monitoring or management will treat the identified resource concern. Two or three monitoring efforts are needed and each requiring less than 2 people and less than 8 hours per effort. Two or three adaptive management efforts are required (such as cutting of limbs that impede monitoring efforts, replacing damaged fence markers, or other minor adaptive management activities). The adaptive mgmt requires hand labor and the occasional use of light equipment. A crew of 2 is needed for the hand labor efforts and the crew will require less than 16 total hours of labor per mgmt effort. Mowing of roads and trail is required to provide access for monitoring and management.

Before Situation:

Rare or declining habitat is deficient due to the absence of annual monitoring and adaptive management actions of medium intensity and complexity.

After Situation:

Rare or declining habitat is improved by implementation of annual adaptive management actions of medium intensity and complexity.

Feature Measure: Monitoring efforts and adaptive m

Scenario Unit:: Acre

Scenario Typical Size: 160.0

Scenario Total Cost: $1,793.49

Scenario Cost/Unit: $11.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	4	$17.64
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	6	$132.12
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	5	$262.30
Rangeland/grassland field monitoring kit	967	Miscellaneous tools needed to complete rangeland/grassland monitoring. Materials may include camera, clippers, plot frame, scale, tape measure, etc. Includes materials and shipping only.	Each	$51.08	1	$51.08
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	20	$380.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	5	$108.55
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	10	$841.80

Practice: 643 - Restoration of Rare or Declining Natural Communities

Scenario #4 - Habitat Monitoring and Management, High Intensity and Complexity

Scenario Description:

This scenario is applied to all land use types including those with wildlife as a modifier, where any resource concern is identified for wildlife, and where high intensity and complexity of monitoring or management will treat the identified resource concern. Two - four monitoring efforts are needed and each requiring less than 2 people and less than 8 hours per effort. The adaptive management actions (2 - 5 efforts) such as cutting of limbs that are impeding access of birds into nest boxes, replacing damaged fence markers, cleaning of nest structures and debris around other structures requires hand labor and light equipment, requiring a 2-person crew less than 1 day per effort.

Before Situation:

Wildlife habitat is deficient due to the absence of annual monitoring and adaptive management actions of high intensity and complexity.

After Situation:

Wildlife habitat is improved by implementation of annual adaptive management actions of high intensity and complexity.

Feature Measure: Monitoring efforts and adaptive m

Scenario Unit:: Acre

Scenario Typical Size: 80.0

Scenario Total Cost: $1,662.79

Scenario Cost/Unit: $20.78

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	8	$35.28
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	6	$132.12
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	3	$157.38
Rangeland/grassland field monitoring kit	967	Miscellaneous tools needed to complete rangeland/grassland monitoring. Materials may include camera, clippers, plot frame, scale, tape measure, etc. Includes materials and shipping only.	Each	$51.08	1	$51.08
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	20	$380.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	3	$65.13
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	10	$841.80

Practice: 644 - Wetland Wildlife Habitat Management

Scenario #8 - Topographic Feature Creation, High

Scenario Description:

Corrective measures will require the use of equipment 150 HP in size or larger due to current site conditions and implementation techniques. The setting is all land uses, but typically is on lands used for the production of agricultural products, where the slope gradient is less than two percent and soils that are not excessively drained, that are being converted back to wetland habitats for fish and wildlife. The State-approved habitat evaluation or appraisal found that a limiting factor for wetland wildlife is the absence of sufficient variability in microtopographic relief in the area. The construction of low intensity and low complexity topographic features will provide for diverse soil hydrologic conditions needed to treat the degraded plant condition and/or inadequate habitat for wetland wildlife. The construction of micro and macro topographic features will require the use of equipment 150 HP in size or larger due to current site conditions and implementation techniques. Appropriate equipment (i.e. – Dozer, Excavator, etc.) will be used to construct planned topographic features essential for identified species.

Before Situation:

The site lacks sufficient micro- and macrotopographic features needed for optimal wetland wildlife habitat for target species. Typically the site has been previously manipulated and utilized for agricultural production. With the loss of ridges and swales and other topographic features scattered throughout the site, both plant and animal species that are dependent on the microenvironments created by these features are no longer present or are in decline within the planning unit.

After Situation:

Appropriate equipment (i.e. - Dozer, Excavator, etc.) was used to construct planned topographic features essential for identified species. As a result of the installation, adequate habitat structure such as micro and macro topographic features will provide for diverse soil hydrologic conditions needed to treat the degraded plant condition and/or inadequate habitat for wetland wildlife.

Feature Measure: number and size of constructed fea

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $424,794.68

Scenario Cost/Unit: $4,247.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Equipment Installation						
Dozer, 200 HP	928	Track mounted Dozer with horsepower range of 160 to 250. Equipment and power unit costs. Labor not included.	Hour	$196.22	1000	$196,220.00
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	$166.20	1000	$166,200.00
Satellite imagery, aerial photography, infrared	966	Infrared imagery	Acre	$0.17	100	$17.00
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	2000	$51,360.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	248	$8,972.64
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	4	$1,960.04

Practice: 644 - Wetland Wildlife Habitat Management

Scenario #10 - Close Risers by Nov.1-Feb.15

Scenario Description:

This scenario addresses inadequate habitat for fish and wildlife on cropland and/or moist soil areas. The resource concern is addressed by providing shallow water habitat for wildlife such as shorebirds, waterfowl, wading birds, mammals, fish, reptiles, amphibians, and other species that require shallow water for at least part of their life cycle. Sites are flooded up to a depth of 18" with an average depth of 9". Water is provided by placing boards in risers of water control structures by November 1 to catch precipitation. Removal of boards after February 15 allows area to drain. Associated practices are P.C. 587, Structure for Water Control and P.C. 356, Dikes.

Before Situation:

There is inadequate habitat to provide optimum resting, nesting, and feeding habitat for waterfowl, shorebirds, and other wildlife (amphibians, reptiles, mammals, invertebrates, etc.).

After Situation:

A single or series of shallow water areas that are managed per standard and specification. Water levels are regulated to maintain temporary wildlife habitat. Water control structures are closed by November 1 and held through February 15 to catch rainfall. Depths are based on actual rainfall for that year; based on climatic data, assume enough rainfall to average 6-8 inches. The producer manages the timing and duration of water required for different species of waterfowl/shorebirds. This management will benefit wildlife while minimizing nutrient export and aquifer depletion. Flooded sites vary from mudflats to water depths of 18" with an average depth of 9". The hydrologic conditions of ponding and saturation (frequency, depth, duration, timing) provides optimum seasonal habitat for waterfowl, shorebirds, and other wildlife (amphibians, reptiles, mammals, invertebrates, etc.). If needed and dikes or water control structures are not currently present on the fields planned to be flooded, these practices may be planned for the same fields and cost shared under Structure for Water Control (587) and Dike (356). Depending on local conditions, other Conservation Practices may also be required.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 15.0

Scenario Total Cost: $152.00

Scenario Cost/Unit: $10.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00

Practice: 646 - Shallow Water Development and Management

Scenario #1 - Shallow Water Management - Low Level

Scenario Description:

This scenario addresses inadequate habitat for fish and wildlife on cropland. The resource concern is addressed by providing shallow water habitat for wildlife such as shorebirds, waterfowl, wading birds, mammals, fish, reptiles, amphibians, and other species that require shallow water for at least part of their life cycle. Sites are flooded up to a depth of 18" with an average depth of 9". Water is provided by natural flooding and/or precipitation.

Before Situation:

There is inadequate habitat to provide optimum resting, nesting, and feeding habitat for waterfowl, shorebirds, and other wildlife (amphibians, reptiles, mammals, invertebrates, etc.).

After Situation:

A single or series of shallow water areas that are managed per standard and specification. Water levels are regulated to maintain temporary wildlife habitat. Timing and duration of flooding and de-watering is dependent on specific species requirements. Water is pumped into area to be flooded. Flooded sites vary from mudflats to water depths of 18" with an average depth of 9". The hydrologic conditions of ponding and saturation (frequency, depth, duration, timing) provides optimum seasonal habitat for waterfowl, shorebirds, and other wildlife (amphibians, reptiles, mammals, invertebrates, etc.). If needed and dikes or water control structures are not currently present on the fields planned to be flooded, these practices may be planned for the same fields and cost shared under Structure for Water Control (587) and Dike (356). If a natural water source (i.e. precipitation or flooding) is not available, Pumping Plant (533) may be cost shared to provide a water source. Depending on local conditions, other Conservation Practices may also be required.

Feature Measure: Acre of shallow water

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $19.00

Scenario Cost/Unit: $19.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	1	$19.00

Practice: 646 - Shallow Water Development and Management

Scenario #2 - Shallow Water Management-High Level

Scenario Description:

This scenario addresses inadequate habitat for fish and wildlife on cropland. To facilitate practice code 643, 644, 645, or 395, seasonal shallow water is provided annually for target species by purchasing of water, lifting of such water, monitoring of the water quality, response by target plant community, use by target flora or fauna. Sites are flooded up to a depth of 18"with an average depth of 9". Monitoring and adaptive management accomplished of existing water control structures is accomplished to meet very specific conditions needed to address previously identified degraded plant conditions or inadequate habitat for fish and/or wildlife. This high-level management is applied to lands used for crop, pasture, hay, forests or wildlife lands where target flora and fauna have been identified as a primary concern. Loss of some level of crop, forage, hay or forest products may occur depending on site specific conditions.

Before Situation:

The site has existing infrastructure (reliable water source, dikes, water control structures, pumps, gates) to provide a reliable seasonal water source. The site is not subject to frequent natural flooding. The potential benefits to target fauna and flora is not being captured. The purchase of water, supply of water and intensive management of season water, coupled with monitoring, adaptive management from highly trained individuals will fully address the identified degraded plant conditions and/or inadequate habitat for fish and/or wildlife.

After Situation:

A single or series of shallow water areas that are managed per standard and specification. Water levels are regulated to maintain temporary wildlife habitat. Timing and duration of flooding and de-watering is dependent on specific species requirements. Water is pumped into area to be flooded. Flooded sites vary from mudflats to water depths of 18" with an average depth of 9". The hydrologic conditions of ponding and saturation (frequency, depth, duration, timing) provides optimum seasonal habitat for waterfowl, shorebirds, and other wildlife (amphibians, reptiles, mammals, invertebrates, etc.). If Dikes or Water Control Structures are not currently present on the fields planned to be flooded, these practices may be planned for the same fields and cost shared under Structure for Water Control (587) and Dike (356). If a natural water source (i.e. precipitation or flooding) is not available, Pumping Plant (533) may be cost shared to provide a water source. Depending on local conditions, other Conservation Practices may also be required.

Feature Measure: Acre of shallow water

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $88.52

Scenario Cost/Unit: $88.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Water management, Flooding & dewatering	969	Includes equipment and power unit. Labor not included.	Acre Foot	$139.03	0.5	$69.52
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	1	$19.00

Practice: 647 - Early Successional Habitat Development/Management

Scenario #1 - Disking

Scenario Description:

This practice addresses inadequate wildlife habitat for species requiring early successional habitat at varying stages. This scenario provides early successional habitat by setting back succession and manipulating species composition by disking vegetation and creating bare ground, forbs for feeding habitat, and NWSGS for nesting habitat all within the home range for grassland birds, such as quail. No more than 1/3 to 1/2 of the area should be disked within 1 year. The typical setting for this scenario is at the edge of crop fields, in pastures, odd areas such as pivot corners, and thinned forest understory. This scenario is applicable nationwide. Where the management of woody plants is required to create or maintain early successional habitat, conservation practice 314 brush management or 666 forest stand improvement should be used. Where chemical control of weeds, including invasive, is required to reduce competition for the desired plant community conservation practice 315 herbaceous weed control should be used. Where the seedbank is inadequate for natural regeneration and seeding is required, use conservation practice 550 range seeding or 327 Conservation Cover.

Before Situation:

The site is static or trending to higher successional plant species. The disturbance regime to maintain a lower successional stage is lacking. Pastures are often monotypic, lacking in diversity. Bare ground for seedling establishment is absent. Stands are often dense and inhibit the movements of younger wildlife species such as game bird chicks.

After Situation:

The application of this scenario improves wildlife habitat for species requiring early successional plant communities by reducing competition and creating bare ground for the establishment of early successional plants. Additionally, brood rearing habitat is improved both by the resultant food resources and the increased openness of the plant community that allows chicks to negotiate the terrain and exploit those food resources.

Feature Measure: width and length of treated area

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $1,174.00

Scenario Cost/Unit: $29.35

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	40	$450.40
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	20	$723.60

Practice: 656 - Constructed Wetland

Scenario #3 - Large greater than 0.5 ac

Scenario Description:

This practice scenario includes the basic earthwork and native and/or organic wetland vegetation needed to create a constructed wetland to treat contaminated agricultural runoff for a large site (i.e. >0.5 ac). All other components, such as water control structures, dikes or upstream sediment basins, must be paid for under facilitating practices. Soil, water and tissue sampling are required. The purpose of the practice is to address resource concerns related to water quality degradation due to excess nutrient and pathogens. Associated practices: Structure for Water Control (587); Sediment Basin (350); Dike (356); Pond Sealing or Lining, Compacted Clay Treatment (521D); Pond Sealing or Lining, Flexible Membrane (521A); Fence (382); Grade Stabilization Structure (410); Pumping Plant (533); Waste Transfer (634)

Before Situation:

Contaminated agricultural runoff causes excess ponding and/or water quality degradation.

After Situation:

A 1 acre constructed wetland (i.e. 95' x 460') will be constructed with an average 18" depth. Only the earthwork and wetland vegetation are considered in this scenario. Any structures or sediment basins will be designed under a separate practice. The constructed wetland is sited near the property boundary, but still takes cropland out of production (1/2 wetland acreage). The constructed wetland treats the effluent by reducing excess nutrients and adding oxygen through wetland plants and functions before the effluent is transported to a waste storage facility or discharged off site, if permitted by regulation.

Feature Measure: Area of Constructed Wetland

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $11,192.13

Scenario Cost/Unit: $11,192.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Clearing and Grubbing	40	Clearing and Grubbing, includes materials, equipment and labor	Acre	$286.81	1	$286.81
Stripping and stockpiling, topsoil	1199	Stripping and stockpiling of topsoil adjacent to stripping area. Includes equipment and labor.	Cubic Yard	$0.89	809	$720.01
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	$2.51	1619	$4,063.69
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	37	$703.00
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	2	$20.42
Test, Plant Tissue Test	301	Tissue analysis for crops. Includes materials and shipping only.	Each	$25.03	1	$25.03
Test, Standard Water Test, Well Water	309	Well Water Suitability test. Includes materials and shipping only.	Each	$44.74	8	$357.92
Native Aquatic Plants, Emergent or Submerged	2336	Native aquatic emergent or submerged. All required materials for establishing vegetation. Includes material and shipping.	Each	$1.32	3605	$4,758.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 666 - Forest Stand Improvement

Scenario #1 - Single stem - Hand tools

Scenario Description:

Adjust species composition and/or density of a stand of trees to meet objectives. The operation is supervised and carried out using hand tools such as chainsaws, weed eaters with saw blades, or machetes. Species that do NOT sprout are targeted (i.e. cedar and pine). This scenario is NOT appropriate to target species that sprout. Resource concerns can include: Forage Quality and Palatability, Noxious and Invasive Plants, Plants not adapted or suited, Productivity, Health and Vigor, Wildfire Hazard, Inadequate Cover/Shelter, Inadequate Quantities and Quality of Feed and Forage, Excessive Greenhouse Gas - CO2 (carbon dioxide), or Classic Gully.

Before Situation:

The density and/or species composition of a stand of trees is inconsistent with desired objectives. The stand could have poor health and vigor because of overstocking or undesirable species to be compatible with objectives for timber, wildlife, or aesthetics.

After Situation:

Density and/or species composition of the stand is consistent with desired objectives. Stand will have good health and vigor with desirable species.

Feature Measure: Area treated

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $8,049.20

Scenario Cost/Unit: $201.23

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	200	$882.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	200	$3,800.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	40	$3,367.20

Practice: 666 - Forest Stand Improvement

Scenario #2 - Single Stem - Chemical

Scenario Description:

Adjust species composition and/or density of a stand of trees to meet objectives. The operation is carried out using hand tools with chemical treatment such as cut stump treatment, hack and squirt, basal spray. or back pack spray. Species that sprout are targeted (i.e. oak, hickory, elm, etc.). This scenario is NOT appropriate to target species that DO NOT sprout. Resource concerns can include: Forage Quality and Palatability, Noxious and Invasive Plants, Plants not adapted or suited, Productivity, Health and Vigor, Wildfire Hazard, Inadequate Cover/Shelter, Inadequate Quantities and Quality of Feed and Forage, Excessive Greenhouse Gas - CO2 (carbon dioxide), or Classic Gully.

Before Situation:

The existing condition of the stand cannot meet the landowners objectives because the composition consists of unwanted species and the stocking exceeds the recommended level.

After Situation:

The composition of the stand can meet the landowners objectives and the growth, condition and quality of the remaining trees are improved.

Feature Measure: Acres treated

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $7,729.28

Scenario Cost/Unit: $193.23

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	96	$6,296.64
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	8	$673.44
Materials						
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.98	40	$759.20

Practice: 666 - Forest Stand Improvement

Scenario #3 - Chemical-Ground-Light Equipment

Scenario Description:

Using ground applied herbicides to release young desirable trees from competing and/or overtopping vegetation using ground-based machinery (typical farm equipment). Typical sites include abandoned fields, pastures, or agricultural fields. Resource concerns can include: Forage Quality and Palatability, Noxious and Invasive Plants, Plants not adapted or suited, Productivity, Health and Vigor, Wildfire Hazard, Inadequate Cover/Shelter, Inadequate Quantities and Quality of Feed and Forage, Excessive Greenhouse Gas - CO2 (carbon dioxide), or Classic Gully.

Before Situation:

An adequately stocked stand of desirable species is not meeting objective due to undesirable vegetation. If left uncontrolled, undesirable vegetation will inhibit desired species. Noxious and invasive species may also be present on the site. Application of herbicides will be by ground equipment as an over-the-top spray.

After Situation:

The released stand of trees contains the composition and quality needed to meet the landowner's objectives and address the resource concerns.

Feature Measure: Acres treated

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $2,287.33

Scenario Cost/Unit: $57.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	40	$248.00
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	6	$217.08
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	40	$1,513.20
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	40	$52.40
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 666 - Forest Stand Improvement

Scenario #4 - Chemical-Ground-Heavy Equipment

Scenario Description:

Using ground applied herbicides to release young desirable trees from competing and/or overtopping vegetation using ground-based machinery (dozers or skidders and NOT typical farm equipment). Typical sites include forestland with terrain too rough and uneven or vegetation too big or thick to be sprayed with normal farm equipment. Resource concerns can include: Forage Quality and Palatability, Noxious and Invasive Plants, Plants not adapted or suited, Productivity, Health and Vigor, Wildfire Hazard, Inadequate Cover/Shelter, Inadequate Quantities and Quality of Feed and Forage, Excessive Greenhouse Gas - CO2 (carbon dioxide), or Classic Gully.

Before Situation:

An adequately stocked stand of desirable species is not meeting objective due to undesirable vegetation. If left uncontrolled, undesirable vegetation will inhibit desired species. Noxious and invasive species may also be present on the site. Application of herbicides will be by ground equipment as an over-the-top spray.

After Situation:

The released stand of trees contains the composition and quality needed to meet the landowner's objectives and address the resource concerns.

Feature Measure: Acres treated

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $7,072.25

Scenario Cost/Unit: $176.81

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application, wildland	1313	Chemical application performed by ground equipment. Includes forestry application methods that include heavy equipment such as skidders. Includes material, equipment, power unit and labor costs.	Acre	$118.18	40	$4,727.20
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	40	$1,513.20
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	40	$52.40
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	1	$490.01

Practice: 666 - Forest Stand Improvement

Scenario #5 - Chemical, Aerial

Scenario Description:

Using aerially applied chemicals to release desirable trees from competing and/or overtopping vegetation. Resource concerns can include: Forage Quality and Palatability, Noxious and Invasive Plants, Plants not adapted or suited, Productivity, Health and Vigor, Wildfire Hazard, Inadequate Cover/Shelter, Inadequate Quantities and Quality of Feed and Forage, Excessive Greenhouse Gas - CO2 (carbon dioxide), or Classic Gully.

Before Situation:

An adequately stocked stand of desirable species and trees is not growing to its potential for the site due to severe competition from undesirable trees and brush. Releasing the desirable trees from the competition will be achieved through the application of appropriate herbicides according to label directions. Application will be by helicopter as an over-the-top spray. The work will be professionally planned and supervised.

After Situation:

The released stand of trees contains the composition and quality needed to meet the landowner's objectives and address the resource concerns.

Feature Measure: Area treated

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $3,855.96

Scenario Cost/Unit: $96.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, aerial application, helicopter	1991	Chemical application performed by helicopter on forest only. Includes equipment, mobilization, and labor.	Acre	$32.78	40	$1,311.20
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	40	$754.80
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	40	$1,513.20
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	40	$52.40

Practice: 666 - Forest Stand Improvement

Scenario #6 - Mechanical, Light Equipment

Scenario Description:

Using light equipment (typically tractors used in normal farming operations) to control undesirable vegetation (disk or bush hog) competing with desirable species. Resource concerns can include: Forage Quality and Palatability, Noxious and Invasive Plants, Plants not adapted or suited, Productivity, Health and Vigor, Wildfire Hazard, Inadequate Cover/Shelter, Inadequate Quantities and Quality of Feed and Forage, Excessive Greenhouse Gas - CO2 (carbon dioxide), or Classic Gully.

Before Situation:

A stand of young, desirable trees is adversely affected by competition either from undesirable species or because the stand is overstocked. The vegetation to be controlled is small enough that it can be mowed or shredded. The work can be done by mowing or shredding strips through the stand, mowing between planted rows, etc.

After Situation:

After adjusting the stocking to an acceptable level and/or controlling the competing vegetation, stand growth, condition, and overall quality is improved. In addition, wildlife habitat is improved with the resulting increase of sunlight reaching the forest floor.

Feature Measure: Area Treated

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $2,630.09

Scenario Cost/Unit: $65.75

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	32	$1,678.72
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	32	$694.72
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 666 - Forest Stand Improvement

Scenario #7 - Mechanical, Medium Equipment

Scenario Description:

Using medium equipment (usually hydro ax & not typical farming equipment) to control undesirable competing vegetation that is competing with desirable species or to reduce the stocking level of a stand of desirable trees too big to be mowed with a bush hog. Resource concerns can include: Forage Quality and Palatability, Noxious and Invasive Plants, Plants not adapted or suited, Productivity, Health and Vigor, Wildfire Hazard, Inadequate Cover/Shelter, Inadequate Quantities and Quality of Feed and Forage, Excessive Greenhouse Gas - CO2 (carbon dioxide), or Classic Gully.

Before Situation:

A stand of desirable trees is adversely affected by competition either from undesirable species, cull trees, or because the stand is overstocked. The vegetation to be controlled is too large to be mowed.

After Situation:

The released stand of trees contains the composition and quality needed to meet the landowner's objectives and address the resource concerns.

Feature Measure: Area treated

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $6,034.45

Scenario Cost/Unit: $150.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Brush Chipper, 6" capacity	938	Brush Chipper, 6" capacity, typically 35 HP. Includes chipper and power unit. Labor not included.	Hour	$21.47	80	$1,717.60
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	20	$440.40
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	80	$2,054.40
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	20	$723.60
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	10	$841.80
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 666 - Forest Stand Improvement

Scenario #8 - Mechanical, Heavy Equipment

Scenario Description:

Using heavy equipment (usually bull dozers, masticator, or mulcher & not typical farming equipment) to control undesirable competing vegetation that is competing with desirable species or to reduce the stocking level of a stand of desirable trees too big to be mowed. Resource concerns can include: Forage Quality and Palatability, Noxious and Invasive Plants, Plants not adapted or suited, Productivity, Health and Vigor, Wildfire Hazard, Inadequate Cover/Shelter, Inadequate Quantities and Quality of Feed and Forage, Excessive Greenhouse Gas - CO2 (carbon dioxide), or Classic Gully.

Before Situation:

A stand of desirable trees is adversely affected by competition either from undesirable species, cull trees, or because the stand is overstocked. The vegetation to be controlled is too large to be mowed or shredded. Therefore other mechanical methods such as using masticators or mulchers is necessary.

After Situation:

The released stand of trees contains the composition and quality needed to meet the landowner's objectives and address the resource concerns.

Feature Measure: Area treated

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $13,515.43

Scenario Cost/Unit: $337.89

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	$86.58	110	$9,523.80
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	110	$2,388.10
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	16	$1,346.88
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: 670 - Lighting System Improvement

Scenario #1 - Lighting, CFL

Scenario Description:

To install dimmable CFLs to replace incandescent lamps on a one-for-one basis. Light fixtures do not have to be replaced. A typical poultry house has 48 fixtures. CFL requirements: minimum 8 Watt, 4100 Kelvin, dimmable, grow-out bulb; industrial grade; suitably protected from dirt accumulation. In high humidity environments or areas subject to wash down, gasketed or weatherproof housings are required to prevent corrosion and premature failure.

Before Situation:

An inefficient lighting system such as one using incandescent lamps has been identified by an on-farm energy audit.

After Situation:

More efficient lighting is provided by Compact Fluorescent Lamps (CFLs) in order to reduce energy use as evidenced by the energy audit. Associated practices/activities: 122-AgEMP - HQ and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each lamp replaced

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $18.88

Scenario Cost/Unit: $18.88

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	0.17	$3.23
Materials						
Lighting, bulb, CFL, 8 watt	1166	8 watt compact fluorescent lamp (CFL), typically 4100 Kelvin, dimmable, grow-out bulb, industrial grade, suitably protected from dirt accumulation. Materials only.	Each	$15.65	1	$15.65

Practice: 670 - Lighting System Improvement

Scenario #2 - Lighting, LED

Scenario Description:

To install dimmable LEDs to replace incandescent lamps on a one-for-one basis. Light fixtures do not have to be replaced. A typical poultry house has 48 fixtures. LED requirements: minimum 6 Watt, 3700 Kelvin, dimmable, grow-out bulb; industrial grade; suitably protected from dirt accumulation. In high humidity environments or areas subject to wash down, gasketed or weatherproof housings are required to prevent corrosion and premature failure.

Before Situation:

An inefficient lighting system such as one using incandescent lamps has been identified by an on-farm energy audit.

After Situation:

More efficient lighting is provided by Light-Emitting Diode (LED) lamps in order to reduce energy use as evidenced by the energy audit. Associated practices/activities: 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each lamp replaced

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $14.07

Scenario Cost/Unit: $14.07

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	0.17	$3.23
Materials						
Lighting, bulb, LED, 6 watt	1167	6 watt light emitting diode (LED), typically 3700 Kelvin, dimmable, grow-out bulb; industrial grade; suitably protected from dirt accumulation. Materials only.	Each	$10.84	1	$10.84

Practice: 670 - Lighting System Improvement

Scenario #3 - Lighting, Linear Fluorescent

Scenario Description:

The lighting system consists of a four-foot, three-lamp fixture with a single electronic ballast. The high-efficiency lighting system uses high-efficiency T8 or T5 fluorescent lamps. Associated materials for installation of replacement fixtures are included. Appropriate disposal of existing lamps, ballasts and other materials is required.

Before Situation:

Inefficient lighting (such as incandescent or T12 fluorescent tubes driven by magnetic ballasts) as evidenced by an on-farm energy audit.

After Situation:

High-efficiency lighting system which reduces energy use. The new lighting equipment will provide suitable light levels and reduce overall power requirements (kW) compared to the existing lighting system as evidenced by the energy audit. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each fixture replaced

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $359.45

Scenario Cost/Unit: $359.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	1	$27.38
Materials						
Lighting, fixture, Fluorescent, 75 watt	1168	75 watt fluorescent lamp fixture with T5 or T8 lamps and ballast. Materials only.	Each	$332.07	1	$332.07

Practice: 670 - Lighting System Improvement

Scenario #4 - Lighting, Pulse-Start Metal Halide

Scenario Description:

The lighting system consists of a Pulse-Start Metal Halide (PSMH) lamp with a matched ballast or light-emitting diode (LED) equivalent fixtures (as detailed in ASABE S612-compliant energy audit). Associated materials for installation of replacement fixtures are included. Appropriate disposal of existing lamps, ballasts and other materials is required

Before Situation:

Inefficient high-bay or exterior lighting (such as mercury vapor, T12 fluorescent, or similar) as evidenced by an on-farm energy audit.

After Situation:

High-efficiency lighting system which reduces energy use. The new lighting equipment will provide suitable light levels and reduce overall power requirements (kW) compared to the existing lighting system as evidenced by the energy audit. Associated practices/activities: may include 122-AgEMP - HQ and activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each fixture replaced

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $28.39

Scenario Cost/Unit: $28.39

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	1	$27.38
Materials						
Lighting, Pulse Start Metal Halide	2425	Replacement of lighting with PSMH Light.	Watt	$1.01	1	$1.01

Practice: 672 - Building Envelope Improvement

Scenario #1 - Building Envelope, Attic Insulation

Scenario Description:

Install a minimum R-7 insulation in addition to existing attic or ceiling to reduce heat transfer. Increased insulation reduces seasonal heat loss and heat gain which reduces the respective need for heating and cooling equipment to operate.

Before Situation:

A poultry house with an inefficient building envelope with limited attic insulation.

After Situation:

A more effective and efficient building envelope can be created through addition of, or increased, attic insulation. Associated practices/activities: 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Area of Attic Insulated

Scenario Unit:: Square Foot

Scenario Typical Size: 20,000.0

Scenario Total Cost: $6,045.59

Scenario Cost/Unit: $0.30

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	48	$912.00
Materials						
Insulation material, cellulose	2272	Cellulose insulation. Unit is a measurement of the in-place volume after being blown. Includes materials only.	Cubic Foot	$0.77	6667	$5,133.59

Practice: 672 - Building Envelope Improvement

Scenario #2 - Building Envelope, Wall Insulation

Scenario Description:

Enclose both sidewalls and endwalls from ceiling to floor in one of two manners: 1) metal exterior, 3.5" fiberglass batts (R-11), vapor barrier, & interior plywood or OSB sheathing, or 2) closed-cell polyurethane foam application (minimum 1" thickness (R-7) of 2.5 lbs/cu.ft. or higher density, (3.0 or higher density preferred) with a form of physical protective barrier on lower 2' (may be 6 lbs/cu.ft. or higher density 1/8" thick foam, or treated lumber). Based on a 40' x 400' poultry house.

Before Situation:

A poultry house with an inefficient building envelope with limited wall insulation.

After Situation:

A more effective and efficient building envelope can be created through addition of, or increased, insulation. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Area of Wall Insulated

Scenario Unit:: Square Foot

Scenario Typical Size: 4,500.0

Scenario Total Cost: $8,550.00

Scenario Cost/Unit: $1.90

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Insulation, polyurethane, R-7, with sheathing skirt	1198	Closed-cell polyurethane foam insulation (minimum 1" thickness (R-7) with a protective sheeting barrier on lower 2 feet of wall height. Includes materials, equipment and labor to install.	Square Foot	$1.90	4500	$8,550.00

Practice: 672 - Building Envelope Improvement

Scenario #3 - Building Envelope, Sidewall Renovation

Scenario Description:

Renovate sidewalls from top of footer to eave to remove flexible curtains and construct an insulated permanent wall in one of two manners: 1) metal exterior, 3.5" fiberglass batts (R-11), vapor barrier, & interior plywood or OSB sheathing, or 2) closed-cell polyurethane foam application (minimum 1" thickness (R-7) of 2.5 lbs/cu.ft. or higher density, (3.0 or higher density preferred) with a form of physical protective barrier on lower 2' (may be 6 lbs/cu.ft. or higher density 1/8" thick foam, or treated lumber). Based on a 40' x 400' poultry house.

Before Situation:

A poultry house has plastic or flexible drop-down curtains in one or more walls. The curtains, which provide little thermal resistance, are obsolete due to changes in the ventilation scheme of the house.

After Situation:

A more effective and efficient building envelope can be created through addition of, or increased, insulation. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Area of Wall Renovated

Scenario Unit:: Square Foot

Scenario Typical Size: 4,620.0

Scenario Total Cost: $16,766.00

Scenario Cost/Unit: $3.63

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	80	$1,520.00
Materials						
Corrugated Steel, 28 gage	223	Corrugated or ribbed, galvanized, 28 gauge, includes fasteners, materials only.	Square Foot	$1.40	4620	$6,468.00
Insulation, polyurethane, R-7, with sheathing skirt	1198	Closed-cell polyurethane foam insulation (minimum 1" thickness (R-7) with a protective sheeting barrier on lower 2 feet of wall height. Includes materials, equipment and labor to install.	Square Foot	$1.90	4620	$8,778.00

Practice: 672 - Building Envelope Improvement

Scenario #4 - Building Envelope, Sealant, Open Truss

Scenario Description:

A typical scenario is sealing the gaps between walls, gables, ceiling, etc. in a poultry house or greenhouse. Sealing is performed by a professional contractor, not merely use of spray foam from a can. The unit basis of payment in this scenario is each house based on 60' x 500' poultry house with an assumed need of sealant to seal 2400 linear feet of gap.

Before Situation:

An agricultural facility with an inefficient building envelope with gaps between walls, ceiling, etc. for a total of 2400 linear feet.

After Situation:

A more effective and efficient building envelope can be created through interior sealing of the exterior walls at the footer plate, eaves, ridge cap, and gable ends. The sealant reduces seasonal heat loss and heat gain due to infiltration which reduces the respective need for heating and cooling equipment to operate. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Length of House

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: $4,260.00

Scenario Cost/Unit: $8.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Sealant	1150	Greenhouse and building gap sealant. Performed by a professional contractor spraying the areas with an approved sealant for poultry production facilities. Includes materials, equipment and labor to install.	Foot	$1.42	3000	$4,260.00

Practice: 672 - Building Envelope Improvement

Scenario #5 - Building Envelope, Sealant, Drop Ceiling

Scenario Description:

A typical scenario is sealing the gaps between walls, gables, ceiling, etc. in a poultry house or greenhouse. Sealing is performed by a professional contractor, not merely use of spray foam from a can. The unit basis of payment in this scenario is each house based on 60' x 500' poultry house with an assumed need of sealant to seal 2400 linear feet of gap.

Before Situation:

An agricultural facility with an inefficient building envelope with gaps between walls, ceiling, etc. for a total of 2400 linear feet.

After Situation:

A more effective and efficient building envelope can be created through interior sealing of the exterior walls at the footer plate, eaves, ridge cap, and gable ends. The sealant reduces seasonal heat loss and heat gain due to infiltration which reduces the respective need for heating and cooling equipment to operate. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Length of House

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: $2,130.00

Scenario Cost/Unit: $4.26

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Sealant	1150	Greenhouse and building gap sealant. Performed by a professional contractor spraying the areas with an approved sealant for poultry production facilities. Includes materials, equipment and labor to install.	Foot	$1.42	1500	$2,130.00

Practice: 672 - Building Envelope Improvement

Scenario #6 - Building Envelope, Greenhouse Screens

Scenario Description:

The mechanical energy screen system consists of a drive motor, support cables, controls, and shade material, which may be woven, knitted, or non-woven strips of aluminum fiber, polyethylene, nylon or other synthetic material. The screen provides a means to better control solar heat gain and heat transfer during night or cold weather conditions to reduce energy use. Screens and similar devices may also be used to divide internal areas and allow for differentiated heating, ventilation, or cooling system operation to reduce energy use.

Before Situation:

Heating and cooling of an existing greenhouse, or similar structure with conditioned spaces, is inefficient due to poorly regulated heat transfer. A need to regulate an entire space for uniform conditions when some portions have differing, intermittent requirements can also reduce efficiency.

After Situation:

The greenhouse is fitted with a mechanically controlled energy screen installed truss-to-truss or gutter-to-gutter, with side screens as necessary, reducing heat loss in the greenhouse. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Area of Screen

Scenario Unit:: Square Foot

Scenario Typical Size: 25,000.0

Scenario Total Cost: $52,688.08

Scenario Cost/Unit: $2.11

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
Materials						
Thermal blanket 10,001 - 50,000 square foot	1148	Thermal blanket greenhouse screens: mechanical energy screen system consists of a drive motor, support cables, controls, and shade material, which may be woven, knitted, or non-woven. Size Range is 10,001 to 50,000 square feet. Materials only.	Square Foot	$2.09	25000	$52,250.00

Practice: 672 - Building Envelope Improvement

Scenario #7 - Greenhouse, Insulate Unglazed Walls

Scenario Description:

A typical scenario is the installation insulation in green house to address energy loss. The insulation can be either of the cellulose or bubble type (or equivalent). The increased insulation reduces seasonal heat loss and heat gain which reduces the respective need for heating and cooling equipment to operate.

Before Situation:

Green house with standard glazing, plastic or polycarbonate walls and no insulation. Heating and cooling of an existing greenhouse is inefficient due to excessive heat loss.

After Situation:

The greenhouse is fitted with insulation installed truss-to-truss or gutter-to-gutter and/or non glazed endwalls and/or sidewalls, reducing heat loss and gain in the greenhouse. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Square Feet of insulation

Scenario Unit:: Square Foot

Scenario Typical Size: 25,000.0

Scenario Total Cost: $7,938.08

Scenario Cost/Unit: $0.32

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
Materials						
Insulation, Greenhouse, Reflective Bubble	2410	Double bubble reflective insulation with aluminum foil on both sides. Includes materials and shipping only.	Square Foot	$0.30	25000	$7,500.00

Practice: 672 - Building Envelope Improvement

Scenario #8 - Building Envelope, Insulated Roll-Up Door

Scenario Description:

A typical scenario is the replacement of non-insulated rollup doors on poultry houses with insulated rollup doors. The increased insulation reduces seasonal heat loss and heat gain which reduces the respective need for heating and cooling equipment to operate.

Before Situation:

Poultry house has non-insulated or inefficiently insulated rollup doors causing high heat loss or gain.

After Situation:

A more effective and efficient energy seal can be created through the addition of, or increased R-value, insulated rollup doors. Associated practices/activities: may include 122-AgEMP - HQ, 672-Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each Door

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $1,528.60

Scenario Cost/Unit: $1,528.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	5	$95.00
Materials						
Door, Insulated, Roll-up	2392	Rolling service insulated steel door, 20 gauge. Includes hardware required to install. Used to replace non insulated door in buildings. Materials only.	Square Foot	$8.96	160	$1,433.60

Practice: 672 - Building Envelope Improvement

Scenario #9 - Building Envelope, Brood Curtain

Scenario Description:

Replace an existing uninsulated curtain with a seven-layer insulated curtain with an R-value of 3 for a livestock building. The curtain's two outer layers are vinyl and polyethylene and the five inner layers are composed of insulating materials with air trapping fibers and a vapor barrier. Payment includes curtain and labor to install. Payment does not includes mounting accessories because the scenario presumes the curtain is replacing an existing curtain.

Before Situation:

The broiler house has an uninsulated mid-house brooding curtain or a brooding curtain which is in poor condition with holes and rips. Either condition allows a significant loss of heat to the off-end during the high-heat period of brooding.

After Situation:

A seven-layer insulated curtain is installed as a replacement for an existing less efficient curtain on a livestock building. Associated practices/activities: may include 122-AgEMP - HQ, 672-Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each Brood Curtain

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $953.00

Scenario Cost/Unit: $953.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	10	$190.00
Materials						
Curtain , 7-Layer, R3 Insulated	2427	Seven layer insulated curtain with an R-value of 3 for a livestock building. Typical curtain size is 4' x 270'. The curtain's two outer layers are vinyl and polyethylene and the five inner layers are composed of insulating materials with air trapping fibers and a vapor barrier. Does not include mounting accessories, assumes it is replacing a non-insulated curtain.	Square Foot	$2.18	350	$763.00

Practice: 672 - Building Envelope Improvement

Scenario #68 - Building Envelope, Tunnel Doors

Scenario Description:

A typical scenario is the installation of tunnel doors to replace tunnel curtain openings. Tunnel curtain openings are typically 5 ft. by 60 ft. for a 40 ft. by 500 ft. poultry house; 600 sq. ft. of opening per house.

Before Situation:

A 40 ft. by 500 ft. poultry house with an inefficient building envelope having 5 ft. by 60 ft. tunnel curtain openings.

After Situation:

A more effective and efficient building envelope can be created through replacement of the tunnel curtain openings with tunnel doors. Associated practices/activities: may include 128-AgEMP, and other activities within 672-Building Envelope Improvement and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Sq. Ft. of opening

Scenario Unit:: Square Foot

Scenario Typical Size: 600.0

Scenario Total Cost: $7,230.00

Scenario Cost/Unit: $12.05

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	24	$456.00
Materials						
Tunnel doors	2413	Tunnel doors are used to replace curtains on tunnel inlets in a poultry house. Includes materials only.	Square Foot	$11.29	600	$6,774.00

Practice: B000BFF1 - Buffer Bundle#1

Scenario #1 - Buffer Bundle#1

Scenario Description:
Addresses water quality degradation, degraded plant condition, fish/wildlife inadequate habitat, and/or air quality impacts.

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 3.0

Scenario Total Cost: $2,256.93

Scenario Cost/Unit: $752.31

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	1	$11.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	10	$123.60
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	10	$190.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	1	$18.87
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	1	$26.78

Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	1	$1.31
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.56	341	$190.96
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	340	$102.00
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	$57.97	1	$57.97
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	$252.12	1	$252.12
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: B000BFF2 - Buffer Bundle#2

Scenario #1 - Buffer Bundle#2

Scenario Description:
Addresses water quality degradation, degraded plant condition, fish/wildlife inadequate habitat, and/or air quality impacts.

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 3.0

Scenario Total Cost: $2,256.93

Scenario Cost/Unit: $752.31

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	1	$11.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	10	$123.60
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	10	$190.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	1	$18.87
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	1	$26.78

Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	1	$1.31
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.56	341	$190.96
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	340	$102.00
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	$57.97	1	$57.97
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	$252.12	1	$252.12
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: B000CPL1 - Crop Bundle#1 - Precision Ag, No till

Scenario #1 - Crop Bundle#1 - Precision Ag, No till

Scenario Description:
?Addresses water quality degradation, air quality, and fish/wildlife inadequate habitat plus an option on soil erosion or soil quality degradation

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $3,480.29

Scenario Cost/Unit: $34.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$9.96	100	$996.00
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$10.78	100	$1,078.00
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.51	$201.02
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.45	$93.20
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.29	$45.10
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	1	$36.18
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	8	$673.44
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	35	$357.35

Practice: B000CPL2 - Crop Bundle#2 - Precision Ag, Reduced till

Scenario #1 - Crop Bundle#2 - Precision Ag, RT

Scenario Description:
?Addresses water quality degradation, air quality, and fish/wildlife inadequate habitat plus an option on soil erosion or soil quality degradation

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $3,480.29

Scenario Cost/Unit: $34.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$9.96	100	$996.00
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$10.78	100	$1,078.00
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.51	$201.02
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.45	$93.20
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.29	$45.10
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	1	$36.18
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	8	$673.44
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	35	$357.35

Practice: B000CPL3 - Crop Bundle#3 - Soil health rotation, No till

Scenario #1 - Crop Bundle#3 - Soil health rotation, NT

Scenario Description:
Addresses soil quality degradation, insufficient water, water quality degradation, and fish/wildlife inadequate habitat

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $3,832.57

Scenario Cost/Unit: $38.33

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$9.96	100	$996.00
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$10.78	100	$1,078.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	13	$1,094.34
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	35	$357.35
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	$252.12	1	$252.12

Practice: B000CPL4 - Crop Bundle#4 - Soil health rotation, Reduced till

Scenario #1 - Crop Bundle#4 - SH rotation, RT

Scenario Description:
?Addresses soil quality degradation, insufficient water, water quality degradation, and fish/wildlife inadequate habitat

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $3,832.57

Scenario Cost/Unit: $38.33

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$9.96	100	$996.00
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$10.78	100	$1,078.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	13	$1,094.34
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	35	$357.35
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	$252.12	1	$252.12

Practice: B000CPL5 - Crop Bundle#5 - Soil Health Assessment, No till

Scenario #1 - Crop Bundle#5 - SH Assessment, NT

Scenario Description:
?Addresses soil quality degradation, insufficient water, water quality degradation, and fish/wildlife inadequate habitat

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $4,238.26

Scenario Cost/Unit: $42.38

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$9.96	100	$996.00
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$10.78	100	$1,078.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	16	$1,346.88
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	15	$153.15
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	35	$357.35
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	$252.12	1	$252.12

Practice: B000CPL6 - Crop Bundle#6 - Soil Health Assessment, Reduced till

Scenario #1 - Crop Bundle#6 - SH Assessment, RT

Scenario Description:
?Addresses soil quality degradation, insufficient water, water quality degradation, and fish/wildlife inadequate habitat

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $4,238.26

Scenario Cost/Unit: $42.38

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$9.96	100	$996.00
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$10.78	100	$1,078.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	16	$1,346.88
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	15	$153.15
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	35	$357.35
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	$252.12	1	$252.12

Practice: B000CPL7 - Crop Bundle#7 - Soil Health -"Organic"

Scenario #1 - Crop Bundle#7 - Soil Health -"Organic"

Scenario Description:
Addresses soil quality degradation, water quality degradation, and fish/wildlife inadequate habitat

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $3,696.41

Scenario Cost/Unit: $36.96

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	1	$11.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	10	$123.60
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	10	$273.80
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	10	$190.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54

Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Nitrogen-Urease inhibitor	260	Nitrogen-Urease inhibitor	Acre	$8.19	100	$819.00
Test, Soil Nitrogen Testing	311	Pre-Side Dress/Deep Soil Testing. Includes materials and shipping only.	Each	$12.86	5	$64.30
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	1	$18.87
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	1	$26.78
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	1	$1.31
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.56	341	$190.96
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	340	$102.00
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	$57.97	1	$57.97
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: B000CPL8 - Crop Bundle#8 - "Organic", Water erosion

Scenario #1 - Crop Bundle#8 - "Organic", Water erosion

Scenario Description:
Addresses soil erosion, soil quality degradation, and water quality degradation plus an option on fish/wildlife inadequate habitat

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $3,000.75

Scenario Cost/Unit: $30.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	1	$27.38
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	14	$1,178.52
Materials						
Nitrogen-Urease inhibitor	260	Nitrogen-Urease inhibitor	Acre	$8.19	100	$819.00
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	15	$153.15
Test, Soil Nitrogen Testing	311	Pre-Side Dress/Deep Soil Testing. Includes materials and shipping only.	Each	$12.86	5	$64.30
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	20	$758.40

USDA - Natural Resources Conservation Service

Mississippi

Practice: B000FST1 - Forest Bundle#1

Scenario #1 - Forest Bundle#1

Scenario Description:

Addresses forest management on sites that are not adapted to natural fire disturbances. Addresses resource concerns air quality impacts, degraded plant condition and fish/wildlife inadequate habitat.

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 111.0

Scenario Total Cost: $8,193.58

Scenario Cost/Unit: $73.82

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	45	$198.45
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	15	$330.30
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	41	$2,689.19
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	11	$135.96
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	7	$191.66
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	49	$931.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	12	$1,010.16
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	17	$1,264.97
Materials						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	$7.07	20	$141.40
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	1	$18.87

Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.98	21	$398.58
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	1	$26.78
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	1	$1.31
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.56	605	$338.80
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	218	$65.40
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

USDA - Natural Resources Conservation Service

Mississippi

Practice: B000LLP1 - Longleaf Pine Bundle#1

Scenario #1 - Longleaf Pine Bundle#1

Scenario Description:

Improves conifer forest health through prescribed burning and grazing management. Addresses water quality degradation, degraded plant condition, and fish/wildlife inadequate habitat.

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 110.0

Scenario Total Cost: $9,228.70

Scenario Cost/Unit: $83.90

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	$7.39	5	$36.95
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	7	$30.87
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	5	$110.10
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	16	$352.32
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	1	$22.02
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	2	$104.92
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	5	$125.20
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	4	$100.16
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	3	$196.77
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	2	$57.16
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	16	$197.76
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	$2.45	2	$4.90
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.82	$323.21
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.72	$149.12
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.46	$71.53
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	12	$203.16
Labor						

Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	7	$191.66
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	32	$876.16
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	33	$627.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	4	$86.84
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	5	$108.55
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	4	$144.72
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54
Materials						
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	$72.51	4	$290.04
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	$6.38	20	$127.60
Post, Wood, CCA treated, 6" x 8'	12	Wood Post, End 6" X 8', CCA Treated. Includes materials and shipping only.	Each	$15.38	8	$123.04
Post, Steel T, 1.33 lbs, 6'	15	Steel Post, Studded 6' - 1.33 lb. Includes materials and shipping only.	Each	$6.81	90	$612.90
Fence, Wire Assembly, Barbed Wire	30	Brace pins, battens, clips, staples. Includes materials and shipping only.	Foot	$0.17	1320	$224.40
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	1	$18.87
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.98	1	$18.98
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	1	$26.78
Gate, Pipe, 12'	1057	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	$169.37	2	$338.74
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	1	$1.31
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	872	$261.60
Tree shelter, solid tube type, 4" x 48"	1566	4" x 48" tree tube for protection from animal damage. Materials only.	Each	$4.22	100	$422.00
Stakes, wood, 1" x 1" x 48"	1578	1" x 1" x 48" wood stakes to fasten items in place. Includes materials only.	Each	$2.07	100	$207.00

Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	$4.39	5	$21.95
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: B000LLP2 - Longleaf Pine Bundle#2

Scenario #1 - Longleaf Pine Bundle#2

Scenario Description:
Improves conifer forest health through prescribed burning and forest stand management. Addresses air quality impacts, degraded plant condition, and fish/wildlife inadequate habitat.

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 125.0

Scenario Total Cost: $9,841.68

Scenario Cost/Unit: $78.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	150	$661.50
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	7	$30.87
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	15	$330.30
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	1	$22.02
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	3	$196.77
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	2	$57.16
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	$2.45	2	$4.90
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	7	$191.66
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	150	$2,850.00
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	30	$2,525.40
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54

CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	17	$1,264.97
Materials						
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.98	1	$18.98
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	$4.39	5	$21.95
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	$252.12	1	$252.12
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: B000LLP4 - Longleaf Pine Bundle #4

Scenario #4 - Longleaf Pine Bundle #4

Scenario Description:
Improves forest health and wildlife habitat through conversion of forest stands that are not predominantly longleaf pine. Addresses degraded plant condition, fish/wildlife inadequate food and habitat, and water quality.

Before Situation:
Resources are protected at the minimum level of the conservation practice standards applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standards applied.

Feature Measure: Acres

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $19,972.83

Scenario Cost/Unit: $399.46

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	157	$692.37
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	32	$704.64
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	$86.58	20	$1,731.60
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	10	$62.00
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	23	$1,508.57
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	4	$114.32
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	$2.45	2	$4.90
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	39	$1,067.82
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	200	$3,800.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	20	$434.20
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	72	$6,060.96
Materials						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	$7.07	10	$70.70
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	30	$1,134.90
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.98	1	$18.98
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	10	$13.10

Tree, conifer, seedling, containerized, 4 cu. in.	1516	Containerized conifer stock, 4 cubic inches (e.g., "4a" plug), 1.1" x 5.2". Includes materials and shipping only.	Each	$0.25	6050	$1,512.50
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	$4.39	6	$26.34
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	3	$769.95

Practice: B000LLP5 - Longleaf Pine Bundle #5

Scenario #4 - Longleaf Pine Bundle #5

Scenario Description:
Improves conifer forest health through prescribed burning and forest stand management, and reduction of pine straw raking. Addresses soil and water quality, degraded plant condition, and fish/wildlife inadequate habitat.

Before Situation:
Resources are protected at the minimum level of the conservation practice standards applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standards applied.

Feature Measure: Acres

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $20,400.72

Scenario Cost/Unit: $408.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	157	$692.37
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	20	$440.40
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	$86.58	16	$1,385.28
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	19	$1,246.21
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	6	$171.48
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	$2.45	2	$4.90
Foregone Income						
FI, reduced pine straw raking	2691	Longleaf pine needles are primary crop.	Acre	$127.12	50	$6,356.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	23	$629.74
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	152	$2,888.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	16	$347.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	54	$4,545.72
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	10	$102.10
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	$7.07	5	$35.35
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	20	$756.60
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.98	1	$18.98

Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	$4.39	5	$21.95
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

USDA - Natural Resources Conservation Service

Mississippi

Practice: B000MRB1 - MRBI Bundle#1 - Irrigated Cropland

Scenario #1 - MRBI Bundle#1 - Irrigated Cropland

Scenario Description:
Addresses soil erosion, insufficient water, and water quality degradation

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $5,892.57

Scenario Cost/Unit: $58.93

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	1	$27.38
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	20	$380.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	4	$336.72
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will include all materials (electrical, controllers, service drops and etc). This cost will include material, labor and equipment.	Each	$472.52	1	$472.52
Switches and Controls, temp sensors	1192	Temperature and soil moisture sensors installed as part of an electronic monitoring (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	$666.86	1	$666.86
Data Logger with Telemetry System	1454	Data Logger W/Graphic Output for water management and telemetry - data communication device with power supply in a weather proof enclosure. Equipment only.	Each	$1,723.25	1	$1,723.25
Soil Moisture Meter	1455	Soil Moisture Sensor Reader. Equipment only.	Each	$292.95	1	$292.95
Soil Moisture Sensor	1456	Soil moisture resistance sensor W/10' cables. Equipment only.	Each	$37.69	2	$75.38
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	20	$758.40
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance irrigation water management and for Activity 202 water quality monitoring .	Each	$1,088.24	1	$1,088.24
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87

Practice: B000MRB2 - MRBI Bundle#2 - Non-Irrigated Cropland #1

Scenario #1 - MRBI Bundle#2 - Non-Irrigated Crop#1

Scenario Description:
Addresses soil erosion, soil quality degradation, and water quality degradation

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $895.30

Scenario Cost/Unit: $8.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	5	$136.90
Materials						
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	20	$758.40

Practice: B000MRB3 - MRBI Bundle#3 - Non-Irrigated Cropland #2

Scenario #1 - MRBI Bundle#3 - Non-Irrigated Crop#2

Scenario Description:
Addresses soil erosion, soil quality degradation, and water quality degradation

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,206.68

Scenario Cost/Unit: $12.07

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	1	$27.38
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90
Materials						
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	20	$758.40

USDA - Natural Resources Conservation Service

Mississippi

Practice: B000MRB4 - MRBI Bundle#4 - Cropland with Water Bodies, No till

Scenario #1 - MRBI Bundle#4 - Crop w/ Water Bodies, NT

Scenario Description:
Addresses soil erosion, soil quality degradation, and water quality degradation

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $2,700.50

Scenario Cost/Unit: $27.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	10	$273.80
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	1	$27.38
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	6	$505.08
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54
Materials						
Nitrogen-Urease inhibitor	260	Nitrogen-Urease inhibitor	Acre	$8.19	100	$819.00
Test, Soil Nitrogen Testing	311	Pre-Side Dress/Deep Soil Testing. Includes materials and shipping only.	Each	$12.86	5	$64.30
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	20	$758.40

Practice: B000MRB5 - MRBI Bundle#5 - Cropland with Water Bodies, Reduced till

Scenario #1 - MRBI Bundle#5 - Crop w/ Water Bodies, RT

Scenario Description:
Addresses soil erosion, soil quality degradation, and water quality degradation

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $2,473.30

Scenario Cost/Unit: $24.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	10	$273.80
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	5	$136.90
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54
Materials						
Nitrogen-Urease inhibitor	260	Nitrogen-Urease inhibitor	Acre	$8.19	100	$819.00
Test, Soil Nitrogen Testing	311	Pre-Side Dress/Deep Soil Testing. Includes materials and shipping only.	Each	$12.86	5	$64.30
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	20	$758.40

USDA - Natural Resources Conservation Service

Mississippi

Practice: B000MRB6 - MRBI Bundle#6 - Pastureland

Scenario #1 - MRBI Bundle#6 - Pastureland

Scenario Description:
Addresses soil quality degradation, water quality degradation, and fish/wildlife inadequate habitat plus an option on soil erosion

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 101.0

Scenario Total Cost: $4,350.75

Scenario Cost/Unit: $43.08

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	$7.39	5	$36.95
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	5	$110.10
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	5	$125.20
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	25	$423.25
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	33	$627.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	5	$108.55
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	$72.51	4	$290.04
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	$6.38	20	$127.60
Post, Wood, CCA treated, 6" x 8'	12	Wood Post, End 6" X 8', CCA Treated. Includes materials and shipping only.	Each	$15.38	8	$123.04
Post, Steel T, 1.33 lbs, 6'	15	Steel Post, Studded 6' - 1.33 lb. Includes materials and shipping only.	Each	$6.81	90	$612.90
Fence, Wire Assembly, Barbed Wire	30	Brace pins, battens, clips, staples. Includes materials and shipping only.	Foot	$0.17	1320	$224.40
Gate, Pipe, 12'	1057	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	$169.37	2	$338.74
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	$47.90	20	$958.00
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

USDA - Natural Resources Conservation Service

Mississippi

Practice: B000PST1 - Pasture Bundle#1 - Organic

Scenario #1 - Pasture Bundle#1 - Organic

Scenario Description:
Addresses water quality degradation, degraded plant condition, and fish/wildlife inadequate habitat

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 111.0

Scenario Total Cost: $9,499.25

Scenario Cost/Unit: $85.58

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	$7.39	5	$36.95
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	5	$110.10
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	5	$125.20
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	30	$507.90
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	33	$627.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	5	$108.55
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	4	$336.72
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	1	$84.18
Materials						
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	$72.51	4	$290.04
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	$6.38	20	$127.60
Post, Wood, CCA treated, 6" x 8'	12	Wood Post, End 6" X 8', CCA Treated. Includes materials and shipping only.	Each	$15.38	8	$123.04
Post, Steel T, 1.33 lbs, 6'	15	Steel Post, Studded 6' - 1.33 lb. Includes materials and shipping only.	Each	$6.81	90	$612.90
Fence, Wire Assembly, Barbed Wire	30	Brace pins, battens, clips, staples. Includes materials and shipping only.	Foot	$0.17	1320	$224.40
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	1	$10.21
Gate, Pipe, 12'	1057	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	$169.37	2	$338.74
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	$566.31	10	$5,663.10
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: B000PST2 - Pasture Bundle#2

Scenario #1 - Pasture Bundle#2

Scenario Description:
Addresses soil quality degradation, water quality degradation, and degraded plant condition plus an option on fish/wildlife inadequate habitat

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 210.0

Scenario Total Cost: $3,342.48

Scenario Cost/Unit: $15.92

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	2	$131.18
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	6	$171.48
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	0	$0.00
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	10	$169.30
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	$48.49	1	$48.49
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	$325.35	1	$325.35
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.42	2000	$840.00
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	$262.29	1	$262.29
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	3	$30.63
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	$47.90	20	$958.00

Practice: B000PST3 - Pasture Bundle#3 -- Soil Health

Scenario #1 - Pasture Bundle#3 -- Soil Health

Scenario Description:
Addresses soil quality degradation, water quality degradation, and degraded plant condition

Before Situation:
Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $2,684.21

Scenario Cost/Unit: $26.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	0	$0.00
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	25	$423.25
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	32	$876.16
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	$47.90	20	$958.00

Practice: E314133Z - Brush management for improved structure and composition

Scenario #1 - Brush mgmt, improved structure and comp

Scenario Description:

Brush management is employed to create a desired plant community, consistent with the related ecological site steady state, which will maintain or enhance the wildlife habitat desired for the identified wildlife species. It will be designed to provide plant structure, density and diversity needed to meet those habitat objectives. This enhancement does not apply to removal of woody vegetation by prescribed fire or removal of woody vegetation to facilitate a land use change.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 314 - Brush Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 314 - Brush Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,433.76

Scenario Cost/Unit: $14.34

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	12	$203.16
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	32	$876.16
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44

Practice: E314134Z - Brush management that maintains or enhances wildlife or fish habitat

Scenario #1 - Brush mgmt, enhance habitat

Scenario Description:

Brush management is employed to create a desired plant community, consistent with the related ecological site steady state, which will maintain or enhance the wildlife habitat desired for the identified wildlife species. It will be designed to provide plant structure, density and diversity needed to meet those habitat objectives. This enhancement does not apply to removal of woody vegetation by prescribed fire or removal of woody vegetation to facilitate a land use change.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 314 - Brush Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 314 - Brush Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,433.76

Scenario Cost/Unit: $14.34

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	12	$203.16
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	32	$876.16
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44

Practice: E315132Z - Herbaceous weed control for desired plant communities/habitats consistent with the ecological site

Scenario #1 - Herbaceous weed control-habitats

Scenario Description:

Mechanical, chemical, or biological, herbaceous weed control will be employed to control targeted, herbaceous weeds so as to create, release, or restore desired plant communities that are consistent with achievable, ecological site, steady state descriptions.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 315 - Herbaceous Weed Control

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 315 - Herbaceous Weed Control

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $131.18

Scenario Cost/Unit: $13.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	2	$131.18

Practice: E315133Z - Herbaceous weed control (inadequate structure and comp) for desired plant communities/habitats

Scenario #1 - Herbaceous weed control-communities

Scenario Description:

Mechanical, chemical, or biological, herbaceous weed control will be employed to control targeted, herbaceous weeds so as to create, release, or restore desired plant communities that are consistent with achievable, ecological site, steady state descriptions.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 315 - Herbaceous Weed Control

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 315 - Herbaceous Weed Control

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $131.18

Scenario Cost/Unit: $13.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	2	$131.18

Practice: E315134Z - Herbaceous weed control (plant pest pressures) for desired plant communities/habitats

Scenario #1 - Herbaceous weed control-pest pressures

Scenario Description:

Mechanical, chemical, or biological, herbaceous weed control will be employed to control targeted, herbaceous weeds so as to create, release, or restore desired plant communities that are consistent with achievable, ecological site, steady state descriptions.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 315 - Herbaceous Weed Control

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 315 - Herbaceous Weed Control

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $131.18

Scenario Cost/Unit: $13.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	2	$131.18

Practice: E327136Z1 - Conservation cover to provide food habitat for pollinators and beneficial insects

Scenario #1 - Conservation cover-pollinator food

Scenario Description:

Seed or plug nectar and pollen producing plants in non-cropped areas such as field borders, vegetative barriers, contour buffer strips, grassed waterways, shelterbelts, hedgerows, windbreaks, conservation cover, and riparian forest and herbaceous buffers.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 327 - Conservation Cover

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 327 - Conservation Cover

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $306.88

Scenario Cost/Unit: $306.88

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Materials						
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	$252.12	1	$252.12

Practice: E327136Z2 - Establish Monarch butterfly habitat

Scenario #1 - Establish monarch butterfly habitat

Scenario Description:

Seed or plug milkweed (Asclepius spp.), the Monarch butterfly larval hostplant, and high-value monarch butterfly nectar plants in non-cropped areas such as field borders, contour buffer strips, and associated grasslands.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 327 - Conservation Cover

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 327 - Conservation Cover

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $2,329.31

Scenario Cost/Unit: $2,329.31

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	1	$52.46
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	2	$131.18
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	1	$84.18
Materials						
Highly Specialized native grass and forb mix	2618	A mix of native grass and forbs to be used for restoration of Monarch butterfly foraging and larva development habitat. Includes material and shipping only.	Acre	$1,981.35	1	$1,981.35

Practice: E327137Z - Conservation cover to provide cover and shelter habitat for pollinators and beneficial insects

Scenario #1 - Conservation cover-pollinator shelter

Scenario Description:

Seed or plug nectar and pollen producing plants in non-cropped areas such as field borders, vegetative barriers, contour buffer strips, grassed waterways, shelterbelts, hedgerows, windbreaks, conservation cover, and riparian forest and herbaceous buffers.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 327 - Conservation Cover

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 327 - Conservation Cover

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $306.88

Scenario Cost/Unit: $306.88

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Materials						
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	$252.12	1	$252.12

Practice: E327139Z - Conservation cover to provide habitat continuity for pollinators and beneficial insects

Scenario #1 - Conservation cover-habitat continuity

Scenario Description:

Seed or plug nectar and pollen producing plants in non-cropped areas such as field borders, vegetative barriers, contour buffer strips, grassed waterways, shelterbelts, hedgerows, windbreaks, conservation cover, and riparian forest and herbaceous buffers.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 327 - Conservation Cover

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 327 - Conservation Cover

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $306.88

Scenario Cost/Unit: $306.88

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Materials						
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	$252.12	1	$252.12

Practice: E328101I - Improved resource conserving crop rotation to reduce water erosion

Scenario #1 - IRCCR water erosion

Scenario Description:

Improve an existing Resource Conserving Crop Rotation. Must enrich and existing rotation which already includes AT LEAST one resource conserving crop as determined by the State Conservationist in a minimum three year crop rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plant pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $420.90

Scenario Cost/Unit: $4.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90

Practice: E328101R - Resource conserving crop rotation to reduce water erosion

Scenario #1 - RCCR water erosion

Scenario Description:

Establish a Resource Conserving Crop Rotation. Rotation must include AT LEAST one resource conserving crop as determined by the State Conservationist in a minimum three year crop rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plan pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,178.52

Scenario Cost/Unit: $11.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	14	$1,178.52

Practice: E328101Z - Conservation crop rotation on recently converted CRP grass/legume cover for water erosion

Scenario #1 - CRP trans crop rotation-water erosion

Scenario Description:

Implement a crop rotation management system on crop land acres that have recently converted from CRP grass/legume conservation cover to annual planted crops. Crop rotation minimizes disturbance resulting in a Soil Tillage Intensity Rating (STIR) less than10 and reduces soil erosion from water to below soil tolerance (T) level. RUSLE2 must be used to document the rotation, soil erosion estimate, and STIR calculations. *This enhancement is limited to acres where the conversion event took place not more than 2 years prior. Enhancement not applicable on hayland.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $252.54

Scenario Cost/Unit: $2.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54

Practice: E328106I - Improved resource conserving crop rotation for soil organic matter improvement

Scenario #1 - IRCCR for SOM improvement

Scenario Description:

Improve an existing Resource Conserving Crop Rotation. Must enrich and existing rotation which already includes AT LEAST one resource conserving crop as determined by the State Conservationist in a minimum three year crop rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plant pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $420.90

Scenario Cost/Unit: $4.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90

Practice: E328106R - Resource conserving crop rotation for soil organic matter improvement

Scenario #1 - RCCR for SOM improvement

Scenario Description:

Establish a Resource Conserving Crop Rotation. Rotation must include AT LEAST one resource conserving crop as determined by the State Conservationist in a minimum three year crop rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plant pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,178.52

Scenario Cost/Unit: $11.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	14	$1,178.52

Practice: E328106Z1 - Soil health crop rotation

Scenario #1 - Soil health crop rotation

Scenario Description:

Implement a crop rotation which addresses all four principle components of soil health: increases diversity of the cropping system; maintains residue throughout the year; keeps a living root; and minimizes soil chemical, physical and biological disturbance. The rotation will include at least 4 different crop and/or cover crop types (crop types include cool season grass, warm season grass, cool season broadleaf, warm season broadleaf) grown in a sequence that will produce a positive trend in the Organic Matter (OM) subfactor value over the life of the rotation, as determined by the Soil Conditioning Index (SCI). RUSLE2 or WEPS must be used to document the rotation and SCI calculations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $420.90

Scenario Cost/Unit: $4.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90

Practice: E328106Z2 - Modifications to improve soil health and increase soil organic matter

Scenario #1 - Mod to improve SH and SOM

Scenario Description:

Use of soil health assessment to evaluate impact of current conservation crop rotation in addressing soil organic matter depletion (primary assessment made in Year 1). Modifications to the crop rotation and/or crop management will be made as a result of the assessment results (adding a new crop and/or cover crop to the rotation; making changes to planting and/or tillage system, harvest timing of crops, or termination timing of cover crops). During Year 3 a follow up assessment will be completed to allow time for the modifications to show increased soil organic matter. Modified system must produce a positive trend in the Organic Matter (OM) subfactor value over the life of the rotation, as determined by the Soil Conditioning Index (SCI). RUSLE2 or WEPS must be used to document the rotation and SCI calculations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $826.59

Scenario Cost/Unit: $8.27

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	8	$673.44
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	15	$153.15

Practice: E328106Z3 - Conservation crop rotation on recently converted CRP grass/legume cover for SOM improvement

Scenario #1 - CRP trans crop rotation-SOM

Scenario Description:

Implement a crop rotation management system on crop land acres that have recently converted from CRP grass/legume conservation cover to annual planted crops. The crop rotation adds diversity to the system; keeps a living root growing; and is managed to minimize soil chemical, physical and biological disturbance and maintain residue cover on the surface. The rotation includes crops and/or cover crops representing 3 of the 4 crop types during the planned crop sequence: warm season grass (WSG), warm season broadleaf (WSB), cool season grass (CSG), or cool season broadleaf (CSB). The crop rotation will produce a positive trend in the Organic Matter (OM) subfactor value over the life of the rotation, as determined by the SCI. Crop rotation minimizes disturbance resulting in a Soil Tillage Intensity Rating (STIR) less than10 and reduces soil erosion from wind to below soil tolerance (T) level. RUSLE2 or WEPS must be used to document the rotation, STIR and SCI calculations. *This enhancement is limited to acres where the conversion event took place not more than 2 years prior. Enhancement not applicable on hayland.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $420.90

Scenario Cost/Unit: $4.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90

Practice: E328107I - Improved resource conserving crop rotation to improve soil compaction

Scenario #1 - IRCCR to improve soil compaction

Scenario Description:

Improve an existing Resource Conserving Crop Rotation. Must enrich and existing rotation which already includes AT LEAST one resource conserving crop as determined by the State Conservationist in a minimum three year crop rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plant pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $420.90

Scenario Cost/Unit: $4.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90

Practice: E328107R - Resource conserving crop rotation to improve soil compaction

Scenario #1 - RCCR to improve soil compaction

Scenario Description:

Establish a Resource Conserving Crop Rotation. Rotation must include AT LEAST one resource conserving crop as determined by the State Conservationist in a minimum three year crop rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plan pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,178.52

Scenario Cost/Unit: $11.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	14	$1,178.52

Practice: E328134I - Improved resource conserving crop rotation to relieve plant pest pressure

Scenario #1 - IRCCR to relieve plant pest pressure

Scenario Description:

Improve an existing Resource Conserving Crop Rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plan pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $420.90

Scenario Cost/Unit: $4.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90

Practice: E328134R - Resource conserving crop rotation to relieve plant pest pressure

Scenario #1 - RCCR to relieve plant pest pressure

Scenario Description:

Establish a Resource Conserving Crop Rotation. Rotation must include AT LEAST one resource conserving crop as determined by the State Conservationist in a minimum three year crop rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plan pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,178.52

Scenario Cost/Unit: $11.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	14	$1,178.52

Practice: E328136Z - Leave standing grain crops unharvested to benefit wildlife food sources

Scenario #1 - Leave standing grain crops for food

Scenario Description:
Implement a crop rotation which allows a portion of grain crops to be left in fields un-harvested to provide food and cover for wildlife during winter months.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $164.83

Scenario Cost/Unit: $4.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.17	$67.01
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.17	$35.21
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.17	$26.44
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	1	$36.18

Practice: E328137Z - Leave standing grain crops unharvested to benefit wildlife cover and shelter

Scenario #1 - Leave standing grain crops for shelter

Scenario Description:

Implement a crop rotation which allows a portion of grain crops to be left in fields un-harvested to provide food and cover for wildlife during winter months.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $164.83

Scenario Cost/Unit: $4.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.17	$67.01
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.17	$35.21
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.17	$26.44
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	1	$36.18

Practice: E329101Z - No till to reduce water erosion

Scenario #1 - No till to reduce water erosion

Scenario Description:

Establish no till system to reduce sheet and rill erosion soil loss. Field(s) must have a soil loss at or below the soil tolerance (T) level for water erosion for the crop rotation and a Soil Tillage Intensity Rating (STIR) of no greater than 10 for each crop in the planned rotation. RUSLE2 must be used to calculate soil loss and STIR.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $252.54

Scenario Cost/Unit: $2.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54

Practice: E329106Z - No till system to increase soil health and soil organic matter content

Scenario #1 - No till system to increase SH and SOM

Scenario Description:

Establish a reduced till system to increase soil health and soil organic matter content. Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 20. The crop rotation must achieve a soil conditioning index (SCI) of zero or higher and produce a positive trend in the Organic Matter (OM) subfactor over the life of the crop rotation. RUSLE2 or WEPS must be used to document STIR and SCI calculations. Residue shall not be burned, grazed, or harvested.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $336.72

Scenario Cost/Unit: $3.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	4	$336.72

Practice: E329114Z - No till to increase plant-available moisture: irrigation water

Scenario #1 - No till for IWM

Scenario Description:

Establish a no till system to increase plant-available moisture. Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 20. RUSLE2 or WEPS must be used to document STIR calculations. Maintain a minimum 60 percent surface residue cover throughout the year to reduce evaporation from the soil surface.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $252.54

Scenario Cost/Unit: $2.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54

Practice: E329115Z - No till to increase plant-available moisture: moisture management

Scenario #1 - No till for moisture mgmt

Scenario Description:

Establish a no till system to increase plant-available moisture. Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 20. RUSLE2 or WEPS must be used to document STIR calculations. Maintain a minimum 60 percent surface residue cover throughout the year to reduce evaporation from the soil surface.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $252.54

Scenario Cost/Unit: $2.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54

Practice: E329144Z - No till to reduce energy

Scenario #1 - No till to reduce energy

Scenario Description:

Establish a no till system which reduces total energy consumption associated with field operations by at least 25% compared to current tillage system (benchmark). Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 20. The current NRCS wind and water erosion prediction technologies must be used to document STIR calculations and energy consumption.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $336.72

Scenario Cost/Unit: $3.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	4	$336.72

Practice: E338136Z - Short-interval burns to promote a healthy herbaceous plant community for wildlife food

Scenario #5 - Short-interval burns to promote a healthy herbaceous plant community for wildlife food

Scenario Description:

The controlled use of fire is applied in a forest to restore fire-adapted plants and forage while improving wildlife habitat, wildlife food supply, and reducing the risk of damage from intense, severe wildfires. The ideal interval between prescribed burns is not often achieved. In order to improve the effectiveness of prescribed burning, the frequency of prescribed burning is increased appropriately, for a specified time period, to help restore ecological conditions in forests and woodlands. Short return interval prescribed burning is used to regenerate desirable tree species, improve the condition of fire-adapted plants and native herbaceous vegetation, improve forage quantity and quality, create wildlife habitat (snags and den/cavity trees), limit encroachment of competing vegetation including non-native species, and reduce the future risk of damage from intense, severe wildfires.

Before Situation:

The site has a mixture of woody sprouts and some herbaceous vegetation in the forest understory.

After Situation:

The site has a mixture of warm season perennial vegetation and cool-season annual forages. Grazing is occurring to manage the herbaceous vegetation and keep undesirable woody vegetation from occupying the forest understory.

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $3,401.13

Scenario Cost/Unit: $85.03

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$66.84	8	$534.72
Truck, water	1448	Water tanker truck. Equipment only. Labor not included.	Hour	$165.27	8	$1,322.16
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	24	$456.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	8	$205.44
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	4	$336.72
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E338137Z1 - Sequential patch burning

Scenario #1 - Sequential patch burning

Scenario Description:

Prescribed burning to promote and enhance conifer forests and maintain a healthy understory. This enhancement is to conduct prescribed burns in a conifer forest, burning only a portion of the area each year to create a mosaic of vegetation in several stages of development, to provide a more diverse wildlife habitat.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 338 - Prescribed Burning

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 338 - Prescribed Burning

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $1,442.33

Scenario Cost/Unit: $144.23

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	2	$57.16
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	$2.45	2	$4.90
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54
Materials						
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	$4.39	5	$21.95
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: E338137Z2 - Short-interval burn

Scenario #1 - Short-interval burn

Scenario Description:

This enhancement is the controlled use of fire in a forest to restore native forest conditions with a focus on improving the condition of fire-adapted plants and wildlife habitat and reducing the risk of damage from intense, severe wildfires.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 338 - Prescribed Burning

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 338 - Prescribed Burning

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $2,075.37

Scenario Cost/Unit: $41.51

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	8	$176.16
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	8	$228.64
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	$2.45	8	$19.60
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	48	$1,314.24
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	1	$36.18
Materials						
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	$4.39	10	$43.90
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E338140Z - Short-interval prescribed burning to promote a healthy herbaceous plant community

Scenario #1 - Short-interval prescribed burning

Scenario Description:

?Increase the frequency of prescribed burning to help restore ecological conditions in forests and woodlands, with a focus on improving the condition of fire-adapted plants and forage while improving wildlife habitat and reducing the risk of damage from intense, severe wildfires. Short return-interval burns can also be effective in regenerating desirable native tree and herbaceous vegetation, and limiting the encroachment of competing vegetation including non-native species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 338 - Prescribed Burning

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 338 - Prescribed Burning

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $3,316.95

Scenario Cost/Unit: $82.92

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$66.84	8	$534.72
Truck, water	1448	Water tanker truck. Equipment only. Labor not included.	Hour	$165.27	8	$1,322.16
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	24	$456.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12”, Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	$25.68	8	$205.44
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E340101Z - Cover crop to reduce water erosion

Scenario #1 - Cover crop to reduce water erosion

Scenario Description:

Cover crop added to current crop rotation to reduce soil erosion from water to below soil tolerance (T) level. Cover crops grown during critical erosion period(s). Species are selected that will have physical characteristics to provide adequate erosion protection.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $785.78

Scenario Cost/Unit: $7.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	1	$27.38
Materials						
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	20	$758.40

Practice: E340106Z1 - Intensive cover cropping to increase soil health and soil organic matter content

Scenario #1 - Cover cropping for SH and SOM

Scenario Description:

Use of cover crops in a cropping system to add diversity, keep the soil covered, and maintain a living root as long as possible. Cover crop will be used during ALL non-crop production periods in an annual crop rotation. Cover crop may be a single species or multi-species mix. Cover crop shall not be harvested or burned. Planned crop rotation including cover crops and associated management activities must achieve a soil conditioning index (SCI) of zero or higher and produce a positive trend in the Organic Matter (OM) subfactor over the life of the crop rotation. RUSLE2 or WEPS must be used to document SCI calculations. Cover crops may be grazed following a prescribed grazing plan that removes no more than 40% of the biomass produced.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,212.56

Scenario Cost/Unit: $12.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	$52.21	20	$1,044.20

Practice: E340106Z2 - Use of multi-species cover crops to improve soil health and increase soil organic matter

Scenario #1 - Multi-species cover crops

Scenario Description:

Implement a multi-species cover crop to add diversity and increase biomass production to improve soil health and increased soil organic matter. Cover crop mix must include a minimum of 4 different species. The cover crop mix will increase diversity of the crop rotation by including crop types currently missing, e.g. Cool Season Grass (CSG), Cool Season Broadleaves (CSB), Warm Season Grasses (WSG), Warm Season Broadleaves (WSB).

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,214.16

Scenario Cost/Unit: $12.14

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	$57.97	20	$1,159.40

Practice: E340106Z3 - Intensive cover cropping (orchard/vineyard floor) to increase soil health and SOM content

Scenario #1 - Cover cropping for orchards/vineyards

Scenario Description:

Implementation of cover crops to provide orchard or vineyard floor coverage throughout the year. Cover crop shall not be harvested, grazed, or burned. Planned cover crop management activities must achieve a soil conditioning index (SCI) of zero or higher and produce a positive trend in the Organic Matter (OM) subfactor over the life of the crop rotation. RUSLE2 or WEPS must be used to document SCI calculations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,098.96

Scenario Cost/Unit: $10.99

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Materials						
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	$52.21	20	$1,044.20

Practice: E340106Z4 - Use of SHA to assist with development of cover crop mix to improve soil health and increase SOM

Scenario #1 - Soil health assessment

Scenario Description:

Use of a soil health assessment to evaluate impact of current conservation crop rotation in addressing soil organic matter depletion (primary assessment made in Year 1). Soil health assessment results will be utilized to determine the correct Carbon to Nitrogen ratio of a multi-species cover crop mix that will be added to the crop rotation. During Year 3 a follow up assessment will be completed to allow time for the addition of a cover crop to increased soil organic matter.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,444.51

Scenario Cost/Unit: $14.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	1	$27.38
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	1	$84.18
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	15	$153.15
Three Species Mix, Warm Season, Annual Grasses and Legumes	2326	Warm season annual grass and legume mix. Includes material and shipping only.	Acre	$58.99	20	$1,179.80

Practice: E340107Z - Cover crop to minimize soil compaction

Scenario #1 - Cover crop to minimize soil compaction

Scenario Description:

Establish a cover crop mix that includes plants with both fibrous root and deep rooted systems. Fibrous to treat and prevent both near surface (0-4”) and deep (>4”) soil compaction and deep rooted to break up deep compacted soils. Cover crop shall not be harvested, grazed, or burned.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,071.58

Scenario Cost/Unit: $10.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	1	$27.38
Materials						
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	$52.21	20	$1,044.20

Practice: E340118Z - Cover crop to reduce water quality degradation by utilizing excess soil nutrients-surface water

Scenario #1 - Cover crop for WQ nutrients-runoff

Scenario Description:

Establish a cover crop mix to take up excess soil nutrients. Select cover crop species for their ability to effectively utilize nutrients. Terminate the cover crop as late as practical to maximize plant biomass production and nutrient uptake. Cover crop shall not be harvested, grazed, or burned.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,071.58

Scenario Cost/Unit: $10.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	1	$27.38
Materials						
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	$52.21	20	$1,044.20

Practice: E340119Z - Cover crop to reduce water quality degradation by utilizing excess soil nutrients-ground water

Scenario #1 - Cover crops for WQ nutrients-drainage

Scenario Description:

Establish a cover crop mix to take up excess soil nutrients. Select cover crop species for their ability to effectively utilize nutrients. Terminate the cover crop as late as practical to maximize plant biomass production and nutrient uptake. Cover crop shall not be harvested, grazed, or burned.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,071.58

Scenario Cost/Unit: $10.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	1	$27.38
Materials						
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	$52.21	20	$1,044.20

Practice: E340134Z - Cover crop to suppress excessive weed pressures and break pest cycles

Scenario #1 - Cover crops for suppression

Scenario Description:

Establish a cover crop mix to suppress excessive weed pressures and break pest cycles. Select cover crop species for their life cycles, growth habits, and other biological, chemical and/or physical characteristics. Select cover crop species that do not harbor pests or diseases of subsequent crops in the rotation. Cover crop shall not be harvested, grazed, or burned.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,098.96

Scenario Cost/Unit: $10.99

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Materials						
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	$52.21	20	$1,044.20

Practice: E345101Z - Reduced tillage to reduce water erosion

Scenario #1 - Reduced tillage to reduce water erosion

Scenario Description:

Establish a reduced tillage system to reduce sheet and rill erosion soil loss. Field(s) must have a soil loss at or below the soil tolerance (T) level for water erosion for the crop rotation and a Soil Tillage Intensity Rating (STIR) of no greater than 40 for each crop in the planned rotation. RUSLE2 must be used to calculate soil loss and STIR.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $336.72

Scenario Cost/Unit: $3.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	4	$336.72

Practice: E345106Z - Reduced tillage to increase soil health and soil organic matter content

Scenario #1 - Reduced tillage for SH and SOM

Scenario Description:

Establish a reduced till system to increase soil health and soil organic matter content. Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 80. The crop rotation must achieve a soil conditioning index (SCI) of zero or higher and produce a positive trend in the Organic Matter (OM) subfactor over the life of the crop rotation. RUSLE2 or WEPS must be used to document STIR and SCI calculations. Residue shall not be burned, grazed, or harvested.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $336.72

Scenario Cost/Unit: $3.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	4	$336.72

Practice: E345114Z - Reduced tillage to increase plant-available moisture: irrigation water

Scenario #1 - Reduced tillage for IWM

Scenario Description:

Establish a reduced till system to increase plant-available moisture. Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 80. RUSLE2 or WEPS must be used to document STIR calculations. Maintain a minimum 60 percent surface residue cover throughout the year to reduce evaporation from the soil surface.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $252.54

Scenario Cost/Unit: $2.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54

Practice: E345115Z - Reduced tillage to increase plant-available moisture: moisture management

Scenario #1 - Reduced tillage for moisture mgmt

Scenario Description:

Establish a reduced till system to increase plant-available moisture. Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 80. RUSLE2 or WEPS must be used to document STIR calculations. Maintain a minimum 60 percent surface residue cover throughout the year to reduce evaporation from the soil surface.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $252.54

Scenario Cost/Unit: $2.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54

Practice: E345128Z - Reduced tillage to reduce tillage induced particulate matter

Scenario #1 - Reduced tillage to reduce PM

Scenario Description:

Establish a reduced tillage system to reduce tillage induced particulate matter. Field(s) must have a soil loss at or below the soil tolerance (T) level for the crop rotation and a Soil Tillage Intensity Rating (STIR) of no greater than 40 for each crop in the planned rotation. RUSLE2 or WEPS must be used to document soil loss and STIR calculations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $252.54

Scenario Cost/Unit: $2.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54

Practice: E345144Z - Reduced tillage to reduce energy use

Scenario #1 - Reduced tillage to reduce energy use

Scenario Description:

Establish a reduced tillage system which reduces total energy consumption associated with field operations by at least 25% compared to conventional tillage systems (benchmark). Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 80. RUSLE2 must be used to document STIR calculations and energy consumption. <State lists will be prepared providing conventional system benchmark energy values and reduced tillage system values for those systems using at least 25% less energy>

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $252.54

Scenario Cost/Unit: $2.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54

Practice: E374144Z1 - Install variable frequency drive(s) on pump(s)

Scenario #1 - Variable frequency drives

Scenario Description:
Install Variable Frequency Drive(s) (CPS 533 Pumping Plant) with the correct sensors, on all pumps indicated in the energy audit.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 374 - Farmstead Energy Improvement

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 374 - Farmstead Energy Improvement

Feature Measure: Each

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 50.0

Scenario Total Cost: $12,386.00

Scenario Cost/Unit: $247.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Variable Speed Drive, 50 HP	1288	Variable speed drive for 50 Horsepower electric motor. Does not include motor. Materials only.	Horsepower	$247.72	50	$12,386.00

Practice: E374144Z2 - Switch fuel source for pump motor(s)

Scenario #1 - Switch fuel source for pump motor(s)

Scenario Description:
Switch fuel source for the pump motor(s) indicated in the audit to a renewable source (wind, solar, geothermal, etc..). (CPS 533 Pumping Plant)

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 374 - Farmstead Energy Improvement

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 374 - Farmstead Energy Improvement

Feature Measure: Horsepower

Scenario Unit:: Horsepower

Scenario Typical Size: 5.0

Scenario Total Cost: $39,465.23

Scenario Cost/Unit: $7,893.05

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	1	$22.02
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	12	$328.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Pump, <= 5 HP, pump and motor, fixed cost portion	1009	Fixed cost portion of a pump less than or equal to 5 HP pump and motor. This portion is a base cost and is not dependant on horsepower. The total cost of any pump will include this fixed cost plus a variable cost portion. The completed pump and motor will include the motor and controls. Includes Includes material and shipping only.	Each	$564.23	1	$564.23
Pump, <= 5 HP, pump and motor, variable cost portion	1010	Variable cost portion of a pump less than or equal to 5 HP pump and motor. This portion IS dependent on the total horsepower for the pump. The total cost of any pump will include this variable cost plus the fixed cost portion. The completed pump and motor will include the motor and controls. Includes material and shipping only.	Horsepower	$424.66	5	$2,123.30
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will include all materials (electrical, controllers, service drops and etc). This cost will include material, labor and equipment.	Each	$472.52	5	$2,362.60
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all materials (electrical, controllers, and service drop, etc). This cost will include material, labor and equipment.	Kilowatt	$8,474.04	4	$33,896.16

Practice: E376128Z - Modify field operations to reduce particulate matter

Scenario #1 - Mod field ops to reduce PM

Scenario Description:
Modify tillage and/or harvest operations to reduce particulates by at least 20 percent below the required levels.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 376 - Field Operations Emissions Reduction

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 376 - Field Operations Emissions Reduction

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $252.54

Scenario Cost/Unit: $2.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54

Practice: E382136Z - Incorporating "wildlife friendly" fencing for connectivity of wildlife food resources

Scenario #1 - Wildlife friendly fence for food access

Scenario Description:
Retrofitting or constructing fences that provide a means to control movement of animals, people, and vehicles, but minimizes wildlife movement impacts.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 382 - Fence

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 382 - Fence

Feature Measure: Acre

Scenario Unit:: Foot

Scenario Typical Size: 1,000.0

Scenario Total Cost: $148.58

Scenario Cost/Unit: $0.15

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	1	$28.58
Materials						
Vinyl Undersill Strips	241	Marking material using the "undersill" strips of vinyl siding. Priced per foot of fence per each wire. Materials only.	Foot	$0.06	2000	$120.00

Practice: E386101Z - Enhanced field borders to reduce water induced erosion along the edge(s) of a field

Scenario #1 - Field borders to reduce water erosion

Scenario Description:

Enhance existing field borders to a width of at least 30 feet and establish a single specie or mixture of species that provide a dense ground cover along the edge(s) of the field.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 386 - Field Border

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 386 - Field Border

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $633.37

Scenario Cost/Unit: $633.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	1	$11.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	$57.97	1	$57.97
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E386106Z - Enhanced field borders to increase carbon storage along the edge(s) of the field

Scenario #1 - Field borders to increase carbon storage

Scenario Description:
Enhance existing field borders to a width of at least 30 feet and establish a single specie or mixture of species that provide a dense ground cover and dense rooting system along the edge(s) of the field.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 386 - Field Border

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 386 - Field Border

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $633.37

Scenario Cost/Unit: $633.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	1	$11.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	$57.97	1	$57.97
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E386136Z - Enhanced field border to provide wildlife food for pollinators along the edge(s) of a field

Scenario #1 - Field border to provide wildlife food

Scenario Description:
Enhance existing field borders to a width of at least 40 feet and establish a mixture of species that provide food for pollinators along the edge(s) of the field.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 386 - Field Border

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 386 - Field Border

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $633.37

Scenario Cost/Unit: $633.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	1	$11.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	$57.97	1	$57.97
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E386137Z - Enhanced field border to provide wildlife cover or shelter along the edge(s) of a field

Scenario #1 - Field border to provide wildlife cover

Scenario Description:
Enhance existing field borders to a width of at least 40 feet and establish a mixture of species that provide wildlife food and cover along the edge(s) of the field.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 386 - Field Border

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 386 - Field Border

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $633.37

Scenario Cost/Unit: $633.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	1	$11.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	$57.97	1	$57.97
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E386139Z - Enhanced field border to provide wildlife habitat continuity along the edge(s) of a field

Scenario #1 - Field border to provide continuity

Scenario Description:
Enhance existing field borders to a width of at least 40 feet and establish a mixture of species that provide wildlife habitat continuity along the edge(s) of the field.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 386 - Field Border

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 386 - Field Border

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $633.37

Scenario Cost/Unit: $633.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	1	$11.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	$57.97	1	$57.97
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E390118Z - Increase riparian herbaceous cover width for nutrient reduction

Scenario #1 - Riparian herbaceous cover-nut reduction

Scenario Description:

Where an existing herbaceous riparian buffer is located along a river, stream, pond, lake, or other waterbody, increase the width of the buffer in order to allow a greater percentage of nutrient removal from surface and subsurface flows. Saturated buffer or nutrient control wetland to capture subsurface drainage.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 390 - Riparian Herbaceous Cover

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 390 - Riparian Herbaceous Cover

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: $986.37

Scenario Cost/Unit: $493.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	2	$12.40
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	2	$43.16
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.82	$323.21
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.72	$149.12
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.46	$71.53
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	2	$75.66
One Species, Cool Season, Native Perennial Grass	2312	Native, cool season perennial grass. Includes material and shipping only.	Acre	$155.64	2	$311.28

Practice: E390126Z - Increase riparian herbaceous cover width to reduce sediment loading

Scenario #1 - Riparian herbaceous cover-seed loading

Scenario Description:

Where an existing herbaceous riparian buffer is located along a river, stream, pond, lake, or other waterbody, increase the width of the buffer in order to allow a greater percentage of nutrient removal from surface and subsurface flows.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 390 - Riparian Herbaceous Cover

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 390 - Riparian Herbaceous Cover

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: $986.37

Scenario Cost/Unit: $493.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	2	$12.40
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	2	$43.16
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.82	$323.21
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.72	$149.12
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.46	$71.53
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	2	$75.66
One Species, Cool Season, Native Perennial Grass	2312	Native, cool season perennial grass. Includes material and shipping only.	Acre	$155.64	2	$311.28

Practice: E390136Z - Increase riparian herbaceous cover width to enhance wildlife habitat

Scenario #1 - Riparian herbaceous cover-habitat

Scenario Description:

Where an existing herbaceous riparian buffer is located along a river, stream, pond, lake, or other waterbody, increase the diversity of native species, control invasive species, install fencing and relocate equipment operations, trails, and livestock, and increase the width of the buffer.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 390 - Riparian Herbaceous Cover

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 390 - Riparian Herbaceous Cover

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 4.0

Scenario Total Cost: $2,871.50

Scenario Cost/Unit: $717.88

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	4	$24.80
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	2	$43.16
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	1	$394.16
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	1	$207.11
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.46	$71.53
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	4	$151.32
Specialized native grass and forb mix	2619	A mix of native grass and forbs to be used for specialized purposes such as wildlife (including pollinators) or ecosystem restoration, requiring species not readility available and/or difficult to produce and harvest. Includes material and shipping only	Acre	$989.71	2	$1,979.42

Practice: E391118Z - Increase riparian forest buffer width for nutrient reduction

Scenario #1 - Riparian forest buffer-nut reduction

Scenario Description:

Where an existing forested riparian area is located along a river, stream, pond, lake, or other waterbody, increase the width of the buffer in order to allow a greater percentage of nutrient removal from surface and subsurface flows. Saturated buffer or nutrient control wetland to capture subsurface drainage.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: $2,957.17

Scenario Cost/Unit: $1,478.58

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	16	$352.32
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	2	$104.92
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	2	$12.40
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	4	$100.16
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	16	$197.76
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.82	$323.21
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.72	$149.12
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.46	$71.53
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	4	$86.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	4	$144.72
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	1	$18.87
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	1	$26.78
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	1	$1.31
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	872	$261.60
Tree shelter, solid tube type, 4" x 48"	1566	4" x 48" tree tube for protection from animal damage. Materials only.	Each	$4.22	100	$422.00

Stakes, wood, 1" x 1" x 48"	1578	1" x 1" x 48" wood stakes to fasten items in place. Includes materials only.	Each	$2.07	100	$207.00
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E391126Z - Increase riparian forest buffer width to reduce sediment loading

Scenario #1 - Riparian forest buffer-seed loading

Scenario Description:

Where an existing forested riparian area is located along a river, stream, pond, lake, or other waterbody, increase the width of the buffer in order to allow a greater percentage of nutrient removal from surface and subsurface flows.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: $2,995.17

Scenario Cost/Unit: $1,497.58

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	16	$352.32
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	2	$104.92
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	2	$12.40
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	4	$100.16
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	16	$197.76
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.82	$323.21
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.72	$149.12
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.46	$71.53
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	18	$342.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	4	$86.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	4	$144.72
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	1	$18.87
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	1	$26.78
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	1	$1.31
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	872	$261.60
Tree shelter, solid tube type, 4" x 48"	1566	4" x 48" tree tube for protection from animal damage. Materials only.	Each	$4.22	100	$422.00

Stakes, wood, 1" x 1" x 48"	1578	1" x 1" x 48" wood stakes to fasten items in place. Includes materials only.	Each	$2.07	100	$207.00
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

USDA - Natural Resources Conservation Service

Mississippi

Practice: E391127Z - Increase stream shading for stream temperature reduction

Scenario #1 - Shade stream to reduce temp

Scenario Description:
Riparian area tree canopy cover density is increased and the extent of the forested riparian area is increased to provide greater stream shading.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: $2,995.17

Scenario Cost/Unit: $1,497.58

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	16	$352.32
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	2	$104.92
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	2	$12.40
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	4	$100.16
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	16	$197.76
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.82	$323.21
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.72	$149.12
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.46	$71.53
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	18	$342.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	4	$86.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	4	$144.72
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	1	$18.87
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	1	$26.78
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	1	$1.31
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	872	$261.60
Tree shelter, solid tube type, 4" x 48"	1566	4" x 48" tree tube for protection from animal damage. Materials only.	Each	$4.22	100	$422.00
Stakes, wood, 1" x 1" x 48"	1578	1" x 1" x 48" wood stakes to fasten items in place. Includes materials only.	Each	$2.07	100	$207.00

Mobilization

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E391136Z - Increase riparian forest buffer width to enhance wildlife habitat

Scenario #1 - Riparian forest buffer-habitat

Scenario Description:

Where an existing forested riparian area is located along a river, stream, pond, lake, or other waterbody, increase the diversity of native species, control invasive species, install fencing and relocate equipment operations, trails, and livestock, and increase the width of the buffer.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: $2,995.17

Scenario Cost/Unit: $1,497.58

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	16	$352.32
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	2	$104.92
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	2	$12.40
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	4	$100.16
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	16	$197.76
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.82	$323.21
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.72	$149.12
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.46	$71.53
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	18	$342.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	4	$86.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	4	$144.72
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	1	$18.87
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	1	$26.78
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	1	$1.31
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	872	$261.60
Tree shelter, solid tube type, 4" x 48"	1566	4" x 48" tree tube for protection from animal damage. Materials only.	Each	$4.22	100	$422.00

Stakes, wood, 1" x 1" x 48"	1578	1" x 1" x 48" wood stakes to fasten items in place. Includes materials only.	Each	$2.07	100	$207.00
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E393118Z - Extend existing filter strip to reduce excess nutrients in surface water

Scenario #1 - Extend filter strips- nut runoff

Scenario Description:

Extend existing filter strips for water quality protection (reduce excess nutrients in surface water). Extend the existing buffer for a total of 60 feet or more to enhance water quality functions. The extended buffers must be composed of at least 5 species of non-noxious, wildlife friendly grasses and/or perennial forbs best suited to site conditions. Include species that provide pollinator food and habitat where possible.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 393 - Filter Strip

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 393 - Filter Strip

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $801.73

Scenario Cost/Unit: $801.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	1	$11.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	$57.97	1	$57.97
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E393122Z - Extend existing filter strip to reduce excess pathogens and chemicals in surface water

Scenario #1 - Extend filter strips-pathogen runoff

Scenario Description:

Extend existing filter strips for water quality protection (reduce excess pathogens and chemicals from manure, bio-solids or compost applications in surface waters). Extend the existing buffer for a total of 60 feet or more to enhance water quality functions. The extended buffers must be composed of at least 5 species of non-noxious, wildlife friendly grasses and/or perennial forbs best suited to site conditions. Include species that provide pollinator food and habitat where possible.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 393 - Filter Strip

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 393 - Filter Strip

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $801.73

Scenario Cost/Unit: $801.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	1	$11.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	$57.97	1	$57.97
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E393126Z - Extend existing filter strip to reduce excess sediment in surface water

Scenario #1 - Extend filter strips-sediment

Scenario Description:

Extend existing filter strips for water quality protection (reduce excess sediment in surface waters). Extend the existing buffer for a total of 60 feet or more to enhance water quality functions. The extended buffers must be composed of at least 5 species of non-noxious, wildlife friendly grasses and/or perennial forbs best suited to site conditions. Include species that provide pollinator food and habitat where possible.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 393 - Filter Strip

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 393 - Filter Strip

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $801.73

Scenario Cost/Unit: $801.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	$11.26	1	$11.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	1	$21.58
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	$7.78	1	$7.78
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	$57.97	1	$57.97
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E449114Z5 - Complete pumping plant evaluation for all existing pumps on a farm.

Scenario #4 - Pumping Plant Evaluation

Scenario Description:

Evaluation of all pumping plants to determine the potential to rehabilitate/replace/reconfigure to perform 10% more efficiently. Evaluate to determine if a Variable Frequency Drive motor controller(s) is recommended and the simple payback in terms of energy savings is less than 10 years.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 449 – Irrigation Water Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in the Conservation Practice Standard, (CPS) 449 – Irrigation Water Management.

Feature Measure: Acres

Scenario Unit:: Acre

Scenario Typical Size: 640.0

Scenario Total Cost: $2,983.67

Scenario Cost/Unit: $4.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	8	$219.04
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	32	$2,693.76
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	$70.87	1	$70.87

Practice: E449114Z6 - Automated Intermittent flood irrigation of rice fields, Year 2-5

Scenario #4 - Automated Intermittent flood irrigation of rice fields, Year 2-5

Scenario Description:

Rice fields are drained and allowed to “dry down” to a saturated soil condition prior to re-flooding the field. System is installed in year 1 with Scenario E449114Z8 and this scenario used in years 2-5.

Before Situation:

Resources are protected at the minimum level of the conservation Practice Standard (CPS) 449 – Irrigation Water Management.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in the Conservation Practice Standard (CPS) 449 – Irrigation Water Management.

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: $977.08

Scenario Cost/Unit: $24.43

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	40	$760.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	6	$217.08

Practice: E449114Z7 - Advanced Automated IWM – Year 2-5, Soil moisture is monitored, recorded and used in decision making

Scenario #4 - Advanced Automated IWM – Year 2-5, soil moisture monitoring

Scenario Description:

Advanced automated irrigation water management using soil moisture monitoring (one sensor per 40 acres or less) with data loggers. Record keeping is such that a daily water balance is calculated and future irrigation is forecast. Equipment was bought in year one, this is monitoring for future years. Subscription service may be used as source for monitoring. System will be monitored and controlled using remote devices.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 449 – Irrigation Water Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 449 – Irrigation Water Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 125.0

Scenario Total Cost: $1,963.52

Scenario Cost/Unit: $15.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	40	$1,095.20
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	24	$868.32

Practice: E449114Z8 - Advanced Automated IWM – Year 1 – Equipment and soil moisture is monitored, recorded and used in decision making

Scenario #4 - Advanced Automated IWM – Year 1 Equipment and soil moisture monitoring

Scenario Description:

Year 1 is used to purchase equipment to do advanced automated irrigation water management. System incuses field specific weather station data with soil moisture monitoring (one sensor station per 40 acres or less) data loggers and telemetry. Sensor stations will included minimum of 2 sensors per site at depths appropriate for the crop and soils. Equipment may include; weather station, sensors, flow meter, data loggers, as needed to monitor soil moisture, determine and forecast crop water use and remotely control irrigation system. Data to be monitored includes crop water use, status of heat and/or frost conditions to permit the producer to make informed irrigation decisions. The installation includes the purchase and installation of equipment, and a data logger to log continuous weather data including rainfall, temp, solar radiation, humidity, wind speed and soil moisture sensors that can be downloaded to a personal computer and associated graphing software. Typical Scenario involves installation on a 120 acre field of irrigated cropland. Producer monitors the station during the growing season to determine timing and amounts of water to apply based on soil moisture sensors, field checks and weather station data. Producer keeps records of collected data and resulting irrigation decisions. This scenario only applies to year one of IWM. The appropriate labor-only IWM scenarios apply in subsequent contract years.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 449 – Irrigation Water Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 449 – Irrigation Water Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 120.0

Scenario Total Cost: $6,607.31

Scenario Cost/Unit: $55.06

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	30	$660.60
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	8	$219.04
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	16	$578.88
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	4	$336.72
Materials						
Switches and Controls, temp sensors	1192	Temperature and soil moisture sensors installed as part of an electronic monitoring (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	$666.86	3	$2,000.58
Data Logger with Telemetry System	1454	Data Logger W/Graphic Output for water management and telemetry - data communication device with power supply in a weather proof enclosure. Equipment only.	Each	$1,723.25	1	$1,723.25
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance irrigation water management and for Activity 202 water quality monitoring .	Each	$1,088.24	1	$1,088.24

USDA - Natural Resources Conservation Service

Mississippi

Practice: E472118Z - Manage livestock access to streams/ditches/other waterbodies to reduce nutrients in surface water

Scenario #1 - Livestock access to waterbody-nutrients

Scenario Description:

Installation of structures and implementation of grazing management actions that restrict livestock access to streams, ditches, and other waterbodies in order to reduce nutrient loading to surface waters.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 472 - Access Control

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 472 - Access Control

Feature Measure: (Stream length protected * 2) + ((C

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: $2,897.14

Scenario Cost/Unit: $2.19

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	$7.39	5	$36.95
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	5	$110.10
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	5	$125.20
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	33	$627.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	5	$108.55
Materials						
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	$72.51	4	$290.04
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	$6.38	20	$127.60
Post, Wood, CCA treated, 6" x 8'	12	Wood Post, End 6" X 8', CCA Treated. Includes materials and shipping only.	Each	$15.38	8	$123.04
Post, Steel T, 1.33 lbs, 6'	15	Steel Post, Studded 6' - 1.33 lb. Includes materials and shipping only.	Each	$6.81	90	$612.90
Fence, Wire Assembly, Barbed Wire	30	Brace pins, battens, clips, staples. Includes materials and shipping only.	Foot	$0.17	1320	$224.40
Gate, Pipe, 12'	1057	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	$169.37	2	$338.74
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E484106Z - Mulching to improve soil health

Scenario #1 - Mulching to improve soil health

Scenario Description:

Implement a crop rotation which utilizes mulch and addresses all four principle components of soil health: increases diversity of the cropping system; maintains residue throughout the year; keeps a living root; and minimizes soil chemical, physical and biological disturbance. Plant-based mulching materials will be applied at least once during the rotation. The rotation will include at least 4 different crop and/or cover crop types (crop types include cool season grass, warm season grass, cool season broadleaf, warm season broadleaf) grown in a sequence that will produce a positive trend in the Organic Matter (OM) subfactor value over the life of the rotation, as determined by the Soil Conditioning Index (SCI). RUSLE2 or WEPS must be used to document the rotation and SCI calculations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 484 - Mulching

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 484 - Mulching

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $168.36

Scenario Cost/Unit: $1.68

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36

Practice: E511137Z1 - Harvest of crops (hay or small grains) using measures that allow desired species to flush or escape

Scenario #1 - Harvest using wildlife friendly methods

Scenario Description:

Harvest of crops (hay or small grains) using conservation measures that allow desired species to flush or escape. <species list State Wildlife Action Plan> Conservation measures include timing of harvest, idling land during the nesting or fawning period, and applying harvest techniques that reduce mortality to wildlife.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 511 - Forage Harvest Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 511 - Forage Harvest Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $164.97

Scenario Cost/Unit: $3.30

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Hay, General Grass	2122	General Grass Hay is Primary Land Use	Ton	$43.24	1.67	$72.21
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00

Practice: E511137Z2 - Forage harvest management that helps maintain or improve wildlife habitat (cover and shelter)

Scenario #1 - FHM for cover and shelter

Scenario Description:

The timely cutting and removal of forages from the field as hay, green-chop, or ensilage in such as way and time frames so as optimize both forage yield/quality and wildlife cover and shelter.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 511 - Forage Harvest Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 511 - Forage Harvest Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $459.43

Scenario Cost/Unit: $4.59

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	25	$423.25
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	1	$36.18

Practice: E511139Z2 - Forage harvest management that helps maintain wildlife habitat continuity (space)

Scenario #1 - FHM for habitat space continuity

Scenario Description:

The timely cutting and removal of forages from the field as hay, green-chop, or ensilage in such as way and time frames so as optimize both forage yield/quality and wildlife cover and shelter for habitat and/or continuity between otherwise disconnected habitats.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 511 - Forage Harvest Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 511 - Forage Harvest Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $164.97

Scenario Cost/Unit: $3.30

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Hay, General Grass	2122	General Grass Hay is Primary Land Use	Ton	$43.24	1.67	$72.21
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00

Practice: E512101Z1 - Cropland conversion to grass-based agriculture to reduce water erosion

Scenario #1 - Convert crop to grass for water erosion

Scenario Description:

Conversion of cropped land to grass-based agriculture. Mixtures of perennial grasses, forbs, and/or legume species are established on cropland where annually-seeded cash crops have been grown.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $485.56

Scenario Cost/Unit: $4.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2319	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	$20.66	20	$413.20

Practice: E512101Z2 - Forage and biomass planting for water erosion to improve soil health

Scenario #1 - Forage planting for SH

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of herbaceous species suitable for pasture, hay, or biomass production that can provide for reduced soil erosion, improving soil health.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,441.16

Scenario Cost/Unit: $14.41

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
One Species, Warm Season, Native Perennial Grass	2322	Native, warm season perennial grass. Includes material and shipping only.	Acre	$68.44	20	$1,368.80

Practice: E512106Z1 - Cropland conversion to grass-based agriculture for soil organic matter improvement

Scenario #1 - Convert crop to grass for SOM

Scenario Description:

Conversion of cropped land to grass-based agriculture. Mixtures of perennial grasses, forbs, and/or legume species are established on cropland where annually-seeded cash crops have been grown.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,332.72

Scenario Cost/Unit: $13.33

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	2	$38.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	4	$336.72
Materials						
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	$47.90	20	$958.00

Practice: E512106Z2 - Forage plantings that can help increase organic matter in depleted soils

Scenario #1 - Forage planting for SOM

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of herbaceous species suitable for pasture, hay, or biomass production that can help improve soil quality of depleted sites through increase or conservation of the organic matter in the soil.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,453.61

Scenario Cost/Unit: $14.54

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	25	$423.25
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	$47.90	20	$958.00

Practice: E512132Z1 - Forage and biomass planting that produces feedstock for biofuels or energy production

Scenario #1 - Forage planting for feedstocks

Scenario Description:

Conversion of cropped land to grass-based agriculture. Mixtures of perennial grasses, forbs, and/or legume species are established on cropland where annually-seeded cash crops have been grown.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $3,590.36

Scenario Cost/Unit: $35.90

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
One Species, Warm Season, Native Perennial Grass	2322	Native, warm season perennial grass. Includes material and shipping only.	Acre	$68.44	50	$3,422.00

Practice: E512132Z2 - Native grasses or legumes in forage base to improve plant productivity and health

Scenario #1 - Native grasses/legumes-plant health

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of perennial, herbaceous species that can provide the structure and composition needed to enhance livestock and wildlife habitat, particularly when targeted forage supply and quality, cover, and shelter are not available in other pastures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $2,151.20

Scenario Cost/Unit: $21.51

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	1	$19.00
Materials						
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	$213.22	10	$2,132.20

Practice: E512133Z1 - Native grasses or legumes in forage base to improve plant community structure and composition

Scenario #1 - Native grasses/legumes-structure/comp

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of perennial, herbaceous species that can provide the structure and composition needed to enhance livestock and wildlife habitat, particularly when targeted forage supply and quality, cover, and shelter are not available in other pastures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $5,498.86

Scenario Cost/Unit: $54.99

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	$213.22	25	$5,330.50

Practice: E512133Z2 - Forage plantings that enhance bird habitat (structure and composition)

Scenario #1 - Forage planting for structure/comp

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of herbaceous species suitable for pasture, hay, or biomass production that can provide cover and shelter components of bird habitat.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $7,428.86

Scenario Cost/Unit: $74.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Materials						
One Species, Warm Season, Native Perennial Grass	2322	Native, warm season perennial grass. Includes material and shipping only.	Acre	$68.44	25	$1,711.00
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	$566.31	10	$5,663.10

Practice: E512136Z1 - Establish pollinator and/or beneficial insect food habitat

Scenario #1 - Establish pollinator habitat-food

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of herbaceous species that can provide nectar for pollinators and forage and other habitat values for wildlife and livestock, particularly at times when targeted nectar, forage supply and quality, cover, and shelter are not available in other pastures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $5,747.28

Scenario Cost/Unit: $57.47

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	1	$84.18
Materials						
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	$566.31	10	$5,663.10

Practice: E512136Z2 - Native grass or legumes in forage base to provide wildlife food

Scenario #1 - Native grasses/legumes-wildlife food

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of perennial, herbaceous species that can provide the structure and composition needed to enhance livestock and wildlife habitat, particularly when targeted forage supply and quality, cover, and shelter are not available in other pastures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $5,747.28

Scenario Cost/Unit: $57.47

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	1	$84.18
Materials						
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	$566.31	10	$5,663.10

Practice: E512137Z - Forage plantings that enhance bird habitat (cover and shelter)

Scenario #1 - Forage planting for cover and shelter

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of herbaceous species suitable for pasture, hay, or biomass production that can provide cover and shelter components of bird habitat.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $7,428.86

Scenario Cost/Unit: $74.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	2	$54.76
Materials						
One Species, Warm Season, Native Perennial Grass	2322	Native, warm season perennial grass. Includes material and shipping only.	Acre	$68.44	25	$1,711.00
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	$566.31	10	$5,663.10

Practice: E512138Z - Establish wildlife corridors to enhance access to water

Scenario #1 - Corridors for water access

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of perennial, herbaceous species that can provide cover needed for wildlife species of concern to move from food/cover/water sources to other food/cover/water sources as needed for their life cycles, and/or to enhance the utility of underused wildlife habitat areas.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $2,627.81

Scenario Cost/Unit: $26.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	25	$423.25
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	$213.22	10	$2,132.20

Practice: E512139Z1 - Establish wildlife corridors to provide habitat continuity

Scenario #1 - Corridors for habitat continuity

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of perennial, herbaceous species that can provide cover needed for wildlife species of concern to move from food/cover/water sources to other food/cover/water sources as needed for their life cycles, and/or to enhance the utility of underused wildlife habitat areas.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $2,517.30

Scenario Cost/Unit: $25.17

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	10	$215.80
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	10	$169.30
Materials						
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	$213.22	10	$2,132.20

Practice: E512139Z2 - Establish pollinator and/or beneficial insect habitat continuity (space)

Scenario #1 - Establish pollinator habitat-space

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of herbaceous species that can provide nectar for pollinators and forage and other habitat values for wildlife and livestock, particularly at times when targeted nectar, forage supply and quality, cover, and shelter are not available in other pastures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $5,831.46

Scenario Cost/Unit: $58.31

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	$566.31	10	$5,663.10

Practice: E512139Z3 - Establish Monarch butterfly habitat in pastures

Scenario #1 - Establish Monarch Butterfly Habitat in pastures

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of herbaceous species that can provide nectar for Monarch butterflies and forage and other habitat values for wildlife and livestock, particularly at times when targeted nectar, forage supply and quality, cover, and shelter are not available in other pastures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $5,831.46

Scenario Cost/Unit: $58.31

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	$566.31	10	$5,663.10

Practice: E512140Z - Native grasses or legumes in forage base

Scenario #1 - Native grasses or legumes in forage base

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of perennial, herbaceous species that can provide the structure and composition needed to enhance livestock and wildlife habitat, particularly when targeted forage supply and quality, cover, and shelter are not available in other pastures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $5,402.86

Scenario Cost/Unit: $54.03

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	$213.22	25	$5,330.50

Practice: E528102Z - Improved grazing management for wind erosion through monitoring activities

Scenario #4 - Grazing mgmt for wind erosion

Scenario Description:

Three predominant key grazing areas are evaluated utilizing the Rangeland Health Assessment protocols to determine how well the ecological processes of the site(s) are functioning. Departure from reference categories will be determined, justified, and ratings described for soil and site stability, hydrologic function, and biotic integrity. Utilizing knowledge learned from this as a part of the ranch resource assessment, a Certified Range Management Consultant or Certified Professional in Range Management will provide recommendations or follow-up evaluations toward mitigating some of the degradation risks that are initially identified.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: $1,638.52

Scenario Cost/Unit: $1.64

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	8	$228.64
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	10	$190.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	4	$144.72
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	12	$1,010.16

Practice: E528104Z - Grazing management that protects sensitive areas from gully erosion

Scenario #1 - Grazing mgmt-sensitive areas-erosion

Scenario Description:

Grazing management employed will provide cover and density needed in the watershed in order to protect sensitive areas such as sinkholes, streams, highly erodible areas, or locations with plants that cannot tolerate defoliation.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: $1,530.04

Scenario Cost/Unit: $1.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	4	$88.08
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	12	$342.96
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	17	$323.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Wire, Polytape	7	Wire, Polytape for electric fence. Rolls of 655' to 825'. Includes materials and shipping only.	Each	$51.00	1	$51.00
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	$325.35	1	$325.35
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	$262.29	1	$262.29

Practice: E528105Z - Prescribed grazing that improves or maintains riparian and watershed function-erosion

Scenario #1 - Prescribed grazing-erosion

Scenario Description:

Grazing management employed will provide cover and density needed in the watershed in order to reduce runoff, improve infiltration, provide for above ground water filtration and sustain applicable fish and wildlife species habitat.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $870.50

Scenario Cost/Unit: $8.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	10	$169.30
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	10	$190.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	$48.49	1	$48.49
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	$325.35	1	$325.35

Practice: E528118Z1 - Prescribed grazing that maintains/improves riparian/watershed function impairment from nutrients

Scenario #1 - Prescribed grazing-nut runoff

Scenario Description:

Grazing management employed will provide cover and density needed in the watershed in order to reduce runoff, improve infiltration, provide for above ground water filtration and sustain applicable fish and wildlife species habitat.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,455.78

Scenario Cost/Unit: $14.56

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	6	$171.48
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	10	$169.30
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	$48.49	4	$193.96
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	$325.35	1	$325.35
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	$262.29	1	$262.29

Practice: E528119Z - Grazing management that protects sensitive areas-ground water from nutrients

Scenario #1 - Grazing mgmt-sensitive area-nut sub water

Scenario Description:

Grazing management employed will provide cover and density needed in the watershed in order to protect sensitive areas such as sinkholes, streams, highly erodible areas, or locations with plants that cannot tolerate defoliation.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: $1,683.04

Scenario Cost/Unit: $1.68

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	4	$88.08
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	12	$342.96
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	17	$323.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Wire, Polytape	7	Wire, Polytape for electric fence. Rolls of 655' to 825'. Includes materials and shipping only.	Each	$51.00	4	$204.00
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	$325.35	1	$325.35
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	$262.29	1	$262.29

Practice: E528122Z - Prescribed grazing that maintains/improves riparian/watershed function-pathogens/chemicals

Scenario #1 - Prescribed grazing-pathogens

Scenario Description:

Grazing management employed will provide cover and density needed in the watershed in order to reduce runoff, improve infiltration, provide for above ground water filtration and sustain applicable fish and wildlife species habitat.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,455.78

Scenario Cost/Unit: $14.56

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	6	$171.48
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	10	$169.30
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	$48.49	4	$193.96
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	$325.35	1	$325.35
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	$262.29	1	$262.29

Practice: E528126Z - Prescribed grazing that maintains/improves riparian/watershed function-min sediment in surface water

Scenario #1 - Prescribed grazing-sediment

Scenario Description:

Grazing management employed will provide cover and density needed in the watershed in order to reduce runoff, improve infiltration, provide for above ground water filtration and sustain applicable fish and wildlife species habitat.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,286.48

Scenario Cost/Unit: $12.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	6	$171.48
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	$48.49	4	$193.96
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	$325.35	1	$325.35
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	$262.29	1	$262.29

Practice: E528133Z1 - Stockpiling cool season forage to improve structure and composition.

Scenario #1 - Stockpile cool season forage-structure

Scenario Description:

Grazing management employed will stop grazing events of selected paddock(s) to allow pasture forages to grow to maximum vegetative biomass accumulation before the end of the growing season.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $2,180.94

Scenario Cost/Unit: $21.81

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	6	$171.48
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	10	$169.30
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	$48.49	1	$48.49
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	$325.35	1	$325.35
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	$0.42	2000	$840.00
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	$262.29	1	$262.29
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	3	$30.63

Practice: E528133Z2 - Grazing management for improving quantity/quality of plant structure/composition for wildlife

Scenario #1 - Grazing mgmt-structure for wildlife

Scenario Description:

Managing the harvest of vegetation with grazing and/or browsing animals for the purpose of improving or maintaining the structure and composition of the plant community that is available for wildlife.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $290.13

Scenario Cost/Unit: $2.90

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	15	$253.95
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	1	$36.18

Practice: E528136Z1 - Grazing management for improving quantity and quality of food for wildlife

Scenario #1 - Grazing mgmt-food

Scenario Description:
Grazing management employed will provide plant structure, density and diversity needed for the desired wildlife species of concern.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: $426.80

Scenario Cost/Unit: $0.43

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	10	$361.80

Practice: E528137Z1 - Grazing management for improving quantity and quality of cover and shelter for wildlife

Scenario #1 - Grazing mgmt-shelter

Scenario Description:
Grazing management employed will provide plant structure, density and diversity needed for the desired wildlife species of concern.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: $426.80

Scenario Cost/Unit: $0.43

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	10	$361.80

Practice: E528137Z2 - Incorporating wildlife refuge areas in contingency plans for prescribed grazing-cover/shelter

Scenario #1 - Add wildlife refuge area-shelter

Scenario Description:

A prescribed grazing plan that includes 12 month (or longer) deferment of a pasture that consists of native grasses and/or legumes and/or perennial forbs for the purpose of meeting the needs for drought/disaster contingency plans that will also provide wildlife habitat for a period of time.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,540.43

Scenario Cost/Unit: $15.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	6	$171.48
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	15	$253.95
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	$48.49	4	$193.96
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	$325.35	1	$325.35
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	$262.29	1	$262.29

Practice: E528138Z - Incorporating wildlife refuge areas in contingency plans for prescribed grazing-water access

Scenario #1 - Add wildlife refuge area-water

Scenario Description:

A prescribed grazing plan that includes 12 month (or longer) deferment of a pasture that consists of native grasses and/or legumes and/or perennial forbs for the purpose of meeting the needs for drought/disaster contingency plans that will also provide wildlife habitat for a period of time.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,540.43

Scenario Cost/Unit: $15.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	6	$171.48
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	15	$253.95
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	$48.49	4	$193.96
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	$325.35	1	$325.35
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	$262.29	1	$262.29

Practice: E528140Z1 - Maintaining quantity and quality of forage for animal health and productivity

Scenario #1 - Maintain forage quantity and quality

Scenario Description:

Managing the harvest of vegetation with grazing and/or browsing animals for the purposes of maintaining desired pasture composition/plant vigor and improving/maintaining quantity and quality of forage for the animals' health and productivity..

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: $3,393.35

Scenario Cost/Unit: $3.39

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	$65.00	1	$65.00
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	4	$88.08
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	12	$342.96
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	$16.93	36	$609.48
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	17	$323.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	2	$72.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	12	$1,010.16
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	$48.49	1	$48.49
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	$325.35	1	$325.35
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	$262.29	1	$262.29
Nutritional Balance Analyzer, fecal sample analysis only	1127	NIRS fecal analysis, animal performance report. Includes materials and shipping only.	Each	$41.03	6	$246.18

Practice: E554118Z1 - Installation of end of pipe or ditch treatment for phosphorus

Scenario #1 - Installation of treatment for P

Scenario Description:
Add end of pipe treatment. If dissolved Phosphorus is the pollutant of concern, add Interim standard 782, Phosphorus Treatment Structure for each pipe outlet in a field.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 554 - Drainage Water Management

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 554 - Drainage Water Management

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $7,007.42

Scenario Cost/Unit: $7,007.42

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	$365.63	6	$2,193.78
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	40	$82.80
Earthfill, Dumped and Spread	51	Earthfill, dumped and spread without compaction effort, includes equipment and labor	Cubic Yard	$3.22	40	$128.80
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	$63.41	16	$1,014.56
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	16	$347.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	4	$336.72
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	$30.50	20	$610.00
Pipe, PVC, 4", SDR 41	983	Materials: - 4" - PVC - SDR 41 100 psi - ASTM D2241	Foot	$1.99	80	$159.20
Tank, Poly enclosed Storage, 300-1000 gal	1074	Water storage tanks. Includes materials and shipping only.	Gallon	$0.92	0	$0.00
Aggregate, gravel, washed, pea gravel	1331	Washed and graded pea gravel river stone. Includes materials and local delivery within 20 miles of quarry.	Cubic Yard	$33.62	20	$672.40
Water Control Structure, Stoplog, Inline, fixed costs portion	2145	Fixed cost portion of Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Fixed cost portion. Materials only.	Each	$318.35	1	$318.35
Water Control Structure, Stoplog, Inline, variable cost portion	2146	Variable cost portion of a Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Calculate total variable costs by multiplying by the structure height x pipe diameter. Materials only.	Height x Diameter	$12.30	36	$442.80
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65
Aggregate, Shipping, Cubic Yard-mile	2360	Mobilization of aggregate material beyond 20 miles of local delivery from quarry to construction site. Cubic Yard-mile (Cubic Yard * miles of haul).	Cubic Yard Mile	$0.35	400	$140.00

Practice: E554118Z2 - Installation of a saturated buffer drain outlet

Scenario #1 - Installation of a vegetated outlet

Scenario Description:
Install Conservation Practice Standard 604, Saturated Buffer so all of the drain outlets on a field are routed through an appropriate buffer.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 554 - Drainage Water Management

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 554 - Drainage Water Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $3,536.30

Scenario Cost/Unit: $3,536.30

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	$1.21	400	$484.00
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$56.65	4	$226.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	4	$76.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	4	$86.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	4	$144.72
Materials						
Pipe, HDPE, 5", PCPT, Single Wall	1271	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 5" diameter - ASTM F405. Material cost only.	Foot	$0.73	400	$292.00
Water Level Control Structure, Inline, 2 Baffle, 10" diameter	2021	Inline Inlet WCS 6' High x 10" Dia.connections , 2 baffle (3 compartments)	Each	$1,969.49	1	$1,969.49
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E554138X - Extend the periods of soil saturation or shallow ponding for wildlife

Scenario #1 - Extend saturation/ponding period

Scenario Description:

Extending the periods of wetness (soil saturation or shallow water), in excess of those required under National Conservation Practice Standard (NCP) Drainage Water Management (554), to meet the additional consideration of wildlife.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 554 - Drainage Water Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 554 - Drainage Water Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 25.0

Scenario Total Cost: $188.34

Scenario Cost/Unit: $7.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	2	$57.16
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	5	$95.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	1	$36.18

USDA - Natural Resources Conservation Service

Mississippi

Practice: E578139X - Stream crossing elimination

Scenario #1 - Stream crossing elimination

Scenario Description:
Existing stream crossings on an operation are consolidated into fewer crossings in order to reduce impacts to stream habitat.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 578 - Stream Crossing

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 578 - Stream Crossing

Feature Measure: Typical feature is 0.09 acres

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: $7,486.57

Scenario Cost/Unit: $7,486.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	$66.84	16	$1,069.44
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	$114.96	8	$919.68
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	$12.74	0.1	$1.27
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	$97.75	16	$1,564.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	32	$608.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	32	$694.72
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	16	$578.88
Materials						
Erosion Control Blanket, biodegradable	1213	Biodegradable erosion control blanket, typically a composite of natural fibers with reinforcing polymer netting. Materials and shipping only.	Square Yard	$1.32	300	$396.00
Cuttings, woody, medium size	1308	Woody cuttings, live stakes or whips typically 1/4" to 1" diameter and 24" to 48" long. Includes materials and shipping only.	Each	$0.48	300	$144.00
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	$25.58	42	$1,074.36
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	$37.92	0.1	$3.79
One Species, Cool Season, Introduced Perennial Grass	2313	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	$31.57	0.1	$3.16
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E580105Z - Stream corridor bank stability improvement

Scenario #1 - Stream bank stability improvement

Scenario Description:
Stream corridor bank vegetation components are established to provide additional streambank stability.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 580 - Streambank and Shoreline Protection

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 580 - Streambank and Shoreline Protection

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: $3,526.32

Scenario Cost/Unit: $1,763.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	8	$176.16
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	8	$228.64
Trailer, enclosed, small	1503	Small enclosed trailer (typically less than 30' in length) pulled by a pickup to transport materials and equipment. Truck not included.	Hour	$7.30	8	$58.40
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	8	$98.88
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	48	$912.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Shrub, seedling or transplant, potted, 1/2 to 1 gal.	1526	Potted shrub, 1/2 to 1 gal. Includes materials and shipping only.	Each	$4.48	65	$291.20
Tree, hardwood, seedling or transplant, potted, 1/2 to 1 gal.	1531	Potted hardwood tree, 1/2 to 1 gal. Includes materials and shipping only.	Each	$4.50	65	$292.50
Tree, conifer, seedling or transplant, potted, 1/2 to 1 gal.	1536	Potted conifer, 1/2 to 1 gal. Includes materials and shipping only.	Each	$4.37	65	$284.05
Tree shelter, mesh tree tube, 48"	1556	48" tall vexar or other open weave tubular tree shelter to protect from animal damage. Materials only.	Each	$1.11	65	$72.15
Tree shelter, solid tube type, 4" x 24"	1563	4" x 24" tree tube for protection from animal damage. Materials only.	Each	$2.23	65	$144.95
Tree shelter, solid tube type, 4" x 48"	1566	4" x 48" tree tube for protection from animal damage. Materials only.	Each	$4.22	65	$274.30
Stakes, wood, 1" x 1" x 48"	1578	1" x 1" x 48" wood stakes to fasten items in place. Includes materials only.	Each	$2.07	195	$403.65

USDA - Natural Resources Conservation Service

Mississippi

Practice: E580137Z - Stream corridor bank vegetation improvement

Scenario #1 - Stream corridor bank veg improvement

Scenario Description:

Stream corridor bank vegetation components are established to improve ecosystem functioning and stability.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 580 - Streambank and Shoreline Protection

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 580 - Streambank and Shoreline Protection

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: $3,526.32

Scenario Cost/Unit: $1,763.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	8	$176.16
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	8	$228.64
Trailer, enclosed, small	1503	Small enclosed trailer (typically less than 30' in length) pulled by a pickup to transport materials and equipment. Truck not included.	Hour	$7.30	8	$58.40
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	8	$98.88
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	48	$912.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	8	$289.44
Materials						
Shrub, seedling or transplant, potted, 1/2 to 1 gal.	1526	Potted shrub, 1/2 to 1 gal. Includes materials and shipping only.	Each	$4.48	65	$291.20
Tree, hardwood, seedling or transplant, potted, 1/2 to 1 gal.	1531	Potted hardwood tree, 1/2 to 1 gal. Includes materials and shipping only.	Each	$4.50	65	$292.50
Tree, conifer, seedling or transplant, potted, 1/2 to 1 gal.	1536	Potted conifer, 1/2 to 1 gal. Includes materials and shipping only.	Each	$4.37	65	$284.05
Tree shelter, mesh tree tube, 48"	1556	48" tall vexar or other open weave tubular tree shelter to protect from animal damage. Materials only.	Each	$1.11	65	$72.15
Tree shelter, solid tube type, 4" x 24"	1563	4" x 24" tree tube for protection from animal damage. Materials only.	Each	$2.23	65	$144.95
Tree shelter, solid tube type, 4" x 48"	1566	4" x 48" tree tube for protection from animal damage. Materials only.	Each	$4.22	65	$274.30
Stakes, wood, 1" x 1" x 48"	1578	1" x 1" x 48" wood stakes to fasten items in place. Includes materials only.	Each	$2.07	195	$403.65

Practice: E590118X - Reduce risks of nutrient losses to surface water by utilizing precision ag technologies

Scenario #1 - Precision ag for nut reduction

Scenario Description:

Utilize precision application technology and techniques to reduce risk of nutrients in surface water by reducing total amount of applied and reducing the potential for delivery of nutrients into water bodies. Precision agriculture technology is utilized to plan and apply nutrients to improve nutrient use efficiency and reduce risk of nutrient losses.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 590 - Nutrient Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 590 - Nutrient Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,603.71

Scenario Cost/Unit: $16.04

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$10.78	100	$1,078.00
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	35	$357.35

Practice: E590118Z - Improving nutrient uptake efficiency and reducing risk of nutrient losses to surface water

Scenario #1 - Nut mgmt for surface water

Scenario Description:

Nutrient management encompasses managing the amount, source, placement, and timing of the application of plant nutrients and soil amendments. Nutrients are currently being applied on the farm based on the 4R nutrient stewardship principles. Enhanced nutrient use efficiency strategies or technologies are utilized to improve nutrient use efficiency and reduce risk of nutrient losses.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 590 - Nutrient Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 590 - Nutrient Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,051.66

Scenario Cost/Unit: $10.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Nitrogen-Urease inhibitor	260	Nitrogen-Urease inhibitor	Acre	$8.19	100	$819.00
Test, Soil Nitrogen Testing	311	Pre-Side Dress/Deep Soil Testing. Includes materials and shipping only.	Each	$12.86	5	$64.30

Practice: E590119X - Reduce risks of nutrient losses to ground water by utilizing precision agriculture technologies to p

Scenario #4 - Prec Ag reduce nut in groundwater

Scenario Description:

Utilize precision application technology and techniques to reduce risk of nutrients in ground water by reducing total amount of applied and reducing the potential for delivery of nutrients into water bodies. Precision agriculture technology is utilized to plan and apply nutrients to improve nutrient use efficiency and reduce risk of nutrient losses.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 590 - Nutrient Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 590 - Nutrient Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,603.71

Scenario Cost/Unit: $16.04

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$10.78	100	$1,078.00
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	35	$357.35

Practice: E590119Z - Improving nutrient uptake efficiency and reducing risk of nutrient losses to groundwater

Scenario #1 - Nut mgmt for groundwater

Scenario Description:

Nutrient management encompasses managing the amount, source, placement, and timing of the application of plant nutrients and soil amendments. Nutrients are currently being applied on the farm based on the 4R nutrient stewardship principles. Enhanced nutrient use efficiency strategies or technologies are utilized to improve nutrient use efficiency and reduce risk of nutrient losses.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 590 - Nutrient Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 590 - Nutrient Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,051.66

Scenario Cost/Unit: $10.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Nitrogen-Urease inhibitor	260	Nitrogen-Urease inhibitor	Acre	$8.19	100	$819.00
Test, Soil Nitrogen Testing	311	Pre-Side Dress/Deep Soil Testing. Includes materials and shipping only.	Each	$12.86	5	$64.30

Practice: E590130Z - Improving nutrient uptake efficiency and reducing risks to air quality - emissions of GHGs

Scenario #1 - Nut mgmt for GHGs

Scenario Description:

Nutrient management encompasses managing the amount, source, placement, and timing of the application of plant nutrients and soil amendments. Nutrients are currently being applied on the farm based on the 4R nutrient stewardship principles. Enhanced nutrient use efficiency strategies or technologies are utilized to improve nutrient use efficiency and reduce risks to air quality by reducing emissions of Greenhouse Gases (GHGs).

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 590 - Nutrient Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 590 - Nutrient Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,051.66

Scenario Cost/Unit: $10.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Nitrogen-Urease inhibitor	260	Nitrogen-Urease inhibitor	Acre	$8.19	100	$819.00
Test, Soil Nitrogen Testing	311	Pre-Side Dress/Deep Soil Testing. Includes materials and shipping only.	Each	$12.86	5	$64.30

Practice: E595116X - Reduce risk of pesticides in surface water by utilizing precision pesticide application techniques

Scenario #1 - Pest mgmt for surface water

Scenario Description:

Utilize precision application techniques to reduce risk of pesticides in surface water by reducing total amount of chemical applied and reducing the potential for delivery of chemicals into water bodies.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 595 - Integrated Pest Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 595 - Integrated Pest Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,248.54

Scenario Cost/Unit: $12.49

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	$9.96	100	$996.00
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54

Practice: E595116Z - Reduce risk of pesticides in surface water by utilizing IPM PAMS techniques

Scenario #1 - IPM PAMS techniques

Scenario Description:

Utilize integrated pest management (IPM) prevent, avoidance, monitoring, and suppression (PAMS) techniques to reduce risk of pesticides in surface water and reducing the potential for delivery of chemicals into water bodies.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 595 - Integrated Pest Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 595 - Integrated Pest Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $526.34

Scenario Cost/Unit: $5.26

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	10	$273.80
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54

Practice: E595116Z2 - Reducing routine neonicotinoid seed treatments on corn and soybean crops.

Scenario #4 - Reducing routine seed treatments

Scenario Description:

Eliminate routine use of neonicotinoid seed treatments to reduce risk of pesticides in surface water by reducing total amount of chemical applied and reducing the potential for delivery of chemicals into water bodies that would impair water quality and fish and wildlife habitat.

Before Situation:

Resources are protected at the minimum level established in the Conservation Practice Standard (CPS) 595 - Integrated Pest Management.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in the Conservation Practice Standard (CPS) 595 - Integrated Pest Management.

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $420.90

Scenario Cost/Unit: $4.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90

Practice: E595129Z - Reduce ozone precursor emissions related to pesticides by utilizing IPM PAMS techniques

Scenario #1 - IPM PAMS techniques for ozone reduction

Scenario Description:

Utilize integrated pest management (IPM) prevent, avoidance, monitoring, and suppression (PAMS) techniques to reduce ozone precursor emissions related to pesticides.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 595 - Integrated Pest Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 595 - Integrated Pest Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $526.34

Scenario Cost/Unit: $5.26

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	10	$273.80
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	3	$252.54

Practice: E612130Z - Planting for high carbon sequestration rate

Scenario #1 - Planting for high carbon sequestration

Scenario Description:

Plant tree species and use stocking levels for higher growth to increase the rate of carbon sequestration (capture). Use species with a longer life span as well as relatively fast growth, and species suitable for durable manufactured products. Increase stocking levels in forests that are not fully stocked. Implement afforestation on appropriate open lands.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $6,070.01

Scenario Cost/Unit: $607.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	6	$132.12
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	4	$24.80
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	6	$150.24
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	$7.01	6	$42.06
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	4	$1,576.64
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	4	$828.44
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	2	$311.02
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	6	$114.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	6	$130.26
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	$36.18	6	$217.08
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	4	$75.48
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	4	$107.12
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	3	$3.93
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	7260	$2,178.00
Mobilization						

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E612132Z - Establishing tree/shrub species to restore native plant communities

Scenario #1 - Tree/shrubs-restore native communities

Scenario Description:

Establish trees and/or shrubs to restore elements of plant diversity that have been lost through past diseases or improper management. For example, disease-resistant varieties of elm and chestnut can be established to restore the ecological functions of American elm and American chestnut. At the stand level, past forest management may have eliminated certain native tree species. Restoring stand-level diversity and function addresses a wide array of resource concerns and strengthens ongoing management activities. This enhancement improves a forest that is already in good condition by increasing plant diversity, and improving health and vigor through adding plants with resistance to disease, pests, or other local hazards. Additional benefits include contributing to carbon storage, and providing diversity in wildlife habitat and food sources.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 5.0

Scenario Total Cost: $3,123.00

Scenario Cost/Unit: $624.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	12	$148.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	12	$228.00
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how to conserve wildlife habitats, improve water quality and soil stability, and how best to comply with environmental regulations. May devise plans for planting and growing new trees, monitoring trees for healthy growth, determining optimal thinning schedules, and increasing carbon capture and storage.	Hour	$74.41	4	$297.64
Materials						
Shrub, seedling or transplant, potted, 1/2 to 1 gal.	1526	Potted shrub, 1/2 to 1 gal. Includes materials and shipping only.	Each	$4.48	50	$224.00
Tree, hardwood, seedling or transplant, potted or B&B, 2-3 gal.	1532	Potted or balled and burlapped hardwood tree, 2-3 gal. Includes materials and shipping only.	Each	$7.08	100	$708.00
Tree, conifer, seedling or transplant, potted or B&B, 2-3 gal.	1537	Potted or balled and burlapped conifer tree, 2-3 gal. Includes materials and shipping only.	Each	$6.90	100	$690.00
Tree shelter, solid tube type, 4" x 60"	1567	4" x 60" tree tube for protection from animal damage. Materials only.	Each	$5.22	150	$783.00

Practice: E612133X1 - Adding food-producing trees and shrubs to existing plantings

Scenario #1 - Adding food-producing trees and shrubs

Scenario Description:

Plant food-producing trees and shrubs for wildlife or human consumption within windbreaks, alley cropping, multi-story cropping, or silvopasture systems, or riparian forest buffers.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Acres

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $1,434.11

Scenario Cost/Unit: $143.41

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	10	$285.80
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	10	$123.60
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	10	$190.00
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	1	$18.87
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	1	$26.78
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	1	$1.31
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.56	341	$190.96
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	340	$102.00
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E612133X2 - Cultural plantings

Scenario #1 - Cultural plantings

Scenario Description:

Plant trees and shrubs that are of cultural significance, such as those species utilized by Tribes in traditional practices, medicinal, species used in basket-making, etc. (e.g., paper birch, slippery elm, witch hazel).

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $1,059.65

Scenario Cost/Unit: $1,059.65

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	10	$123.60
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	10	$190.00
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	1	$18.87
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	1	$26.78
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	1	$1.31
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	681	$204.30
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E612136Z - Tree/shrub planting for wildlife food

Scenario #1 - Tree/shrub planting for wildlife food

Scenario Description:

?Tree or shrub planting to enhance habitat for native wildlife. A minimum of five tree or shrub species will be used; they will be species that provide food and/or cover for identified wildlife species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $1,118.29

Scenario Cost/Unit: $1,118.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	11	$135.96
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	11	$209.00
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	1	$18.87
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	1	$26.78
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	1	$1.31
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.56	605	$338.80
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	218	$65.40

Practice: E612137Z - Tree/shrub planting for wildlife cover

Scenario #1 - Tree/shrub planting for wildlife cover

Scenario Description:

Tree or shrub planting to enhance habitat for native wildlife. A minimum of five tree or shrub species will be used; they will be species that provide food and/or cover for identified wildlife species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: $1,118.29

Scenario Cost/Unit: $1,118.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	1	$6.20
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	$12.36	11	$135.96
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.36	$74.56
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.23	$35.77
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	11	$209.00
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.87	1	$18.87
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$26.78	1	$26.78
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	1	$1.31
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.56	605	$338.80
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	$0.30	218	$65.40

USDA - Natural Resources Conservation Service

Mississippi

Practice: E643139X - Creating native plant refugia

Scenario #1 - Creating native plant refugia

Scenario Description:

Provide protection from adverse environmental conditions to create refugia for documented occurrences of sensitive plant communities.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 643 - Restoration and Management of Rare and Declining Habitats

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 643 - Restoration and Management of Rare and Declining Habitats

Feature Measure: Feet of Fence

Scenario Unit:: Foot

Scenario Typical Size: 440.0

Scenario Total Cost: $3,323.03

Scenario Cost/Unit: $7.55

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	$7.39	8	$59.12
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	2	$8.82
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	8	$176.16
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	$25.04	8	$200.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	2	$168.36
Materials						
Wire, Woven, Galvanized, 12.5 Gauge, 48"	4	Galvanized 12.5 gauge, 48" - 330' roll. Includes materials and shipping only.	Each	$261.88	3	$785.64
Post, Wood, CCA treated, 6" x 12-14'	13	Wood Post, Line/End 6" X 12-14', CCA Treated. Includes materials and shipping only.	Each	$27.48	38	$1,044.24
Fence, Wire Assembly, Woven Wire	35	Brace pins, twist sticks, staples. Includes materials and shipping only.	Foot	$0.12	1648	$197.76
Gate, Game, 8' High X 4'	1082	4' Wide Game Gate (8' Tall). Includes materials and shipping only.	Each	$205.99	1	$205.99
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E644136Z - Managing Flood-Irrigated Landscapes for Wildlife

Scenario #4 - Manage flood irrigated landscape for wildlife food

Scenario Description:

When flooded to shallow depths at the appropriate time of year, flood-irrigated cropland and pastureland provides foraging habitat for breeding and migratory waterfowl and waterbirds.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 644 – Wetland Wildlife Habitat Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 644 – Wetland Wildlife Habitat Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $1,037.08

Scenario Cost/Unit: $20.74

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	9	$198.18
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	22	$418.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90

Practice: E646136Z1 - Close structures to capture/retain rainfall to improve food for waterfowl/wading birds during winter

Scenario #1 - Close structures to improve food

Scenario Description:

When flooded to shallow depths during fall and winter, agricultural fields provide ideal foraging habitat for myriad species of waterfowl and wading birds . In addition, flooded conditions promote establishment of aquatic invertebrate populations, thus providing protein-rich food sources for shorebirds as well as waterfowl and wading birds.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $1,168.23

Scenario Cost/Unit: $23.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	9	$198.18
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	2.5	$131.15
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	22	$418.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90

Practice: E646136Z2 - Extend retention of rainfall to provide food for late winter habitat

Scenario #1 - Extend retention - food

Scenario Description:

When flooded to shallow depths during fall and retention of the captured rainfall is extended into late winter, agricultural fields provide maximum foraging habitat for myriad species of waterfowl and wading birds. Agriculture fields are typically drained in preparation of spring planting, but retention of water into late winter will provide high quality food for wildlife during a time when it may otherwise be in low abundance.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $1,372.45

Scenario Cost/Unit: $27.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	11	$242.22
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	2.5	$131.15
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	26	$494.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	6	$505.08

Practice: E646136Z3 - Shorebird habitat, late season shallow water with manipulation to improve food sources

Scenario #1 - Late season shallow water - food

Scenario Description:

Suitable shorebird habitat is limited during the summer and fall as birds migrate south post-breeding and providing shallow water and mud flat habitat will benefit a variety of shorebird species. Optimal conditions are created when water levels are slowly reduced through evaporation, which allows for propagation of invertebrates (typically insect larvae) used as food by shorebirds. Manipulation of vegetation, preferably through rolling, creates open conditions required by this suite of birds as a means to detect and avoid predators, and provides nutrient inputs for invertebrate production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $2,457.39

Scenario Cost/Unit: $49.15

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	9	$198.18
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	4.5	$236.07
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	50	$839.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	22	$418.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24

Practice: E646136Z4 - Shorebird habitat, extended late season shallow water with manipulation to improve food sources

Scenario #1 - Extended late season shallow water-food

Scenario Description:

When flooded to shallow depths during fall and retention of the captured rainfall is extended into late winter, the shallow water and mud flat habitat will benefit a variety of shorebird species. Optimal conditions are created when water levels are slowly reduced through evaporation, which allows for propagation of invertebrates (typically insect larvae) used as food by shorebirds. Agriculture fields are typically drained in preparation of spring planting, but retention of water into late winter will provide high quality food for wildlife during a time when it may otherwise be in low abundance. Manipulation of vegetation, preferably through rolling, creates open conditions required by this suite of birds as a means to detect and avoid predators, and provides nutrient inputs for invertebrate production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $2,714.07

Scenario Cost/Unit: $54.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	11	$242.22
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	5.5	$288.53
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	50	$839.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	26	$494.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	6	$505.08
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24

Practice: E646137X - Renovate small, shallow pothole and playa sites which may seasonally hold water

Scenario #1 - Shallow water development and management

Scenario Description:
Renovate small, shallow pothole and playa sites which may seasonally hold water.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 4.0

Scenario Total Cost: $6,491.14

Scenario Cost/Unit: $1,622.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	$2.07	1613	$3,338.91
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	4	$24.80
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	$21.58	3	$64.74
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	$394.16	0.41	$161.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	$207.11	0.23	$47.64
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	$155.51	0.36	$55.98
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	4	$151.32
Six Species Mix, Native Forb	2334	Native forb mix. Includes material and shipping only.	Acre	$952.01	2	$1,904.02
Native Grass and Forb Mix, for Wildlife (including pollinators) or Ecosystem Restoration	2335	Native grass and forb/legume mix, including specialized species. Includes material and shipping only.	Acre	$252.12	1	$252.12
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	$490.01	1	$490.01

Practice: E646137Z1 - Close structures to capture and retain rainfall to improve cover and shelter for birds during winter

Scenario #1 - Close structures during winter.

Scenario Description:
When flooded to shallow depths during fall and winter, agricultural fields provide ideal cover and shelter for myriad species of waterfowl and wading birds.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $1,168.23

Scenario Cost/Unit: $23.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	9	$198.18
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	2.5	$131.15
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	22	$418.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90

Practice: E646137Z2 - Extend retention of captured rainfall to provide enhanced cover and shelter for late winter habitat

Scenario #1 - Extend retention-cover and shelter

Scenario Description:

When flooded to shallow depths during the fall and retained into late winter, agricultural fields provide maximum shelter and cover for myriad species of waterfowl and wading birds. Agriculture fields are typically drained in preparation of spring planting, but retention of water into late winter will provide shelter and cover for waterfowl and shorebirds during a time when it may otherwise be in low abundance.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $1,372.45

Scenario Cost/Unit: $27.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	11	$242.22
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	2.5	$131.15
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	26	$494.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	6	$505.08

Practice: E646137Z3 - Shorebird habitat, late season shallow water with manipulation to improve cover and shelter

Scenario #1 - Late season shallow water - cover

Scenario Description:

Suitable shorebird habitat is limited during the summer and fall as birds migrate south post-breeding. Providing shallow water and mud flat habitat will benefit a variety of shorebird species. Improved conditions are created when water levels are slowly reduced through evaporation, which allows for propagation of invertebrates (typically insect larvae) used as food by shorebirds. Manipulation of vegetation, preferably through rolling, creates open conditions required by this suite of birds as a means to detect and avoid predators, and provides nutrient inputs for invertebrate production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $2,457.39

Scenario Cost/Unit: $49.15

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	9	$198.18
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	4.5	$236.07
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	50	$839.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	22	$418.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24

Practice: E646137Z4 - Extended late season shallow water with manipulation to improve cover and shelter

Scenario #1 - Extended late season shallow water-cover

Scenario Description:

Suitable shorebird habitat is limited during the summer and fall as birds migrate south post-breeding. Agriculture fields are typically drained in preparation of spring planting, but retention of water into late winter will provide shelter and cover for waterfowl and shorebirds during a time when it may otherwise be in low abundance. Optimal conditions are created when water levels are slowly reduced and manipulation of vegetation, preferably through rolling, creates open conditions required by this suite of birds as a means to detect and avoid predators, and provides nutrient inputs for invertebrate production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $2,714.07

Scenario Cost/Unit: $54.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	11	$242.22
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	5.5	$288.53
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	50	$839.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	26	$494.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	6	$505.08
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24

Practice: E646138Z1 - Close structures to capture and retain rainfall to provide water for birds during winter

Scenario #1 - Close structures to provide water

Scenario Description:
When flooded to shallow depths during fall and winter, agricultural fields provide water essential for myriad species of waterfowl and wading birds.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $1,168.23

Scenario Cost/Unit: $23.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	9	$198.18
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	2.5	$131.15
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	22	$418.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90

Practice: E646138Z2 - Extend retention of captured rainfall to provide late winter water habitat

Scenario #1 - Extend winter water habitat

Scenario Description:

When flooded to shallow depths during fall and winter, agricultural fields provide water essential for myriad species of waterfowl and wading birds. Agriculture fields are typically drained in preparation of spring planting, but retention of water into late winter will provide water for shorebirds and waterfowl during a time when it may otherwise be in low abundance.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $1,372.45

Scenario Cost/Unit: $27.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	11	$242.22
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	2.5	$131.15
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	26	$494.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	6	$505.08

Practice: E646138Z3 - Shorebird habitat, late season shallow water with manipulation

Scenario #1 - Late season shallow water

Scenario Description:

Suitable water is limited during the summer and fall as birds migrate south post-breeding. Providing shallow water and mud flat habitat will benefit a variety of shorebird species. Improved conditions are created when water levels are slowly reduced through evaporation. Manipulation of vegetation, preferably through rolling, creates open water conditions required by this suite of birds as a means to detect and avoid predators, and provides nutrient inputs for invertebrate production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $2,457.39

Scenario Cost/Unit: $49.15

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	9	$198.18
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	4.5	$236.07
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	50	$839.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	22	$418.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24

Practice: E646138Z4 - Shorebird habitat, extended late season shallow water with manipulation

Scenario #1 - Extended late season shallow water

Scenario Description:

Suitable water is limited during the summer and fall as birds migrate south post-breeding. Agriculture fields are typically drained in preparation of spring planting, but retention of water into late winter will provide habitat during a time when it may otherwise be in low abundance. Optimal conditions are created when water levels are slowly reduced and manipulation of vegetation, preferably through rolling, creates open water conditions required by this suite of birds as a means to detect and avoid predators, and provides nutrient inputs for invertebrate production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $2,714.07

Scenario Cost/Unit: $54.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	11	$242.22
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	5.5	$288.53
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	50	$839.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	26	$494.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	6	$505.08
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24

Practice: E646139Z1 - Close structures to capture and retain rainfall for birds to improve habitat continuity

Scenario #1 - Close structures - habitat continuity

Scenario Description:

When flooded to shallow depths during fall and winter, agricultural fields provide habitat for myriad species of migratory birds. Those flooded conditions promote a network or continuity of habitat that is available to migratory waterfowl, shorebirds, and wading birds.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $1,168.23

Scenario Cost/Unit: $23.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	9	$198.18
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	2.5	$131.15
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	22	$418.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90

Practice: E646139Z2 - Extend retention of captured rainfall to provide habitat continuity during late winter

Scenario #1 - Extend retention - habitat continuity

Scenario Description:

When flooded to shallow depths during the fall and retained into late winter, agricultural fields provide habitat for myriad species of migratory birds. Agriculture fields are typically drained in preparation of spring planting, but retention of water into late winter will provide a network or continuity of habitat for waterfowl, wading birds, and shorebirds during a time when it may otherwise be in low abundance.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $1,372.45

Scenario Cost/Unit: $27.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	11	$242.22
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	2.5	$131.15
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	26	$494.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	6	$505.08

Practice: E646139Z3 - Shorebird habitat, late season shallow water with manipulation to enhance habitat continuity

Scenario #1 - Late season shallow water-continuity

Scenario Description:

Suitable water is limited during the summer and fall as birds migrate south post-breeding. Providing shallow water and mud flat habitat will benefit a variety of shorebird species. Improved conditions are created when water levels are slowly reduced through evaporation. Manipulation of vegetation, preferably through rolling, creates open water conditions required by this suite of birds as a means to detect and avoid predators, and provides nutrient inputs for invertebrate production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $2,457.39

Scenario Cost/Unit: $49.15

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	9	$198.18
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	4.5	$236.07
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	50	$839.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	22	$418.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	5	$420.90
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24

Practice: E646139Z4 - Shorebird habitat, extended late season shallow water with manipulation - habitat continuity

Scenario #1 - Extended late season water-continuity

Scenario Description:

Suitable water is limited during the summer and fall as birds migrate south post-breeding. Providing shallow water with manipulation of vegetation creates a network or continuity of habitat required by this suite of migratory birds during a time when it may otherwise be in low abundance.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $2,714.07

Scenario Cost/Unit: $54.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	11	$242.22
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	5.5	$288.53
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	$16.78	50	$839.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	26	$494.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	6	$505.08
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24

Practice: E647136Z1 - Manipulate vegetation on fields where rainfall is to be captured and retained-food

Scenario #1 - Manipulate veg for food

Scenario Description:

Harvested and idled agricultural lands, notably those occurring within rice rotations, contain high densities of residual (i.e., waste) grain and natural seeds following harvest. Seed densities in harvested rice fields may rival those documented in intensively managed moist-soil units. When flooded to shallow depths during fall and winter, these agricultural fields provide ideal foraging habitat for myriad species of waterfowl and wading birds. In addition, flooded conditions promote establishment of aquatic invertebrate populations, thus providing protein-rich food sources for shorebirds as well as waterfowl and wading birds. In many cases, light manipulation of dense vegetation is needed to improve the accessibility of food resources to waterfowl, wading birds, and shorebirds.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $1,153.54

Scenario Cost/Unit: $23.07

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	$58.32	8	$466.56
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	8	$173.68
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: E647136Z3 - Establish and maintenance of moist soil vegetation on cropland edges to increase wildlife food

Scenario #1 - Moist soil vegetation-food

Scenario Description:

The wetter or more water saturated portions of cropland fields such as areas adjacent to field drains, have the potential to produce a significant amount of moist soil plants which are a tremendously valuable source of forage and cover for many waterfowl, shorebird and wading bird species, especially during a period of time when such plants may be limited. Under normal cropland production, the native vegetation is restricted on these sites through mechanical and/or chemical control. These maintained moist soil plants also will provide filtering and improve water quality.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $567.75

Scenario Cost/Unit: $11.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	3	$157.38
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	3	$65.13
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24

Practice: E647137Z1 - Manipulate vegetation on fields where rainfall is to be captured and retained-cover/shelter

Scenario #1 - Manipulate veg for cover/shelter

Scenario Description:

This enhancement is to provide cover and shelter for wildlife by retaining some standing rice stubble and by encouraging the establishment of early successional, naturally occurring vegetation in fields post harvest. Allowing some standing rice stubble and naturally occurring vegetation to develop will help provide food and cover for wildlife while enhancing aquatic habitat and improving water quality.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $1,153.54

Scenario Cost/Unit: $23.07

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	$58.32	8	$466.56
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	8	$173.68
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	2	$513.30

Practice: E647137Z2 - Establish and maintenance of moist soil vegetation on cropland edges to increase cover/shelter

Scenario #1 - Moist soil vegetation-cover/shelter

Scenario Description:

The wetter or more water saturated portions of cropland fields such as areas adjacent to field drains, have the potential to produce a significant amount of moist soil plants which are a tremendously valuable source of forage and cover for many waterfowl, shorebird and wading bird species, especially during a period of time when such plants may be limited. Under normal cropland production, the native vegetation is restricted on these sites through mechanical and/or chemical control. These maintained moist soil plants also will provide filtering and improve water quality.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $567.75

Scenario Cost/Unit: $11.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	3	$157.38
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	3	$65.13
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24

Practice: E647139Z1 - Establish/maintain habitat continuity, naturally occurring vegetation in ditches/ditch bank borders

Scenario #1 - Naturally occurring veg in ditches

Scenario Description:

This enhancement is to encourage the establishment of early successional, naturally occurring vegetation in ditches, side slope and bank borders to provide cover, critical nesting and brood rearing habitat as well as filtering overland flow and improving water quality. Ditches perform the critical function of removing water from agricultural lands. Allowing naturally occurring vegetation to develop along ditches, including side slopes, banks and borders, will help provide food and cover for wildlife while enhancing aquatic habitat and improving water quality. Ditches and ditch borders provide a foundation that supports a diverse wildlife community including Northern Bobwhite (Colinus virginianus) and other birds preferring early successional cover. Rabbits, furbearers, amphibians and many other species that inhabit agriculture areas will use this vegetative cover. These areas can also provide critical nesting habitat for the Mottled Duck (Anas fulvigula).

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $567.75

Scenario Cost/Unit: $11.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	$52.46	3	$157.38
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	3	$65.13
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	2	$345.24

Practice: E666106Z1 - Implementing sustainable practices for pine straw raking

Scenario #1 - Sustainable pine straw raking

Scenario Description:

?Adopts guidelines for sustaining soil quality and wildlife habitat on sites where pine straw raking is currently practiced. Raking and removal of pine needles (“pine straw”) provides valuable landscaping material but at a high cost to soil fertility, soil organic matter, wildlife habitat, and in some cases, soil compaction, soil erosion and water quality degradation. Straw removal also makes prescribed burning less feasible by removal of the fine fuels needed to carry frequent surface fires that maintain longleaf pine and its characteristic understory. This enhancement is most applicable to longleaf pine forestland because: (1) longleaf-dominated ecosystems with their characteristic suite of flora and fauna historically predominated in most places where pines are currently grown in the Southeast, and (2) longleaf is the favored species for pine straw operations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $7,493.61

Scenario Cost/Unit: $149.87

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	4	$114.32
Foregone Income						
FI, reduced pine straw raking	2691	Longleaf pine needles are primary crop.	Acre	$127.12	50	$6,356.00
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	10	$841.80
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	10	$102.10
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	$7.07	5	$35.35

Practice: E666106Z2 - Maintaining and improving forest soil quality

Scenario #1 - Maintain/improve forest SQ

Scenario Description:

?Adopts guidelines for maintaining and improving soil quality on sites where forest management activities are practiced. These guidelines will increase soil organic matter content, improve nutrient cycling, and increase infiltration and retention of precipitation. Avoiding soil compaction will allow for greater root development and tree growth, limit windthrow, and reduce drought stress. Increasing carbon storage on site will maintain the soil microbial community and provide wildlife benefits.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $1,800.66

Scenario Cost/Unit: $36.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	4	$17.64
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	4	$114.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	13	$1,094.34
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	10	$102.10
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	$7.07	5	$35.35
Certified Organic, Three plus Species Mix, Cool Season, Annual Grasses and Legumes	2343	Certified organic cool season annual grass and legume mix. Includes material and shipping only.	Acre	$80.29	3	$240.87

Practice: E666107Z - Maintaining and improving forest soil quality by limiting compaction

Scenario #1 - Maintain/improve forest compaction

Scenario Description:

?Adopts guidelines for maintaining and improving soil quality on sites where forest management activities are practiced. These guidelines will increase soil organic matter content, improve nutrient cycling, and increase infiltration and retention of precipitation. Avoiding soil compaction will allow for greater root development and tree growth, limit windthrow, and reduce drought stress. Increasing carbon storage on site will maintain the soil microbial community and provide wildlife benefits.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $1,800.66

Scenario Cost/Unit: $36.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	4	$17.64
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	4	$114.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	13	$1,094.34
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	10	$102.10
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	$7.07	5	$35.35
Certified Organic, Three plus Species Mix, Cool Season, Annual Grasses and Legumes	2343	Certified organic cool season annual grass and legume mix. Includes material and shipping only.	Acre	$80.29	3	$240.87

Practice: E666115Z1 - Converting loblolly and slash pine plantations to longleaf pine to retain soil moisture

Scenario #1 - Convert to longleaf pine-soil moisture

Scenario Description:

Longleaf pine has greater wildlife habitat value, is more resistant to insects and disease, and is better able to withstand hurricane-force winds than other southern pines, particularly loblolly and slash pines. Because of rapid early growth, loblolly and slash pines have often been planted on soils and sites better suited to longleaf. Loblolly has a higher rate of evapotranspiration than longleaf and can deplete soil moisture. Loblolly and slash pine plantations can be converted to longleaf by clearcutting and planting seedlings but mature tree cover is then lost for 20 or more years. This enhancement will gradually convert an existing loblolly or slash pine plantation to longleaf while at the same time maintaining mature tree cover with the associated benefits of wildlife habitat and visual quality, and moderating effects on soil temperature, soil moisture and understory plants.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $5,528.40

Scenario Cost/Unit: $110.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	14	$308.28
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	10	$62.00
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	2	$57.16
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	48	$912.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	18	$1,515.24
Materials						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	$7.07	10	$70.70
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	10	$378.30
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	10	$13.10
Tree, conifer, seedling, containerized, 4 cu. in.	1516	Containerized conifer stock, 4 cubic inches (e.g., "4a" plug), 1.1" x 5.2". Includes materials and shipping only.	Each	$0.25	6050	$1,512.50
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	$4.39	1	$4.39
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E666115Z2 - Enhance development of the forest understory to improve site moisture

Scenario #1 - Forest understory to improve moisture

Scenario Description:

?Forest stand improvement to manage the structure and composition of overstory and understory vegetation so that additional moisture is captured and filtered through the vegetation and soil. Managing the understory vegetation will increase available water to the plants, minimize run-off and erosion, and improve water quality.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: $4,637.28

Scenario Cost/Unit: $231.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	$86.58	16	$1,385.28
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	16	$1,049.44
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	16	$347.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	11	$925.98
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	20	$756.60
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E666118Z - Enhance development of the forest understory to capture nutrients in surface water

Scenario #1 - Understory-nutrients in surface water

Scenario Description:

?Forest stand improvement to manage the structure and composition of overstory and understory vegetation so that additional moisture is captured and filtered through the vegetation and soil, thus minimizing nutrient movement in surface water. Managing the understory vegetation will increase available water to the plants, minimize run-off and erosion, and improve water quality.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: $4,637.28

Scenario Cost/Unit: $231.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	$86.58	16	$1,385.28
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	16	$1,049.44
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	16	$347.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	11	$925.98
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	20	$756.60
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E666119Z - Enhance development of the forest understory to capture nutrients -ground water

Scenario #1 - Understory-nutrients in ground water

Scenario Description:

?Forest stand improvement to manage the structure and composition of overstory and understory vegetation so that additional moisture is captured and filtered through the vegetation and soil, thus minimizing nutrient loss through ground water. Managing the understory vegetation will increase available water to the plants, minimize run-off and erosion, and improve water quality.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: $4,637.28

Scenario Cost/Unit: $231.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	$86.58	16	$1,385.28
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	16	$1,049.44
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	16	$347.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	11	$925.98
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	20	$756.60
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E666130Z - Increase on-site carbon storage

Scenario #1 - Increase on-site carbon storage

Scenario Description:

Utilize forest management techniques to increase on-site carbon storage, including uneven-aged management, longer rotations, leave-tree retention, snags and down woody debris, and soil organic matter.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: $1,094.34

Scenario Cost/Unit: $10.94

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	13	$1,094.34

Practice: E666132Z1 - Crop tree management for mast production

Scenario #1 - Crop tree management for mast production

Scenario Description:
Forest stand improvement using crop tree management techniques to increase mast production

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $3,291.06

Scenario Cost/Unit: $329.11

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	25	$110.25
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	6	$132.12
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	25	$1,639.75
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	25	$475.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	8	$673.44
Materials						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	$7.07	10	$70.70
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.98	10	$189.80

Practice: E666132Z2 - Reduce forest stand density to improve a degraded plant community

Scenario #1 - Forest density-degraded plant community

Scenario Description:

?Open pine or conifer management reduces the number of trees per acre while still maintaining the stand as forest land. It restores elements of stand structure that were formerly created by fire on sites where it is not currently feasible to conduct prescribed burning at the intensity needed to open the canopy. The open stand condition allows a significant amount of sunlight to reach the forest floor and stimulate understory vegetation. The initial treatment creates a stand structure that allows prescribed burning to be applied to limit redevelopment of the woody component of the understory and maintain open conditions. The vegetation management, and wide spacing between trees or clumps of trees, provides visual appeal, reduces the risk of wildfire, and provides wildlife habitat for many at-risk and listed wildlife species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: $5,332.80

Scenario Cost/Unit: $266.64

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	$86.58	20	$1,731.60
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	20	$1,311.80
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	20	$434.20
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	11	$925.98
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	20	$756.60
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E666133X - Forest Stand Improvement to rehabilitate degraded hardwood stands

Scenario #1 - FSI-structure/composition in hardwoods

Scenario Description:

?Mixed species hardwood stands have been subjected to poor logging practices (“high-grading”) for decades. Without professional forestry assistance the best species and individual trees are removed, often before maturity (“diameter-limit cutting”), leaving the poorest species and individual trees to regenerate the stand. Reversing this process requires cutting or killing poor quality trees while retaining any desirable species that might still be present. A combination of 3 silvicultural methods are applied: crop tree release, group selection (all trees removed from an area 0.25 to 1.0 acre in size) and small clear-cuts (all trees removed from an area 1-3 acres in size). A professional forester is needed to recognize and mark crop trees to be retained and delineate areas without crop trees to be clear-cut. Thinning and forest stand improvement will include cutting with hand tools (chainsaws) and injection. Costs involved in any commercial harvesting including marking, access, and transportation are not included in this scenario. However the costs involved in marking trees to be treated or left and supervising the TSI work is included.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acres treated

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $4,853.64

Scenario Cost/Unit: $485.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	16	$70.56
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	40	$2,623.60
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	16	$457.28
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	16	$304.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	8	$673.44
Materials						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	$7.07	10	$70.70
Herbicide, Triazine	1321	Broad spectrum herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$43.74	10	$437.40
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E666133Z1 - Creating structural diversity with patch openings

Scenario #1 - Structural diversity with patch openings

Scenario Description:

Forest stand improvement that creates patch openings. Size and shape of patches will be based on characteristic natural wind disturbances, which will vary geographically and by forest type.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 15.0

Scenario Total Cost: $6,367.20

Scenario Cost/Unit: $424.48

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	150	$661.50
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	15	$330.30
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	150	$2,850.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	30	$2,525.40

Practice: E666133Z2 - Converting loblolly and slash pine plantations to longleaf pine with FSI and prescribed burning

Scenario #1 - Convert to longleaf pine-FSI and burning

Scenario Description:

Longleaf pine has greater wildlife habitat value, is more resistant to insects and disease, and is better able to withstand hurricane-force winds than other southern pines, particularly loblolly and slash pines. Because of rapid early growth, loblolly and slash pines have often been planted on soils and sites better suited to longleaf. Loblolly and slash pine plantations can be converted to longleaf by clearcutting and planting seedlings but mature tree cover is then lost for 20 or more years. This enhancement will gradually convert an existing loblolly or slash pine plantation to longleaf while at the same time maintaining mature tree cover with the associated benefits of wildlife habitat and visual quality, and moderating effects on soil temperature, soil moisture and understory plants.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $5,528.40

Scenario Cost/Unit: $110.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	14	$308.28
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	10	$62.00
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	2	$57.16
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	48	$912.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	18	$1,515.24
Materials						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	$7.07	10	$70.70
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	10	$378.30
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	10	$13.10
Tree, conifer, seedling, containerized, 4 cu. in.	1516	Containerized conifer stock, 4 cubic inches (e.g., "4a" plug), 1.1" x 5.2". Includes materials and shipping only.	Each	$0.25	6050	$1,512.50
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	$4.39	1	$4.39
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E666134Z - Enhance development of the forest understory to create conditions resistant to pests

Scenario #1 - Forest understory-resistant to pests

Scenario Description:

?Forest stand improvement that manages the structure and composition of overstory and understory vegetation to reduce vulnerability to damage by insects and diseases of forest trees. Managing the understory vegetation will also reduce the risk of wildfire, and promote development of herbaceous plants that benefit wildlife.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: $4,637.28

Scenario Cost/Unit: $231.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	$86.58	16	$1,385.28
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	16	$1,049.44
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	16	$347.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	11	$925.98
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	20	$756.60
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E666135Z1 - Reduce height of the forest understory to limit wildfire risk

Scenario #1 - Forest understory-limit wildfire risk

Scenario Description:

?Forest stand improvement that manages forest structure to reduce the risk of wildfire, and creates conditions that facilitate prescribed burning. The fire risk reduction is accomplished by reducing the height of the woody understory and midstory, creating space between the ground cover and the tree canopy.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: $4,637.28

Scenario Cost/Unit: $231.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	$86.58	16	$1,385.28
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	16	$1,049.44
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	16	$347.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	11	$925.98
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	20	$756.60
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E666135Z2 - Reduce forest density and manage understory along roads to limit wildfire risk

Scenario #1 - Manage understory-limit wildfire risk

Scenario Description:

Opening the tree canopy along roads ("daylighting"), and providing space between ground vegetation and tree crowns, minimizes the spread of wildfires that often start along roads. Additionally, opening the canopy will allow more sunlight to reach the forest floor and promote flowering plants, and will reduce maintenance needs by allowing moisture to evaporate from roads.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $2,630.06

Scenario Cost/Unit: $263.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	8	$35.28
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	$86.58	8	$692.64
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	8	$524.72
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	8	$173.68
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	8	$673.44
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	10	$378.30

Practice: E666136Z1 - Reduce forest density and manage understory along roads to improve wildlife food sources

Scenario #1 - Manage understory-wildlife food sources

Scenario Description:

Opening the tree canopy along roads ("daylighting") allows more sunlight to reach the forest floor and promotes the growth of herbaceous plants. The resulting condition is more visually appealing for users of the roadway, and improves wildlife habitat and food sources for many wildlife species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $2,630.06

Scenario Cost/Unit: $263.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	8	$35.28
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	$86.58	8	$692.64
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	8	$524.72
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	8	$152.00
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	8	$173.68
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	8	$673.44
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	10	$378.30

Practice: E666136Z2 - Reduce forest stand density to improve wildlife food sources

Scenario #1 - Stand density-wildlife food sources

Scenario Description:

?Open pine or conifer management reduces the number of trees per acre while still maintaining the stand as forest land. It restores elements of wildlife habitat that formerly resulted from fire, on sites where it is not currently feasible to conduct prescribed burning. The open stand condition allows a significant amount of sunlight to reach the forest floor and stimulate understory vegetation. The initial treatment creates a stand structure that allows prescribed burning to be applied, where feasible, to limit redevelopment of the woody component of the understory and maintain open conditions. The vegetation management, and wide spacing between trees or clumps of trees, provides visual appeal, reduces the risk of wildfire, and provides wildlife habitat for many at-risk and listed wildlife species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: $5,332.80

Scenario Cost/Unit: $266.64

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	$86.58	20	$1,731.60
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	20	$1,311.80
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	20	$434.20
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	11	$925.98
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	20	$756.60
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62

Practice: E666136Z3 - Create patch openings to enhance wildlife food sources and availability

Scenario #1 - Patch openings-food and availability

Scenario Description:

?Forest stand improvement that creates patch openings. Size, shape, and arrangement of patches will be based on natural features, and emulate patches that would result from natural disturbance regimes of wind or fire, varying geographically and by forest type. The treatment will create diversity in stand composition and structure, and enhance wildlife food availability.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 15.0

Scenario Total Cost: $3,999.42

Scenario Cost/Unit: $266.63

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	120	$529.20
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	12	$264.24
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	120	$2,280.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	11	$925.98

Practice: E666137Z1 - Snags, den trees, and coarse woody debris for wildlife habitat

Scenario #1 - Snags and den trees for wildlife

Scenario Description:
Create and retain snags, den trees, forest stand structural diversity, and coarse woody debris on the forest floor to provide cover/shelter for native wildlife species.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $460.30

Scenario Cost/Unit: $46.03

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	7	$30.87
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	1	$22.02
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	3	$196.77
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	7	$191.66
Materials						
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.98	1	$18.98

Practice: E666137Z2 - Summer roosting habitat for native forest-dwelling bat species

Scenario #1 - Summer roosting habitat for bats

Scenario Description:
Creates new potential roost trees within upland and riparian forests to achieve desired summer habitat for forest dwelling bat species.

Before Situation:
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: $1,886.34

Scenario Cost/Unit: $188.63

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	13	$57.33
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	6	$132.12
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	13	$852.67
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	13	$247.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	4	$336.72
Materials						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	$7.07	10	$70.70
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$18.98	10	$189.80

Practice: E666137Z3 - Increase diversity in pine plantation monocultures

Scenario #1 - Improve pine plantation diversity

Scenario Description:

Creates small openings to provide diversity in pine plantations, which are typically monocultures and inhospitable to wildlife. Small openings are one-half (0.5) to three (3) acres in size. The cleared area will have the vegetation removed through harvesting, mulching, or other means compatible with the site.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: $848.96

Scenario Cost/Unit: $424.48

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	20	$88.20
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	20	$380.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	4	$336.72

Practice: E666137Z4 - Converting loblolly and slash pine plantations to longleaf pine to enhance wildlife habitat

Scenario #1 - Convert to longleaf pine-habitat

Scenario Description:

Longleaf pine has greater wildlife habitat value, is more resistant to insects and disease, and is better able to withstand hurricane-force winds than other southern pines, particularly loblolly and slash pines. Because of rapid early growth, loblolly and slash pines have often been planted on soils and sites better suited to longleaf. Loblolly and slash pine plantations can be converted to longleaf by clearcutting and planting seedlings but mature tree cover is then lost for 20 or more years. This enhancement will gradually convert an existing loblolly or slash pine plantation to longleaf while at the same time maintaining mature tree cover with the associated benefits of wildlife habitat and visual quality, and moderating effects on soil temperature, soil moisture and understory plants.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $5,528.40

Scenario Cost/Unit: $110.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	14	$308.28
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	$6.20	10	$62.00
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	2	$57.16
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	$27.38	16	$438.08
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	48	$912.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	18	$1,515.24
Materials						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	$7.07	10	$70.70
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	10	$378.30
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$1.31	10	$13.10
Tree, conifer, seedling, containerized, 4 cu. in.	1516	Containerized conifer stock, 4 cubic inches (e.g., "4a" plug), 1.1" x 5.2". Includes materials and shipping only.	Each	$0.25	6050	$1,512.50
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	$4.39	1	$4.39
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	$256.65	1	$256.65

Practice: E666137Z5 - Implementing sustainable practices for pine straw raking to enhance wildlife habitat

Scenario #1 - Sustainable pine straw raking-habitat

Scenario Description:

?Adopts guidelines for sustaining soil quality and wildlife habitat on sites where pine straw raking is currently practiced. Raking and removal of pine needles (“pine straw”) provides valuable landscaping material but at a high cost to soil fertility, soil organic matter, wildlife habitat, and in some cases, soil compaction, soil erosion and water quality degradation. Straw removal also makes prescribed burning less feasible by removal of the fine fuels needed to carry frequent surface fires that maintain longleaf pine and its characteristic understory. This enhancement is most applicable to longleaf pine forestland because: (1) longleaf-dominated ecosystems with their characteristic suite of flora and fauna historically predominated in most places where pines are currently grown in the Southeast, and (2) longleaf is the favored species for pine straw operations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: $7,493.61

Scenario Cost/Unit: $149.87

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	2	$44.04
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	$28.58	4	$114.32
Foregone Income						
FI, reduced pine straw raking	2691	Longleaf pine needles are primary crop.	Acre	$127.12	50	$6,356.00
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	10	$841.80
Materials						
Test, Soil Test, Standard	299	Includes materials, shiping, labor, and equipment costs.	Each	$10.21	10	$102.10
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	$7.07	5	$35.35

Practice: E666137Z6 - Create patch openings to enhance wildlife cover and shelter

Scenario #1 - Patch openings-cover and shelter

Scenario Description:

?Forest stand improvement that creates patch openings. Size, shape, and arrangement of patches will be based on natural features, and emulate patches that would result from natural disturbance regimes of wind or fire, varying geographically and by forest type. The treatment will create diversity in stand composition and structure, and enhance the availability of wildlife food and cover.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 15.0

Scenario Total Cost: $3,999.42

Scenario Cost/Unit: $266.63

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	$4.41	120	$529.20
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	$22.02	12	$264.24
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	$19.00	120	$2,280.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	11	$925.98

Practice: E666137Z7 - Enhance development of the forest understory to provide wildlife cover and shelter

Scenario #1 - Understory to provide cover/shelter

Scenario Description:

?Forest stand improvement that manages the structure and composition of overstory and understory vegetation to improve the quantity and quality of wildlife cover and shelter. Reducing the number of trees per acre provides canopy openings that allow sunlight to reach the forest floor and promote the growth of herbaceous plants, improving wildlife shelter and cover in the forest understory. The treatment also creates conditions that facilitate the use of prescribed burning as a follow-up practice to maintain wildlife shelter and cover.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: $4,637.28

Scenario Cost/Unit: $231.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	$86.58	16	$1,385.28
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	$65.59	16	$1,049.44
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12”, Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	$21.71	16	$347.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	$84.18	11	$925.98
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	$37.83	20	$756.60
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$172.62	1	$172.62