| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 313 | Waste Storage Facility | Above Ground Steel/Concrete Storage Facility, 25,000 to 100,000 cubic foot storage | Cu-Ft | $2.55 |
| 313 | Waste Storage Facility | HU-Above Ground Steel/Concrete Storage Facility, 25,000 to 100,000 cubic foot storage | Cu-Ft | $3.06 |
| 313 | Waste Storage Facility | Wp_Above Ground Steel/Concrete Storage Facility, 25,000 to 100,000 cubic foot storage | Cu-Ft | $3.06 |
| 313 | Waste Storage Facility | Above Ground Steel/Concrete Storage Facility, greater than 100,000 cubic foot storage | Cu-Ft | $1.97 |
| 313 | Waste Storage Facility | HU-Above Ground Steel/Concrete Storage Facility, greater than 100,000 cubic foot storage | Cu-Ft | $2.36 |
| 313 | Waste Storage Facility | Wp_Above Ground Steel/Concrete Storage Facility, greater than 100,000 cubic foot storage | Cu-Ft | $2.36 |
| 313 | Waste Storage Facility | Above Ground Steel/Concrete Storage Facility, less than 25,000 cubic foot storage | Cu-Ft | $5.90 |
| 313 | Waste Storage Facility | HU-Above Ground Steel/Concrete Storage Facility, less than 25,000 cubic foot storage | Cu-Ft | $7.08 |
| 313 | Waste Storage Facility | Wp_Above Ground Steel/Concrete Storage Facility, less than 25,000 cubic foot storage | Cu-Ft | $7.08 |
| 313 | Waste Storage Facility | Concrete Tank with Lid, Buried, 15,000 to 24,999 cubic foot storage | Cu-Ft | $5.64 |
| 313 | Waste Storage Facility | HU-Concrete Tank with Lid, Buried, 15,000 to 24,999 cubic foot storage | Cu-Ft | $6.76 |
| 313 | Waste Storage Facility | Wp_Concrete Tank with Lid, Buried, 15,000 to 24,999 cubic foot storage | Cu-Ft | $6.76 |
| 313 | Waste Storage Facility | Concrete Tank with Lid, Buried, 25,000 to 49,999 cubic foot storage | Cu-Ft | $4.62 |
| 313 | Waste Storage Facility | HU-Concrete Tank with Lid, Buried, 25,000 to 49,999 cubic foot storage | Cu-Ft | $5.54 |
| 313 | Waste Storage Facility | Wp_Concrete Tank with Lid, Buried, 25,000 to 49,999 cubic foot storage | Cu-Ft | $5.54 |
| 313 | Waste Storage Facility | Concrete Tank with Lid, Buried, 5,000 to 14,999 cubic foot storage | Cu-Ft | $6.52 |
| 313 | Waste Storage Facility | HU-Concrete Tank with Lid, Buried, 5,000 to 14,999 cubic foot storage | Cu-Ft | $7.83 |
| 313 | Waste Storage Facility | Wp_Concrete Tank with Lid, Buried, 5,000 to 14,999 cubic foot storage | Cu-Ft | $7.83 |
| 313 | Waste Storage Facility | Concrete Tank with Lid, Buried, 50,000 to 74,999 cubic foot storage | Cu-Ft | $3.80 |
| 313 | Waste Storage Facility | HU-Concrete Tank with Lid, Buried, 50,000 to 74,999 cubic foot storage | Cu-Ft | $4.57 |
| 313 | Waste Storage Facility | Wp_Concrete Tank with Lid, Buried, 50,000 to 74,999 cubic foot storage | Cu-Ft | $4.57 |
| 313 | Waste Storage Facility | Concrete Tank with Lid, Buried, 75,000 to 109,999 cubic foot storage | Cu-Ft | $3.48 |
| 313 | Waste Storage Facility | HU-Concrete Tank with Lid, Buried, 75,000 to 109,999 cubic foot storage | Cu-Ft | $4.18 |
| 313 | Waste Storage Facility | Wp_Concrete Tank with Lid, Buried, 75,000 to 109,999 cubic foot storage | Cu-Ft | $4.18 |
| 313 | Waste Storage Facility | Concrete Tank with Lid, Buried, equal to or greater than 110,000 cubic foot storage | Cu-Ft | $3.08 |
| 313 | Waste Storage Facility | HU-Concrete Tank with Lid, Buried, equal to or greater than 110,000 cubic foot storage | Cu-Ft | $3.69 |
| 313 | Waste Storage Facility | Wp_Concrete Tank with Lid, Buried, equal to or greater than 110,000 cubic foot storage | Cu-Ft | $3.69 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 313 | Waste Storage Facility | Concrete Tank with Lid, Buried, less than 5,000 cubic foot storage | Cu-Ft | $8.18 |
| 313 | Waste Storage Facility | HU-Concrete Tank with Lid, Buried, less than 5,000 cubic foot storage | Cu-Ft | $9.82 |
| 313 | Waste Storage Facility | Wp_Concrete Tank with Lid, Buried, less than 5,000 cubic foot storage | Cu-Ft | $9.82 |
| 313 | Waste Storage Facility | Dry Stack, Concrete Floor, Concrete Walls | SqFt | $12.15 |
| 313 | Waste Storage Facility | HU-Dry Stack, Concrete Floor, Concrete Walls | SqFt | $14.58 |
| 313 | Waste Storage Facility | Wp_Dry Stack, Concrete Floor, Concrete Walls | SqFt | $14.58 |
| 313 | Waste Storage Facility | Dry Stack, Concrete Floor, NO Walls | SqFt | $6.47 |
| 313 | Waste Storage Facility | HU-Dry Stack, Concrete Floor, NO Walls | SqFt | $7.76 |
| 313 | Waste Storage Facility | Wp_Dry Stack, Concrete Floor, NO Walls | SqFt | $7.76 |
| 313 | Waste Storage Facility | Earthen Storage Facility, greater than or equal to 50,000 cubic foot storage | Cu-Ft | $0.33 |
| 313 | Waste Storage Facility | HU-Earthen Storage Facility, greater than or equal to 50,000 cubic foot storage | Cu-Ft | $0.40 |
| 313 | Waste Storage Facility | Wp_Earthen Storage Facility, greater than or equal to 50,000 cubic foot storage | Cu-Ft | $0.40 |
| 313 | Waste Storage Facility | Earthen Storage Facility, High Water Table | Cu-Ft | $0.94 |
| 313 | Waste Storage Facility | HU-Earthen Storage Facility, High Water Table | Cu-Ft | $1.13 |
| 313 | Waste Storage Facility | Wp_Earthen Storage Facility, High Water Table | Cu-Ft | $1.13 |
| 313 | Waste Storage Facility | Earthen Storage Facility, less than 50,000 cubic foot storage | Cu-Ft | $0.68 |
| 313 | Waste Storage Facility | HU-Earthen Storage Facility, less than 50,000 cubic foot storage | Cu-Ft | $0.81 |
| 313 | Waste Storage Facility | Wp_Earthen Storage Facility, less than 50,000 cubic foot storage | Cu-Ft | $0.81 |
| 314 | Brush Management | Chemical, Individual Plant Treatment | Ac | $28.03 |
| 314 | Brush Management | HU-Chemical, Individual Plant Treatment | Ac | $33.63 |
| 314 | Brush Management | Mechanical and Chemical, Cut Stump plus Chemical Treatment, Pile and Burn, Chip, etc. | Ac | $529.95 |
| 314 | Brush Management | HU-Mechanical and Chemical, Cut Stump plus Chemical Treatment, Pile and Burn, Chip, etc. | Ac | $635.94 |
| 314 | Brush Management | Mechanical and Chemical, Small Woody Vegetation, Medium Infestations | Ac | $39.51 |
| 314 | Brush Management | HU-Mechanical and Chemical, Small Woody Vegetation, Medium Infestations | Ac | $47.41 |
| 314 | Brush Management | Mechanical, Large Woody Vegetation, High Density | Ac | $336.60 |
| 314 | Brush Management | HU-Mechanical, Large Woody Vegetation, High Density | Ac | $403.92 |
| 314 | Brush Management | Mechanical, Large Woody Vegetation, Light Density | Ac | $114.03 |
| 314 | Brush Management | HU-Mechanical, Large Woody Vegetation, Light Density | Ac | $136.83 |
| 314 | Brush Management | Mechanical, Large Woody Vegetation, Medium Density | Ac | $176.93 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 314 | Brush Management | HU-Mechanical, Large Woody Vegetation, Medium Density | Ac | $212.32 |
| 315 | Herbaceous Weed Treatment | Biological Control - Insects | Ac | $46.94 |
| 315 | Herbaceous Weed Treatment | HU-Biological Control - Insects | Ac | $56.33 |
| 315 | Herbaceous Weed Treatment | Wp_Biological Control - Insects | Ac | $56.33 |
| 315 | Herbaceous Weed Treatment | Biological Control - Targeted Grazing | Ac | $34.68 |
| 315 | Herbaceous Weed Treatment | HU-Biological Control - Targeted Grazing | Ac | $41.61 |
| 315 | Herbaceous Weed Treatment | Wp_Biological Control - Targeted Grazing | Ac | $41.61 |
| 315 | Herbaceous Weed Treatment | Chemical, Aerial Application | Ac | $32.61 |
| 315 | Herbaceous Weed Treatment | HU-Chemical, Aerial Application | Ac | $39.13 |
| 315 | Herbaceous Weed Treatment | Wp_Chemical, Aerial Application | Ac | $39.13 |
| 315 | Herbaceous Weed Treatment | Chemical, Ground Application | Ac | $41.96 |
| 315 | Herbaceous Weed Treatment | HU-Chemical, Ground Application | Ac | $50.35 |
| 315 | Herbaceous Weed Treatment | Wp_Chemical, Ground Application | Ac | $50.35 |
| 315 | Herbaceous Weed Treatment | Chemical, Spot Treatment | Ac | $91.94 |
| 315 | Herbaceous Weed Treatment | HU-Chemical, Spot Treatment | Ac | $110.33 |
| 315 | Herbaceous Weed Treatment | Wp_Chemical, Spot Treatment | Ac | $110.33 |
| 315 | Herbaceous Weed Treatment | Mechanical | Ac | $27.22 |
| 315 | Herbaceous Weed Treatment | HU-Mechanical | Ac | $32.67 |
| 315 | Herbaceous Weed Treatment | Wp_Mechanical | Ac | $32.67 |
| 315 | Herbaceous Weed Treatment | Mechanical and chemical | Ac | $28.35 |
| 315 | Herbaceous Weed Treatment | HU-Mechanical and chemical | Ac | $34.02 |
| 315 | Herbaceous Weed Treatment | Wp_Mechanical and chemical | Ac | $34.02 |
| 315 | Herbaceous Weed Treatment | Mechanical, hand and chemical | Ac | $92.38 |
| 315 | Herbaceous Weed Treatment | HU-Mechanical, hand and chemical | Ac | $110.85 |
| 315 | Herbaceous Weed Treatment | Wp_Mechanical, hand and chemical | Ac | $110.85 |
| 315 | Herbaceous Weed Treatment | Mechanical, Hand Tools | Ac | $48.40 |
| 315 | Herbaceous Weed Treatment | HU-Mechanical, Hand Tools | Ac | $58.08 |
| 315 | Herbaceous Weed Treatment | Wp_Mechanical, Hand Tools | Ac | $58.08 |
| 316 | Animal Mortality Facility | Static Pile, Concrete Bin | SqFt | $36.40 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 316 | Animal Mortality Facility | HU-Static Pile, Concrete Bin | SqFt | $43.68 |
| 316 | Animal Mortality Facility | Wp_Static Pile, Concrete Bin | SqFt | $43.68 |
| 316 | Animal Mortality Facility | Static Pile, Concrete Pad | SqFt | $9.71 |
| 316 | Animal Mortality Facility | HU-Static Pile, Concrete Pad | SqFt | $11.65 |
| 316 | Animal Mortality Facility | Wp_Static Pile, Concrete Pad | SqFt | $11.65 |
| 316 | Animal Mortality Facility | Static Pile, Wood Bin(s) | SqFt | $14.31 |
| 316 | Animal Mortality Facility | HU-Static Pile, Wood Bin(s) | SqFt | $17.17 |
| 316 | Animal Mortality Facility | Wp_Static Pile, Wood Bin(s) | SqFt | $17.17 |
| 317 | Composting Facility | Bins, wood or concrete walls on concrete slab | SqFt | $16.28 |
| 317 | Composting Facility | HU-Bins, wood or concrete walls on concrete slab | SqFt | $19.54 |
| 317 | Composting Facility | Composter, Windrow, All-Weather Surface | SqFt | $0.85 |
| 317 | Composting Facility | HU-Composter, Windrow, All-Weather Surface | SqFt | $1.02 |
| 317 | Composting Facility | Composter, Windrow, with Compacted Earth Floor | SqFt | $0.38 |
| 317 | Composting Facility | HU-Composter, Windrow, with Compacted Earth Floor | SqFt | $0.46 |
| 319 | On-Farm Secondary Containment Facility | Concrete Containment Wall | CuYd | $952.35 |
| 319 | On-Farm Secondary Containment Facility | HU-Concrete Containment Wall | CuYd | $1,142.82 |
| 319 | On-Farm Secondary Containment Facility | Corrugated Metal Wall Containment | SqFt | $14.54 |
| 319 | On-Farm Secondary Containment Facility | HU-Corrugated Metal Wall Containment | SqFt | $17.45 |
| 319 | On-Farm Secondary Containment Facility | Double Wall Tank | Gal | $1.58 |
| 319 | On-Farm Secondary Containment Facility | HU-Double Wall Tank | Gal | $1.90 |
| 319 | On-Farm Secondary Containment Facility | Earthen Containment | CuYd | $32.41 |
| 319 | On-Farm Secondary Containment Facility | HU-Earthen Containment | CuYd | $38.89 |
| 319 | On-Farm Secondary Containment Facility | Modular Block Containment Wall | SqFt | $24.82 |
| 319 | On-Farm Secondary Containment Facility | HU-Modular Block Containment Wall | SqFt | $29.78 |
| 320 | Irrigation Canal or Lateral | Irrigation Canal | CuYd | $1.45 |
| 320 | Irrigation Canal or Lateral | HU-Irrigation Canal | CuYd | $2.17 |
| 320 | Irrigation Canal or Lateral | Wp_Irrigation Canal | CuYd | $2.03 |
| 320 | Irrigation Canal or Lateral | Relocate Canal or Lateral | CuYd | $2.39 |
| 320 | Irrigation Canal or Lateral | HU-Relocate Canal or Lateral | CuYd | $3.58 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 320 | Irrigation Canal or Lateral | Wp_Relocate Canal or Lateral | CuYd | $3.34 |
| 325 | High Tunnel System | Contiguous US Snow, Gothic Style | SqFt | $3.40 |
| 325 | High Tunnel System | HU-Contiguous US Snow, Gothic Style | SqFt | $4.07 |
| 325 | High Tunnel System | High Tunnel, Quonset Style | SqFt | $2.77 |
| 325 | High Tunnel System | HU-High Tunnel, Quonset Style | SqFt | $3.32 |
| 327 | Conservation Cover | Conservation Cover for Water Quality and Wildlife, Foregone Income - Level 1 (Year 1) | Ac | $245.66 |
| 327 | Conservation Cover | HU-Conservation Cover for Water Quality and Wildlife, Foregone Income - Level 1 (Year 1) | Ac | $268.85 |
| 327 | Conservation Cover | Introduced Species | Ac | $119.73 |
| 327 | Conservation Cover | HU-Introduced Species | Ac | $143.67 |
| 327 | Conservation Cover | Wp_Introduced Species | Ac | $143.67 |
| 327 | Conservation Cover | Monarch Species Mix | Ac | $673.30 |
| 327 | Conservation Cover | HU-Monarch Species Mix | Ac | $807.96 |
| 327 | Conservation Cover | Wp_Monarch Species Mix | Ac | $807.96 |
| 327 | Conservation Cover | Native Species | Ac | $152.81 |
| 327 | Conservation Cover | HU-Native Species | Ac | $183.38 |
| 327 | Conservation Cover | Wp_Native Species | Ac | $183.38 |
| 327 | Conservation Cover | Orchard or Vineyard Alleyways | Ac | $82.41 |
| 327 | Conservation Cover | HU-Orchard or Vineyard Alleyways | Ac | $98.90 |
| 327 | Conservation Cover | Wp_Orchard or Vineyard Alleyways | Ac | $98.90 |
| 327 | Conservation Cover | Pollinator Species | Ac | $535.66 |
| 327 | Conservation Cover | HU-Pollinator Species | Ac | $642.80 |
| 327 | Conservation Cover | Wp_Pollinator Species | Ac | $642.80 |
| 327 | Conservation Cover | Pollinator Species with Forgone Income | Ac | $413.40 |
| 327 | Conservation Cover | HU-Pollinator Species with Forgone Income | Ac | $467.97 |
| 327 | Conservation Cover | Wp_Pollinator Species with Forgone Income | Ac | $467.97 |
| 328 | Conservation Crop Rotation | Basic Rotation Organic and Non-Organic | Ac | $9.87 |
| 328 | Conservation Crop Rotation | HU-Basic Rotation Organic and Non-Organic | Ac | $11.84 |
| 328 | Conservation Crop Rotation | Wp_Basic Rotation Organic and Non-Organic | Ac | $11.84 |
| 328 | Conservation Crop Rotation | Specialty Crops Organic and Non-Organic | Ac | $26.31 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 328 | Conservation Crop Rotation | HU-Specialty Crops Organic and Non-Organic | Ac | $31.57 |
| 328 | Conservation Crop Rotation | Wp_Specialty Crops Organic and Non-Organic | Ac | $31.57 |
| 329 | Residue and Tillage Management, No Till | No-Till/Strip-Till | Ac | $15.94 |
| 329 | Residue and Tillage Management, No Till | HU-No-Till/Strip-Till | Ac | $19.13 |
| 329 | Residue and Tillage Management, No Till | Wp_No-Till/Strip-Till | Ac | $19.13 |
| 338 | Prescribed Burning | Level Terrain, Herbaceous and/or Low-Volatile Woody Fuel, less than or equal to 640 acres | Ac | $6.85 |
| 338 | Prescribed Burning | HU-Level Terrain, Herbaceous and/or Low-Volatile Woody Fuel, less than or equal to 640 acres | Ac | $10.28 |
| 338 | Prescribed Burning | Level Terrain, High-Volatile Woody Fuel, less than 4-foot tall, less than or equal to 640 acres | Ac | $9.56 |
| 338 | Prescribed Burning | HU-Level Terrain, High-Volatile Woody Fuel, less than 4-foot tall, less than or equal to 640 acres | Ac | $14.34 |
| 338 | Prescribed Burning | Pile Burning, Rangeland | Ac | $4.88 |
| 338 | Prescribed Burning | HU-Pile Burning, Rangeland | Ac | $7.33 |
| 338 | Prescribed Burning | Site Preparation | Ac | $18.82 |
| 338 | Prescribed Burning | HU-Site Preparation | Ac | $28.23 |
| 338 | Prescribed Burning | Understory Burn | Ac | $66.98 |
| 338 | Prescribed Burning | HU-Understory Burn | Ac | $100.47 |
| 340 | Cover Crop | Cover Crop - Adaptive Management | No | $1,887.56 |
| 340 | Cover Crop | HU-Cover Crop - Adaptive Management | No | $2,265.08 |
| 340 | Cover Crop | Wp_Cover Crop - Adaptive Management | No | $2,265.08 |
| 340 | Cover Crop | Cover Crop - Basic (Organic and Non-organic) | Ac | $51.54 |
| 340 | Cover Crop | HU-Cover Crop - Basic (Organic and Non-organic) | Ac | $61.85 |
| 340 | Cover Crop | Wp_Cover Crop - Basic (Organic and Non-organic) | Ac | $61.85 |
| 340 | Cover Crop | Cover Crop - Multiple Species (Organic and Non-organic) | Ac | $63.07 |
| 340 | Cover Crop | HU-Cover Crop - Multiple Species (Organic and Non-organic) | Ac | $75.69 |
| 340 | Cover Crop | Wp_Cover Crop - Multiple Species (Organic and Non-organic) | Ac | $75.69 |
| 342 | Critical Area Planting | Introduced Species, Minimal Site Preparation | Ac | $51.65 |
| 342 | Critical Area Planting | HU-Introduced Species, Minimal Site Preparation | Ac | $61.97 |
| 342 | Critical Area Planting | Wp_Introduced Species, Minimal Site Preparation | Ac | $61.97 |
| 342 | Critical Area Planting | Native or Introduced Vegetation - Moderate Grading (Organic and Non-Organic) | Ac | $455.74 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 342 | Critical Area Planting | HU-Native or Introduced Vegetation - Moderate Grading (Organic and Non-Organic) | Ac | $546.89 |
| 342 | Critical Area Planting | Wp_Native or Introduced Vegetation - Moderate Grading (Organic and Non-Organic) | Ac | $546.89 |
| 342 | Critical Area Planting | Native or Introduced Vegetation - Normal Tillage (Organic and Non-Organic) | Ac | $210.62 |
| 342 | Critical Area Planting | HU-Native or Introduced Vegetation - Normal Tillage (Organic and Non-Organic) | Ac | $252.75 |
| 342 | Critical Area Planting | Wp_Native or Introduced Vegetation - Normal Tillage (Organic and Non-Organic) | Ac | $252.75 |
| 342 | Critical Area Planting | Native or Introduced Vegetation including shrub planting - Normal Tillage | Ac | $777.01 |
| 342 | Critical Area Planting | HU-Native or Introduced Vegetation including shrub planting - Normal Tillage | Ac | $932.41 |
| 342 | Critical Area Planting | Wp_Native or Introduced Vegetation including shrub planting - Normal Tillage | Ac | $932.41 |
| 342 | Critical Area Planting | Native Species, Minimal Site Preparation | Ac | $128.11 |
| 342 | Critical Area Planting | HU-Native Species, Minimal Site Preparation | Ac | $153.73 |
| 342 | Critical Area Planting | Wp_Native Species, Minimal Site Preparation | Ac | $153.73 |
| 345 | Residue and Tillage Management, Reduced Till | Residue and Tillage Management, Reduced Till | Ac | $14.16 |
| 345 | Residue and Tillage Management, Reduced Till | HU-Residue and Tillage Management, Reduced Till | Ac | $17.00 |
| 345 | Residue and Tillage Management, Reduced Till | Wp_Residue and Tillage Management, Reduced Till | Ac | $17.00 |
| 348 | Dam, Diversion | Concrete Structure | CuYd | $1,397.49 |
| 348 | Dam, Diversion | HU-Concrete Structure | CuYd | $2,096.24 |
| 348 | Dam, Diversion | Earth Fill | CuYd | $3.92 |
| 348 | Dam, Diversion | HU-Earth Fill | CuYd | $5.88 |
| 348 | Dam, Diversion | Rock Structure | CuYd | $83.68 |
| 348 | Dam, Diversion | HU-Rock Structure | CuYd | $125.52 |
| 348 | Dam, Diversion | Wood Structure | Ft | $406.08 |
| 348 | Dam, Diversion | HU-Wood Structure | Ft | $609.12 |
| 348 | Dam, Diversion | Wood Structure, with Apron, Sidewalls, and Toewall | SqFt | $217.49 |
| 348 | Dam, Diversion | HU-Wood Structure, with Apron, Sidewalls, and Toewall | SqFt | $326.24 |
| 351 | Well Decommissioning | Drilled Well, 300-foot depth or less | Ft | $3.85 |
| 351 | Well Decommissioning | HU-Drilled Well, 300-foot depth or less | Ft | $4.62 |
| 351 | Well Decommissioning | Wp_Drilled Well, 300-foot depth or less | Ft | $4.62 |
| 351 | Well Decommissioning | Drilled Well, greater than 300-foot depth | Ft | $6.04 |
| 351 | Well Decommissioning | HU-Drilled Well, greater than 300-foot depth | Ft | $7.25 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 351 | Well Decommissioning | Wp_Drilled Well, greater than 300-foot depth | Ft | $7.25 |
| 351 | Well Decommissioning | Drilled Well, Type IV, greater than or equal to 200-foot Depth | Ft | $18.49 |
| 351 | Well Decommissioning | HU-Drilled Well, Type IV, greater than or equal to 200-foot Depth | Ft | $22.19 |
| 351 | Well Decommissioning | Wp_Drilled Well, Type IV, greater than or equal to 200-foot Depth | Ft | $22.19 |
| 351 | Well Decommissioning | Drilled Well, Type V, greater than or equal to 200-foot Depth | Ft | $20.99 |
| 351 | Well Decommissioning | HU-Drilled Well, Type V, greater than or equal to 200-foot Depth | Ft | $25.19 |
| 351 | Well Decommissioning | Wp_Drilled Well, Type V, greater than or equal to 200-foot Depth | Ft | $25.19 |
| 351 | Well Decommissioning | Shallow Well, 25-foot depth or less | Ft | $53.76 |
| 351 | Well Decommissioning | HU-Shallow Well, 25-foot depth or less | Ft | $64.52 |
| 351 | Well Decommissioning | Wp_Shallow Well, 25-foot depth or less | Ft | $64.52 |
| 355 | Groundwater Testing | Basic Water Quality Test | No | $201.28 |
| 355 | Groundwater Testing | HU-Basic Water Quality Test | No | $241.53 |
| 356 | Dike | Material Haul, greater than 1 Mile | CuYd | $3.73 |
| 356 | Dike | HU-Material Haul, greater than 1 Mile | CuYd | $5.59 |
| 356 | Dike | Material Haul, less than or equal to 1 Mile | CuYd | $3.44 |
| 356 | Dike | HU-Material Haul, less than or equal to 1 Mile | CuYd | $5.16 |
| 360 | Waste Facility Closure | Demolition of Concrete Waste Storage Structure | Cu-Ft | $1.94 |
| 360 | Waste Facility Closure | HU-Demolition of Concrete Waste Storage Structure | Cu-Ft | $2.33 |
| 360 | Waste Facility Closure | Wp_Demolition of Concrete Waste Storage Structure | Cu-Ft | $2.33 |
| 360 | Waste Facility Closure | Feedlot Closure, Soil Remediation | Cu-Ft | $0.23 |
| 360 | Waste Facility Closure | HU-Feedlot Closure, Soil Remediation | Cu-Ft | $0.28 |
| 360 | Waste Facility Closure | Wp_Feedlot Closure, Soil Remediation | Cu-Ft | $0.28 |
| 360 | Waste Facility Closure | Liquid Waste Impoundment Closure with 75% Liquids and 25% Solids | Cu-Ft | $0.16 |
| 360 | Waste Facility Closure | HU-Liquid Waste Impoundment Closure with 75% Liquids and 25% Solids | Cu-Ft | $0.20 |
| 360 | Waste Facility Closure | Wp_Liquid Waste Impoundment Closure with 75% Liquids and 25% Solids | Cu-Ft | $0.20 |
| 360 | Waste Facility Closure | Liquid Waste Impoundment Conversion to Fresh Water Storage with 75% Liquids and 25% Solids | Cu-Ft | $0.12 |
| 360 | Waste Facility Closure | HU-Liquid Waste Impoundment Conversion to Fresh Water Storage with 75% Liquids and 25% Solids | Cu-Ft | $0.14 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 360 | Waste Facility Closure | Wp_Liquid Waste Impoundment Conversion to Fresh Water Storage with 75% Liquids and 25% Solids | Cu-Ft | $0.14 |
| 362 | Diversion | Diversion, Concrete Tee Wall | Ft | $71.96 |
| 362 | Diversion | HU-Diversion, Concrete Tee Wall | Ft | $86.35 |
| 362 | Diversion | Diversion, Earth Berm (cubic yard) | CuYd | $5.19 |
| 362 | Diversion | HU-Diversion, Earth Berm (cubic yard) | CuYd | $6.23 |
| 362 | Diversion | Diversion, Earth Berm (Lin. Ft.), less than 15 cubic yard per 100 feet | Ft | $1.73 |
| 362 | Diversion | HU-Diversion, Earth Berm (Lin. Ft.), less than 15 cubic yard per 100 feet | Ft | $2.08 |
| 362 | Diversion | Diversion, Excavation | CuYd | $2.72 |
| 362 | Diversion | HU-Diversion, Excavation | CuYd | $3.26 |
| 367 | Roofs and Covers | Flexible Membrane Cover | SqFt | $2.85 |
| 367 | Roofs and Covers | HU-Flexible Membrane Cover | SqFt | $3.42 |
| 367 | Roofs and Covers | Flexible Roof | SqFt | $12.69 |
| 367 | Roofs and Covers | HU-Flexible Roof | SqFt | $15.23 |
| 367 | Roofs and Covers | Timber or Steel Sheet Roof | SqFt | $11.96 |
| 367 | Roofs and Covers | HU-Timber or Steel Sheet Roof | SqFt | $14.36 |
| 367 | Roofs and Covers | Wood Framed Building for Manure Equipment, sub-zero conditions | SqFt | $61.15 |
| 367 | Roofs and Covers | HU-Wood Framed Building for Manure Equipment, sub-zero conditions | SqFt | $73.38 |
| 368 | Emergency Animal Mortality Management | Burial | AU | $72.11 |
| 368 | Emergency Animal Mortality Management | HU-Burial | AU | $86.53 |
| 368 | Emergency Animal Mortality Management | Forced Air Incineration | AU | $206.30 |
| 368 | Emergency Animal Mortality Management | HU-Forced Air Incineration | AU | $247.56 |
| 368 | Emergency Animal Mortality Management | Outside Windrow Composting | AU | $550.80 |
| 368 | Emergency Animal Mortality Management | HU-Outside Windrow Composting | AU | $660.96 |
| 374 | Farmstead Energy Improvement | Automatic Controller System | No | $976.31 |
| 374 | Farmstead Energy Improvement | HU-Automatic Controller System | No | $1,464.46 |
| 374 | Farmstead Energy Improvement | Heating, Building (1,000BTU/Hour) | kBTU/Hr | $8.58 |
| 374 | Farmstead Energy Improvement | HU-Heating, Building (1,000BTU/Hour) | kBTU/Hr | $12.87 |
| 374 | Farmstead Energy Improvement | Heating, Radiant Tube System | No | $767.72 |
| 374 | Farmstead Energy Improvement | HU-Heating, Radiant Tube System | No | $1,151.58 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 374 | Farmstead Energy Improvement | Motor Upgrade, 10 to 100 Horsepower (HP) | HP | $41.85 |
| 374 | Farmstead Energy Improvement | HU-Motor Upgrade, 10 to 100 Horsepower (HP) | HP | $62.77 |
| 374 | Farmstead Energy Improvement | Motor Upgrade, greater than 1 to less than 10 Horsepower (HP) | HP | $374.34 |
| 374 | Farmstead Energy Improvement | HU-Motor Upgrade, greater than 1 to less than 10 Horsepower (HP) | HP | $561.51 |
| 374 | Farmstead Energy Improvement | Motor Upgrade, greater than 100 Horsepower (HP) | HP | $51.84 |
| 374 | Farmstead Energy Improvement | HU-Motor Upgrade, greater than 100 Horsepower (HP) | HP | $77.76 |
| 374 | Farmstead Energy Improvement | Motor Upgrade, less than or equal to 1 Horsepower (HP) | HP | $295.18 |
| 374 | Farmstead Energy Improvement | HU-Motor Upgrade, less than or equal to 1 Horsepower (HP) | HP | $442.77 |
| 374 | Farmstead Energy Improvement | Plate Cooler | No | $12,359.38 |
| 374 | Farmstead Energy Improvement | HU-Plate Cooler | No | $18,539.07 |
| 374 | Farmstead Energy Improvement | Scroll Compressor | HP | $289.42 |
| 374 | Farmstead Energy Improvement | HU-Scroll Compressor | HP | $434.13 |
| 374 | Farmstead Energy Improvement | Variable Speed Drive, greater than 5 Horsepower (HP) | HP | $54.76 |
| 374 | Farmstead Energy Improvement | HU-Variable Speed Drive, greater than 5 Horsepower (HP) | HP | $82.14 |
| 378 | Pond | Embankment Pond with CMP Riser, HDPE Barrel and PVC Sheet Pile | CuYd | $3.26 |
| 378 | Pond | HU-Embankment Pond with CMP Riser, HDPE Barrel and PVC Sheet Pile | CuYd | $4.89 |
| 378 | Pond | Excavated Pit | CuYd | $1.80 |
| 378 | Pond | HU-Excavated Pit | CuYd | $2.70 |
| 380 | Windbreak/Shelterbelt Establishment | Per Plant, Three Rows or More, Trees, Machine Planted | No | $1.77 |
| 380 | Windbreak/Shelterbelt Establishment | HU-Per Plant, Three Rows or More, Trees, Machine Planted | No | $2.13 |
| 382 | Fence | Barbed/Smooth Wire | Ft | $2.00 |
| 382 | Fence | HU-Barbed/Smooth Wire | Ft | $2.40 |
| 382 | Fence | Wp_Barbed/Smooth Wire | Ft | $2.40 |
| 382 | Fence | Chain Link Safety Fence | Ft | $9.93 |
| 382 | Fence | HU-Chain Link Safety Fence | Ft | $11.92 |
| 382 | Fence | Wp_Chain Link Safety Fence | Ft | $11.92 |
| 382 | Fence | Electric | Ft | $1.39 |
| 382 | Fence | HU-Electric | Ft | $1.67 |
| 382 | Fence | Wp_Electric | Ft | $1.67 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 382 | Fence | Protection, Sensitive Areas / Threatened, Endangered, and/or Sensitive Species | Ft | $3.92 |
| 382 | Fence | HU-Protection, Sensitive Areas / Threatened, Endangered, and/or Sensitive Species | Ft | $4.70 |
| 382 | Fence | Wp_Protection, Sensitive Areas / Threatened, Endangered, and/or Sensitive Species | Ft | $4.70 |
| 382 | Fence | Wire Difficult | Ft | $3.03 |
| 382 | Fence | HU-Wire Difficult | Ft | $3.64 |
| 382 | Fence | Wp_Wire Difficult | Ft | $3.64 |
| 382 | Fence | Woven Wire | Ft | $2.40 |
| 382 | Fence | HU-Woven Wire | Ft | $2.89 |
| 382 | Fence | Wp_Woven Wire | Ft | $2.89 |
| 382 | Fence | Woven Wire/No Climb Safety Fence | Ft | $5.04 |
| 382 | Fence | HU-Woven Wire/No Climb Safety Fence | Ft | $6.05 |
| 382 | Fence | Wp_Woven Wire/No Climb Safety Fence | Ft | $6.05 |
| 383 | Fuel Break | Forested | Ac | $783.81 |
| 383 | Fuel Break | HU-Forested | Ac | $940.57 |
| 383 | Fuel Break | National Forestry Initiative | Ac | $1,560.12 |
| 383 | Fuel Break | HU-National Forestry Initiative | Ac | $1,872.14 |
| 383 | Fuel Break | Structure | Ac | $1,139.59 |
| 383 | Fuel Break | HU-Structure | Ac | $1,367.51 |
| 384 | Woody Residue Treatment | Chipping | Ac | $402.51 |
| 384 | Woody Residue Treatment | HU-Chipping | Ac | $483.02 |
| 384 | Woody Residue Treatment | Consolidated Slash, Pile, Hand, no burning | Ac | $114.11 |
| 384 | Woody Residue Treatment | HU-Consolidated Slash, Pile, Hand, no burning | Ac | $136.93 |
| 384 | Woody Residue Treatment | Consolidated Slash, Pile, Mechanical, no burning | Ac | $82.65 |
| 384 | Woody Residue Treatment | HU-Consolidated Slash, Pile, Mechanical, no burning | Ac | $99.18 |
| 384 | Woody Residue Treatment | Pile and Burn | Ac | $352.58 |
| 384 | Woody Residue Treatment | HU-Pile and Burn | Ac | $423.09 |
| 384 | Woody Residue Treatment | Restoration / Conservation Treatment following Catastrophic Events | Ac | $590.16 |
| 384 | Woody Residue Treatment | HU-Restoration / Conservation Treatment following Catastrophic Events | Ac | $708.20 |
| 386 | Field Border | Field Border, Introduced Species | Ac | $65.49 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 386 | Field Border | HU-Field Border, Introduced Species | Ac | $78.59 |
| 386 | Field Border | Wp_Field Border, Introduced Species | Ac | $78.59 |
| 386 | Field Border | Field Border, Native Species | Ac | $122.74 |
| 386 | Field Border | HU-Field Border, Native Species | Ac | $147.29 |
| 386 | Field Border | Wp_Field Border, Native Species | Ac | $147.29 |
| 386 | Field Border | Field Border, Native Species, Forgone Income | Ac | $367.14 |
| 386 | Field Border | HU-Field Border, Native Species, Forgone Income | Ac | $391.69 |
| 386 | Field Border | Wp_Field Border, Native Species, Forgone Income | Ac | $391.69 |
| 386 | Field Border | Field Border, Pollinator | Ac | $383.33 |
| 386 | Field Border | HU-Field Border, Pollinator | Ac | $459.99 |
| 386 | Field Border | Wp_Field Border, Pollinator | Ac | $459.99 |
| 386 | Field Border | Field Border, Pollinator, Forgone Income | Ac | $627.73 |
| 386 | Field Border | HU-Field Border, Pollinator, Forgone Income | Ac | $704.39 |
| 386 | Field Border | Wp_Field Border, Pollinator, Forgone Income | Ac | $704.39 |
| 388 | Irrigation Field Ditch | Irrigation Field Ditch, 10 to 20 cubic feet per second | Ft | $2.18 |
| 388 | Irrigation Field Ditch | HU-Irrigation Field Ditch, 10 to 20 cubic feet per second | Ft | $3.27 |
| 388 | Irrigation Field Ditch | Irrigation Field Ditch, 2.5 to 10 cubic feet per second | Ft | $1.33 |
| 388 | Irrigation Field Ditch | HU-Irrigation Field Ditch, 2.5 to 10 cubic feet per second | Ft | $2.00 |
| 388 | Irrigation Field Ditch | Irrigation Field Ditch, less than 2.5 cubic feet per second | Ft | $0.81 |
| 388 | Irrigation Field Ditch | HU-Irrigation Field Ditch, less than 2.5 cubic feet per second | Ft | $1.22 |
| 390 | Riparian Herbaceous Cover | Aquatic Wildlife | Ac | $1,972.21 |
| 390 | Riparian Herbaceous Cover | HU-Aquatic Wildlife | Ac | $2,958.31 |
| 390 | Riparian Herbaceous Cover | Wp_Aquatic Wildlife | Ac | $2,761.09 |
| 390 | Riparian Herbaceous Cover | Cool Season Grasses with Forbs | Ac | $472.43 |
| 390 | Riparian Herbaceous Cover | HU-Cool Season Grasses with Forbs | Ac | $708.64 |
| 390 | Riparian Herbaceous Cover | Wp_Cool Season Grasses with Forbs | Ac | $661.40 |
| 390 | Riparian Herbaceous Cover | Native Species, Pollinator Planting | Ac | $112.46 |
| 390 | Riparian Herbaceous Cover | HU-Native Species, Pollinator Planting | Ac | $168.69 |
| 390 | Riparian Herbaceous Cover | Wp_Native Species, Pollinator Planting | Ac | $157.44 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 390 | Riparian Herbaceous Cover | Native Species, Pollinator Planting, Forgone Income | Ac | $136.77 |
| 390 | Riparian Herbaceous Cover | HU-Native Species, Pollinator Planting, Forgone Income | Ac | $192.99 |
| 390 | Riparian Herbaceous Cover | Wp_Native Species, Pollinator Planting, Forgone Income | Ac | $181.75 |
| 391 | Riparian Forest Buffer | Per Plant, Trees and/or Shrub, Hand Planted with Protection Tubes | No | $7.86 |
| 391 | Riparian Forest Buffer | HU-Per Plant, Trees and/or Shrub, Hand Planted with Protection Tubes | No | $11.79 |
| 391 | Riparian Forest Buffer | Per Plant, Trees and/or Shrub, Machine Planted with Protection Tubes | No | $6.32 |
| 391 | Riparian Forest Buffer | HU-Per Plant, Trees and/or Shrub, Machine Planted with Protection Tubes | No | $9.48 |
| 393 | Filter Strip | Filter Strip, Introduced species | Ac | $128.97 |
| 393 | Filter Strip | HU-Filter Strip, Introduced species | Ac | $154.76 |
| 393 | Filter Strip | Wp_Filter Strip, Introduced species | Ac | $154.76 |
| 393 | Filter Strip | Filter Strip, Introduced species, Forgone Income | Ac | $373.37 |
| 393 | Filter Strip | HU-Filter Strip, Introduced species, Forgone Income | Ac | $399.16 |
| 393 | Filter Strip | Wp_Filter Strip, Introduced species, Forgone Income | Ac | $399.16 |
| 393 | Filter Strip | Filter Strip, Native species | Ac | $181.83 |
| 393 | Filter Strip | HU-Filter Strip, Native species | Ac | $218.20 |
| 393 | Filter Strip | Wp_Filter Strip, Native species | Ac | $218.20 |
| 393 | Filter Strip | Filter Strip, Native species, Forgone Income | Ac | $426.24 |
| 393 | Filter Strip | HU-Filter Strip, Native species, Forgone Income | Ac | $462.60 |
| 393 | Filter Strip | Wp_Filter Strip, Native species, Forgone Income | Ac | $462.60 |
| 394 | Firebreak | Constructed - Light Equipment | 100 Ft | $2.79 |
| 394 | Firebreak | HU-Constructed - Light Equipment | 100 Ft | $3.35 |
| 394 | Firebreak | Constructed, Medium Equipment, Flat to Medium Slopes | Ft | $0.26 |
| 394 | Firebreak | HU-Constructed, Medium Equipment, Flat to Medium Slopes | Ft | $0.31 |
| 394 | Firebreak | Constructed, Medium Equipment, Steep Slopes | Ft | $1.35 |
| 394 | Firebreak | HU-Constructed, Medium Equipment, Steep Slopes | Ft | $1.62 |
| 394 | Firebreak | Vegetated, Permanent | Ft | $0.33 |
| 394 | Firebreak | HU-Vegetated, Permanent | Ft | $0.39 |
| 396 | Aquatic Organism Passage | Blockage Removal | CuYd | $33.00 |
| 396 | Aquatic Organism Passage | HU-Blockage Removal | CuYd | $39.60 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 396 | Aquatic Organism Passage | Bottomless Culvert | CuYd | $458.35 |
| 396 | Aquatic Organism Passage | HU-Bottomless Culvert | CuYd | $550.02 |
| 396 | Aquatic Organism Passage | Earthen Dam Removal | CuYd | $43.89 |
| 396 | Aquatic Organism Passage | HU-Earthen Dam Removal | CuYd | $52.67 |
| 396 | Aquatic Organism Passage | Low Water Crossing | CuYd | $458.66 |
| 396 | Aquatic Organism Passage | HU-Low Water Crossing | CuYd | $550.40 |
| 396 | Aquatic Organism Passage | Nature-Like Fishway | Ac | $63,245.25 |
| 396 | Aquatic Organism Passage | HU-Nature-Like Fishway | Ac | $75,894.30 |
| 410 | Grade Stabilization Structure | Concrete Block | SqFt | $5.85 |
| 410 | Grade Stabilization Structure | HU-Concrete Block | SqFt | $8.77 |
| 410 | Grade Stabilization Structure | Embankment, with a Principal Spillway Pipe greater than 12 inches | CuYd | $4.34 |
| 410 | Grade Stabilization Structure | HU-Embankment, with a Principal Spillway Pipe greater than 12 inches | CuYd | $6.50 |
| 410 | Grade Stabilization Structure | Grade Control, Large | CuYd | $1,505.60 |
| 410 | Grade Stabilization Structure | HU-Grade Control, Large | CuYd | $2,258.41 |
| 412 | Grassed Waterway | Base Waterway | Ac | $1,788.16 |
| 412 | Grassed Waterway | HU-Base Waterway | Ac | $2,682.24 |
| 412 | Grassed Waterway | Wp_Base Waterway | Ac | $2,503.42 |
| 412 | Grassed Waterway | With Checks | Ac | $2,235.06 |
| 412 | Grassed Waterway | HU-With Checks | Ac | $3,352.58 |
| 412 | Grassed Waterway | Wp_With Checks | Ac | $3,129.08 |
| 420 | Wildlife Habitat Planting | High Species Diversity on Cropland with Foregone Income | Ac | $694.77 |
| 420 | Wildlife Habitat Planting | HU-High Species Diversity on Cropland with Foregone Income | Ac | $783.86 |
| 420 | Wildlife Habitat Planting | High Species Diversity on Fallow or Non-Cropland, no Foregone Income | Ac | $398.46 |
| 420 | Wildlife Habitat Planting | HU-High Species Diversity on Fallow or Non-Cropland, no Foregone Income | Ac | $478.15 |
| 420 | Wildlife Habitat Planting | Specialized Habitat Requirements on Non-Cropland, no Foregone Income | Ac | $831.44 |
| 420 | Wildlife Habitat Planting | HU-Specialized Habitat Requirements on Non-Cropland, no Foregone Income | Ac | $997.73 |
| 420 | Wildlife Habitat Planting | Very Small Acreage (<.5 ac) Planting with Seedlings | Ac | $20,383.38 |
| 420 | Wildlife Habitat Planting | HU-Very Small Acreage (<.5 ac) Planting with Seedlings | Ac | $24,460.05 |
| 428 | Irrigation Ditch Lining | Buried Flexible Liner | SqYd | $9.11 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 428 | Irrigation Ditch Lining | HU-Buried Flexible Liner | SqYd | $13.66 |
| 428 | Irrigation Ditch Lining | Wp_Buried Flexible Liner | SqYd | $12.75 |
| 428 | Irrigation Ditch Lining | Concrete Lining | SqYd | $9.44 |
| 428 | Irrigation Ditch Lining | HU-Concrete Lining | SqYd | $14.16 |
| 428 | Irrigation Ditch Lining | Wp_Concrete Lining | SqYd | $13.22 |
| 428 | Irrigation Ditch Lining | Flexible Lining | SqYd | $4.91 |
| 428 | Irrigation Ditch Lining | HU-Flexible Lining | SqYd | $7.37 |
| 428 | Irrigation Ditch Lining | Wp_Flexible Lining | SqYd | $6.88 |
| 428 | Irrigation Ditch Lining | GCL Liner | SqYd | $9.30 |
| 428 | Irrigation Ditch Lining | HU-GCL Liner | SqYd | $13.94 |
| 428 | Irrigation Ditch Lining | Wp_GCL Liner | SqYd | $13.01 |
| 430 | Irrigation Pipeline | Alfalfa Valve, greater than or equal to 10 inch | No | $414.25 |
| 430 | Irrigation Pipeline | HU-Alfalfa Valve, greater than or equal to 10 inch | No | $621.37 |
| 430 | Irrigation Pipeline | Wp_Alfalfa Valve, greater than or equal to 10 inch | No | $579.95 |
| 430 | Irrigation Pipeline | Alfalfa Valve, less than or equal to 8 inch | No | $257.10 |
| 430 | Irrigation Pipeline | HU-Alfalfa Valve, less than or equal to 8 inch | No | $385.66 |
| 430 | Irrigation Pipeline | Wp_Alfalfa Valve, less than or equal to 8 inch | No | $359.95 |
| 430 | Irrigation Pipeline | High Density Polyethylene (HDPE), Corrugated Plastic Pipe | Lb | $1.87 |
| 430 | Irrigation Pipeline | HU-High Density Polyethylene (HDPE), Corrugated Plastic Pipe | Lb | $2.80 |
| 430 | Irrigation Pipeline | Wp_High Density Polyethylene (HDPE), Corrugated Plastic Pipe | Lb | $2.61 |
| 430 | Irrigation Pipeline | High Density Polyethylene (HDPE), Iron Pipe Size (IPS) and Tubing, greater than or equal to 10 inch | Lb | $1.52 |
| 430 | Irrigation Pipeline | HU-High Density Polyethylene (HDPE), Iron Pipe Size (IPS) and Tubing, greater than or equal to 10 inch | Lb | $2.27 |
| 430 | Irrigation Pipeline | Wp_High Density Polyethylene (HDPE), Iron Pipe Size (IPS) and Tubing, greater than or equal to 10 inch | Lb | $2.12 |
| 430 | Irrigation Pipeline | High Density Polyethylene (HDPE), Iron Pipe Size (IPS) and Tubing, less than or equal to 8 inch | Lb | $1.75 |
| 430 | Irrigation Pipeline | HU-High Density Polyethylene (HDPE), Iron Pipe Size (IPS) and Tubing, less than or equal to 8 inch | Lb | $2.62 |
| 430 | Irrigation Pipeline | Wp_High Density Polyethylene (HDPE), Iron Pipe Size (IPS) and Tubing, less than or equal to 8 inch | Lb | $2.45 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 430 | Irrigation Pipeline | Horizontal Boring | Ft | $100.44 |
| 430 | Irrigation Pipeline | HU-Horizontal Boring | Ft | $150.66 |
| 430 | Irrigation Pipeline | Wp_Horizontal Boring | Ft | $140.62 |
| 430 | Irrigation Pipeline | Polyvinyl Chloride (PVC), Pipe, greater than or equal to 10 inch | Lb | $1.16 |
| 430 | Irrigation Pipeline | HU-Polyvinyl Chloride (PVC), Pipe, greater than or equal to 10 inch | Lb | $1.73 |
| 430 | Irrigation Pipeline | Wp_Polyvinyl Chloride (PVC), Pipe, greater than or equal to 10 inch | Lb | $1.62 |
| 430 | Irrigation Pipeline | Polyvinyl Chloride (PVC), Pipe, less than or equal to 8 inch | Lb | $1.45 |
| 430 | Irrigation Pipeline | HU-Polyvinyl Chloride (PVC), Pipe, less than or equal to 8 inch | Lb | $2.17 |
| 430 | Irrigation Pipeline | Wp_Polyvinyl Chloride (PVC), Pipe, less than or equal to 8 inch | Lb | $2.03 |
| 430 | Irrigation Pipeline | Steel, Corrugated Steel Pipe | Lb | $0.75 |
| 430 | Irrigation Pipeline | HU-Steel, Corrugated Steel Pipe | Lb | $1.12 |
| 430 | Irrigation Pipeline | Wp_Steel, Corrugated Steel Pipe | Lb | $1.04 |
| 430 | Irrigation Pipeline | Steel, Iron Pipe Size (IPS), greater than or equal to 10 inch | Lb | $1.17 |
| 430 | Irrigation Pipeline | HU-Steel, Iron Pipe Size (IPS), greater than or equal to 10 inch | Lb | $1.76 |
| 430 | Irrigation Pipeline | Wp_Steel, Iron Pipe Size (IPS), greater than or equal to 10 inch | Lb | $1.64 |
| 430 | Irrigation Pipeline | Steel, Iron Pipe Size (IPS), less than or equal to 8 inch | Lb | $1.27 |
| 430 | Irrigation Pipeline | HU-Steel, Iron Pipe Size (IPS), less than or equal to 8 inch | Lb | $1.90 |
| 430 | Irrigation Pipeline | Wp_Steel, Iron Pipe Size (IPS), less than or equal to 8 inch | Lb | $1.77 |
| 430 | Irrigation Pipeline | Surface Aluminum, Aluminum Irrigation Pipe | Lb | $2.91 |
| 430 | Irrigation Pipeline | HU-Surface Aluminum, Aluminum Irrigation Pipe | Lb | $4.36 |
| 430 | Irrigation Pipeline | Wp_Surface Aluminum, Aluminum Irrigation Pipe | Lb | $4.07 |
| 430 | Irrigation Pipeline | Surface High Density Polyethylene (HDPE), Iron Pipe Size (IPS) and Tubing | Lb | $1.69 |
| 430 | Irrigation Pipeline | HU-Surface High Density Polyethylene (HDPE), Iron Pipe Size (IPS) and Tubing | Lb | $2.54 |
| 430 | Irrigation Pipeline | Wp_Surface High Density Polyethylene (HDPE), Iron Pipe Size (IPS) and Tubing | Lb | $2.37 |
| 430 | Irrigation Pipeline | Surface Steel, Iron Pipe Size (IPS) | Lb | $1.17 |
| 430 | Irrigation Pipeline | HU-Surface Steel, Iron Pipe Size (IPS) | Lb | $1.76 |
| 430 | Irrigation Pipeline | Wp_Surface Steel, Iron Pipe Size (IPS) | Lb | $1.64 |
| 441 | Irrigation System, Microirrigation | Micro Sprinkler | Ac | $1,455.79 |
| 441 | Irrigation System, Microirrigation | HU-Micro Sprinkler | Ac | $2,183.68 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 441 | Irrigation System, Microirrigation | Orchard System | Ac | $2,355.62 |
| 441 | Irrigation System, Microirrigation | HU-Orchard System | Ac | $3,533.43 |
| 441 | Irrigation System, Microirrigation | Shelterbelt Drip | SqFt | $0.02 |
| 441 | Irrigation System, Microirrigation | HU-Shelterbelt Drip | SqFt | $0.04 |
| 441 | Irrigation System, Microirrigation | Subsurface Drip Irrigation (SDI) | Ac | $1,013.99 |
| 441 | Irrigation System, Microirrigation | HU-Subsurface Drip Irrigation (SDI) | Ac | $1,520.98 |
| 441 | Irrigation System, Microirrigation | Surface drip tubing Vineyard | Ac | $1,158.24 |
| 441 | Irrigation System, Microirrigation | HU-Surface drip tubing Vineyard | Ac | $1,737.35 |
| 441 | Irrigation System, Microirrigation | Truck Garden | Ac | $1,590.55 |
| 441 | Irrigation System, Microirrigation | HU-Truck Garden | Ac | $2,385.83 |
| 442 | Sprinkler System | Center Pivot, >/=1,200 feet | Ac | $443.15 |
| 442 | Sprinkler System | HU-Center Pivot, >/=1,200 feet | Ac | $531.78 |
| 442 | Sprinkler System | Wp_Center Pivot, >/=1,200 feet | Ac | $531.78 |
| 442 | Sprinkler System | Center Pivot, 600 to 800 feet | Ac | $868.07 |
| 442 | Sprinkler System | HU-Center Pivot, 600 to 800 feet | Ac | $1,041.69 |
| 442 | Sprinkler System | Wp_Center Pivot, 600 to 800 feet | Ac | $1,041.69 |
| 442 | Sprinkler System | Center Pivot, 801 to 1,200 feet | Ac | $574.78 |
| 442 | Sprinkler System | HU-Center Pivot, 801 to 1,200 feet | Ac | $689.73 |
| 442 | Sprinkler System | Wp_Center Pivot, 801 to 1,200 feet | Ac | $689.73 |
| 442 | Sprinkler System | Center Pivot, less than 600 feet | Ac | $1,164.65 |
| 442 | Sprinkler System | HU-Center Pivot, less than 600 feet | Ac | $1,397.58 |
| 442 | Sprinkler System | Wp_Center Pivot, less than 600 feet | Ac | $1,397.58 |
| 442 | Sprinkler System | Handline | Ft | $2.46 |
| 442 | Sprinkler System | HU-Handline | Ft | $3.69 |
| 442 | Sprinkler System | Wp_Handline | Ft | $3.44 |
| 442 | Sprinkler System | Linear Move System | Ft | $56.14 |
| 442 | Sprinkler System | HU-Linear Move System | Ft | $84.21 |
| 442 | Sprinkler System | Wp_Linear Move System | Ft | $78.59 |
| 442 | Sprinkler System | Pod System | No | $150.56 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 442 | Sprinkler System | HU-Pod System | No | $225.84 |
| 442 | Sprinkler System | Wp_Pod System | No | $210.78 |
| 442 | Sprinkler System | Traveling Gun System, greater than 3-inch Hose | No | $21,313.76 |
| 442 | Sprinkler System | HU-Traveling Gun System, greater than 3-inch Hose | No | $31,970.64 |
| 442 | Sprinkler System | Wp_Traveling Gun System, greater than 3-inch Hose | No | $29,839.26 |
| 442 | Sprinkler System | Wheel Line System | Ft | $9.63 |
| 442 | Sprinkler System | HU-Wheel Line System | Ft | $14.45 |
| 442 | Sprinkler System | Wp_Wheel Line System | Ft | $13.48 |
| 443 | Irrigation System, Surface and Subsurface | Polyvinyl Chloride (PVC) Gated Pipe | Lb | $1.01 |
| 443 | Irrigation System, Surface and Subsurface | HU-Polyvinyl Chloride (PVC) Gated Pipe | Lb | $1.52 |
| 443 | Irrigation System, Surface and Subsurface | Surge Valve with Controller | No | $1,285.65 |
| 443 | Irrigation System, Surface and Subsurface | HU-Surge Valve with Controller | No | $1,928.48 |
| 449 | Irrigation Water Management | Advanced IWM, Year 1 | No | $2,641.10 |
| 449 | Irrigation Water Management | HU-Advanced IWM, Year 1 | No | $3,169.31 |
| 449 | Irrigation Water Management | Wp_Advanced IWM, Year 1 | No | $3,169.31 |
| 449 | Irrigation Water Management | Advanced IWM, Year 1, Contracted | No | $3,078.05 |
| 449 | Irrigation Water Management | HU-Advanced IWM, Year 1, Contracted | No | $3,693.65 |
| 449 | Irrigation Water Management | Wp_Advanced IWM, Year 1, Contracted | No | $3,693.65 |
| 449 | Irrigation Water Management | Advanced IWM, Years 2 and 3 | No | $526.20 |
| 449 | Irrigation Water Management | HU-Advanced IWM, Years 2 and 3 | No | $631.44 |
| 449 | Irrigation Water Management | Wp_Advanced IWM, Years 2 and 3 | No | $631.44 |
| 449 | Irrigation Water Management | Advanced IWM, Years 2 and 3, Contracted | No | $963.15 |
| 449 | Irrigation Water Management | HU-Advanced IWM, Years 2 and 3, Contracted | No | $1,155.78 |
| 449 | Irrigation Water Management | Wp_Advanced IWM, Years 2 and 3, Contracted | No | $1,155.78 |
| 449 | Irrigation Water Management | Basic IWM | No | $328.88 |
| 449 | Irrigation Water Management | HU-Basic IWM | No | $394.65 |
| 449 | Irrigation Water Management | Wp_Basic IWM | No | $394.65 |
| 449 | Irrigation Water Management | Basic IWM, Contracted | No | $547.35 |
| 449 | Irrigation Water Management | HU-Basic IWM, Contracted | No | $656.82 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 449 | Irrigation Water Management | Wp_Basic IWM, Contracted | No | $656.82 |
| 449 | Irrigation Water Management | Basic Orchard or Truck Garden | No | $1,167.33 |
| 449 | Irrigation Water Management | HU-Basic Orchard or Truck Garden | No | $1,400.79 |
| 449 | Irrigation Water Management | Wp_Basic Orchard or Truck Garden | No | $1,400.79 |
| 449 | Irrigation Water Management | Intermediate IWM, Year 1 | No | $983.96 |
| 449 | Irrigation Water Management | HU-Intermediate IWM, Year 1 | No | $1,180.75 |
| 449 | Irrigation Water Management | Wp_Intermediate IWM, Year 1 | No | $1,180.75 |
| 449 | Irrigation Water Management | Intermediate IWM, Year 1, Contracted | No | $1,275.26 |
| 449 | Irrigation Water Management | HU-Intermediate IWM, Year 1, Contracted | No | $1,530.31 |
| 449 | Irrigation Water Management | Wp_Intermediate IWM, Year 1, Contracted | No | $1,530.31 |
| 449 | Irrigation Water Management | Intermediate IWM, Years 2 and 3 | No | $526.20 |
| 449 | Irrigation Water Management | HU-Intermediate IWM, Years 2 and 3 | No | $631.44 |
| 449 | Irrigation Water Management | Wp_Intermediate IWM, Years 2 and 3 | No | $631.44 |
| 449 | Irrigation Water Management | Intermediate IWM, Years 2 and 3, Contracted | No | $817.50 |
| 449 | Irrigation Water Management | HU-Intermediate IWM, Years 2 and 3, Contracted | No | $981.00 |
| 449 | Irrigation Water Management | Wp_Intermediate IWM, Years 2 and 3, Contracted | No | $981.00 |
| 449 | Irrigation Water Management | Orchard/Truck Garden with Weather Station | No | $3,577.81 |
| 449 | Irrigation Water Management | HU-Orchard/Truck Garden with Weather Station | No | $4,293.37 |
| 449 | Irrigation Water Management | Wp_Orchard/Truck Garden with Weather Station | No | $4,293.37 |
| 462 | Precision Land Forming | Minor Shaping | Ac | $2,287.29 |
| 462 | Precision Land Forming | HU-Minor Shaping | Ac | $2,744.75 |
| 462 | Precision Land Forming | Wp_Minor Shaping | Ac | $2,744.75 |
| 462 | Precision Land Forming | Shaping Existing Lot Acre | Ac | $3,493.41 |
| 462 | Precision Land Forming | HU-Shaping Existing Lot Acre | Ac | $4,192.09 |
| 462 | Precision Land Forming | Wp_Shaping Existing Lot Acre | Ac | $4,192.09 |
| 462 | Precision Land Forming | Shaping Relocation New Feedlot | Ac | $3,353.77 |
| 462 | Precision Land Forming | HU-Shaping Relocation New Feedlot | Ac | $4,024.53 |
| 462 | Precision Land Forming | Wp_Shaping Relocation New Feedlot | Ac | $4,024.53 |
| 464 | Irrigation Land Leveling | Irrigation Land Leveling (cubic Yard) | CuYd | $1.10 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 464 | Irrigation Land Leveling | HU-Irrigation Land Leveling (cubic Yard) | CuYd | $1.65 |
| 472 | Access Control | Monitoring | Ac | $21.68 |
| 472 | Access Control | HU-Monitoring | Ac | $26.02 |
| 472 | Access Control | Wp_Monitoring | Ac | $26.02 |
| 472 | Access Control | Trail and Road Closure: Heavy Duty Gate | No | $2,056.22 |
| 472 | Access Control | HU-Trail and Road Closure: Heavy Duty Gate | No | $2,467.46 |
| 472 | Access Control | Wp_Trail and Road Closure: Heavy Duty Gate | No | $2,467.46 |
| 484 | Mulching | Erosion Control Blanket, Extended Term | SqFt | $0.68 |
| 484 | Mulching | HU-Erosion Control Blanket, Extended Term | SqFt | $0.82 |
| 484 | Mulching | Erosion Control Blanket, Short Term | SqFt | $0.11 |
| 484 | Mulching | HU-Erosion Control Blanket, Short Term | SqFt | $0.14 |
| 484 | Mulching | Natural Material, Full Coverage | Ac | $167.48 |
| 484 | Mulching | HU-Natural Material, Full Coverage | Ac | $200.98 |
| 484 | Mulching | Orchards | Ac | $2,020.08 |
| 484 | Mulching | HU-Orchards | Ac | $2,424.10 |
| 484 | Mulching | Tree and Shrub | SqFt | $0.11 |
| 484 | Mulching | HU-Tree and Shrub | SqFt | $0.13 |
| 490 | Tree/Shrub Site Preparation | Chemical, Hand Application | Ac | $86.15 |
| 490 | Tree/Shrub Site Preparation | HU-Chemical, Hand Application | Ac | $103.38 |
| 490 | Tree/Shrub Site Preparation | Mechanical, Light | Ac | $96.66 |
| 490 | Tree/Shrub Site Preparation | HU-Mechanical, Light | Ac | $115.99 |
| 500 | Obstruction Removal | Feedlot Fence Removal | Ft | $5.24 |
| 500 | Obstruction Removal | HU-Feedlot Fence Removal | Ft | $6.29 |
| 500 | Obstruction Removal | Wp_Feedlot Fence Removal | Ft | $6.29 |
| 500 | Obstruction Removal | Loose Rock & Debris Removal | CuYd | $8.08 |
| 500 | Obstruction Removal | HU-Loose Rock & Debris Removal | CuYd | $9.70 |
| 500 | Obstruction Removal | Wp_Loose Rock & Debris Removal | CuYd | $9.70 |
| 500 | Obstruction Removal | Removal and Disposal of Fence | Ft | $0.79 |
| 500 | Obstruction Removal | HU-Removal and Disposal of Fence | Ft | $0.95 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 500 | Obstruction Removal | Wp_Removal and Disposal of Fence | Ft | $0.95 |
| 500 | Obstruction Removal | Removal and Disposal of Steel and/or Concrete Structures | SqFt | $11.32 |
| 500 | Obstruction Removal | HU-Removal and Disposal of Steel and/or Concrete Structures | SqFt | $13.58 |
| 500 | Obstruction Removal | Wp_Removal and Disposal of Steel and/or Concrete Structures | SqFt | $13.58 |
| 500 | Obstruction Removal | Removal and Disposal of Wood Structures | SqFt | $5.89 |
| 500 | Obstruction Removal | HU-Removal and Disposal of Wood Structures | SqFt | $7.06 |
| 500 | Obstruction Removal | Wp_Removal and Disposal of Wood Structures | SqFt | $7.06 |
| 500 | Obstruction Removal | Shed and Barn Removal | SqFt | $2.35 |
| 500 | Obstruction Removal | HU-Shed and Barn Removal | SqFt | $2.82 |
| 500 | Obstruction Removal | Wp_Shed and Barn Removal | SqFt | $2.82 |
| 511 | Forage Harvest Management | Improved Forage Quality | Ac | $1.44 |
| 511 | Forage Harvest Management | HU-Improved Forage Quality | Ac | $1.73 |
| 511 | Forage Harvest Management | Perennial Crops, Delayed Mowing | Ac | $24.82 |
| 511 | Forage Harvest Management | HU-Perennial Crops, Delayed Mowing | Ac | $25.11 |
| 512 | Pasture and Hay Planting | Pollinator Friendly, NO Foregone Income | Ac | $119.06 |
| 512 | Pasture and Hay Planting | HU-Pollinator Friendly, NO Foregone Income | Ac | $142.87 |
| 512 | Pasture and Hay Planting | Pollinator Friendly, with Foregone Income included | Ac | $268.49 |
| 512 | Pasture and Hay Planting | HU-Pollinator Friendly, with Foregone Income included | Ac | $299.82 |
| 512 | Pasture and Hay Planting | Seedbed Preparation, Seed and Seeding, Introduced Perennial Grasses with Legume | Ac | $61.78 |
| 512 | Pasture and Hay Planting | HU-Seedbed Preparation, Seed and Seeding, Introduced Perennial Grasses with Legume | Ac | $74.14 |
| 516 | Livestock Pipeline | Adverse Conditions | Ft | $3.72 |
| 516 | Livestock Pipeline | HU-Adverse Conditions | Ft | $5.27 |
| 516 | Livestock Pipeline | Wp_Adverse Conditions | Ft | $4.65 |
| 516 | Livestock Pipeline | Below Frost PVC, HDPE, IPS, PE | Ft | $1.35 |
| 516 | Livestock Pipeline | HU-Below Frost PVC, HDPE, IPS, PE | Ft | $1.92 |
| 516 | Livestock Pipeline | Wp_Below Frost PVC, HDPE, IPS, PE | Ft | $1.69 |
| 516 | Livestock Pipeline | Buried PVC, IPS, HDPE, PE | Ft | $1.33 |
| 516 | Livestock Pipeline | HU-Buried PVC, IPS, HDPE, PE | Ft | $1.89 |
| 516 | Livestock Pipeline | Wp_Buried PVC, IPS, HDPE, PE | Ft | $1.67 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 516 | Livestock Pipeline | Horizontal Boring | Ft | $43.61 |
| 516 | Livestock Pipeline | HU-Horizontal Boring | Ft | $61.79 |
| 516 | Livestock Pipeline | Wp_Horizontal Boring | Ft | $54.52 |
| 516 | Livestock Pipeline | Steel, Iron Pipe Size (IPS) | Ft | $4.12 |
| 516 | Livestock Pipeline | HU-Steel, Iron Pipe Size (IPS) | Ft | $5.84 |
| 516 | Livestock Pipeline | Wp_Steel, Iron Pipe Size (IPS) | Ft | $5.15 |
| 516 | Livestock Pipeline | Surface High Density Polyethylene (HDPE), Iron Pipe Size (IPS) and Tubing | Ft | $0.83 |
| 516 | Livestock Pipeline | HU-Surface High Density Polyethylene (HDPE), Iron Pipe Size (IPS) and Tubing | Ft | $1.17 |
| 516 | Livestock Pipeline | Wp_Surface High Density Polyethylene (HDPE), Iron Pipe Size (IPS) and Tubing | Ft | $1.03 |
| 516 | Livestock Pipeline | Surface Steel, Iron Pipe Size (IPS) | Ft | $3.29 |
| 516 | Livestock Pipeline | HU-Surface Steel, Iron Pipe Size (IPS) | Ft | $4.66 |
| 516 | Livestock Pipeline | Wp_Surface Steel, Iron Pipe Size (IPS) | Ft | $4.11 |
| 520 | Pond Sealing or Lining, Compacted Soil Treatment | Bentonite Treatment - Covered | CuYd | $29.06 |
| 520 | Pond Sealing or Lining, Compacted Soil Treatment | HU-Bentonite Treatment - Covered | CuYd | $34.87 |
| 520 | Pond Sealing or Lining, Compacted Soil Treatment | Material haul  < 1 mile | CuYd | $10.10 |
| 520 | Pond Sealing or Lining, Compacted Soil Treatment | HU-Material haul  < 1 mile | CuYd | $12.13 |
| 521 | Pond Sealing or Lining, Geomembrane or Geosynthetic Clay Liner | Flexible Membrane, Covered with Liner Drainage and Venting | SqYd | $18.82 |
| 521 | Pond Sealing or Lining, Geomembrane or Geosynthetic Clay Liner | HU-Flexible Membrane, Covered with Liner Drainage and Venting | SqYd | $22.59 |
| 521 | Pond Sealing or Lining, Geomembrane or Geosynthetic Clay Liner | Flexible Membrane, Covered without Liner Drainage or Venting | SqYd | $10.80 |
| 521 | Pond Sealing or Lining, Geomembrane or Geosynthetic Clay Liner | HU-Flexible Membrane, Covered without Liner Drainage or Venting | SqYd | $12.97 |
| 521 | Pond Sealing or Lining, Geomembrane or Geosynthetic Clay Liner | Flexible Membrane, Uncovered without Liner Drainage or Venting | SqYd | $9.85 |
| 521 | Pond Sealing or Lining, Geomembrane or Geosynthetic Clay Liner | HU-Flexible Membrane, Uncovered without Liner Drainage or Venting | SqYd | $11.82 |
| 528 | Prescribed Grazing | Habitat Management, Rest Rotation | Ac | $6.49 |
| 528 | Prescribed Grazing | HU-Habitat Management, Rest Rotation | Ac | $7.54 |
| 528 | Prescribed Grazing | Wp_Habitat Management, Rest Rotation | Ac | $7.54 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 528 | Prescribed Grazing | Habitat Management, Standard | Ac | $3.96 |
| 528 | Prescribed Grazing | HU-Habitat Management, Standard | Ac | $4.76 |
| 528 | Prescribed Grazing | Wp_Habitat Management, Standard | Ac | $4.76 |
| 528 | Prescribed Grazing | Pasture Intensive, Small Acreage | Ac | $46.62 |
| 528 | Prescribed Grazing | HU-Pasture Intensive, Small Acreage | Ac | $55.94 |
| 528 | Prescribed Grazing | Wp_Pasture Intensive, Small Acreage | Ac | $55.94 |
| 528 | Prescribed Grazing | Pasture Moderate | Ac | $19.96 |
| 528 | Prescribed Grazing | HU-Pasture Moderate | Ac | $23.95 |
| 528 | Prescribed Grazing | Wp_Pasture Moderate | Ac | $23.95 |
| 528 | Prescribed Grazing | Pasture, Standard | Ac | $5.64 |
| 528 | Prescribed Grazing | HU-Pasture, Standard | Ac | $6.77 |
| 528 | Prescribed Grazing | Wp_Pasture, Standard | Ac | $6.77 |
| 528 | Prescribed Grazing | Range, Deferment | Ac | $6.64 |
| 528 | Prescribed Grazing | HU-Range, Deferment | Ac | $6.75 |
| 528 | Prescribed Grazing | Wp_Range, Deferment | Ac | $6.75 |
| 528 | Prescribed Grazing | Range, Intensive | Ac | $16.80 |
| 528 | Prescribed Grazing | HU-Range, Intensive | Ac | $20.16 |
| 528 | Prescribed Grazing | Wp_Range, Intensive | Ac | $20.16 |
| 528 | Prescribed Grazing | Range, Standard,  2,500 Acres or greater. | Ac | $1.40 |
| 528 | Prescribed Grazing | HU-Range, Standard,  2,500 Acres or greater. | Ac | $1.68 |
| 528 | Prescribed Grazing | Wp_Range, Standard,  2,500 Acres or greater. | Ac | $1.68 |
| 528 | Prescribed Grazing | Range, Standard, Less than 2,500 acres | Ac | $3.20 |
| 528 | Prescribed Grazing | HU-Range, Standard, Less than 2,500 acres | Ac | $3.85 |
| 528 | Prescribed Grazing | Wp_Range, Standard, Less than 2,500 acres | Ac | $3.85 |
| 533 | Pumping Plant | Electric-Powered Pump, 30 to 74 HP | HP | $161.77 |
| 533 | Pumping Plant | HU-Electric-Powered Pump, 30 to 74 HP | HP | $242.66 |
| 533 | Pumping Plant | Wp_Electric-Powered Pump, 30 to 74 HP | HP | $226.48 |
| 533 | Pumping Plant | Electric-Powered Pump, 75 HP or greater | HP | $123.48 |
| 533 | Pumping Plant | HU-Electric-Powered Pump, 75 HP or greater | HP | $185.22 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 533 | Pumping Plant | Wp_Electric-Powered Pump, 75 HP or greater | HP | $172.87 |
| 533 | Pumping Plant | Electric-Powered Pump, greater than 5 to 30 Horse Power | HP | $252.26 |
| 533 | Pumping Plant | HU-Electric-Powered Pump, greater than 5 to 30 Horse Power | HP | $378.39 |
| 533 | Pumping Plant | Wp_Electric-Powered Pump, greater than 5 to 30 Horse Power | HP | $353.16 |
| 533 | Pumping Plant | Electric-Powered Pump, less than or equal to 5 Horse Power | HP | $1,135.42 |
| 533 | Pumping Plant | HU-Electric-Powered Pump, less than or equal to 5 Horse Power | HP | $1,703.13 |
| 533 | Pumping Plant | Wp_Electric-Powered Pump, less than or equal to 5 Horse Power | HP | $1,589.59 |
| 533 | Pumping Plant | Electric-Powered Pump, less than or equal to 5 Horse Power with Pressure Tank or VFD | HP | $1,772.43 |
| 533 | Pumping Plant | HU-Electric-Powered Pump, less than or equal to 5 Horse Power with Pressure Tank or VFD | HP | $2,658.65 |
| 533 | Pumping Plant | Wp_Electric-Powered Pump, less than or equal to 5 Horse Power with Pressure Tank or VFD | HP | $2,481.41 |
| 533 | Pumping Plant | Internal Combustion-Powered Pump, greater than 7.5 to 75 Horse Power | HP | $328.87 |
| 533 | Pumping Plant | HU-Internal Combustion-Powered Pump, greater than 7.5 to 75 Horse Power | HP | $493.30 |
| 533 | Pumping Plant | Wp_Internal Combustion-Powered Pump, greater than 7.5 to 75 Horse Power | HP | $460.41 |
| 533 | Pumping Plant | Internal Combustion-Powered Pump, greater than 75 Horse Power | HP | $313.88 |
| 533 | Pumping Plant | HU-Internal Combustion-Powered Pump, greater than 75 Horse Power | HP | $470.83 |
| 533 | Pumping Plant | Wp_Internal Combustion-Powered Pump, greater than 75 Horse Power | HP | $439.44 |
| 533 | Pumping Plant | Internal Combustion-Powered Pump, less than or equal to 7.5 Horse Power | HP | $384.89 |
| 533 | Pumping Plant | HU-Internal Combustion-Powered Pump, less than or equal to 7.5 Horse Power | HP | $577.33 |
| 533 | Pumping Plant | Wp_Internal Combustion-Powered Pump, less than or equal to 7.5 Horse Power | HP | $538.84 |
| 533 | Pumping Plant | Lagoon PTO | No | $36.72 |
| 533 | Pumping Plant | HU-Lagoon PTO | No | $55.08 |
| 533 | Pumping Plant | Wp_Lagoon PTO | No | $51.41 |
| 533 | Pumping Plant | Photovoltaic-Powered Pump, 251 to 400 ft total head | No | $2,661.64 |
| 533 | Pumping Plant | HU-Photovoltaic-Powered Pump, 251 to 400 ft total head | No | $3,992.46 |
| 533 | Pumping Plant | Wp_Photovoltaic-Powered Pump, 251 to 400 ft total head | No | $3,726.30 |
| 533 | Pumping Plant | Photovoltaic-Powered Pump, greater than 400 ft total head | No | $3,423.12 |
| 533 | Pumping Plant | HU-Photovoltaic-Powered Pump, greater than 400 ft total head | No | $5,134.68 |
| 533 | Pumping Plant | Wp_Photovoltaic-Powered Pump, greater than 400 ft total head | No | $4,792.37 |
| 533 | Pumping Plant | Photovoltaic-Powered Pump, less than or equal to 250 ft total head | No | $2,116.40 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 533 | Pumping Plant | HU-Photovoltaic-Powered Pump, less than or equal to 250 ft total head | No | $3,174.60 |
| 533 | Pumping Plant | Wp_Photovoltaic-Powered Pump, less than or equal to 250 ft total head | No | $2,962.96 |
| 533 | Pumping Plant | Soft Start 30-75 hp | HP | $36.03 |
| 533 | Pumping Plant | HU-Soft Start 30-75 hp | HP | $54.05 |
| 533 | Pumping Plant | Wp_Soft Start 30-75 hp | HP | $50.45 |
| 533 | Pumping Plant | Soft Start less than or equal to 25 hp | HP | $52.25 |
| 533 | Pumping Plant | HU-Soft Start less than or equal to 25 hp | HP | $78.38 |
| 533 | Pumping Plant | Wp_Soft Start less than or equal to 25 hp | HP | $73.15 |
| 533 | Pumping Plant | Tractor Power Take Off (PTO) Pump | HP | $81.01 |
| 533 | Pumping Plant | HU-Tractor Power Take Off (PTO) Pump | HP | $121.52 |
| 533 | Pumping Plant | Wp_Tractor Power Take Off (PTO) Pump | HP | $113.42 |
| 533 | Pumping Plant | Turbine Pump Bowl Replacement | HP | $94.73 |
| 533 | Pumping Plant | HU-Turbine Pump Bowl Replacement | HP | $142.09 |
| 533 | Pumping Plant | Wp_Turbine Pump Bowl Replacement | HP | $132.62 |
| 533 | Pumping Plant | Variable Frequency Drive, 75HP or greater | HP | $53.42 |
| 533 | Pumping Plant | HU-Variable Frequency Drive, 75HP or greater | HP | $80.13 |
| 533 | Pumping Plant | Wp_Variable Frequency Drive, 75HP or greater | HP | $74.79 |
| 533 | Pumping Plant | Variable Frequency Drive, less than 75 HP | HP | $60.31 |
| 533 | Pumping Plant | HU-Variable Frequency Drive, less than 75 HP | HP | $90.46 |
| 533 | Pumping Plant | Wp_Variable Frequency Drive, less than 75 HP | HP | $84.43 |
| 533 | Pumping Plant | Well Pump Test | Hr | $149.80 |
| 533 | Pumping Plant | HU-Well Pump Test | Hr | $179.75 |
| 533 | Pumping Plant | Wp_Well Pump Test | Hr | $179.75 |
| 533 | Pumping Plant | Windmill-Powered Pump | Ft | $541.50 |
| 533 | Pumping Plant | HU-Windmill-Powered Pump | Ft | $812.26 |
| 533 | Pumping Plant | Wp_Windmill-Powered Pump | Ft | $758.11 |
| 548 | Grazing Land Mechanical Treatment | Range, Mechanical Treatment | Ac | $11.41 |
| 548 | Grazing Land Mechanical Treatment | HU-Range, Mechanical Treatment | Ac | $17.11 |
| 550 | Range Planting | Native, Heavy Preparation | Ac | $88.08 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 550 | Range Planting | HU-Native, Heavy Preparation | Ac | $104.49 |
| 550 | Range Planting | Native, Standard Preparation | Ac | $80.32 |
| 550 | Range Planting | HU-Native, Standard Preparation | Ac | $95.17 |
| 550 | Range Planting | Native, Wildlife or Pollinator | Ac | $222.21 |
| 550 | Range Planting | HU-Native, Wildlife or Pollinator | Ac | $244.28 |
| 558 | Roof Runoff Structure | 4- to 6-Inch Aluminum Roof Gutter | Ft | $8.34 |
| 558 | Roof Runoff Structure | HU-4- to 6-Inch Aluminum Roof Gutter | Ft | $10.00 |
| 558 | Roof Runoff Structure | 7- to 9-Inch Aluminum Roof Gutter | Ft | $13.20 |
| 558 | Roof Runoff Structure | HU-7- to 9-Inch Aluminum Roof Gutter | Ft | $15.84 |
| 558 | Roof Runoff Structure | Concrete Curb | Ft | $18.19 |
| 558 | Roof Runoff Structure | HU-Concrete Curb | Ft | $21.82 |
| 558 | Roof Runoff Structure | Trench Drain | Ft | $8.40 |
| 558 | Roof Runoff Structure | HU-Trench Drain | Ft | $10.08 |
| 560 | Access Road | New 6-inch Gravel Road in Wet, Level Terrain | Ft | $9.91 |
| 560 | Access Road | HU-New 6-inch Gravel Road in Wet, Level Terrain | Ft | $14.86 |
| 560 | Access Road | Wp_New 6-inch Gravel Road in Wet, Level Terrain | Ft | $13.87 |
| 560 | Access Road | New Earth Road in Dry, Level Terrain | Ft | $5.57 |
| 560 | Access Road | HU-New Earth Road in Dry, Level Terrain | Ft | $8.36 |
| 560 | Access Road | Wp_New Earth Road in Dry, Level Terrain | Ft | $7.80 |
| 560 | Access Road | Rehabilitation of Existing 6-inch Gravel Road in Wet, Level Terrain | Ft | $2.22 |
| 560 | Access Road | HU-Rehabilitation of Existing 6-inch Gravel Road in Wet, Level Terrain | Ft | $3.33 |
| 560 | Access Road | Wp_Rehabilitation of Existing 6-inch Gravel Road in Wet, Level Terrain | Ft | $3.11 |
| 561 | Heavy Use Area Protection | Rock and Gravel on Geotextile | SqFt | $1.04 |
| 561 | Heavy Use Area Protection | HU-Rock and Gravel on Geotextile | SqFt | $1.25 |
| 561 | Heavy Use Area Protection | Wp_Rock and Gravel on Geotextile | SqFt | $1.25 |
| 570 | Stormwater Runoff Control | Silt Fence | Ft | $1.83 |
| 570 | Stormwater Runoff Control | HU-Silt Fence | Ft | $2.19 |
| 570 | Stormwater Runoff Control | Straw Bale Dam | Ft | $6.81 |
| 570 | Stormwater Runoff Control | HU-Straw Bale Dam | Ft | $8.17 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 570 | Stormwater Runoff Control | Straw Wattles | Ft | $1.90 |
| 570 | Stormwater Runoff Control | HU-Straw Wattles | Ft | $2.27 |
| 574 | Spring Development | Spring Development | No | $1,706.47 |
| 574 | Spring Development | HU-Spring Development | No | $2,559.71 |
| 575 | Trails and Walkways | Natural Trail or Walkway | SqFt | $0.19 |
| 575 | Trails and Walkways | HU-Natural Trail or Walkway | SqFt | $0.23 |
| 576 | Livestock Shelter Structure | Permanent Fabricated Wind Shelter | Ft | $26.43 |
| 576 | Livestock Shelter Structure | HU-Permanent Fabricated Wind Shelter | Ft | $31.72 |
| 576 | Livestock Shelter Structure | Wp_Permanent Fabricated Wind Shelter | Ft | $31.72 |
| 576 | Livestock Shelter Structure | Portable Fabricated Wind Shelter, equal to or greater than 8 foot | Ft | $33.37 |
| 576 | Livestock Shelter Structure | HU-Portable Fabricated Wind Shelter, equal to or greater than 8 foot | Ft | $40.05 |
| 576 | Livestock Shelter Structure | Wp_Portable Fabricated Wind Shelter, equal to or greater than 8 foot | Ft | $40.05 |
| 576 | Livestock Shelter Structure | Portable Fabricated Wind Shelter, less than 8 foot height. | Ft | $23.90 |
| 576 | Livestock Shelter Structure | HU-Portable Fabricated Wind Shelter, less than 8 foot height. | Ft | $28.68 |
| 576 | Livestock Shelter Structure | Wp_Portable Fabricated Wind Shelter, less than 8 foot height. | Ft | $28.68 |
| 578 | Stream Crossing | Culvert Installation | DiaInFt | $2.03 |
| 578 | Stream Crossing | HU-Culvert Installation | DiaInFt | $3.05 |
| 578 | Stream Crossing | Hard-armored Low-water Crossing | SqFt | $2.61 |
| 578 | Stream Crossing | HU-Hard-armored Low-water Crossing | SqFt | $3.91 |
| 578 | Stream Crossing | Low-water Stream using Prefabricated Products | SqFt | $3.91 |
| 578 | Stream Crossing | HU-Low-water Stream using Prefabricated Products | SqFt | $5.86 |
| 580 | Streambank and Shoreline Protection | Bankfull Bench and Vegetative Bioengineering | Ft | $18.48 |
| 580 | Streambank and Shoreline Protection | HU-Bankfull Bench and Vegetative Bioengineering | Ft | $27.72 |
| 580 | Streambank and Shoreline Protection | Large Wood Toe Protection and Vegetative Bioengineering | Ft | $47.80 |
| 580 | Streambank and Shoreline Protection | HU-Large Wood Toe Protection and Vegetative Bioengineering | Ft | $71.70 |
| 580 | Streambank and Shoreline Protection | Rock Riprap with Bankfull Bench and Vegetative Bioengineering | CuYd | $54.34 |
| 580 | Streambank and Shoreline Protection | HU-Rock Riprap with Bankfull Bench and Vegetative Bioengineering | CuYd | $81.50 |
| 580 | Streambank and Shoreline Protection | Rock Stream Barb and Vegetative Bioengineering | CuYd | $56.73 |
| 580 | Streambank and Shoreline Protection | HU-Rock Stream Barb and Vegetative Bioengineering | CuYd | $85.10 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 580 | Streambank and Shoreline Protection | Vegetative Bioengineering, less than or equal to 50 cfs bankfull flow | Ft | $10.39 |
| 580 | Streambank and Shoreline Protection | HU-Vegetative Bioengineering, less than or equal to 50 cfs bankfull flow | Ft | $15.58 |
| 582 | Open Channel | Excavation and Fill, Difficult Conditions | CuYd | $4.31 |
| 582 | Open Channel | HU-Excavation and Fill, Difficult Conditions | CuYd | $6.47 |
| 582 | Open Channel | Excavation and Fill, Normal Conditions | CuYd | $3.77 |
| 582 | Open Channel | HU-Excavation and Fill, Normal Conditions | CuYd | $5.65 |
| 582 | Open Channel | Excavation, Difficult Conditions | CuYd | $1.88 |
| 582 | Open Channel | HU-Excavation, Difficult Conditions | CuYd | $2.82 |
| 582 | Open Channel | Excavation, Normal Conditions | CuYd | $1.33 |
| 582 | Open Channel | HU-Excavation, Normal Conditions | CuYd | $2.00 |
| 582 | Open Channel | Less than 50 cfs Bankfull Channel Flow | Ft | $4.19 |
| 582 | Open Channel | HU-Less than 50 cfs Bankfull Channel Flow | Ft | $6.29 |
| 584 | Channel Bed Stabilization | Cross-Vane, Boulder (boulder or concrete or other fabricated materials) | CuYd | $108.80 |
| 584 | Channel Bed Stabilization | HU-Cross-Vane, Boulder (boulder or concrete or other fabricated materials) | CuYd | $163.21 |
| 584 | Channel Bed Stabilization | Cross-Vane, Log (wood and rock) | No | $4,960.88 |
| 584 | Channel Bed Stabilization | HU-Cross-Vane, Log (wood and rock) | No | $7,441.32 |
| 584 | Channel Bed Stabilization | Less than 50 cfs Bankfull Gravel Substrate | Ft | $3.12 |
| 584 | Channel Bed Stabilization | HU-Less than 50 cfs Bankfull Gravel Substrate | Ft | $4.68 |
| 584 | Channel Bed Stabilization | Stream Restoration with Gravel | CuYd | $34.34 |
| 584 | Channel Bed Stabilization | HU-Stream Restoration with Gravel | CuYd | $51.51 |
| 584 | Channel Bed Stabilization | Stream Restoration with Rock Structure | CuYd | $51.90 |
| 584 | Channel Bed Stabilization | HU-Stream Restoration with Rock Structure | CuYd | $77.85 |
| 585 | Stripcropping | Stripcropping - wind and water erosion | Ac | $1.35 |
| 585 | Stripcropping | HU-Stripcropping - wind and water erosion | Ac | $1.63 |
| 587 | Structure for Water Control | Active Screen | No | $5,012.67 |
| 587 | Structure for Water Control | HU-Active Screen | No | $6,015.20 |
| 587 | Structure for Water Control | Wp_Active Screen | No | $6,015.20 |
| 587 | Structure for Water Control | Concrete or Steel Pipe, greater than or equal to 30-inch diameter | DiaInFt | $2.18 |
| 587 | Structure for Water Control | HU-Concrete or Steel Pipe, greater than or equal to 30-inch diameter | DiaInFt | $3.26 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 587 | Structure for Water Control | Wp_Concrete or Steel Pipe, greater than or equal to 30-inch diameter | DiaInFt | $3.05 |
| 587 | Structure for Water Control | Corrugated Metal Pipe (CMP) Turnout | No | $359.27 |
| 587 | Structure for Water Control | HU-Corrugated Metal Pipe (CMP) Turnout | No | $538.90 |
| 587 | Structure for Water Control | Wp_Corrugated Metal Pipe (CMP) Turnout | No | $502.98 |
| 587 | Structure for Water Control | Culvert, Less than 30 inches Corrugated Metal Pipe (CMP) | DiaInFt | $1.33 |
| 587 | Structure for Water Control | HU-Culvert, Less than 30 inches Corrugated Metal Pipe (CMP) | DiaInFt | $2.00 |
| 587 | Structure for Water Control | Wp_Culvert, Less than 30 inches Corrugated Metal Pipe (CMP) | DiaInFt | $1.86 |
| 587 | Structure for Water Control | Culvert, less than 30 inches High Density Polyethylene (HDPE) | DiaInFt | $1.18 |
| 587 | Structure for Water Control | HU-Culvert, less than 30 inches High Density Polyethylene (HDPE) | DiaInFt | $1.77 |
| 587 | Structure for Water Control | Wp_Culvert, less than 30 inches High Density Polyethylene (HDPE) | DiaInFt | $1.65 |
| 587 | Structure for Water Control | Flow Meter with Electronic Index | In | $211.03 |
| 587 | Structure for Water Control | HU-Flow Meter with Electronic Index | In | $253.23 |
| 587 | Structure for Water Control | Wp_Flow Meter with Electronic Index | In | $253.23 |
| 587 | Structure for Water Control | Flow Meter with Mechanical Index | In | $114.14 |
| 587 | Structure for Water Control | HU-Flow Meter with Mechanical Index | In | $136.97 |
| 587 | Structure for Water Control | Wp_Flow Meter with Mechanical Index | In | $136.97 |
| 587 | Structure for Water Control | Inline Flashboard Riser, Metal | DiaInFt | $2.18 |
| 587 | Structure for Water Control | HU-Inline Flashboard Riser, Metal | DiaInFt | $3.27 |
| 587 | Structure for Water Control | Wp_Inline Flashboard Riser, Metal | DiaInFt | $3.06 |
| 587 | Structure for Water Control | Miscellaneous Structure, Extra Small | No | $2,124.15 |
| 587 | Structure for Water Control | HU-Miscellaneous Structure, Extra Small | No | $3,186.22 |
| 587 | Structure for Water Control | Wp_Miscellaneous Structure, Extra Small | No | $2,973.81 |
| 587 | Structure for Water Control | Miscellaneous Structure, Large | No | $13,486.79 |
| 587 | Structure for Water Control | HU-Miscellaneous Structure, Large | No | $20,230.18 |
| 587 | Structure for Water Control | Wp_Miscellaneous Structure, Large | No | $18,881.50 |
| 587 | Structure for Water Control | Miscellaneous Structure, Medium | No | $6,769.82 |
| 587 | Structure for Water Control | HU-Miscellaneous Structure, Medium | No | $10,154.73 |
| 587 | Structure for Water Control | Wp_Miscellaneous Structure, Medium | No | $9,477.75 |
| 587 | Structure for Water Control | Miscellaneous Structure, Small | No | $4,406.87 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 587 | Structure for Water Control | HU-Miscellaneous Structure, Small | No | $6,610.31 |
| 587 | Structure for Water Control | Wp_Miscellaneous Structure, Small | No | $6,169.62 |
| 587 | Structure for Water Control | Miscellaneous Structure, Very Large | CuYd | $1,642.16 |
| 587 | Structure for Water Control | HU-Miscellaneous Structure, Very Large | CuYd | $2,463.24 |
| 587 | Structure for Water Control | Wp_Miscellaneous Structure, Very Large | CuYd | $2,299.03 |
| 587 | Structure for Water Control | Miscellaneous Structure, Winter, Very Large | CuYd | $2,109.67 |
| 587 | Structure for Water Control | HU-Miscellaneous Structure, Winter, Very Large | CuYd | $3,164.51 |
| 587 | Structure for Water Control | Wp_Miscellaneous Structure, Winter, Very Large | CuYd | $2,953.54 |
| 587 | Structure for Water Control | Slide Gate | Ft | $976.05 |
| 587 | Structure for Water Control | HU-Slide Gate | Ft | $1,464.07 |
| 587 | Structure for Water Control | Wp_Slide Gate | Ft | $1,366.46 |
| 587 | Structure for Water Control | Stationary Screen | cfs | $2,425.54 |
| 587 | Structure for Water Control | HU-Stationary Screen | cfs | $2,910.65 |
| 587 | Structure for Water Control | Wp_Stationary Screen | cfs | $2,910.65 |
| 590 | Nutrient Management | Adaptive NM | No | $1,906.12 |
| 590 | Nutrient Management | HU-Adaptive NM | No | $2,287.35 |
| 590 | Nutrient Management | Wp_Adaptive NM | No | $2,287.35 |
| 590 | Nutrient Management | Basic NM (Non-Organic/Organic) | Ac | $6.36 |
| 590 | Nutrient Management | HU-Basic NM (Non-Organic/Organic) | Ac | $7.64 |
| 590 | Nutrient Management | Wp_Basic NM (Non-Organic/Organic) | Ac | $7.64 |
| 590 | Nutrient Management | Basic NM with Manure and/or Compost (Non-Organic/Organic) | Ac | $13.44 |
| 590 | Nutrient Management | HU-Basic NM with Manure and/or Compost (Non-Organic/Organic) | Ac | $16.13 |
| 590 | Nutrient Management | Wp_Basic NM with Manure and/or Compost (Non-Organic/Organic) | Ac | $16.13 |
| 590 | Nutrient Management | Basic NM with Manure Injection or Incorporation | Ac | $25.30 |
| 590 | Nutrient Management | HU-Basic NM with Manure Injection or Incorporation | Ac | $30.36 |
| 590 | Nutrient Management | Wp_Basic NM with Manure Injection or Incorporation | Ac | $30.36 |
| 590 | Nutrient Management | Basic Precision NM (Non-Organic/Organic) | Ac | $38.23 |
| 590 | Nutrient Management | HU-Basic Precision NM (Non-Organic/Organic) | Ac | $45.88 |
| 590 | Nutrient Management | Wp_Basic Precision NM (Non-Organic/Organic) | Ac | $45.88 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 590 | Nutrient Management | Small Farm NM (Non-Organic/Organic) | No | $209.69 |
| 590 | Nutrient Management | HU-Small Farm NM (Non-Organic/Organic) | No | $251.62 |
| 590 | Nutrient Management | Wp_Small Farm NM (Non-Organic/Organic) | No | $251.62 |
| 595 | Pest Management Conservation System | Plant Health PAMS (acs) High labor only (intensive scouting etc.) | Ac | $32.61 |
| 595 | Pest Management Conservation System | HU-Plant Health PAMS (acs) High labor only (intensive scouting etc.) | Ac | $39.13 |
| 595 | Pest Management Conservation System | Wp_Plant Health PAMS (acs) High labor only (intensive scouting etc.) | Ac | $39.13 |
| 595 | Pest Management Conservation System | Plant Health PAMS (acs) High Labor, materials and mitigation. | Ac | $300.76 |
| 595 | Pest Management Conservation System | HU-Plant Health PAMS (acs) High Labor, materials and mitigation. | Ac | $360.91 |
| 595 | Pest Management Conservation System | Wp_Plant Health PAMS (acs) High Labor, materials and mitigation. | Ac | $360.91 |
| 595 | Pest Management Conservation System | Plant Health PAMS (acs) Low labor only | Ac | $10.67 |
| 595 | Pest Management Conservation System | HU-Plant Health PAMS (acs) Low labor only | Ac | $12.80 |
| 595 | Pest Management Conservation System | Wp_Plant Health PAMS (acs) Low labor only | Ac | $12.80 |
| 595 | Pest Management Conservation System | Plant Health PAMS (acs) Low Labor, materials and mitigation. | Ac | $41.69 |
| 595 | Pest Management Conservation System | HU-Plant Health PAMS (acs) Low Labor, materials and mitigation. | Ac | $50.03 |
| 595 | Pest Management Conservation System | Wp_Plant Health PAMS (acs) Low Labor, materials and mitigation. | Ac | $50.03 |
| 595 | Pest Management Conservation System | Plant health PAMS (Small Farm - each) labor only | No | $400.59 |
| 595 | Pest Management Conservation System | HU-Plant health PAMS (Small Farm - each) labor only | No | $480.71 |
| 595 | Pest Management Conservation System | Wp_Plant health PAMS (Small Farm - each) labor only | No | $480.71 |
| 595 | Pest Management Conservation System | Plant Health PAMS activities (Small Farm - each) labor, materials and mitigation. | No | $5,349.59 |
| 595 | Pest Management Conservation System | HU-Plant Health PAMS activities (Small Farm - each) labor, materials and mitigation. | No | $6,419.51 |
| 595 | Pest Management Conservation System | Wp_Plant Health PAMS activities (Small Farm - each) labor, materials and mitigation. | No | $6,419.51 |
| 603 | Herbaceous Wind Barriers | Cool Season Annual/Perennial Species | Lnft | $0.05 |
| 603 | Herbaceous Wind Barriers | HU-Cool Season Annual/Perennial Species | Lnft | $0.07 |
| 606 | Subsurface Drain | Corrugated Plastic Pipe (CPP), Single-Wall, greater than or equal to 8-inch | Lb | $1.62 |
| 606 | Subsurface Drain | HU-Corrugated Plastic Pipe (CPP), Single-Wall, greater than or equal to 8-inch | Lb | $2.42 |
| 606 | Subsurface Drain | Corrugated Plastic Pipe (CPP), Single-Wall, less than or equal to 6-inch | Lb | $3.63 |
| 606 | Subsurface Drain | HU-Corrugated Plastic Pipe (CPP), Single-Wall, less than or equal to 6-inch | Lb | $5.44 |
| 606 | Subsurface Drain | Corrugated Plastic Pipe (CPP), Twin-Wall, greater than or equal to 8-inch | Lb | $2.12 |
| 606 | Subsurface Drain | HU-Corrugated Plastic Pipe (CPP), Twin-Wall, greater than or equal to 8-inch | Lb | $3.18 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 606 | Subsurface Drain | Enveloped Corrugated Plastic Pipe (CPP), Single-Wall, less than or equal to 6-inch | Lb | $4.67 |
| 606 | Subsurface Drain | HU-Enveloped Corrugated Plastic Pipe (CPP), Single-Wall, less than or equal to 6-inch | Lb | $7.01 |
| 606 | Subsurface Drain | Pond Perimeter Drain | Ft | $8.67 |
| 606 | Subsurface Drain | HU-Pond Perimeter Drain | Ft | $13.00 |
| 607 | Surface Drain, Field Ditch | Field Drainage Ditch | CuYd | $1.20 |
| 607 | Surface Drain, Field Ditch | HU-Field Drainage Ditch | CuYd | $1.80 |
| 610 | Salinity and Sodic Soil Management | Dryland Monitor Wells, Year 1 | Ac | $46.52 |
| 610 | Salinity and Sodic Soil Management | HU-Dryland Monitor Wells, Year 1 | Ac | $55.82 |
| 610 | Salinity and Sodic Soil Management | Prevent Dry Intense Cropping | Ac | $82.27 |
| 610 | Salinity and Sodic Soil Management | HU-Prevent Dry Intense Cropping | Ac | $87.25 |
| 610 | Salinity and Sodic Soil Management | Soil Management, NON-Irrigated | Ac | $13.97 |
| 610 | Salinity and Sodic Soil Management | HU-Soil Management, NON-Irrigated | Ac | $16.77 |
| 612 | Tree/Shrub Establishment | Forested Area, Per Plant, Tree, Hand Planted | No | $1.03 |
| 612 | Tree/Shrub Establishment | HU-Forested Area, Per Plant, Tree, Hand Planted | No | $1.24 |
| 612 | Tree/Shrub Establishment | Forested Area, Per Plant, Tree, Hand Planted with Protection Tubes | No | $1.73 |
| 612 | Tree/Shrub Establishment | HU-Forested Area, Per Plant, Tree, Hand Planted with Protection Tubes | No | $2.07 |
| 612 | Tree/Shrub Establishment | Tree/Shrub Regeneration Area with Protection | Ac | $303.50 |
| 612 | Tree/Shrub Establishment | HU-Tree/Shrub Regeneration Area with Protection | Ac | $364.20 |
| 614 | Watering Facility | Automatic or Winter, No Storage, less than 450 Gallons | No | $612.57 |
| 614 | Watering Facility | HU-Automatic or Winter, No Storage, less than 450 Gallons | No | $918.85 |
| 614 | Watering Facility | Wp_Automatic or Winter, No Storage, less than 450 Gallons | No | $857.59 |
| 614 | Watering Facility | Permanent Drinking with Storage, 1,000 to 5,000 Gallons | Gal | $1.41 |
| 614 | Watering Facility | HU-Permanent Drinking with Storage, 1,000 to 5,000 Gallons | Gal | $2.11 |
| 614 | Watering Facility | Wp_Permanent Drinking with Storage, 1,000 to 5,000 Gallons | Gal | $1.97 |
| 614 | Watering Facility | Permanent Drinking with Storage, 500 to 1,000 Gallons | Gal | $1.53 |
| 614 | Watering Facility | HU-Permanent Drinking with Storage, 500 to 1,000 Gallons | Gal | $2.29 |
| 614 | Watering Facility | Wp_Permanent Drinking with Storage, 500 to 1,000 Gallons | Gal | $2.14 |
| 614 | Watering Facility | Permanent Drinking with Storage, greater than 5,000 gallons | Gal | $0.68 |
| 614 | Watering Facility | HU-Permanent Drinking with Storage, greater than 5,000 gallons | Gal | $1.02 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 614 | Watering Facility | Wp_Permanent Drinking with Storage, greater than 5,000 gallons | Gal | $0.96 |
| 614 | Watering Facility | Permanent Drinking with Storage, less than 500 Gallons | Gal | $1.74 |
| 614 | Watering Facility | HU-Permanent Drinking with Storage, less than 500 Gallons | Gal | $2.60 |
| 614 | Watering Facility | Wp_Permanent Drinking with Storage, less than 500 Gallons | Gal | $2.43 |
| 614 | Watering Facility | Storage Tank | Gal | $0.58 |
| 614 | Watering Facility | HU-Storage Tank | Gal | $0.86 |
| 614 | Watering Facility | Wp_Storage Tank | Gal | $0.81 |
| 614 | Watering Facility | Winter, with Storage | Gal | $2.17 |
| 614 | Watering Facility | HU-Winter, with Storage | Gal | $3.25 |
| 614 | Watering Facility | Wp_Winter, with Storage | Gal | $3.04 |
| 620 | Underground Outlet | Approved Plastic Pipe, greater than 12-inch to less than or equal to 18-inch | Ft | $17.17 |
| 620 | Underground Outlet | HU-Approved Plastic Pipe, greater than 12-inch to less than or equal to 18-inch | Ft | $20.59 |
| 620 | Underground Outlet | Approved Plastic Pipe, greater than 6-inch to less than or equal to 12-inch | Ft | $7.94 |
| 620 | Underground Outlet | HU-Approved Plastic Pipe, greater than 6-inch to less than or equal to 12-inch | Ft | $9.51 |
| 620 | Underground Outlet | Approved Plastic Pipe, greater than 6-inch to less than or equal to 12-inch, with Riser | Ft | $8.36 |
| 620 | Underground Outlet | HU-Approved Plastic Pipe, greater than 6-inch to less than or equal to 12-inch, with Riser | Ft | $10.02 |
| 620 | Underground Outlet | Approved Plastic Pipe, Less than or Equal to 6-inch | Ft | $6.30 |
| 620 | Underground Outlet | HU-Approved Plastic Pipe, Less than or Equal to 6-inch | Ft | $7.54 |
| 620 | Underground Outlet | Approved Plastic Pipe, Less than or Equal to 6-inch, with Riser | Ft | $4.15 |
| 620 | Underground Outlet | HU-Approved Plastic Pipe, Less than or Equal to 6-inch, with Riser | Ft | $4.97 |
| 632 | Waste Separation Facility | Concrete Basin | Cu-Ft | $5.67 |
| 632 | Waste Separation Facility | HU-Concrete Basin | Cu-Ft | $6.81 |
| 632 | Waste Separation Facility | Earthen Settling Structure, greater than 0.5 ac-ft design storage | Cu-Ft | $0.26 |
| 632 | Waste Separation Facility | HU-Earthen Settling Structure, greater than 0.5 ac-ft design storage | Cu-Ft | $0.31 |
| 632 | Waste Separation Facility | Earthen Settling Structure, less than or equal to 0.5 ac-ft design storage | Cu-Ft | $0.58 |
| 632 | Waste Separation Facility | HU-Earthen Settling Structure, less than or equal to 0.5 ac-ft design storage | Cu-Ft | $0.69 |
| 632 | Waste Separation Facility | Mechanical Separation, General | No | $28,165.49 |
| 632 | Waste Separation Facility | HU-Mechanical Separation, General | No | $33,798.59 |
| 632 | Waste Separation Facility | Mechanical Separation, Screw Press | No | $28,375.12 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 632 | Waste Separation Facility | HU-Mechanical Separation, Screw Press | No | $34,050.14 |
| 634 | Waste Transfer | Agitator, Large, Used for Mixing a Tank, greater than 15-foot depth | No | $7,900.77 |
| 634 | Waste Transfer | HU-Agitator, Large, Used for Mixing a Tank, greater than 15-foot depth | No | $9,480.93 |
| 634 | Waste Transfer | Wp_Agitator, Large, Used for Mixing a Tank, greater than 15-foot depth | No | $9,480.93 |
| 634 | Waste Transfer | Agitator, Medium, Used for Mixing a Basin, 10- to 15-foot depth | No | $7,246.48 |
| 634 | Waste Transfer | HU-Agitator, Medium, Used for Mixing a Basin, 10- to 15-foot depth | No | $8,695.77 |
| 634 | Waste Transfer | Wp_Agitator, Medium, Used for Mixing a Basin, 10- to 15-foot depth | No | $8,695.77 |
| 634 | Waste Transfer | Agitator, Small, Used for Mixing a Basin or Pit, less than 10-foot depth | No | $6,373.62 |
| 634 | Waste Transfer | HU-Agitator, Small, Used for Mixing a Basin or Pit, less than 10-foot depth | No | $7,648.34 |
| 634 | Waste Transfer | Wp_Agitator, Small, Used for Mixing a Basin or Pit, less than 10-foot depth | No | $7,648.34 |
| 634 | Waste Transfer | Concrete Channel | SqFt | $9.66 |
| 634 | Waste Transfer | HU-Concrete Channel | SqFt | $11.60 |
| 634 | Waste Transfer | Wp_Concrete Channel | SqFt | $11.60 |
| 634 | Waste Transfer | Concrete Channel, with Push-off Wall at Pond and Safety Gate | SqFt | $15.25 |
| 634 | Waste Transfer | HU-Concrete Channel, with Push-off Wall at Pond and Safety Gate | SqFt | $18.30 |
| 634 | Waste Transfer | Wp_Concrete Channel, with Push-off Wall at Pond and Safety Gate | SqFt | $18.30 |
| 634 | Waste Transfer | Conveyor System | Ft | $23.98 |
| 634 | Waste Transfer | HU-Conveyor System | Ft | $28.78 |
| 634 | Waste Transfer | Wp_Conveyor System | Ft | $28.78 |
| 634 | Waste Transfer | Hard-hose Reel System | No | $37,066.62 |
| 634 | Waste Transfer | HU-Hard-hose Reel System | No | $44,479.94 |
| 634 | Waste Transfer | Wp_Hard-hose Reel System | No | $44,479.94 |
| 634 | Waste Transfer | Hard-hose Reel System with Booster incorporated into Traveler | No | $46,206.62 |
| 634 | Waste Transfer | HU-Hard-hose Reel System with Booster incorporated into Traveler | No | $55,447.94 |
| 634 | Waste Transfer | Wp_Hard-hose Reel System with Booster incorporated into Traveler | No | $55,447.94 |
| 634 | Waste Transfer | Hopper Inlet, with 24-inch Diameter Gravity Pipeline to Waste Storage Facility | Ft | $107.15 |
| 634 | Waste Transfer | HU-Hopper Inlet, with 24-inch Diameter Gravity Pipeline to Waste Storage Facility | Ft | $128.58 |
| 634 | Waste Transfer | Wp_Hopper Inlet, with 24-inch Diameter Gravity Pipeline to Waste Storage Facility | Ft | $128.58 |
| 634 | Waste Transfer | Pressure Flow through Pipeline from Waste Storage Pond to Waste Application Site | Ft | $7.99 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 634 | Waste Transfer | HU-Pressure Flow through Pipeline from Waste Storage Pond to Waste Application Site | Ft | $9.58 |
| 634 | Waste Transfer | Wp_Pressure Flow through Pipeline from Waste Storage Pond to Waste Application Site | Ft | $9.58 |
| 634 | Waste Transfer | Pressure Pipe at Headquarters | Ft | $12.26 |
| 634 | Waste Transfer | HU-Pressure Pipe at Headquarters | Ft | $14.71 |
| 634 | Waste Transfer | Wp_Pressure Pipe at Headquarters | Ft | $14.71 |
| 634 | Waste Transfer | Wastewater Catch Basin, less than 1,000 gallons | Gal | $6.18 |
| 634 | Waste Transfer | HU-Wastewater Catch Basin, less than 1,000 gallons | Gal | $7.42 |
| 634 | Waste Transfer | Wp_Wastewater Catch Basin, less than 1,000 gallons | Gal | $7.42 |
| 634 | Waste Transfer | Wastewater Reception Pit or Basin, 1,000 to 5,000 gallons | Gal | $2.77 |
| 634 | Waste Transfer | HU-Wastewater Reception Pit or Basin, 1,000 to 5,000 gallons | Gal | $3.32 |
| 634 | Waste Transfer | Wp_Wastewater Reception Pit or Basin, 1,000 to 5,000 gallons | Gal | $3.32 |
| 634 | Waste Transfer | Wastewater Reception Pit, greater than 5,000 gallons | Gal | $2.13 |
| 634 | Waste Transfer | HU-Wastewater Reception Pit, greater than 5,000 gallons | Gal | $2.55 |
| 634 | Waste Transfer | Wp_Wastewater Reception Pit, greater than 5,000 gallons | Gal | $2.55 |
| 635 | Vegetated Treatment Area | Constructed VTA with runoff delivered via gated pipe | Ac | $2,662.46 |
| 635 | Vegetated Treatment Area | HU-Constructed VTA with runoff delivered via gated pipe | Ac | $3,194.95 |
| 635 | Vegetated Treatment Area | Wp_Constructed VTA with runoff delivered via gated pipe | Ac | $3,194.95 |
| 635 | Vegetated Treatment Area | Constructed VTA with runoff delivered via gravel filled spreader trench | Ac | $2,499.53 |
| 635 | Vegetated Treatment Area | HU-Constructed VTA with runoff delivered via gravel filled spreader trench | Ac | $2,999.44 |
| 635 | Vegetated Treatment Area | Wp_Constructed VTA with runoff delivered via gravel filled spreader trench | Ac | $2,999.44 |
| 635 | Vegetated Treatment Area | Existing Area, Pod Sprinkler System Distribution | Ac | $2,110.15 |
| 635 | Vegetated Treatment Area | HU-Existing Area, Pod Sprinkler System Distribution | Ac | $2,532.19 |
| 635 | Vegetated Treatment Area | Wp_Existing Area, Pod Sprinkler System Distribution | Ac | $2,532.19 |
| 635 | Vegetated Treatment Area | Existing VTA with wastewater delivered via a weir system | Ac | $1,258.57 |
| 635 | Vegetated Treatment Area | HU-Existing VTA with wastewater delivered via a weir system | Ac | $1,510.28 |
| 635 | Vegetated Treatment Area | Wp_Existing VTA with wastewater delivered via a weir system | Ac | $1,510.28 |
| 635 | Vegetated Treatment Area | Existing VTA with wastewater delivered via gated pipe | Ac | $1,420.53 |
| 635 | Vegetated Treatment Area | HU-Existing VTA with wastewater delivered via gated pipe | Ac | $1,704.63 |
| 635 | Vegetated Treatment Area | Wp_Existing VTA with wastewater delivered via gated pipe | Ac | $1,704.63 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 638 | Water and Sediment Control Basin | WASCOB, Topsoil | CuYd | $3.49 |
| 638 | Water and Sediment Control Basin | HU-WASCOB, Topsoil | CuYd | $5.23 |
| 642 | Water Well | Deep Well, 1000-foot depth or greater with 4-inch Casing | Lnft | $50.53 |
| 642 | Water Well | HU-Deep Well, 1000-foot depth or greater with 4-inch Casing | Lnft | $75.80 |
| 642 | Water Well | Wp_Deep Well, 1000-foot depth or greater with 4-inch Casing | Lnft | $70.75 |
| 642 | Water Well | Deep Well, 1000-foot depth or greater with 6-inch Casing | Lnft | $46.79 |
| 642 | Water Well | HU-Deep Well, 1000-foot depth or greater with 6-inch Casing | Lnft | $70.18 |
| 642 | Water Well | Wp_Deep Well, 1000-foot depth or greater with 6-inch Casing | Lnft | $65.50 |
| 642 | Water Well | Shallow Well 50 Foot Depth or Less | Lnft | $78.21 |
| 642 | Water Well | HU-Shallow Well 50 Foot Depth or Less | Lnft | $117.32 |
| 642 | Water Well | Wp_Shallow Well 50 Foot Depth or Less | Lnft | $109.50 |
| 642 | Water Well | Shallow Well, 50 to 100-foot depth | Lnft | $50.42 |
| 642 | Water Well | HU-Shallow Well, 50 to 100-foot depth | Lnft | $75.63 |
| 642 | Water Well | Wp_Shallow Well, 50 to 100-foot depth | Lnft | $70.59 |
| 642 | Water Well | Typical Well, 100- to 600-foot depth with 4-inch Casing | Lnft | $29.57 |
| 642 | Water Well | HU-Typical Well, 100- to 600-foot depth with 4-inch Casing | Lnft | $44.35 |
| 642 | Water Well | Wp_Typical Well, 100- to 600-foot depth with 4-inch Casing | Lnft | $41.40 |
| 642 | Water Well | Typical Well, 600- to 1000-foot depth with 6-inch Casing | Lnft | $33.98 |
| 642 | Water Well | HU-Typical Well, 600- to 1000-foot depth with 6-inch Casing | Lnft | $50.98 |
| 642 | Water Well | Wp_Typical Well, 600- to 1000-foot depth with 6-inch Casing | Lnft | $47.58 |
| 643 | Restoration of Rare or Declining Natural Communities | Beaver Dam Analogues or Post-Assisted Log Structures | Lnft | $28.69 |
| 643 | Restoration of Rare or Declining Natural Communities | HU-Beaver Dam Analogues or Post-Assisted Log Structures | Lnft | $34.43 |
| 643 | Restoration of Rare or Declining Natural Communities | Monitoring, Management, High Intensity and Complexity, Includes Foregone Income for Grazing Land | Ac | $29.34 |
| 643 | Restoration of Rare or Declining Natural Communities | HU-Monitoring, Management, High Intensity and Complexity, Includes Foregone Income for Grazing Land | Ac | $34.29 |
| 643 | Restoration of Rare or Declining Natural Communities | Rock Structure | CuYd | $516.84 |
| 643 | Restoration of Rare or Declining Natural Communities | HU-Rock Structure | CuYd | $620.21 |
| 644 | Wetland Wildlife Habitat Management | Idling Cropland for Wetland Wildlife - Level 2 | Ac | $234.18 |
| 644 | Wetland Wildlife Habitat Management | HU-Idling Cropland for Wetland Wildlife - Level 2 | Ac | $243.02 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 644 | Wetland Wildlife Habitat Management | Management and Monitoring on Idled Cropland for Wetland Wildlife, foregone income - Level 1 (Year 2-5) | Ac | $230.30 |
| 644 | Wetland Wildlife Habitat Management | HU-Management and Monitoring on Idled Cropland for Wetland Wildlife, foregone income - Level 1 (Year 2-5) | Ac | $238.36 |
| 644 | Wetland Wildlife Habitat Management | Monitoring and Management | Ac | $157.88 |
| 644 | Wetland Wildlife Habitat Management | HU-Monitoring and Management | Ac | $161.36 |
| 644 | Wetland Wildlife Habitat Management | Monitoring and Management - Level 3 | Ac | $169.41 |
| 644 | Wetland Wildlife Habitat Management | HU-Monitoring and Management - Level 3 | Ac | $176.70 |
| 644 | Wetland Wildlife Habitat Management | Topographic Feature Creation | Ac | $196.99 |
| 644 | Wetland Wildlife Habitat Management | HU-Topographic Feature Creation | Ac | $208.29 |
| 645 | Upland Wildlife Habitat Management | Honeybee Habitat Multi Species Mix with Monitoring and Foregone Income | Ac | $212.22 |
| 645 | Upland Wildlife Habitat Management | HU-Honeybee Habitat Multi Species Mix with Monitoring and Foregone Income | Ac | $226.56 |
| 645 | Upland Wildlife Habitat Management | Honeybee Habitat Multi Species Mix with Monitoring, No Foregone Income | Ac | $71.71 |
| 645 | Upland Wildlife Habitat Management | HU-Honeybee Habitat Multi Species Mix with Monitoring, No Foregone Income | Ac | $86.05 |
| 645 | Upland Wildlife Habitat Management | Honeybee Monitoring | Ac | $19.81 |
| 645 | Upland Wildlife Habitat Management | HU-Honeybee Monitoring | Ac | $23.77 |
| 645 | Upland Wildlife Habitat Management | Lek Monitoring | No | $440.11 |
| 645 | Upland Wildlife Habitat Management | HU-Lek Monitoring | No | $528.13 |
| 645 | Upland Wildlife Habitat Management | Monitoring, Management, FI and Training, Medium Intensity and Complexity | Ac | $156.71 |
| 645 | Upland Wildlife Habitat Management | HU-Monitoring, Management, FI and Training, Medium Intensity and Complexity | Ac | $159.95 |
| 645 | Upland Wildlife Habitat Management | Monitoring, Management, Foregone Income, May Require Training, High Intensity and High Complexity | Ac | $165.65 |
| 645 | Upland Wildlife Habitat Management | HU-Monitoring, Management, Foregone Income, May Require Training, High Intensity and High Complexity | Ac | $170.68 |
| 645 | Upland Wildlife Habitat Management | Monitoring, Management, No Foregone Income, No Training Required, Low Intensity and Low Complexity | Ac | $13.77 |
| 645 | Upland Wildlife Habitat Management | HU-Monitoring, Management, No Foregone Income, No Training Required, Low Intensity and Low Complexity | Ac | $16.52 |
| 645 | Upland Wildlife Habitat Management | Snag Creation, Tree Topping Or Tree Girdling | Ac | $115.15 |
| 645 | Upland Wildlife Habitat Management | HU-Snag Creation, Tree Topping Or Tree Girdling | Ac | $138.17 |
| 647 | Early Successional Habitat Development-Mgt | Disking | Ac | $47.30 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 647 | Early Successional Habitat Development-Mgt | HU-Disking | Ac | $70.96 |
| 647 | Early Successional Habitat Development-Mgt | Mowing | Ac | $116.31 |
| 647 | Early Successional Habitat Development-Mgt | HU-Mowing | Ac | $174.46 |
| 649 | Structures for Wildlife | Escape Ramp | No | $81.15 |
| 649 | Structures for Wildlife | HU-Escape Ramp | No | $97.39 |
| 649 | Structures for Wildlife | Fence Markers, Vinyl Undersill | Ft | $0.12 |
| 649 | Structures for Wildlife | HU-Fence Markers, Vinyl Undersill | Ft | $0.14 |
| 649 | Structures for Wildlife | Wildlife Friendly Fence Retrofit with Fence Markers | Ft | $1.32 |
| 649 | Structures for Wildlife | HU-Wildlife Friendly Fence Retrofit with Fence Markers | Ft | $1.59 |
| 649 | Structures for Wildlife | Wildlife Friendly Fence Retrofit, Replacement of Wire Only with Fence Markers | Ft | $0.94 |
| 649 | Structures for Wildlife | HU-Wildlife Friendly Fence Retrofit, Replacement of Wire Only with Fence Markers | Ft | $1.13 |
| 649 | Structures for Wildlife | Wildlife Structures of Low Intensity with Low Complexity | Ac | $28.55 |
| 649 | Structures for Wildlife | HU-Wildlife Structures of Low Intensity with Low Complexity | Ac | $34.26 |
| 650 | Windbreak/Shelterbelt Renovation | Removal with Skidsteer, less than or equal to 8-inch Tree Diameter at Breast Height (DBH) | Ft | $1.11 |
| 650 | Windbreak/Shelterbelt Renovation | HU-Removal with Skidsteer, less than or equal to 8-inch Tree Diameter at Breast Height (DBH) | Ft | $1.33 |
| 650 | Windbreak/Shelterbelt Renovation | Supplemental Plantings, Container (partial windbreak) | No | $4.61 |
| 650 | Windbreak/Shelterbelt Renovation | HU-Supplemental Plantings, Container (partial windbreak) | No | $5.53 |
| 650 | Windbreak/Shelterbelt Renovation | Thinning | Ft | $0.51 |
| 650 | Windbreak/Shelterbelt Renovation | HU-Thinning | Ft | $0.61 |
| 655 | Forest Trails and Landings | Grading and Shaping with Vegetative Establishment | Ft | $2.78 |
| 655 | Forest Trails and Landings | HU-Grading and Shaping with Vegetative Establishment | Ft | $3.34 |
| 657 | Wetland Restoration | Ditch plug | CuYd | $7.22 |
| 657 | Wetland Restoration | HU-Ditch plug | CuYd | $8.17 |
| 657 | Wetland Restoration | Drain tile removal | Lnft | $6.55 |
| 657 | Wetland Restoration | HU-Drain tile removal | Lnft | $7.85 |
| 657 | Wetland Restoration | Drained Wetland | CuYd | $7.30 |
| 657 | Wetland Restoration | HU-Drained Wetland | CuYd | $8.76 |
| 657 | Wetland Restoration | Embankment - Fill Height <= 3 feet | CuYd | $7.35 |
| 657 | Wetland Restoration | HU-Embankment - Fill Height <= 3 feet | CuYd | $8.58 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 659 | Wetland Enhancement | Embankment - Fill Height <= 3 feet | CuYd | $7.35 |
| 659 | Wetland Enhancement | HU-Embankment - Fill Height <= 3 feet | CuYd | $8.58 |
| 659 | Wetland Enhancement | Excavated Depressional Area. | CuYd | $4.85 |
| 659 | Wetland Enhancement | HU-Excavated Depressional Area. | CuYd | $5.82 |
| 660 | Tree/Shrub Pruning | High Height | Ac | $293.69 |
| 660 | Tree/Shrub Pruning | HU-High Height | Ac | $352.43 |
| 660 | Tree/Shrub Pruning | White Pine Blister Rust | Ac | $223.41 |
| 660 | Tree/Shrub Pruning | HU-White Pine Blister Rust | Ac | $268.09 |
| 666 | Forest Stand Improvement | Aspen Regeneration | Ac | $276.10 |
| 666 | Forest Stand Improvement | HU-Aspen Regeneration | Ac | $331.32 |
| 666 | Forest Stand Improvement | Intermediate Silvicultural Treatment | Ac | $432.19 |
| 666 | Forest Stand Improvement | HU-Intermediate Silvicultural Treatment | Ac | $518.63 |
| 666 | Forest Stand Improvement | Pre-Commercial Thinning, High Intensity | Ac | $550.21 |
| 666 | Forest Stand Improvement | HU-Pre-Commercial Thinning, High Intensity | Ac | $660.25 |
| 670 | Energy Efficient Lighting System | Automatic Controller System | No | $244.49 |
| 670 | Energy Efficient Lighting System | HU-Automatic Controller System | No | $366.73 |
| 670 | Energy Efficient Lighting System | Lighting - LED | No | $6.20 |
| 670 | Energy Efficient Lighting System | HU-Lighting - LED | No | $9.31 |
| 672 | Energy Efficient Building Envelope | Building Envelope - Attic Insulation | SqFt | $0.38 |
| 672 | Energy Efficient Building Envelope | HU-Building Envelope - Attic Insulation | SqFt | $0.57 |
| 672 | Energy Efficient Building Envelope | Building Envelope - Sealant | Ft | $0.84 |
| 672 | Energy Efficient Building Envelope | HU-Building Envelope - Sealant | Ft | $1.25 |
| 672 | Energy Efficient Building Envelope | Building Envelope - Wall Insulation | SqFt | $0.94 |
| 672 | Energy Efficient Building Envelope | HU-Building Envelope - Wall Insulation | SqFt | $1.41 |
| 770 | Livestock Confinement Facility | Livestock Confinement | Ft | $21.79 |
| 770 | Livestock Confinement Facility | HU-Livestock Confinement | Ft | $26.15 |
| 770 | Livestock Confinement Facility | Wp_Livestock Confinement | Ft | $26.15 |
| 800 | Controlling Existing Flowing Wells | Basic Flowing Well | No | $4,204.65 |
| 800 | Controlling Existing Flowing Wells | HU-Basic Flowing Well | No | $5,045.58 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| 800 | Controlling Existing Flowing Wells | Complicated Flowing Well | No | $13,750.38 |
| 800 | Controlling Existing Flowing Wells | HU-Complicated Flowing Well | No | $16,500.45 |
| 800 | Controlling Existing Flowing Wells | Standard Flowing Well | No | $9,885.62 |
| 800 | Controlling Existing Flowing Wells | HU-Standard Flowing Well | No | $11,862.74 |
| 808 | Soil Carbon Amendment | Biochar | Ac | $645.85 |
| 808 | Soil Carbon Amendment | HU-Biochar | Ac | $775.02 |
| 808 | Soil Carbon Amendment | Carbon By-Product - Imported | Ac | $154.72 |
| 808 | Soil Carbon Amendment | HU-Carbon By-Product - Imported | Ac | $185.66 |
| 808 | Soil Carbon Amendment | Compost - Low Rate - Imported | Ac | $74.15 |
| 808 | Soil Carbon Amendment | HU-Compost - Low Rate - Imported | Ac | $88.97 |
| 808 | Soil Carbon Amendment | Compost - Low Rate On-Farm | Ac | $57.69 |
| 808 | Soil Carbon Amendment | HU-Compost - Low Rate On-Farm | Ac | $69.23 |
| 808 | Soil Carbon Amendment | Compost - Moderate Rate - Imported | Ac | $182.67 |
| 808 | Soil Carbon Amendment | HU-Compost - Moderate Rate - Imported | Ac | $219.21 |
| 808 | Soil Carbon Amendment | Compost - Moderate Rate - On-Farm | Ac | $132.63 |
| 808 | Soil Carbon Amendment | HU-Compost - Moderate Rate - On-Farm | Ac | $159.16 |
| 808 | Soil Carbon Amendment | Compost and Biochar Mix | Ac | $250.37 |
| 808 | Soil Carbon Amendment | HU-Compost and Biochar Mix | Ac | $300.45 |
| 808 | Soil Carbon Amendment | Whole Orchard Recycling | Ac | $239.96 |
| 808 | Soil Carbon Amendment | HU-Whole Orchard Recycling | Ac | $287.96 |
| 910 | TA Planning | TSP-Technical Services-Conservation Planning | No | $0.00 |
| 911 | TA Design | TSP-Technical Services-Design Services | No | $0.00 |
| 912 | TA Application | TSP-Technical Services-Installation Oversight | No | $0.00 |
| 913 | TA Check-Out | TSP-Technical Services-Checkout Certification | No | $0.00 |
| E314A | Brush management to improve wildlife habitat | Brush management to improve wildlife habitat | Ac | $18.66 |
| E314A | Brush management to improve wildlife habitat | HU-Brush management to improve wildlife habitat | Ac | $18.66 |
| E315A | Herbaceous weed treatment to create plant communities consistent with the ecological site | HU-Herbaceous weed treatment to create plant communities consistent with the ecological site | Ac | $14.05 |
| E315A | Herbaceous weed treatment to create plant communities consistent with the ecological site | Herbaceous weed treatment to create plant communities consistent with the ecological site | Ac | $14.05 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| E327A | Conservation cover for pollinators and beneficial insects | Conservation cover for pollinators and beneficial insects | Ac | $150.74 |
| E327A | Conservation cover for pollinators and beneficial insects | HU-Conservation cover for pollinators and beneficial insects | Ac | $150.74 |
| E327B | Establish Monarch butterfly habitat | Establish Monarch butterfly habitat | Ac | $841.98 |
| E327B | Establish Monarch butterfly habitat | HU-Establish Monarch butterfly habitat | Ac | $841.98 |
| E328A | Resource conserving crop rotation | HU-Resource conserving crop rotation | Ac | $13.59 |
| E328A | Resource conserving crop rotation | Resource conserving crop rotation | Ac | $13.59 |
| E328B | Improved resource conserving crop rotation | HU-Improved resource conserving crop rotation | Ac | $4.86 |
| E328B | Improved resource conserving crop rotation | Improved resource conserving crop rotation | Ac | $4.86 |
| E328C | Conservation crop rotation on recently converted CRP grass/legume cover | HU-Conservation crop rotation on recently converted CRP grass/legume cover for water erosion | Ac | $2.91 |
| E328C | Conservation crop rotation on recently converted CRP grass/legume cover | Conservation crop rotation on recently converted CRP grass/legume cover for water erosion | Ac | $2.91 |
| E328D | Leave standing grain crops unharvested to benefit wildlife | Leave standing grain crops unharvested to benefit wildlife | Ac | $3.77 |
| E328D | Leave standing grain crops unharvested to benefit wildlife | HU-Leave standing grain crops unharvested to benefit wildlife | Ac | $3.77 |
| E328E | Soil health crop rotation | Soil health crop rotation | Ac | $4.86 |
| E328E | Soil health crop rotation | HU-Soil health crop rotation | Ac | $4.86 |
| E328F | Modifications to improve soil health and increase soil organic matter | HU-Modifications to improve soil health and increase soil organic matter | Ac | $2.13 |
| E328F | Modifications to improve soil health and increase soil organic matter | Modifications to improve soil health and increase soil organic matter | Ac | $2.13 |
| E328G | Crop rotation on recently converted CRP grass/legume cover for soil organic matter improvement | HU-Crop rotation on recently converted CRP grass/legume cover for soil organic matter improvement | Ac | $4.86 |
| E328G | Crop rotation on recently converted CRP grass/legume cover for soil organic matter improvement | Crop rotation on recently converted CRP grass/legume cover for soil organic matter improvement | Ac | $4.86 |
| E328H | Conservation crop rotation to reduce the concentration of salts | Conservation crop rotation to reduce the concentration of salts | Ac | $3.88 |
| E328H | Conservation crop rotation to reduce the concentration of salts | HU-Conservation crop rotation to reduce the concentration of salts | Ac | $3.88 |
| E328I | Forage harvest to reduce water quality impacts by utilization of excess soil nutrients | Forage harvest to reduce water quality impacts by utilization of excess soil nutrients | Ac | $4.47 |
| E328I | Forage harvest to reduce water quality impacts by utilization of excess soil nutrients | HU-Forage harvest to reduce water quality impacts by utilization of excess soil nutrients | Ac | $4.47 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| E328J | Improved crop rotation to provide benefits to pollinators | HU-Improved crop rotation to provide benefits to pollinators | Ac | $77.68 |
| E328J | Improved crop rotation to provide benefits to pollinators | Improved crop rotation to provide benefits to pollinators | Ac | $77.68 |
| E328K | Multiple crop types to benefit wildlife | Multiple crop types to benefit wildlife | Ac | $4.86 |
| E328K | Multiple crop types to benefit wildlife | HU-Multiple crop types to benefit wildlife | Ac | $4.86 |
| E328L | Leaving tall crop residue for wildlife | Leaving tall crop residue for wildlife | Ac | $9.71 |
| E328L | Leaving tall crop residue for wildlife | HU-Leaving tall crop residue for wildlife | Ac | $9.71 |
| E328M | Diversify crop rotation with canola or sunflower to provide benefits to pollinators | HU-Diversify crop rotation with canola or sunflower to provide benefits to pollinators | Ac | $9.71 |
| E328M | Diversify crop rotation with canola or sunflower to provide benefits to pollinators | Diversify crop rotation with canola or sunflower to provide benefits to pollinators | Ac | $9.71 |
| E329A | No till to reduce soil erosion | No till to reduce soil erosion | Ac | $2.91 |
| E329A | No till to reduce soil erosion | HU-No till to reduce soil erosion | Ac | $2.91 |
| E329B | No till to reduce tillage induced particulate matter | HU-No till to reduce tillage induced particulate matter | Ac | $2.91 |
| E329B | No till to reduce tillage induced particulate matter | No till to reduce tillage induced particulate matter | Ac | $2.91 |
| E329C | No till to increase plant-available moisture | HU-No till to increase plant-available moisture | Ac | $2.91 |
| E329C | No till to increase plant-available moisture | No till to increase plant-available moisture | Ac | $2.91 |
| E329D | No till system to increase soil health and soil organic matter content | HU-No till system to increase soil health and soil organic matter content | Ac | $3.88 |
| E329D | No till system to increase soil health and soil organic matter content | No till system to increase soil health and soil organic matter content | Ac | $3.88 |
| E329E | No till to reduce energy | No till to reduce energy | Ac | $3.88 |
| E329E | No till to reduce energy | HU-No till to reduce energy | Ac | $3.88 |
| E338B | Short-interval burns to promote a healthy herbaceous plant community | HU-Short-interval burns to promote a healthy herbaceous plant community | Ac | $85.97 |
| E338B | Short-interval burns to promote a healthy herbaceous plant community | Short-interval burns to promote a healthy herbaceous plant community | Ac | $85.97 |
| E338C | Sequential patch burning | HU-Sequential patch burning | Ac | $161.53 |
| E338C | Sequential patch burning | Sequential patch burning | Ac | $161.53 |
| E340A | Cover crop to reduce soil erosion | HU-Cover crop to reduce soil erosion | Ac | $6.86 |
| E340A | Cover crop to reduce soil erosion | Cover crop to reduce soil erosion | Ac | $6.86 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| E340B | Intensive cover cropping to increase soil health and soil organic matter content | Intensive cover cropping to increase soil health and soil organic matter content | Ac | $11.53 |
| E340B | Intensive cover cropping to increase soil health and soil organic matter content | HU-Intensive cover cropping to increase soil health and soil organic matter content | Ac | $11.53 |
| E340C | Use of multi-species cover crops to improve soil health and increase soil organic matter | HU-Use of multi-species cover crops to improve soil health and increase soil organic matter | Ac | $10.29 |
| E340C | Use of multi-species cover crops to improve soil health and increase soil organic matter | Use of multi-species cover crops to improve soil health and increase soil organic matter | Ac | $10.29 |
| E340D | Intensive orchard/vineyard floor cover cropping to increase soil health | HU-Intensive orchard/vineyard floor cover cropping to increase soil health | Ac | $10.29 |
| E340D | Intensive orchard/vineyard floor cover cropping to increase soil health | Intensive orchard/vineyard floor cover cropping to increase soil health | Ac | $10.29 |
| E340E | Use of soil health assessment to assist with development of cover crop mix to improve soil health | HU-Use of soil health assessment to assist with development of cover crop mix to improve soil health | Ac | $2.96 |
| E340E | Use of soil health assessment to assist with development of cover crop mix to improve soil health | Use of soil health assessment to assist with development of cover crop mix to improve soil health | Ac | $2.96 |
| E340F | Cover crop to minimize soil compaction | HU-Cover crop to minimize soil compaction | Ac | $9.94 |
| E340F | Cover crop to minimize soil compaction | Cover crop to minimize soil compaction | Ac | $9.94 |
| E340G | Cover crop to reduce water quality degradation by utilizing excess soil nutrients | Cover crop to reduce water quality degradation by utilizing excess soil nutrients | Ac | $9.94 |
| E340G | Cover crop to reduce water quality degradation by utilizing excess soil nutrients | HU-Cover crop to reduce water quality degradation by utilizing excess soil nutrients | Ac | $9.94 |
| E340H | Cover crop to suppress excessive weed pressures and break pest cycles | Cover crop to suppress excessive weed pressures and break pest cycles | Ac | $10.29 |
| E340H | Cover crop to suppress excessive weed pressures and break pest cycles | HU-Cover crop to suppress excessive weed pressures and break pest cycles | Ac | $10.29 |
| E340I | Using cover crops for biological strip till | HU-Using cover crops for biological strip till | Ac | $11.33 |
| E340I | Using cover crops for biological strip till | Using cover crops for biological strip till | Ac | $11.33 |
| E345A | Reduced tillage to reduce soil erosion | Reduced tillage to reduce soil erosion | Ac | $3.88 |
| E345A | Reduced tillage to reduce soil erosion | HU-Reduced tillage to reduce soil erosion | Ac | $3.88 |
| E345B | Reduced tillage to reduce tillage induced particulate matter | Reduced tillage to reduce tillage induced particulate matter | Ac | $2.91 |
| E345B | Reduced tillage to reduce tillage induced particulate matter | HU-Reduced tillage to reduce tillage induced particulate matter | Ac | $2.91 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| E345C | Reduced tillage to increase plant-available moisture | HU-Reduced tillage to increase plant-available moisture | Ac | $2.91 |
| E345C | Reduced tillage to increase plant-available moisture | Reduced tillage to increase plant-available moisture | Ac | $2.91 |
| E345D | Reduced tillage to increase soil health and soil organic matter content | Reduced tillage to increase soil health and soil organic matter content | Ac | $3.88 |
| E345D | Reduced tillage to increase soil health and soil organic matter content | HU-Reduced tillage to increase soil health and soil organic matter content | Ac | $3.88 |
| E345E | Reduced tillage to reduce energy use | HU-Reduced tillage to reduce energy use | Ac | $2.91 |
| E345E | Reduced tillage to reduce energy use | Reduced tillage to reduce energy use | Ac | $2.91 |
| E373A | Dust suppressant re-application for stabilization | Dust Suppressant Re-application, Once per Year | SqFt | $0.21 |
| E373A | Dust suppressant re-application for stabilization | HU-Dust Suppressant Re-application, Once per Year | SqFt | $0.21 |
| E374A | Install variable frequency drive(s) on pump(s) | Install variable frequency drive(s) on pump(s) | BHP | $103.95 |
| E374A | Install variable frequency drive(s) on pump(s) | HU-Install variable frequency drive(s) on pump(s) | BHP | $103.95 |
| E374B | Switch fuel source for pump motor(s) | Switch fuel source for pump motor(s) | HP | $2,901.98 |
| E374B | Switch fuel source for pump motor(s) | HU-Switch fuel source for pump motor(s) | HP | $2,901.98 |
| E382A | Incorporating "wildlife friendly" fencing for connectivity of wildlife food resources | HU-Incorporating "wildlife friendly" fencing for connectivity of wildlife food resources | Ft | $0.16 |
| E382A | Incorporating "wildlife friendly" fencing for connectivity of wildlife food resources | Incorporating "wildlife friendly" fencing for connectivity of wildlife food resources | Ft | $0.16 |
| E382B | Installing electrical fence offsets and wire for cross-fencing to improve grazing management | HU-Installing electrical fence offsets and wire for cross-fencing to improve grazing management | Ft | $0.48 |
| E382B | Installing electrical fence offsets and wire for cross-fencing to improve grazing management | Installing electrical fence offsets and wire for cross-fencing to improve grazing management | Ft | $0.48 |
| E386A | Enhanced field borders to reduce soil erosion along the edge(s) of a field | Enhanced field borders to reduce soil erosion along the edge(s) of a field | Ac | $561.01 |
| E386A | Enhanced field borders to reduce soil erosion along the edge(s) of a field | HU-Enhanced field borders to reduce soil erosion along the edge(s) of a field | Ac | $561.01 |
| E386B | Enhanced field borders to increase carbon storage along the edge(s) of the field | Enhanced field borders to increase carbon storage along the edge(s) of the field | Ac | $640.54 |
| E386B | Enhanced field borders to increase carbon storage along the edge(s) of the field | HU-Enhanced field borders to increase carbon storage along the edge(s) of the field | Ac | $640.54 |
| E386C | Enhanced field borders to decrease particulate emissions along the edge(s) of the field | Enhanced field borders to decrease particulate emissions along the edge(s) of the field | Ac | $574.19 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| E386C | Enhanced field borders to decrease particulate emissions along the edge(s) of the field | HU-Enhanced field borders to decrease particulate emissions along the edge(s) of the field | Ac | $574.19 |
| E386D | Enhanced field borders to increase food for pollinators along the edge(s) of a field | Enhanced field borders to increase food for pollinators along the edge(s) of a field | Ac | $640.54 |
| E386D | Enhanced field borders to increase food for pollinators along the edge(s) of a field | HU-Enhanced field borders to increase food for pollinators along the edge(s) of a field | Ac | $640.54 |
| E386E | Enhanced field borders to increase wildlife food and habitat along the edge(s) of a field | Enhanced field borders to increase wildlife food and habitat along the edge(s) of a field | Ac | $640.54 |
| E386E | Enhanced field borders to increase wildlife food and habitat along the edge(s) of a field | HU-Enhanced field borders to increase wildlife food and habitat along the edge(s) of a field | Ac | $640.54 |
| E390A | Increase riparian herbaceous cover width for sediment and nutrient reduction | Increase riparian herbaceous cover width for sediment and nutrient reduction | Ac | $448.81 |
| E390A | Increase riparian herbaceous cover width for sediment and nutrient reduction | HU-Increase riparian herbaceous cover width for sediment and nutrient reduction | Ac | $448.81 |
| E390B | Increase riparian herbaceous cover width to enhance wildlife habitat | Increase riparian herbaceous cover width to enhance wildlife habitat | Ac | $325.99 |
| E390B | Increase riparian herbaceous cover width to enhance wildlife habitat | HU-Increase riparian herbaceous cover width to enhance wildlife habitat | Ac | $325.99 |
| E391A | Increase riparian forest buffer width for sediment and nutrient reduction | HU-Increase riparian forest buffer width for sediment and nutrient reduction | Ac | $1,987.01 |
| E391A | Increase riparian forest buffer width for sediment and nutrient reduction | Increase riparian forest buffer width for sediment and nutrient reduction | Ac | $1,987.01 |
| E391B | Increase stream shading for stream temperature reduction | HU-Increase stream shading for stream temperature reduction | Ac | $2,011.49 |
| E391B | Increase stream shading for stream temperature reduction | Increase stream shading for stream temperature reduction | Ac | $2,011.49 |
| E391C | Increase riparian forest buffer width to enhance wildlife habitat | HU-Increase riparian forest buffer width to enhance wildlife habitat | Ac | $2,011.49 |
| E391C | Increase riparian forest buffer width to enhance wildlife habitat | Increase riparian forest buffer width to enhance wildlife habitat | Ac | $2,011.49 |
| E393A | Extend existing filter strip to reduce water quality impacts | Extend existing filter strip to reduce water quality impacts | Ac | $834.74 |
| E393A | Extend existing filter strip to reduce water quality impacts | HU-Extend existing filter strip to reduce water quality impacts | Ac | $834.74 |
| E412A | Enhance a grassed waterway | Waterway, reshape/extend/widen | Ac | $4,138.53 |
| E412A | Enhance a grassed waterway | HU-Waterway, reshape/extend/widen | Ac | $4,138.53 |
| E420A | Establish pollinator habitat | Establish Pollinator Habitat | Ac | $507.74 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| E420A | Establish pollinator habitat | HU-Establish Pollinator Habitat | Ac | $507.74 |
| E420B | Establish monarch butterfly habitat | Establish Monarch Habitat | Ac | $841.98 |
| E420B | Establish monarch butterfly habitat | HU-Establish Monarch Habitat | Ac | $841.98 |
| E449A | Complete pumping plant evaluation for water savings | Complete pumping plant evaluation for water savings | Ac | $5.40 |
| E449A | Complete pumping plant evaluation for water savings | HU-Complete pumping plant evaluation for water savings | Ac | $5.40 |
| E449C | Advanced Automated IWM - Year 2-5, soil moisture monitoring | Advanced Automated IWM - Year 2-5, soil moisture monitoring | Ac | $19.56 |
| E449C | Advanced Automated IWM - Year 2-5, soil moisture monitoring | HU-Advanced Automated IWM - Year 2-5, soil moisture monitoring | Ac | $19.56 |
| E449D | Advanced Automated IWM - Year 1, Equipment and soil moisture or water level monitoring | Advanced Automated IWM - Year 1, Equipment and soil moisture or water level monitoring | Ac | $51.72 |
| E449D | Advanced Automated IWM - Year 1, Equipment and soil moisture or water level monitoring | HU-Advanced Automated IWM - Year 1, Equipment and soil moisture or water level monitoring | Ac | $51.72 |
| E449F | Intermediate IWM - Year 1, Equipment with Soil or Water Level monitoring | HU-Intermediate IWM - Year 1, Equipment with Soil moisture or Water Level monitoring | Ac | $41.92 |
| E449F | Intermediate IWM - Year 1, Equipment with Soil or Water Level monitoring | Intermediate IWM - Year 1, Equipment with Soil moisture or Water Level monitoring | Ac | $41.92 |
| E449H | Intermediate IWM - Years 2 -5, using soil moisture or water level monitoring | Intermediate IWM - Years 2 - 5, using soil moisture or water level monitoring | Ac | $43.85 |
| E449H | Intermediate IWM - Years 2 -5, using soil moisture or water level monitoring | HU-Intermediate IWM - Years 2 - 5, using soil moisture or water level monitoring | Ac | $43.85 |
| E449I | Sprinkler Irrigation Equipment Retrofit | IWM - Year 1, Retrofit Equipment with Speed Control on Sprinkler Irrigation | No | $1,402.71 |
| E449I | Sprinkler Irrigation Equipment Retrofit | HU-IWM - Year 1, Retrofit Equipment with Speed Control on Sprinkler Irrigation | No | $1,402.71 |
| E472A | Manage livestock access to waterbodies to reduce nutrients or pathogens to surface water | Manage livestock access to waterbodies to reduce nutrients or pathogens to surface water | Ft | $2.31 |
| E472A | Manage livestock access to waterbodies to reduce nutrients or pathogens to surface water | HU-Manage livestock access to waterbodies to reduce nutrients or pathogens to surface water | Ft | $2.31 |
| E484A | Mulching to improve soil health | HU-Mulching to improve soil health | Ac | $1.94 |
| E484A | Mulching to improve soil health | Mulching to improve soil health | Ac | $1.94 |
| E484B | Reduce particulate matter emissions by using orchard or vineyard generated woody materials as mulch | HU-Reduce particulate matter emissions by using orchard or vineyard generated woody materials as mulch | Ac | $14.61 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| E484B | Reduce particulate matter emissions by using orchard or vineyard generated woody materials as mulch | Reduce particulate matter emissions by using orchard or vineyard generated woody materials as mulch | Ac | $14.61 |
| E484C | Mulching with natural materials in specialty crops for weed control | HU-Mulching with natural materials in specialty crops for weed control | Ac | $37.75 |
| E484C | Mulching with natural materials in specialty crops for weed control | Mulching with natural materials in specialty crops for weed control | Ac | $37.75 |
| E511A | Harvest of crops (hay or small grains) using measures that allow desired species to flush or escape | HU-Harvest of crops (hay or small grains) using measures that allow desired species to flush or escape | Ac | $3.39 |
| E511A | Harvest of crops (hay or small grains) using measures that allow desired species to flush or escape | Harvest of crops (hay or small grains) using measures that allow desired species to flush or escape | Ac | $3.39 |
| E511B | Forage harvest management that helps maintain wildlife habitat cover, shelter or continuity | Forage harvest management that helps maintain wildlife habitat cover, shelter or continuity | Ac | $6.52 |
| E511B | Forage harvest management that helps maintain wildlife habitat cover, shelter or continuity | HU-Forage harvest management that helps maintain wildlife habitat cover, shelter or continuity | Ac | $6.52 |
| E511C | Forage testing for improved harvesting methods and hay quality | Hay quality record keepoing for livestock producers | No | $122.56 |
| E511C | Forage testing for improved harvesting methods and hay quality | HU-Hay quality record keepoing for livestock producers | No | $122.56 |
| E512A | Cropland conversion to grass-based agriculture to reduce soil erosion | Cropland conversion to grass-based agriculture to reduce soil erosion | Ac | $7.03 |
| E512A | Cropland conversion to grass-based agriculture to reduce soil erosion | HU-Cropland conversion to grass-based agriculture to reduce soil erosion | Ac | $7.03 |
| E512B | Forage and biomass planting to reduce soil erosion or increase organic matter to build soil health | Forage and biomass planting to reduce soil erosion or increase organic matter to build soil health | Ac | $23.14 |
| E512B | Forage and biomass planting to reduce soil erosion or increase organic matter to build soil health | HU-Forage and biomass planting to reduce soil erosion or increase organic matter to build soil health | Ac | $23.14 |
| E512C | Cropland conversion to grass for soil organic matter improvement | HU-Cropland conversion to grass for soil organic matter improvement | Ac | $10.52 |
| E512C | Cropland conversion to grass for soil organic matter improvement | Cropland conversion to grass for soil organic matter improvement | Ac | $10.52 |
| E512D | Forage plantings that help increase organic matter in depleted soils | HU-Forage plantings that help increase organic matter in depleted soils | Ac | $13.10 |
| E512D | Forage plantings that help increase organic matter in depleted soils | Forage plantings that help increase organic matter in depleted soils | Ac | $13.10 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| E512E | Forage and biomass planting that produces feedstock for biofuels or energy production. | Forage and biomass planting that produces feedstock for biofuels or energy production. | Ac | $57.61 |
| E512E | Forage and biomass planting that produces feedstock for biofuels or energy production. | HU-Forage and biomass planting that produces feedstock for biofuels or energy production. | Ac | $57.61 |
| E512F | Establishing native grass or legumes in forage base to improve the plant community | HU-Establishing native grass or legumes in forage base to improve the plant community | Ac | $19.07 |
| E512F | Establishing native grass or legumes in forage base to improve the plant community | Establishing native grass or legumes in forage base to improve the plant community | Ac | $19.07 |
| E512G | Native grasses or legumes in forage base | Native grasses or legumes in forage base | Ac | $28.71 |
| E512G | Native grasses or legumes in forage base | HU-Native grasses or legumes in forage base | Ac | $28.71 |
| E512H | Forage plantings that enhance bird habitat cover and shelter or structure and composition | HU-Forage plantings that enhance bird habitat cover and shelter or structure and composition | Ac | $26.55 |
| E512H | Forage plantings that enhance bird habitat cover and shelter or structure and composition | Forage plantings that enhance bird habitat cover and shelter or structure and composition | Ac | $26.55 |
| E512I | Establish pollinator and/or beneficial insect and/or monarch habitat | HU-Establish pollinator and/or beneficial insect and/or monarch habitat | Ac | $27.79 |
| E512I | Establish pollinator and/or beneficial insect and/or monarch habitat | Establish pollinator and/or beneficial insect and/or monarch habitat | Ac | $27.79 |
| E512J | Establish wildlife corridors to provide habitat continuity or access to water | HU-Establish wildlife corridors to provide habitat continuity or access to water | Ac | $18.09 |
| E512J | Establish wildlife corridors to provide habitat continuity or access to water | Establish wildlife corridors to provide habitat continuity or access to water | Ac | $18.09 |
| E528A | Maintaining quantity and quality of forage for animal health and productivity | HU-Maintaining quantity and quality of forage for animal health and productivity | Ac | $3.92 |
| E528A | Maintaining quantity and quality of forage for animal health and productivity | Maintaining quantity and quality of forage for animal health and productivity | Ac | $3.92 |
| E528C | Incorporating wildlife refuge areas in contingency plans for wildlife. | HU-Incorporating wildlife refuge areas in contingency plans for wildlife. | Ac | $17.29 |
| E528C | Incorporating wildlife refuge areas in contingency plans for wildlife. | Incorporating wildlife refuge areas in contingency plans for wildlife. | Ac | $17.29 |
| E528D | Grazing management for improving quantity and quality of food or cover and shelter for wildlife | Grazing management for improving quantity and quality of food or cover and shelter for wildlife | Ac | $0.55 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| E528D | Grazing management for improving quantity and quality of food or cover and shelter for wildlife | HU-Grazing management for improving quantity and quality of food or cover and shelter for wildlife | Ac | $0.55 |
| E528E | Improved grazing management for enhanced plant structure and composition for wildlife | Improved grazing management for enhanced plant structure and composition for wildlife | Ac | $4.08 |
| E528E | Improved grazing management for enhanced plant structure and composition for wildlife | HU-Improved grazing management for enhanced plant structure and composition for wildlife | Ac | $4.08 |
| E528F | Stockpiling cool season forage to improve structure and composition or plant productivity and health | Stockpiling cool season forage to improve structure and composition or plant productivity and health | Ac | $24.59 |
| E528F | Stockpiling cool season forage to improve structure and composition or plant productivity and health | HU-Stockpiling cool season forage to improve structure and composition or plant productivity and health | Ac | $24.59 |
| E528G | Improved grazing management on pasture for plant productivity and health with monitoring activities | Improved grazing management on pasture for plant productivity and health with monitoring activities | Ac | $11.29 |
| E528G | Improved grazing management on pasture for plant productivity and health with monitoring activities | HU-Improved grazing management on pasture for plant productivity and health with monitoring activities | Ac | $11.29 |
| E528H | Prescribed grazing to improve/maintain riparian and watershed function-elevated water temperature | HU-Prescribed grazing to improve/maintain riparian and watershed function-elevated water temperature | Ac | $1.61 |
| E528H | Prescribed grazing to improve/maintain riparian and watershed function-elevated water temperature | Prescribed grazing to improve/maintain riparian and watershed function-elevated water temperature | Ac | $1.61 |
| E528I | Grazing management that protects sensitive areas -surface or ground water from nutrients | Grazing management that protects sensitive areas -surface or ground water from nutrients | Ac | $1.75 |
| E528I | Grazing management that protects sensitive areas -surface or ground water from nutrients | HU-Grazing management that protects sensitive areas -surface or ground water from nutrients | Ac | $1.75 |
| E528J | Prescribed grazing on pastureland that improves riparian and watershed function | HU-Prescribed grazing on pastureland that improves riparian and watershed function | Ac | $16.08 |
| E528J | Prescribed grazing on pastureland that improves riparian and watershed function | Prescribed grazing on pastureland that improves riparian and watershed function | Ac | $16.08 |
| E528K | Improved grazing management for soil compaction on pasture through monitoring activities | HU-Improved grazing management for soil compaction on pasture through monitoring activities | Ac | $8.17 |
| E528K | Improved grazing management for soil compaction on pasture through monitoring activities | Improved grazing management for soil compaction on pasture through monitoring activities | Ac | $8.17 |
| E528L | Prescribed grazing that improves or maintains riparian and watershed function-erosion | HU-Prescribed grazing that improves or maintains riparian and watershed function-erosion | Ac | $10.59 |
| E528L | Prescribed grazing that improves or maintains riparian and watershed function-erosion | Prescribed grazing that improves or maintains riparian and watershed function-erosion | Ac | $10.59 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| E528M | Grazing management that protects sensitive areas from gully erosion | Grazing management that protects sensitive areas from gully erosion | Ac | $1.60 |
| E528M | Grazing management that protects sensitive areas from gully erosion | HU-Grazing management that protects sensitive areas from gully erosion | Ac | $1.60 |
| E528N | Improved grazing management through monitoring activities | HU-Improved grazing management through monitoring activities | Ac | $1.86 |
| E528N | Improved grazing management through monitoring activities | Improved grazing management through monitoring activities | Ac | $1.86 |
| E528O | Clipping mature forages to set back vegetative growth for improved forage quality | HU-Clipping mature forages to set back vegetative growth for improved forage quality | Ac | $34.91 |
| E528O | Clipping mature forages to set back vegetative growth for improved forage quality | Clipping mature forages to set back vegetative growth for improved forage quality | Ac | $34.91 |
| E528P | Implementing Bale or Swath Grazing to increase organic matter and reduce nutrients in surface water | Implementing bale or swath grazing to increase organic matter or reduce nutrients in surface water | Ac | $136.51 |
| E528P | Implementing Bale or Swath Grazing to increase organic matter and reduce nutrients in surface water | HU-Implementing bale or swath grazing to increase organic matter or reduce nutrients in surface water | Ac | $136.51 |
| E528Q | Use of body condition scoring for livestock on a monthly basis to keep track of herd health | HU-Use of body condition scoring for livestock on a monthly basis to keep track of herd health | Ac | $1.79 |
| E528Q | Use of body condition scoring for livestock on a monthly basis to keep track of herd health | Use of body condition scoring for livestock on a monthly basis to keep track of herd health | Ac | $1.79 |
| E528R | Management Intensive Rotational Grazing | HU-Management Intensive Rotational Grazing | Ac | $34.11 |
| E528R | Management Intensive Rotational Grazing | Management Intensive Rotational Grazing | Ac | $34.11 |
| E533A | Advanced Pumping Plant Automation | Advanced Pumping Plant Automation | No | $5,194.76 |
| E533A | Advanced Pumping Plant Automation | HU-Advanced Pumping Plant Automation | No | $5,194.76 |
| E533B | Complete pumping plant evaluation for energy savings | Complete pumping plant evaluation for energy savings | Ac | $5.40 |
| E533B | Complete pumping plant evaluation for energy savings | HU-Complete pumping plant evaluation for energy savings | Ac | $5.40 |
| E550A | Range planting for increasing/maintaining organic matter | HU-Range planting for increasing/maintaining organic matter | Ac | $43.30 |
| E550A | Range planting for increasing/maintaining organic matter | Range planting for increasing/maintaining organic matter | Ac | $43.30 |
| E550B | Range planting for improving forage, browse, or cover for wildlife | HU-Range planting for improving forage, browse, or cover for wildlife | Ac | $20.04 |
| E550B | Range planting for improving forage, browse, or cover for wildlife | Range planting for improving forage, browse, or cover for wildlife | Ac | $20.04 |
| E570A | Enhanced rain garden for wildlife | HU-Enhanced rain garden for wildlife | SqFt | $0.18 |
| E570A | Enhanced rain garden for wildlife | Enhanced rain garden for wildlife | SqFt | $0.18 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| E578A | Stream crossing elimination | HU-Stream crossing elimination | No | $7,322.45 |
| E578A | Stream crossing elimination | Stream crossing elimination | No | $7,322.45 |
| E580A | Stream corridor bank stability improvement | HU-Stream corridor bank stability improvement | Ac | $2,074.36 |
| E580A | Stream corridor bank stability improvement | Stream corridor bank stability improvement | Ac | $2,074.36 |
| E580B | Stream corridor bank vegetation improvement | HU-Stream corridor bank vegetation improvement | Ac | $2,074.36 |
| E580B | Stream corridor bank vegetation improvement | Stream corridor bank vegetation improvement | Ac | $2,074.36 |
| E590A | Improving nutrient uptake efficiency and reducing risk of nutrient losses | HU-Improving nutrient uptake efficiency and reducing risk of nutrient losses | Ac | $26.55 |
| E590A | Improving nutrient uptake efficiency and reducing risk of nutrient losses | Improving nutrient uptake efficiency and reducing risk of nutrient losses | Ac | $26.55 |
| E590B | Reduce risks of nutrient loss to surface water by utilizing precision agriculture technologies | HU-Reduce risks of nutrient loss to surface water by utilizing precision agriculture technologies | Ac | $14.27 |
| E590B | Reduce risks of nutrient loss to surface water by utilizing precision agriculture technologies | Reduce risks of nutrient loss to surface water by utilizing precision agriculture technologies | Ac | $14.27 |
| E590C | Improving nutrient uptake efficiency and reducing risk of nutrient losses on pasture | HU-Improving nutrient uptake efficiency and reducing risk of nutrient losses on pasture | Ac | $16.80 |
| E590C | Improving nutrient uptake efficiency and reducing risk of nutrient losses on pasture | Improving nutrient uptake efficiency and reducing risk of nutrient losses on pasture | Ac | $16.80 |
| E595A | Reduce risk of pesticides in surface water by utilizing precision pesticide application techniques | Reduce risk of pesticides in surface water by utilizing precision pesticide application techniques | Ac | $10.50 |
| E595A | Reduce risk of pesticides in surface water by utilizing precision pesticide application techniques | HU-Reduce risk of pesticides in surface water by utilizing precision pesticide application techniques | Ac | $10.50 |
| E595B | Reduce risk of pesticides in water and air by utilizing IPM PAMS techniques | HU-Reduce risk of pesticides in water and air by utilizing IPM PAMS techniques | Ac | $6.40 |
| E595B | Reduce risk of pesticides in water and air by utilizing IPM PAMS techniques | Reduce risk of pesticides in water and air by utilizing IPM PAMS techniques | Ac | $6.40 |
| E595E | Eliminate use of chemical treatments to control pests and to increase the presence of dung beetles | HU-Eliminate use of chemical treatments to control pests and to increase the presence of dung beetles | Ac | $5.79 |
| E595E | Eliminate use of chemical treatments to control pests and to increase the presence of dung beetles | Eliminate use of chemical treatments to control pests and to increase the presence of dung beetles | Ac | $5.79 |
| E612A | Cropland conversion to trees or shrubs for long term improvement of water quality | Cropland conversion to trees or shrubs for long term improvement of water quality | Ac | $295.92 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| E612A | Cropland conversion to trees or shrubs for long term improvement of water quality | HU-Cropland conversion to trees or shrubs for long term improvement of water quality | Ac | $295.92 |
| E612B | Planting for high carbon sequestration rate | Planting for high carbon sequestration rate | Ac | $1,218.33 |
| E612B | Planting for high carbon sequestration rate | HU-Planting for high carbon sequestration rate | Ac | $1,218.33 |
| E612C | Establishing tree/shrub species to restore native plant communities | Establishing tree/shrub species to restore native plant communities | Ac | $932.51 |
| E612C | Establishing tree/shrub species to restore native plant communities | HU-Establishing tree/shrub species to restore native plant communities | Ac | $932.51 |
| E612D | Adding food-producing trees and shrubs to existing plantings | Adding food-producing trees and shrubs to existing plantings | Ac | $202.66 |
| E612D | Adding food-producing trees and shrubs to existing plantings | HU-Adding food-producing trees and shrubs to existing plantings | Ac | $202.66 |
| E612E | Cultural plantings | Cultural plantings | Ac | $1,858.66 |
| E612E | Cultural plantings | HU-Cultural plantings | Ac | $1,858.66 |
| E612G | Tree/shrub planting for wildlife food | HU-Tree/shrub planting for wildlife food | Ac | $1,872.37 |
| E612G | Tree/shrub planting for wildlife food | Tree/shrub planting for wildlife food | Ac | $1,872.37 |
| E643B | Restoration and management of rare or declining habitat | Restoration and management of rare or declining habitat | Ft | $7.70 |
| E643B | Restoration and management of rare or declining habitat | HU-Restoration and management of rare or declining habitat | Ft | $7.70 |
| E645A | Reduction of attractants to human-subsidized predators in sensitive wildlife species habitat | HU-Reduction of attractants to human-subsidized predators in sensitive wildlife species habitat | No | $50.04 |
| E645A | Reduction of attractants to human-subsidized predators in sensitive wildlife species habitat | Reduction of attractants to human-subsidized predators in sensitive wildlife species habitat | No | $50.04 |
| E645B | Manage existing shrub thickets to provide adequate shelter for wildlife | HU-Manage existing shrub thickets to provide adequate shelter for wildlife | Ac | $298.61 |
| E645B | Manage existing shrub thickets to provide adequate shelter for wildlife | Manage existing shrub thickets to provide adequate shelter for wildlife | Ac | $298.61 |
| E645C | Edge feathering for wildlife cover | Edge feathering for wildlife cover | Ac | $817.08 |
| E645C | Edge feathering for wildlife cover | HU-Edge feathering for wildlife cover | Ac | $817.08 |
| E666A | Maintaining and improving forest soil quality | HU-Maintaining and improving forest soil quality | Ac | $39.67 |
| E666A | Maintaining and improving forest soil quality | Maintaining and improving forest soil quality | Ac | $39.67 |
| E666D | Forest management to enhance understory vegetation | HU-Forest management to enhance understory vegetation | Ac | $252.40 |
| E666D | Forest management to enhance understory vegetation | Forest management to enhance understory vegetation | Ac | $252.40 |
| E666E | Reduce height of the forest understory to limit wildfire risk | Reduce height of the forest understory to limit wildfire risk | Ac | $252.40 |

| Code | Practice | Component | Units | Unit Cost |
|---|---|---|---|---|
| E666E | Reduce height of the forest understory to limit wildfire risk | HU-Reduce height of the forest understory to limit wildfire risk | Ac | $252.40 |
| E666F | Reduce forest stand density to create open stand structure | HU-Reduce forest stand density to create open stand structure | Ac | $289.52 |
| E666F | Reduce forest stand density to create open stand structure | Reduce forest stand density to create open stand structure | Ac | $289.52 |
| E666G | Reduce forest density and manage understory along roads to limit wildfire risk and improve habitat | Reduce forest density and manage understory along roads to limit wildfire risk and improve habitat | Ac | $293.44 |
| E666G | Reduce forest density and manage understory along roads to limit wildfire risk and improve habitat | HU-Reduce forest density and manage understory along roads to limit wildfire risk and improve habitat | Ac | $293.44 |
| E666H | Increase on-site carbon storage | HU-Increase on-site carbon storage | Ac | $12.62 |
| E666H | Increase on-site carbon storage | Increase on-site carbon storage | Ac | $12.62 |
| E666K | Creating structural diversity with patch openings | Creating structural diversity with patch openings | Ac | $532.77 |
| E666K | Creating structural diversity with patch openings | HU-Creating structural diversity with patch openings | Ac | $532.77 |
| E666M | Maintaining structural diversity in dry Western forests | HU-Maintaining structural diversity in dry Western forests | Ac | $245.17 |
| E666M | Maintaining structural diversity in dry Western forests | Maintaining structural diversity in dry Western forests | Ac | $245.17 |
| E666N | Creating structural diversity in dry Western forests | Creating structural diversity in dry Western forests | Ac | $1,024.15 |
| E666N | Creating structural diversity in dry Western forests | HU-Creating structural diversity in dry Western forests | Ac | $1,024.15 |
| E666O | Snags, den trees, and coarse woody debris for wildlife habitat | Snags, den trees, and coarse woody debris for wildlife habitat | Ac | $54.54 |
| E666O | Snags, den trees, and coarse woody debris for wildlife habitat | HU-Snags, den trees, and coarse woody debris for wildlife habitat | Ac | $54.54 |
| E666P | Summer roosting habitat for native forest-dwelling bat species | Summer roosting habitat for native forest-dwelling bat species | Ac | $212.25 |
| E666P | Summer roosting habitat for native forest-dwelling bat species | HU-Summer roosting habitat for native forest-dwelling bat species | Ac | $212.25 |