


ELEVATION



FABRIC ANCHOR DETAIL

NOTES:

1. Wires of mesh support shall be minimum gage no. 12.
2. Temporary sediment fence shall be installed prior to any grading work in the area to be protected. They shall be maintained throughout the construction period and removed in conjunction with the final grading and site stabilization.
3. Filter fabric shall meet the requirements of material specification 592 Geotextile Table 1 or 2, Class I with equivalent opening size of at least 30 for nonwoven and 50 for woven.
4. Fence posts shall be either wood post with a minimum cross-sectional area of 3.0 sq. in. or a standard steel post.

| | | | |
|----------|-------------|----------|--------|
| Designed | M. QUINONES | Date | 4/1/14 |
| Drawn | | Checked | |
| | | Approved | |

SILT FENCE WITH WIRE SUPPORT


 United States
 Department of
 Agriculture

 Natural Resources
 Conservation Service