

UNITED STATES DEPARTMENT OF AGRICULTURE
NATURAL RESOURCES CONSERVATION SERVICE

CONSTRUCTION SPECIFICATION
CS-05: "STRUCTURE REMOVAL"

5.1 SCOPE

The work shall consist of the removal, salvage, and disposal of man-made structures, including buried structures and fences.

5.2 REMOVAL

Structures shall be removed to the extent and depth shown on the drawings or as designated by the technical representative.

All hazardous material shall be identified prior to structure removal by a qualified individual and identified accordingly in a report or by drawings.

5.3 SALVAGE

Structures designated as salvageable shall be carefully removed, disassembled and neatly placed in the storage area shown on the drawings or other selected areas approved by the landowner. All salvaged materials is the property of the owner, unless otherwise specified.

5.4 DISPOSAL OF REFUSE AND UNSALVAGED MATERIALS

Refuse and unsalvageable materials shall be disposed of by burning and/or burying at locations shown on the drawings or as approved by the landowner and the technical representative in accordance with all local, state and federal regulations. Materials to be buried shall be placed at least 2 feet below the surrounding ground line and have a minimum of 2 feet of cover with the finished surface free of depressions and graded to drain.

5.5 HAZARDOUS MATERIAL

All identified hazardous material shall be disposed of in accordance with local, state and federal regulations.